


Interconnected Traditions

Semitic Languages, Literatures, and Cultures

A Festschrift for Geoffrey Khan

Volume 1: Hebrew and the Wider Semitic World

EDITED BY AARON D. HORNKOHL, NADIA VIDRO,
JANET C. E. WATSON, ELEANOR COGHILL,
MAGDALEN M. CONNOLLY, AND BENJAMIN M. OUTHWAITE



Cambridge Semitic Languages and Cultures

General Editor: Geoffrey Khan

This is the first Open Access book series in the field; it combines the high peer-review and editorial standards with the fair Open Access model offered by OBP. The series includes philological and linguistic studies of Semitic languages, editions of Semitic texts, and studies of Semitic cultures. Titles cover all periods, traditions and methodological approaches to the field. The editorial board comprises Geoffrey Khan, Aaron Hornkohl, Esther-Miriam Wagner, Anne Burberry, and Benjamin Kantor.

You can access the full series catalogue here:
<https://www.openbookpublishers.com/series/2632-6914>



If you would like to join our community and interact with authors of the books, sign up to be contacted about events relating to the series and receive publication updates and news here:
<https://forms.gle/RWymsw3hdsUjZTXv5>



INTERCONNECTED
TRADITIONS
VOLUME 1

Interconnected Traditions

Semitic Languages, Literatures, and
Cultures—A Festschrift for Geoffrey Khan

Volume 1: Hebrew and the Wider
Semitic World

Edited by
Aaron D. Hornkohl, Nadia Vidro, Janet C.
E. Watson, Eleanor Coghill, Magdalen M.
Connolly, and Benjamin M. Outhwaite





<https://www.openbookpublishers.com>

©2025 Aaron D. Hornkohl, Nadia Vidro, Janet C. E. Watson, Eleanor Coghill,
Magdalen M. Connolly, and Benjamin M. Outhwaite



This work is licensed under a Creative Commons Attribution-NonCommercial 4.0 International (CC BY-NC 4.0). This license allows you to share, copy, distribute, and transmit the text; to adapt the text for non-commercial purposes of the text providing attribution is made to the authors (but not in any way that suggests that they endorse you or your use of the work). Attribution should include the following information:

Aaron D. Hornkohl, Nadia Vidro, Janet C. E. Watson, Eleanor Coghill, Magdalen M. Connolly, and Benjamin M. Outhwaite, *Interconnected Traditions: Semitic Languages, Literatures, and Cultures—A Festschrift for Geoffrey Khan. Volume 1: Hebrew and the Wider Semitic World*. Cambridge, UK: Open Book Publishers, 2025,
<https://doi.org/10.11647/OBP.0463>

Further details about CC BY-NC licenses are available at
<http://creativecommons.org/licenses/by-nc/4.0/>

All external links were active at the time of publication unless otherwise stated and have been archived via the Internet Archive Wayback Machine at
<https://archive.org/web>

Any digital material and resources associated with this volume will be available at
<https://doi.org/10.11647/OBP.0463#resources>

Semitic Languages and Cultures 35

ISSN (print): 2632-6906

ISBN Paperback: 978-1-80511-576-2

ISSN (digital): 2632-6914

ISBN Hardback: 978-1-80511-577-9

ISBN Digital (PDF): 978-1-80511-578-6

DOI: 10.11647/OBP.0463

Cover image: Cambridge University Library T-S NS 264.63, assorted writing exercises in Hebrew, Judaeo-Arabic, and Arabic, part of a letter, and some legal text (courtesy of the Syndics of Cambridge University Library).

Cover design: Jeevanjot Kaur Nagpal

The fonts used in this volume are Cambria Math, Charis SIL, David, Estrangelo Edessa, Kahle, Mandaic Hebrew, Narkisim, Paleo Hebrew, SBL Greek, SBL Hebrew, Scheherazade New, Segoe UI Historic, Times New Roman.

CONTENTS: VOLUME I

Contents: Volume I.....	v
Contents: Volume II.....	ix
Preface: A Tribute to Geoffrey Khan, Regius Professor of Hebrew, Cambridge.....	xv
Volume I: Hebrew, Comparative Semitics, and the Semitic Languages	1
A. Hebrew	3
<i>Bo Isaksson</i>	
Geoffrey Khan's Contribution to the Problem of Biblical Hebrew Consecutive <i>weqatal</i>	5
<i>Aaron D. Hornkohl</i>	
The Origins of <i>Wayyiqtol</i> : A First-person Account.....	37
<i>Christo van der Merwe</i>	
Fronting in the Protases of ׀ Conditionals	69
<i>Robert S. D. Crellin</i>	
Considerations for the Design of Dependency Treebanks for Linguistic Research in Biblical Hebrew	99
<i>Ambjörn Sjörs</i>	
Notes on the Reciprocal Function of <i>Nif'al</i> in Biblical Hebrew.....	131
<i>Benjamin Kantor</i>	
Healed by 'his wound(s)', 'his bruising', or 'in his company'? : Isaiah 53.5 and <i>Dagesh Mavhin</i>	157

Elizabeth Robar

- Why Do Psalms, Proverbs, and Job Use Different
Accents? 189

Gary A. Rendsburg

- The Pronunciation of תִּזְכְּרוּ (Num. 15.40) in Rabbinic
Sources and in Light of Phoenician 223

Cynthia L. Miller-Naudé and Jacobus A. Naudé

- A Case for Distributive Quantification of *kol* in Biblical
Hebrew 259

Adina Moshavi

- Kol* as a Universal Quantifier in Biblical Hebrew..... 291

Ethan Jones

- A More Polite Suggestion: The Lengthened Imperative
in Biblical Hebrew 331

Noam Mizrahi

- Lexis-coding Orthography in 4QIsa^m (4Q66)..... 359

Moshe Florentin

- The Vocabulary of the Samaritan Pentateuch: A General
Overview..... 385

Edward Cook

- Some Cases of Grammaticalisation in Mishnaic Hebrew
and Their Diachronic Implications 403

Mila Neishtadt

- Rabbinic Hebrew *kyd* ~ *ʿkyd*: Insights from Palestinian
Arabic 421

Yehudit Henshke

- The Realisation of *Şere* in Contemporary Hebrew:
 Monophthongal or Diphthongal? 455

Yaron Peleg

- The Bible and Modern Hebrew 479

B. Comparative Semitics and the Semitic Languages 489

Aaron J. Koller

- Alphabetical Order and Alphabetical Thinking in the
 East and West: From Antiquity to the Middle Ages 491

Tania Notarius

- “Every glance of their eyes—like a flame, two flames”:
 A Case of Ugaritic Gt *’mr* ‘see’ Reconsidered 529

Lutz Edzard

- Loan Translation or Independent Development: The
 Figura Etymologica in Semitic and in Yiddish 555

Simon Hopkins

- On the Pronunciation of Sacred Names 577

Benjamin Suchard

- The Shape of the Teen Numerals in Central Semitic 611

Na‘ama Pat-El

- The Gender of Paired Body Parts in Semitic 631

Janet C. E. Watson

- Fieldwork: Chance, Choice, Change 661

Clive Holes

- ‘The Cobbler Made Money from the Town of ‘Ifač’: A
Satirical Poem in Iraqi Arabic on Corruption in the Iraqi
Parliament..... 681

Leonid Kogan and Maria Bulakh

- Attributive Possession in Soqotri: The Evidence of the
‘Vienna Corpus’ 695

Holger Gzella

- Christian Palestinian Aramaic between Greek and
Arabic 747

John Healey

- Aramaic: Lingua Franca, Koine, or Both? 771

Matthew Morgenstern and Tom Alfia

- Arabic Spells against Menstrual Bleeding in Mandaic
Script 797

Johan Lundberg

- Dots and Word Stress in Classical East Syriac..... 821

Ivri Bunis

- The Late Western Aramaic Suffixing of Pronominal
Direct Objects via -t- < /yāt/..... 843

Viktor Golinets

- The Significance of the Newly Found Amorite–
Akkadian Bilinguals for Hebrew Lexicography 879

- Index..... 901

CONTENTS: VOLUME II

Contents: Volume I.....	v
Contents: Volume II.....	ix
Volume II: The Medieval World, Judaeo-Arabic, and Neo-Aramaic.....	1
C. The Medieval World and Judaeo-Arabic	3
<i>Stefan Reif</i>	
To What Extent is Geniza Research on Jewish Liturgy a Continuation of the Work of Leopold Zunz?	5
<i>Aharon Maman</i>	
New Geniza Fragments from the Commentary of R. Isaac b. Samuel al-Kanzī the Sephardi on Joshua and Judges	31
<i>Benjamin M. Outhwaite</i>	
The Cacophony of Colophons in the Cairo Codex of the Prophets	65
<i>Vincent Beiler</i>	
Does the Cairo Codex Represent a Scribal School?	111
<i>Judith Olszowy-Schlanger</i>	
Hebrew Script Terminology in Cairo Geniza Book Lists.....	147
<i>Ronny Vollandt</i>	
Geniza Book Lists as Indirect Sources of Medieval Jewish Book History in the Near East.....	177

Estara Arrant

An Exploration of Geniza Targum Fragments as Objects
of Personal Study and Everyday Use 217

Mordechai Akiva Friedman

Two Judaeo-Arabic Letters to Abraham Maimonides: A
Recommendation and a Condemnation of a Communal
Leader..... 257

Michael Rand z"l

A Fragment of the *Maḥberot* ‘Azar’el ben Yosef 287

Nick Posegay

Some Notes on Melody: Sa‘adya Gaon and Why
‘naghma’ Means ‘vowel’ in Judaeo-Arabic..... 311

Tamar Zewi

“You Shall Not Boil a Kid in Its Mother’s Milk” in
Sa‘adya Gaon’s Translation of the Pentateuch..... 341

Ofra Tirosh-Becker

Judaeo-Arabic Translations from the Bible to Robinson
Crusoe: Centre versus Periphery..... 363

Wiktor Gębski

Comparative Notes on the Jewish Arabic Dialects of
Gabes and Djerba (Tunisia)..... 399

Benjamin Hary

Written Egyptian Judaeo-Arabic: Implications for the
Spoken Variety 429

Gregor Schwarb

The Arabic Counterpart of the Byzantine Karaite

Treatise *Marpe la-ʿAšem* 459*Miriam Goldstein*

Early Tenth-Century Judaeo-Arabic Exegesis on the

Visit to Abraham 489

Nadia Vidro

Yūsuf ibn Nūḥ and Yūsuf ibn Baḥṭawayh: One

Grammarian or Two? 523

*José Martínez Delgado*A Lexicographical Analysis of *Sharḥ al-ʾAlfāz* by Abū al-Faraj Hārūn (*Parashat Bereshit*) 547*Diana Lipton and Meira Polliack*

Wrestlers before the King: Image and Text in Ancient

and Medieval Representations of the First Murder 575

María Ángeles Gallego

From Bibliography to History: The Early Study of

Andalusi Judaism in the Modern Era 611

D. Neo-Aramaic 639

Steven E. Fassberg

Neo-Aramaic 2MS and 2FS Genitive Pronominal Suffixes

in the Light of Earlier Aramaic 641

Samuel Fox

Being Born in Neo-Aramaic 655

Alessandro Mengozzi

- Not Such a Dummy or Otiose After All: NENA Verbs
with Non-referential 3FS Object Pronouns..... 673

*Phillip Yu. Burlakov, Anna S. Cherkashina, Charles G. Häberl,
and Sergey V. Loesov*

- The Church Militant: A Modern Western Aramaic
Account..... 695

Otto Jastrow

- A Syriac Christian in the Turkish Army: A Text in the
Ṭuroyo Dialect of Midin 721

Charles G. Häberl

- War and Fieldwork..... 739

Dorota Molin

- Indefiniteness Marking: NENA and Its Areal and Semitic
Parallels 755

Paul M. Noorlander

- Miracles of Saint Ephrem: Legends in the Neo-Aramaic
Dialect of Umra d-Shish 785

Lidia Napiorkowska

- Relating Morphological and Sociolinguistic Variety in
Modern Hebrew to Neo-Aramaic..... 823

Eleanor Coghill

- The North-Eastern Neo-Aramaic Dialect of Tin 855

Hezy Mutzafi


- Five Enigmatic Neo-Aramaic Lexemes and Their
Possible Etymologies..... 895

Werner Arnold

Animals in the Western Neo-Aramaic Proverbs of

Maṣlūla 923

Index 931



A drawing of Geoffrey Khan, by Yoel Hornkohl, 17 September 2024

PREFACE: A TRIBUTE TO GEOFFREY KHAN, REGIUS PROFESSOR OF HEBREW, CAMBRIDGE

I am given to understand that this is the third Festschrift prepared in Geoffrey's honour. The first was an informal, in-house anthology prepared by Geoffrey's graduate students to mark his fiftieth birthday. The second was *Studies in Semitic Linguistics and Manuscripts: A Liber Discipulorum in Honour of Professor Geoffrey Khan* (Uppsala University Library, 2018). Edited by four of Geoffrey's former PhD students, containing 21 articles by former students and colleagues, and running 467 pages, it was presented to Geoffrey on the occasion of his sixtieth birthday.

The secret project known by the impenetrable codename *GKFS25* began in the spring of 2021. I had previously been approached by a post-doc and former student of Geoffrey's, Magdalen Connolly, with the idea that we start preparing a Festschrift to mark his retirement. A committee of area editors was formed, and we began soliciting contributions. Four years later, we have finally seen its publication. The present work, comprising two volumes each running to nearly a thousand pages, presents over 60 contributions representing the efforts of nearly 70 contributors, including colleagues present and past, near and far, among them many former students of Geoffrey's. The size, scope, and topical diversity of the work, the number of editorial and contributing participants, and the open-access nature of the publication are all testament to Geoffrey's unique scholarly and personal

attributes, which can, at the risk of oversimplification, be distilled into two: world-leading expertise in multiple fields and personal care for students and colleagues.

The journey to publication has been an extended one. Along the way, among those involved—honouree, editors, contributors—we have witnessed births, marriages, appointments, promotions, retirements, moves, arrivals, fresh starts, publications, awards, and the founding and deepening of bonds. We have also seen or experienced death, bereavement, illness, the effects of pandemic and war, departures, disappointment, fallings out, and separation. It may be tempting to recall the former, and leave the latter unmentioned. But having experienced the lot, we surely cheat ourselves out of the full effect if we shy away from acknowledging the ups with the downs, even if the associated feelings are a mixture of bitter and sweet. The adjective *interconnected*, used in the title to describe the linguistic, literary, and cultural traditions that Geoffrey's work has so illuminated, is also an apt descriptor of the people whom he has touched.

1.0. Geoffrey Khan's Biography

Geoffrey Allan Khan was born in Cheltenham, England, 1 February 1958, but was brought up in his formative years in Middlesbrough, North Yorkshire. His background was mixed: English mother, South Asian father of Iranian descent; Muslim paternal grandfather who married a Catholic; a paternal great-grandmother who was the daughter of a Welsh Wesleyan missionary; and Geoffrey also has Native American ancestry in his DNA. De-

spite being known to some of his Israel-based language informants as *Alon Cohen* ($\approx$ Allan Khan; *Geoffrey* is hard for some to pronounce), he has no known Jewish heritage. His parents separated when he was young, and he was raised by his mother and grandmother. He attended a comprehensive school, where, due in part to frequent playground violence and racial abuse, he, in his own words, “took refuge in learning languages.” One of his first loves was Italian, a language in which he remains sufficiently proficient to communicate effectively in both spoken and written form. Over the course of his teenage years, he collected a wide range of ‘Teach Yourself’ books in every language from Samoan to Finnish. These volumes still grace his bookshelves to this day.

Relatives encouraged Geoffrey to pursue studies in Law or Medicine, as they equated such career paths with success. But Geoffrey was interested in languages—the more exotic, the better—which led him to the Semitic languages, with their distinctive scripts.

Geoffrey studied for a BA degree in Semitic Languages (Hebrew, Aramaic, Arabic, Akkadian, Ethiopic) at the School of Oriental and African Studies (SOAS), University of London, which he completed in 1980. He went on, thereafter, to graduate studies in the same institution and was awarded a PhD in 1984 for a thesis entitled ‘Extraposition and Pronominal Agreement in Semitic languages’, which concerned the form and function of various syntactic structures in Arabic, Hebrew, Aramaic, Akkadian and Amharic. This was subsequently published as his first monograph, *Studies in Semitic Syntax* (Oxford University Press, 1988). This established Geoffrey as a respected Semitist.

Geoffrey met Colette, his wife, at SOAS, where she was also studying. In 1983 he moved to Cambridge to take up a post-doctoral research position in the Taylor-Schechter Genizah Research Unit (GRU) at Cambridge University Library. Geoffrey and Colette married in January 1984. They would eventually adopt two children, Hannah and Jonathan. Hannah and partner Matt and Jonathan and partner Giovanna have to date provided Geoffrey and Colette with a granddaughter each, Sofia and Giorgia, respectively.

Geoffrey would spend ten years working in the GRU, 1983–1987 as Research Assistant and 1987–1993 as Research Associate. His employment during this time felt rather precarious, as it involved one-year contracts that required renewal from year to year, and he supplemented his income through other work in the University. The experience of being dependent on temporary contracts was to have a profound effect on Geoffrey, giving him a special sensitivity to a situation often faced by young scholars. Many of his students, colleagues, and others have benefited over the years from his concern and practical efforts to further their careers.

The ten years spent as a post-doctoral researcher were decisive for Geoffrey's career. In his Geniza work, he gained skills, knowledge, and perspective through familiarity with a trove of authentic source material in numerous languages and got to assess critically the textbook learning to which he had been exposed in his undergraduate days (more on this below). The time also did nothing to diminish his love for languages and ancient sources. In a famous photograph (reproduced in volume II, page

2), Solomon Schechter sits examining a Geniza document, surrounded by crates of manuscripts. Geoffrey has confessed more than once that his early dream was “to be that man.”

Yet, though perhaps tendentially introverted, Geoffrey is no recluse. Indeed, a significant portion of his scholarship depends on engaging with people. In the early 1990s, Geoffrey spent a year in Jerusalem, where he would often devote hours to poring over medieval manuscripts preserved on microfilm at what was then called the Jewish National and University Library (today’s National Library of Israel). As intriguing as the research proved, Geoffrey felt the need for diversion from the long and solitary days in the bowels of the library. Having come across Neo-Aramaic-speakers in London and aware of the presence of communities in Jerusalem, he endeavoured to seek some out. His method? Looking up the surname *Arbel* in the telephone directory and phoning up one number after another. But since *Arbel* can derive from either the name of the northern Iraqi city Erbil (from which a community of Neo-Aramaic-speaking Jews had immigrated to Israel) or the name of a mountain in the Galilee, it took several attempts before he found a speaker of Neo-Aramaic. So began a career-long interest in the study and preservation of endangered living Semitic languages to accompany Geoffrey’s deep and lasting interest in ancient Semitic tongues. His manuscript-based scholarship was now significantly augmented to include data from language survey conducted in such far-flung places as Iraq and Tbilisi, Chicago and Turlock, and several Jerusalem taxis (often driven by Neo-Aramaic

speakers). Attempting to find one such village, he and co-researchers were even temporarily detained by authorities for having unwittingly crossed an international border!

By the end of his post-doctoral days, Geoffrey had already made a name for himself in research on, *inter alia*, Semitics, the Cairo Geniza, Judaeo-Arabic, medieval grammatical traditions, Masoretic studies, and modern Aramaic. In 1993, he was appointed Lecturer in Hebrew and Aramaic in what was then called the Faculty of Oriental Studies (today's Faculty of Asian and Middle Eastern Studies), University of Cambridge. In 1999, he was promoted to Reader in Semitic Philology; in 2002, to Professor in Semitic Philology. He was elected Regius Professor of Hebrew in 2012.

While many of Geoffrey's academic achievements are well documented, his hobbies and pastimes are somewhat less well known. Among other things, he served as a bellringer in the University's parish church, Great St Mary's. At school he was a very promising athlete and over the past couple of years he has become an avid rower. This surely marks an improvement in Geoffrey's river-going prowess in comparison to the time he took a relative out punting and gave her concussion with the pole!

2.0. Significance of Geoffrey's Contributions

Geoffrey Khan has written, edited, co-written, or co-edited more than thirty books and has over two-hundred articles to his name. These broadly cover Semitics, medieval manuscripts, Arabic papyri and documents, Neo-Aramaic, medieval reading and grammatical traditions, exegesis, Judaeo-Arabic, and ancient Hebrew. Unsurprisingly, some of the more common descriptions one hears

from people familiar with Geoffrey and his work laud the multiplicity of areas in which he has made significant scholarly contributions. His work ethic also often gets mentioned: speedy editorial turn arounds and emails written in the wee hours. Others remark on his kindness and humanity, the way he has proactively looked out for his students, junior colleagues, and others. In all of these and other ways Geoffrey has been an exemplary, if not exactly imitable, role model. Yet he is also characterised by an attribute no less important, but somewhat less discussed: *subversiveness*.

One of Geoffrey's most oft repeated pieces of advice is continually to question accepted theories. Far from a sweeping rejection of the achievements of past scholars, this attitude seems rather to reflect an insatiable hunger for truth coupled with an unwillingness to be content with anything less than genuinely satisfying and comprehensive explanations of the data. Geoffrey does not come across as someone inherently adventurous or rebellious, but his quiet and unrelenting commitment to deep understanding has inevitably made him into what is today called a *disruptor*, challenging aspects of conventional wisdom and received opinion in every academic domain to which he has turned his hand. Ironically, some of this subversive disruption has involved reassessment of scholarly distrust of ancient tradition, which Geoffrey takes more seriously than many others, seeking to explain rather than explain away.

The effects of the shake-up that Geoffrey has brought to the many fields in which he has been active promises to endure. Indeed, if the shortlist of candidates for Geoffrey's replacement as Regius Professor can be taken as evidence, his very election to

the post and subsequent tenure are one more step in the upsetting of centuries of tradition with regard to the role. For the first time in history, the list included no one from the UK, but did include two women, three Jews, and four nationalities.

Here follow a few further examples of Geoffrey's disruptive or innovative scholarly approaches.

As a student of Biblical Hebrew, Geoffrey has taken more seriously than many the importance of the medieval lenses through which most biblical pronunciation and grammar are viewed. Dissatisfied with standard accounts of the received Tiberian reading tradition—since these did not align with contemporary medieval descriptions of the pronunciation—he almost literally rewrote the book on the oral realisation of Tiberian Hebrew, and has continued to work to expand knowledge of this and other medieval reading traditions and to explore their historical depth.

Similarly, and not surprisingly, Geoffrey has stressed the importance of working not from printed editions, but from authentic medieval sources, including those not entirely in line with the so-called standard or received traditions. For example, this has helped to familiarise academic readership with the diversity of ancient, medieval, and modern biblical reading traditions, including variety among manuscripts of a given tradition.

Somewhat relatedly, Geoffrey is neither pure philologist nor pure (modern) linguist, but readily derives benefit from both emphases: expertise in the language, and all that goes into its representation in old texts, coupled with openness to insights from crosslinguistic investigations of related and unrelated languages, living and dead. Though not without his own theoretical

preferences (when a language informant-colleague expressed unfamiliarity with Chomsky, Geoffrey replied that she hadn't missed much), Geoffrey fruitfully engages with linguists of all stripes! This, along with his knowledge of modern Semitic languages, especially Neo-Aramaic, has led him to innovative theories to explain pre-modern language and texts by reference to the recycling of phenomena.

And, of course, the significance of his academic contributions extends beyond the academy. He has rather impressed scholarly and non-scholarly audiences alike with his proficiency in the modern versions of the languages he studies, whether Hebrew, Assyrian (Neo-Aramaic), or Arabic.

As enjoyable as Geoffrey finds investigating and describing the intricacies of the Neo-Aramaic lexicon and grammar, he has played a pivotal role in cataloguing priceless linguistic and extralinguistic heritage on the verge of oblivion, which Geoffrey himself has described as no less important than the material cultural products that one often finds displayed in museums.

While not exactly a techie, Geoffrey was an early adopter of the computer and other technological advances and has sought to collaborate with tech-savvy students and colleagues and to promote their research. He remains amazingly receptive to new and different approaches to old problems and is often ahead of his time in the ability to grasp the potential of new technologies. Never jealous of recognition, he regularly partners with colleagues at various career stages, not just mentoring, but gratefully profiting from the exchange of perspectives and ideas.

3.0. Impact on the Academic Community

It is difficult to overstate Geoffrey's impact on the academic community. As outlined in the previous section, the significance of his scholarly contributions, measured in terms of the fields in which he has been active, entails influence over many researchers in diverse domains. Not only this, but, as may be gleaned from the affiliations of contributors to this Festschrift, Geoffrey's former students are strategically placed in academic positions around the world in the various disciplines in which he has worked and continue to produce first-rate scholarship, effectively disseminating *Khanesque* approaches and ideas.

Yet, not all of Geoffrey's impact is given to simple quantification. Take, by way of example, his generosity with time, which though always characteristic, has been particularly evident in the few years leading up to his retirement. While shepherding his own graduate students to complete their dissertations and wrapping up collaborative post-doctoral research projects in an effort to wind down his formal scholarly activities, several unforeseen colleague deaths and/or departures in Cambridge and farther afield would culminate in offers on Geoffrey's part to fill in as supervisor. That Geoffrey was *qualified* to do this in several fields is testament to the range of his scholarly expertise; that he was *willing* to do it is testament to the humanity that so defines him.

Geoffrey has approached research, teaching, supervision, and administration with profound humility, exhibited in many ways. On several occasions while debating his and other approaches to linguistic issues, he has been heard to say, "But I

might be wrong!” Another way this comes out: Geoffrey will listen and ask questions, but is often slow to disagree or correct outright, and never insists others adopt his view. This is due partly to his non-confrontational disposition, coupled, I think, with the patient optimism that understanding and agreement may come with time and repeated exposure, and, again, the aforementioned humility that allows him to appreciate his own benefit from exchange with students and colleagues. But more often, of course, it is we interlocutors who benefit, often after the extended time and exposure it takes to wrap our heads around Geoffrey’s ideas.

Geoffrey’s humility, patience, and non-confrontational manner also have their disadvantages. Some can find him initially inscrutable. More than one PhD student, post-doc, and colleague has come away from a meeting with Geoffrey uncertain as to his opinion of their work. Only after multiple meetings do we realise that we are unlikely to receive any critique clearer than a few questions or brief remarks and the suggestion of a pertinent article. But, again, this is not mere amicability on Geoffrey’s part, or a desire to avoid offense, but also a deep conviction that the research is ours and that it is not his place to impose his views upon us.

Among other things, Geoffrey has also excelled at grant capture, heading up numerous collaborative research schemes with local and distant co-researchers. His regular invitations to speak, contribute a study, or assess academic work also constitute important forms of scholarly impact. Among other things, he is a member of the British Academy and the Academy of the Hebrew

Language, and has served as President of the British & Irish Association for Jewish Studies, as an External Assessor of Hebrew Graduate Programmes for the Israeli Institute for Higher Education, and as General Editor of the *Journal of Semitic Studies*, the *Encyclopedia of Hebrew Language and Linguistics*, the forthcoming *Cambridge Grammar of Biblical Hebrew*, and the series in which this Festschrift has been published, *Cambridge Semitic Languages and Cultures*. These last two works showcase a final dimension of Geoffrey's impact via his commitment to maximum accessibility to the fruits of research, manifested most practically in his establishment of important open-access resources with Open Book Publishers. For example, since the 2020 publication of the inaugural volume in the *Cambridge Semitic Languages and Cultures*, 35 further works have been published, embodying Geoffrey's vision for increased exposure of the Semitic world far beyond the confines of traditional academic audiences, including, and in particular, allowing communities from the Middle East and beyond easy access to work that describes their languages and cultures.

When it comes to post-doctoral researchers working with Geoffrey on collaborative projects, he has regularly encouraged and facilitated their own research outputs. And he has shown flexibility and support when they have been offered career upgrades midway through projects. More generally, whether formally or informally, he has worked hard to support, fund, and lobby on behalf of early-career scholars near and far in search of post-docs and permanent positions. Despite this success and the practical benefit that so many have derived therefrom, he has

often admitted—a fact verified by Colette—to losing sleep over his inability to do more.

Geoffrey has also been a model colleague. Again, despite feeling comfortable in his own company, Geoffrey has worked to cultivate friendly relationships with scholars the world over and has been accessible to colleagues and students at all levels.

4.0. Structure of the Festschrift

In line with Geoffrey's commitment to the maximally accessible dissemination of research, this *Festschrift* has been published in both open-access digital editions and affordable printed formats. Due to the number of contributions, their length, and the variety in their subject matter, they are divided into two volumes, with each volume further subdivided into two sections. The volumes and sections are topical and broadly chronological. Volume 1, section A, is dedicated to contributions on Hebrew, ranging from biblical to modern. Volume 1, section B, contains articles on comparative Semitic philology and linguistics and on the Semitic languages more broadly. Volume 2, section A, is devoted to contributions dealing with the medieval and late pre-modern periods, including the Cairo Geniza, grammatical traditions, and Judaeo-Arabic. Volume 2, section B, is reserved for studies on Neo-Aramaic. A few contributions did not lend themselves to straightforward classification according to this scheme. The editors beg contributor and reader indulgence.

Contributors were given a 6000-word limit. Adherence was predictably erratic. Some contributors endeavoured from the start to follow the guidelines; others willingly shortened their

pieces upon request; for still others, various factors made reduction impossible and/or undesirable; and there were even some who felt the need to lengthen their articles during the editorial process! The editors erred on the side of leniency. While this may be controversial, it is fitting in a collection of studies dedicated to Geoffrey, who in his capacity as General Editor of the *Encyclopedia of Hebrew Language and Literature (EHLL)* (Brill, 2013), was also obliged to deal with entries exceeding word limits. This, along with other idiosyncratic authorial demands, he consistently handled with consummate editorial largesse. Indeed, it is a little-known irony that *EHLL*'s entry on 'Shewa', written by Geoffrey himself, far overshot the meagre word limit allotted to it by the editors: much ado about nothing indeed!

5.0. Humorous Anecdotes about 'the Great Khan'

It is not all rigorous study when it comes to Geoffrey. He has also fostered an atmosphere of light-hearted collegiality. A past cohort of Geoffrey's PhD students affectionately referred to him among themselves as 'the Great Khan'. Indeed, an endearing quality of Geoffrey's is the willingness to laugh at himself, especially at stories told about him. Festschrift co-editor Ben Outhwaite, current Director of Cambridge University Library's Genizah Research Unit, was in the second year of his BA at Cambridge in (what was then called) the Faculty of Oriental Studies (today's Faculty of Asian and Middle Eastern Studies) when Geoffrey was appointed Lecturer. Ben recounts a few anecdotes.

5.1. Misled by the Fathers

I was one year into a Hebrew degree, having learned Biblical Hebrew from the Revd Prof. John Emerton, the Revd John Snaith and, fortunately, Meira Polliack, when Geoffrey turned up as the new guy in the Faculty of Oriental Studies. He taught me Samuel (I think...) and, definitely, Targum of Samuel.

The first class was just me and him (there were as few students then as now), and he began with “So you’ve got a year of Hebrew.” “Yes,” I said (proudly, as I was top of the class...), “And so you know that *qamets* is a long vowel and *pataḥ* a short vowel.” “Yes <inward yawn>, I know all that” (I was very hard working back then). “Well, it’s all rubbish. If you look at the manuscripts of the Geniza—grammatical texts and transcriptions—you’ll see exactly how the Tiberian vowels were pronounced.”

Silence, as Ben is stunned and blown away. Who is this prodigy? Have I been misled by the Reverend fathers? (I had my suspicions...)

5.2. Exam Prep

Some months later (maybe a year), and we’re doing Aramaic (biblical) and Targum. Every time I come to the lecture, Geoffrey is just printing his notes off, having moments ago finished them. Seeing a teacher in Hebrew at the Faculty with a computer then (or in the faculty after lunch AND awake) was a rarity for a start. He launches into BA, and pretty soon he is sketching out a Neo-Aramaic verbal paradigm on the white board and introducing me to the geography of northern Iraq. Similarly when we get to Targum. I reckon I could talk to the Assyrians at this point. By the end of term, we are still around Samuel ch. 2, and we have to get to 11. Knowing I live in Cambridge, he suggests we meet

in the first week of the holiday and we'll have a couple of mammoth sessions to do the remaining nine chapters. I still have my notes from this time. First page: neat notes on the emphatic, rare vocab, etc. Skip forward a few pages, and about 3 hours later, my notes consist of one long squiggle the full length of the page as I've lost the ability to write. When we hit chapter 9, verse something, on our second session, Geoffrey abruptly stops. That's enough for the exam, he declares. I then knew to revise the last few verses we'd covered with particular care.

5.3. A Hazard behind the Wheel

Or the time we were driving back from a board meeting in the Rylands (GK was driving), and I made the mistake of asking him on the motorway about the nature of *tsere*. He got so engrossed in the discussion that it was a few minutes before the beeping of all the cars behind and around us made him realise he was tootling along the middle lane at 15mph!

6.0. Acknowledgements

I would first like to thank the Festschrift's co-editors, Magdalen, Nadia, Janet, Eleanor, and Ben, for serving as area editors, and Magdalen, especially, for her initiative in proposing the project all the way back in 2021 and, in addition to her area editor duties, undertaking the bulk of the logistics and communications by filling the central role of project secretary, all during an especially trying time. Particular thanks also to the series editors and to Rupert Gatti, Alessandra Tosi, and the publishing team at OBP, who were happy not only to publish the Festschrift as part of the *Cambridge Semitic Languages and Cultures* series, but also to keep

it a secret from the series's General Editor. Anne Burberry helped with consistency checking and performed the indexing. Paul Moore helpfully reviewed several contributions on short notice. I am grateful to my Hebrew Division colleagues in the Faculty of Asian and Middle Eastern Studies, Yaron Peleg, Ben Kantor, and Michael Rand (z"l), as well as to the Faculty's Finance Officer, Yuni, for their flexibility and creativity in the (totally above-board) routing of monies to fund the project out of Geoffrey's sight. I wish also to thank Wiktor Gębski, who took up the role of event planner for the Faculty Reception and Trinity College Dinner. Gratitude is also due to the contributors, who were willing both to adhere (mostly) to formatting guidelines and to wait patiently (mostly) the four years it has taken to prepare the publication—all the while communicating pleasantly and respectfully with the editors. Most also furnished peer reviews, some multiple. Many thanks, also, to Colette Khan, for her support and fact checking, and to her and to Geoffrey's family, for ensuring Geoffrey stay in town for the presentation of this *Festschrift*. Thank you, also, to the editors' and contributors' partners and families, for whom their loved one's participation no doubt involved some sacrifice.

And, of course, this *Festschrift* would not exist were it not for the inspiring demeanour and accomplishments of its honouree, whose intellect, wisdom, hard work, and care have enriched so many of our lives.

7.0. Concluding Dedication

As Geoffrey's 42-year-long period of paid academic employment in Cambridge comes to an end, one can only speculate as to the nature of his future unpaid activities. Doubtless more time with grandchildren and less time in administrative duties. It bears mentioning that Geoffrey need not have retired this year. University policy changed to allow up to two more years. But Geoffrey has been keen both to make way for others to move up and to divest himself of paperwork and meetings.

But how much else will change? The last few years have seen Geoffrey stop taking on students and forgo applying for the research grants he was so adept at capturing. His students have wrapped up their studies and he and his research teams are working hard to finish their projects. While this is gradually resulting in the creation of a Geoffrey-shaped gap, it is comforting to think that he will still be active and available, hopefully for many years to come. Indeed, as prolific a scholar as Geoffrey has been while burdened with formal academic and administrative responsibilities, one wonders if he might be even more fruitful in retirement.

Whatever the future holds, it is with great admiration and appreciation that we dedicate this Festschrift to Geoffrey Khan, wishing him continued involvement in the scholarly and non-scholarly pursuits he so loves and for which he is so loved. Geoffrey, you will be missed, but, I think, also oft invited back. So please don't spend too much of your free time off doing fieldwork, language survey, or cooking classes!

Aaron D. Hornkohl,
on behalf of the Editors,
Girton, February 2025

VOLUME I:
HEBREW, COMPARATIVE SEMITICS,
AND THE SEMITIC LANGUAGES



Carpet page of the Leningrad Codex (Firkovich B19a, fol. 474a); photographer: unknown; public domain

A. HEBREW

GEOFFREY KHAN'S CONTRIBUTION TO THE PROBLEM OF BIBLICAL HEBREW CONSECUTIVE *WEQAṬAL*

Bo Isaksson

The *weqaṭal* clause-type plays a major role in the system of consecutive tenses (Notarius 2013, 22; Isaksson 2021, 201–4). While *wayyiqṭol* in the most recent research stands out as a relatively transparent clause-type in comparative Semitic perspective,¹ *weqaṭal* and its alternation with the imperfective/future long *yiqṭol* is commonly regarded as inexplicable. How is it that *weqaṭal* is not a past tense/perfective formation like *qaṭal*, but instead expresses future and habitual meanings?²

¹ See, e.g., Geoffrey Khan's recent research (2021a, 319–40). The jussive *wa-yiqṭol* and past perfective *wa-yiqṭol*, both with short *yiqṭol*, are homonymous clause-types (Khan 2020, I:534). They are inherited from Proto-Semitic (Baranowski 2016b; Huehnergard and Pat-El 2019, 7, 9; Hornkohl 2019, 556; Isaksson 2021, 209).

² Khan has shown that *shewa* was pronounced [a], and that the gemination behind *dagesh forte* in *wayyiqṭol* is a Second Temple innovation in the reading tradition. Accordingly, I henceforth term the consecutive tenses *wa-qaṭal* and *wa(y)-yiqṭol*, respectively (see Khan 2020, I:534; Isaksson 2021, 213 fn. 32). I will avoid calling *wa-qaṭal* and *wa(y)-yiqṭol*

This is a question that Khan endeavours to answer in a recent article (Khan 2021a). In the present article I will critically evaluate Khan's study on the origin of Biblical Hebrew (BH) *wa-qatal*. Does Khan's study solve the enigma of *wa-qatal* or not?

Khan's argumentation has two foundation stones:

- (1) Typological parallels of *wa-qatal* in Northeastern Neo-Aramaic (NENA) dialects, especially a form with an origin as active participle: *bət-qatəl*.
- (2) The theory of constructions by Joan Bybee (2010; 2015)

I start with Khan's parallels of *wa-qatal* in NENA (§1.0), then I proceed with Khan's application of Bybee's construction theory to *wa-qatal* (§2.0). Finally, I summarise the scholarly outcome of Khan's article concerning *wa-qatal* (§3.1), express some of my hesitations (§3.2), and make some suggestions for future research (§3.3).

1.0. Khan's Typological Parallels in Northeastern Neo-Aramaic

A central concept for Khan is 'discourse dependency'. It is mainly defined by examples from NENA, discussed in another recent article (Khan 2021b). In his view, the NENA 'subjunctive' *bət-qatəl* is a typological parallel to both the narrative *wa(y)-yiqtol* and future/habitual *wa-qatal*. Their semantic relation to the preceding clause is one of 'discourse dependency'. *Bət-qatəl* is derived from

'tenses'; they are clause-types. I will also avoid calling them 'consecutive', since a more appropriate concept is 'discourse continuity' (connected with the clausal pattern *wa-VERB*, Isaksson 2021, 217ff.).

an earlier active participle *qatəl*. It is occasionally used in narrative, and then often describes customs or habitual actions. An example is:

- (1) Neo-Aramaic (Barwar dialect B16:18): *bət-qatəl* encodes a custom with past reference

<i>qam-šàwma</i>	<i>ʾíθ</i>	<i>xošéḇə</i>	<i>bnàθa</i>
before-fast	there.is	Sunday.of	girls
<i>bnáθa</i>	<i>kúlla</i>	<i>ṭṭ-azí-wa</i>	<i>bēθa</i>
girls	all	FUT-go.SBJV.3PL-PST	home
<i>b-šaqlí-wa</i>	<i>ʾixála</i>	<i>mən-dáwwa</i>	<i>dáwwa</i>
FUT-take.SBJV.3PL-PST	food	from-this.OBL	this.OBL
<i>dáwwa</i>	<i>ṭ-azí-wa</i>	<i>gu-xa-tùra</i>	
this.OBL	FUT-go.SBJV.3PL-PST	in-a-mountain	
<i>ṭ-atwì-wa</i>	<i>ṭ-axlì-wa</i>	<i>b-šatì-wa</i>	
FUT-come.SBJV-3PL-PST	FUT-eat.SBJV.3PL-PST	FUT-drink.SBJV-PST	

‘Before the fast (of Lent) was Girls’ Sunday. All the girls **went** home, **took** food from here and from there, then **went** to the mountains, they **sat**, **ate** and **drank**.’ (Khan 2021b, 152)

But *bət-qatəl* can also be used as a future form, as is shown in (2).

- (2) Neo-Aramaic (Barwar dialect A1:17): *bət-qatəl* as predictive future

<i>b-nayàs-li</i>	<i>ṭ-axəl-li</i>
FUT-bite.SBJV.3MS-1MS	FUT-eat.SBJV.3MS-1MS

‘He will bite me. He will eat me.’ (Khan 2021b, 148)

An interesting feature of *bət-qatəl* is its use in subordinate clauses, as is shown in (3).

- (3) Neo-Aramaic (Barwar dialect A15:5): *bət-qatəl* as subjunctive in narration

ṣəlye = le[|] ta-t-ʾázəl ʾürxa.[|]
 go.PTCP = COP.3MS to-COMP-go.SBJV.3MS road

‘He went down in order to set off on the road.’ (Khan 2021b, 177)

Bət-qatəl is also sporadically used in events that are dependent on what precedes. Specifically, *bət-qatəl* may express an apodosis in NENA, as in (4).

- (4) Neo-Aramaic (Barwar dialect A23:5): *bət-qatəl* as apodosis

ʾən-kpìn-ni,[|] t-axlən-ne.[|]
 if-hunger.PFV-1S FUT-eat.SBJV.1MS-3MS

‘If I am hungry, I shall eat it.’ (Khan 2021b, 149)

The various functions of *bət-qatəl*—customary action, habituality, predictive future—inspire Khan to a comparison with the BH *wa-qatal*. Khan suggests that, since *wa-qatal* is attested as an apodosis in the most ancient Northwest Semitic texts (Amarna Canaanite, Ugaritic), it is reasonable also to regard *wa-qatal* as a clause-type with an origin as apodosis, and to hold that *wa-qatal* developed future and habitual meanings from its original apodosis functions. In those ancient apodoses, *wa-qatal* could have future time reference (Smith 1991, 6–15; Sivan 1998, 92; 2001, 221; Tropper 2012, 716ff.; Renz 2016, 442; Baranowski 2016a, 173–78). Example (5) shows a *wa-qatal* apodosis in Ugaritic.

- (5) *w hm ḥt ʾl w lʾikt ʾmk*

‘and if the Hittite has attacked, then I will send [*wa-laʾiktū*] (a letter) to you....’ (KTU 2.30, 17–18; quoted from Sivan 1998, 92)

It seems that in the early stages of Northwest Semitic the initial *wa-* before a futural *qatal* was optional in the function of apodosis. In Amarna Canaanite there are many examples of $\emptyset$ -*qatal* with future time reference, as in (6) (Baranowski 2016a, 173–78).

- (6) ²²ù šum-ma *ia-a-nu* ERÍN.MEŠ pi-ṭa-tu₄ ²³pa-ṭa-ra-at KUR
LUGAL-ri a-na LÚ-MEŠ ²⁴\ ḥa-pí-ri

‘If **there are no** archers, the land of the king **will desert** to the ‘Apiru.’ (EA 290:22–24; Baranowski 2016a, 174, his emphasis)

Since the NENA *bət-qatal* is a subjunctive according to Khan, he suggests that *wa-qatal* is also a subjunctive, originally used in close dependence on a protasis in a conditional relationship.³

In order to understand the development of the BH *wa-qatal* from its original function as apodosis, Khan applies Bybee’s construction theory to *wa-qatal*.

³ I am not fully convinced that the linguistic literature to which Khan refers confirms his concept ‘discourse dependency’, even if taken as an entirely semantic, not syntactic, notion (Khan 2021a, 341). Khan’s main reference is Cristofaro (2003), but, as far as I can see, Cristofaro does not support the idea that a *wa-qatal* apodosis has an historical origin “in subordinate constructions” (Khan 2021a, 340). Cristofaro’s central concept seems to be ‘assertiveness’ (2003, 32): which clause in a conditional linking is asserted? The answer should be the apodosis. Cristofaro’s definition of subordination seems to suggest that an apodosis *wa-qatal* is not a subordinate clause.

2.0. Khan's Application of Bybee's Construction Theory

With Bybee's construction theory as theoretical foundation, Khan sets out to reconstruct how the original *wa-qatal* in apodosis position could develop into a general clause for future and habitual action in BH.

Khan's answer is that *wa-qatal* is a 'construction' in Bybee's sense. The original apodosis *wa-qatal* was 'schematised' by step-by-step extensions of its meanings. This terminology deserves brief elaboration.

Bybee begins by defining 'chunking': "When two or more words are often used together, they also develop a sequential relation" (Bybee 2010, 25, 33). 'Constructions' are sequential chunks "that sometimes have special meanings and other properties" (Bybee 2010, 36). High frequency is determinative. The more a sequence of morphemes or words is used together, the stronger the sequence will be perceived as a unit and the less associated with its component parts. This process leads to increasing autonomy of the construction (Bybee 2010, 36, 48).

Example: the English phrase *be going to* is a chunk, which, because of its frequency, was extended in usage and developed into a general future morpheme *gonna*.

Be going to is a construction, with many extensional steps that widen its applicability. It is a construction, since the futural/intentional meaning cannot be deduced from the parts of the construction, *be + going + to*. The original construction was SUBJECT + BE + *going to* + VERB, where the capitalised items are

schematic. This construction is still in living usage (Bybee 2010, 96; 2015, 124).

Gonna is a grammatical morpheme, which has undergone grammaticalisation from the construction *be going to*. It is a future auxiliary. In the case of *gonna*, a construction has acquired grammatical meaning and a phonetically reduced form (Bybee 2010, 106; 2015, 268). At the same time *be going to* also persists as a construction with its analysable elements and futural meaning.

Khan's idea is that BH *wa-qatal* was a chunk with high frequency that became a construction. "Constructions often contain explicit lexical material," such as the conjunction *wa-* in *wa-qatal*, and "have a special form, meaning and pragmatic effect that cannot be captured by more general principles of grammar" (Bybee 2010, 76ff.). Since *wa-qatal* is a construction, the meanings of *wa-qatal* cannot be deduced from the separate elements *wa* + *qatal*. A grammatical analysis of *wa-* and *qatal* separately does not help. This is one of the reasons BH scholarship has found *wa-qatal* enigmatic. In the construction, *wa-* is the invariant part and *qatal* is schematic with multiple forms: *wa-QATAL*.⁴

This is a significant theoretical advancement and an excellent application of modern linguistic theory to an enigma in BH.⁵

An established construction *wa-qatal* with future and habitual meanings does not seem to be attested in Archaic Hebrew

⁴ Khan nowhere says this explicitly, as far as I can see, but it is an inevitable conclusion.

⁵ A forerunner to this idea is found in Smith (1991, 8): "It would appear that the future uses of **qatal* in BH conditional sentences were extended to **qatal* in independent clauses in the form of the 'converted perfect'."

poetry (Notarius 2013, 288ff., 304). This is an important methodological observation. *Wa-qaṭal* as a construction outside the apodosis domain must have developed in a diachronic stage close to, or within, Classical Biblical Hebrew (CBH).⁶ If we seek examples of the successive extensions of the *wa-qaṭal* construction, we should preferably search for traces of the steps within CBH texts. The construction *wa-qaṭal* is primarily a Classical Hebrew innovation.⁷

The idea of *wa-qaṭal* as a construction in Bybee's sense necessarily leads to a new understanding of the historical origin of *wa-qaṭal* as a clause-type. *Wa-qaṭal* is not a 'tense'. Though a construction, it is still a clause, and this clause has a normal connective *wa-* (cf. Isaksson 2021, 218ff.). The retained connective *wa-* is probably the reason why *wa-qaṭal* did not become a verbal morpheme (Khan 2021a, 342). There is no phonetic reduction in *wa-qaṭal*, as there is, for example, in the case of *gonna*.

The construction *wa-qaṭal* was generalised in several steps. Khan outlines some of the possible extensions. As many scholars have assumed, the starting point was a conditional relationship.

- (7) אִם-אֶמְצָא בְּסֹדֶם חֲמִשִּׁים צְדִיקִים בְּתוֹךְ הָעִיר וְנִשְׁאַתִּי לְכָל-הַמָּקוֹם בְּעִבְיָרָם:
'If I find at Sodom fifty righteous in the city, **then I will spare** the whole place for their sake.' (Gen. 18.26)⁸

⁶ For the concept of *domain*, see Cohen (2014).

⁷ For corresponding uses of *wa-qaṭal* in pre-exilic Hebrew inscriptions, see Gogel (1998, 77ff.); Schüle (2000, 137–39); Renz (2016).

⁸ Cf. Khan (2021a, 308). I have replaced Khan's example with another from my corpus.

Example (7) illustrates the proposed origin of *wa-qatal* as a construction. This type of linking with *wa-qatal* as apodosis has typological parallels in early Northwest Semitic. There is a contingency in the semantics of the linking: in a logical sense, *wa-qatal* ‘depends’ on the truth-value of the protasis. For Khan this is an important observation and a reason for application of the concept ‘discourse dependency’ to *wa-qatal*.

The contingency fades away when we consider the first logical extension of the *wa-qatal* construction (Khan 2021a, 312): a *wa-qatal* is allowed to follow not only a protasis, but also a temporal clause, as in (8).

- (8) וְהָיָה כִּי־יִרְאוּ אֶתְךָ הַמִּצְרִים וְאָמְרוּ אֲשֶׁתְּךָ זֹאת וְהָרְגוּ אֹתִי וְאַתָּה יָחִי:
 ‘When the Egyptians see you, **they will say** “This is his wife,” **and they will kill me** and let you live.’ (Gen. 12.12; Khan 2021a, 309)

The generalisation exemplified in (8) is a case of *schematisation*: the functional range of *wa-qatal* is extended to follow a temporal clause. In a temporal clause, events are not just contingent, as they are in a conditional apodosis, but are presupposed to take place (Khan 2021a, 311).

The schematisation takes a step further when the preceding clause is not subordinated, but constitutes a main clause, as in (9).

- (9) וְקִוְיָ וְדִרְדָּר תִּצְמַח לְךָ וְאַכְלָתָ אֶת־עֵשֶׂב הַשָּׂדֶה:
 ‘It will yield you brambles and thistles, **and you will eat** the produce of the land.’ (Gen. 3.18)⁹

⁹ I prefer this clear example to the one given by Khan (2021a, 309), namely 1 Sam. 17.32.

In (9) the *wa-qaṭal* clause has future time reference, as in (7) and (8), but it is now coordinated with a long *yiqṭol(u)* main clause.

Khan designates the relation between the two clauses as one of semantic ‘dependence’ (Khan 2021a, 341), but I would suggest that it is more accurate to speak of semantic coordination. None of the clauses is semantically subordinate to the other. The clauses are of ‘equal status’, using terms taken from Halliday (2004, 374, 489), and both are ‘assertive’ in Cristofaro’s (2003, 33ff.) terminology.

Already at this stage of extension of the functional range of *wa-qaṭal* we observe alternation between the long *yiqṭol(u)* and the *wa-qaṭal* construction, which is one of the fundamental features of the system of consecutive tenses.¹⁰

The next step outlined by Khan is that *wa-qaṭal* is cognitively—but not temporally—bound to the preceding clause, which may express no more than a state of affairs, as in (10).

- (10) רק איִדְיָרָאֵת אֱלֹהִים בַּמָּקוֹם הַזֶּה וְהִרְגִּינִי עַל־דְּבַר אִשְׁתִּי:
 ‘But there is no fear of God in this place **and they will kill me** because of my wife.’ (Gen. 20.11; Khan 2021a, 309, 312)

The first clause in (10) is verbless and refers to the general situation of the speaker. Khan remarks that the linking is analogous to a topic-comment relationship, which is similar to conditional

¹⁰ This is not something Khan discusses, but, as will be argued further on in this article, the connection between *yiqṭol(u)* and *wa-qaṭal* is fundamental from the start of the construction’s development.

linking.¹¹ The verbless clause can also be interpreted as a state that constitutes the reason for the action in the *wa-qatal* clause: ‘therefore they will kill me’. The fundamental point here is the steps of schematisation taken from the original conditional linking to one where the preceding verbless clause may describe a topic or give a reason for *wa-qatal*. The construction *wa-qatal* has been extended to relate to a state of affairs that serves as the reason for Abraham’s prediction.

A further step in the process of schematisation might be when *wa-qatal* can follow left-dislocation, which Khan analyses as a topic after which *wa-qatal* follows as comment, as in (11).

- (11) וְהַנְשֹׂאִים בְּכֶם וְהַבְּאִתִּי מֵרֶךְ בְּלִבְכֶם בְּאַרְצֵת אֹיְבֵיהֶם
 ‘As for those of you who may be left—I will bring weakness
 into their hearts in the lands of their enemies...’ (Lev.
 26.36; Khan 2021a, 309, 312)

Topics may be full clauses, but in (11) the topic is just a noun phrase, as is the case also with left-dislocation, and *wa-qatal* follows as comment with anaphoric pronominal suffixes. It is reasonable to state, as Khan does, that *wa-qatal* in this case expresses posteriority, since the left-dislocation with its *nif'al* participle, implies the existence of the people at speech time, and that after that time God will execute his plan on them.

¹¹ A *topic* “represents an entity the existence of which is agreed upon by the speaker and his audience. As such, it constitutes the framework which has been selected for the following discourse” (Haiman 1978, 585).

A further step in schematisation is encountered when *wa-qaṭal* partakes in a complex background description with past habitual action, as in (12).

- (12) וַאֲדַעְלָה מִן־הָאָרֶץ וְהִשְׁקָה אֶת־כָּל־פְּנֵי־הָאָדָמָה:
 ‘A mist used to go up from the earth **and would water** the whole face of the ground.’ (Gen. 2.6; Khan 2021a, 309, 312ff.)

The first clause, with a long *yiqṭol(u)* (יַעְלֶה), establishes a past habitual action which disrupts the historical main line in the creation story and introduces background description. This is a perfectly normal usage of an imperfective gram with past time reference. The extension of *wa-qaṭal* concerns the semantics: that the *wa-qaṭal* construction is able to describe a past habitual action. In the earlier steps of schematisation *wa-qaṭal* has expressed a future meaning; now it expresses another typical meaning of an imperfective gram, habitual past.

Khan explains the habituality of *wa-qaṭal* as a schematisation of the *conditional* linking. As an argument he refers to his typological parallel *bəṭ-qaṭal* in NENA, which can be used for habitual action (Khan 2021a, 312ff.). On this point it must be remarked that habitual action is practically non-existent in CBH conditional linkings, occurring neither in protases nor apodoses.¹² I will return to the issue later in this article.

¹² There is a general present habitual meaning in the apodosis of Num. 12.6, encoded with a long *yiqṭol(u)*. See further Table 2 below.

A further step in schematisation might be the encoding of past habitual actions in a series of sequential *wa-qatal* clauses, as in (13).

- (13) בִּי מִן־הַבָּאֵר הָהוּא יִשְׁקוּ הָעֶדְרִים וְהָאֵבֶן גְּדֹלָה עַל־פִּי הַבָּאֵר: וְנֹאֲסָפוּ־שָׁמָּה
כָּל־הָעֶדְרִים וְגָלְלוּ אֶת־הָאֵבֶן מֵעַל־פִּי הַבָּאֵר וְהִשְׁקוּ אֶת־הָעֶזְאֵן וְהִשְׁיבוּ אֶת־
הָאֵבֶן עַל־פִּי הַבָּאֵר לְמִקְמָהּ:

‘...because the flocks used to be watered from that well—the stone over the mouth of the well was large—³and all the flocks **would gather** there, **and they would roll** the stone from the mouth of the well, **and they would water** the sheep, **and they put back** the stone in its place on the mouth of the well.’ (Gen. 29.2–3; Khan 2021a, 309ff., 312ff.)

In (13) a *yiqtol(u)* (יִשְׁקוּ) clause initiates a background description that is continued by four sequential habitual *wa-qatal* clauses.¹³ Khan (2021a, 314) does not mention that the series of habitual *wa-qatal* clauses in (13) comes after an initial *yiqtol(u)* with past habitual meaning. He instead explains *wa-qatal*’s habituality as due to its semantic similarity to the ‘dependence’ of an apodosis.

A further step of schematisation is illustrated in (14), where *wa-qatal* clauses continue an active participle clause.

¹³ The habituality of *wa-qatal* in (12) and (13) is semantically distant from the meanings normally found in an apodosis. The conclusion must be that the schematisation of *wa-qatal* has taken many extensional steps when it is used for habitual background.

- (14) שְׂרָפִים עֹמְדִים | מִמַּעַל לוֹ עָשׂ כְּנָפִים שֵׁשׁ כְּנָפִים לְאֶחָד בְּשֵׁתֵימָם | יְכֶסֶה פָּנָיו
וּבְשֵׁתֵימָם יְכֶסֶה רַגְלָיו וּבְשֵׁתֵימָם יְעוֹפֶף: וְקָרָא זֶה אֶל־זֶה וְאָמַר קְדוֹשׁ | קְדוֹשׁ
קְדוֹשׁ יְהוָה צְבָאוֹת מְלֵא כָּל־הָאָרֶץ כְּבוֹדוֹ:
‘Seraphim stood above Him, each having six wings; **with two he covered** his face, and **with two he covered** his feet, and **with two he flew**. And one **would call out** to another **and would say** “Holy, Holy, Holy, is the LORD of hosts. The whole earth is full of His glory.” (Isa. 6.2–3; Khan 2021a, 310, 312ff.)

Like the prophetic dreams in the Joseph story, the prophetic vision in (14) begins with an active participle clause.¹⁴ The Seraphim were standing (שְׂרָפִים עֹמְדִים), and this standing is elaborated with a number of accompanying actions: covering face and feet, flying, calling out, and saying. The actions that accompany the standing are coded with three *yiqtol(u)* (יְכֶסֶה, יְכֶסֶה, יְעוֹפֶף) followed by two *wa-qatal* clauses (וְקָרָא, וְאָמַר). After the past continuous participle both *yiqtol(u)* and *wa-qatal* express past continuity or past habituality. According to Khan, the dependence of the original apodosis in this case has been schematised to a cognitive topical reference point. In my view, it should be enough to observe that the repetitive actions are initiated by a participle and continued with *yiqtol(u)* and *wa-qatal* clauses. When an initial focused constituent (בְּשֵׁתֵימָם) is needed, a *yiqtol(u)* is used; when there is no initial constituent, *wa-qatal* clauses are used instead.

A further step of schematisation is shown in (15), where an independent *wa-qatal* clause expresses a past habitual action.

¹⁴ Gen. 40.17; 41.2, 5, 17–19, 22; cf. also Gen. 28.12f.; Judg. 7.13.

(15) וַעֲלֶה הָאִישׁ הַהוּא מֵעִירוֹ מִיָּמִים | יְמִימָה לְהִשְׁתַּחֲוֹת וּלְזָבַח לַיהוָה צִבְאוֹת
בְּשָׁלָה

‘And this man used to go up from his city yearly to worship and to sacrifice to the Lord of Hosts in Shiloh.’ (1 Sam. 1.3; Khan 2021a, 313ff.)

Khan does not comment on the unusual character of this background clause. In example (15), a *wa-qatal* construction—a continuity clause—disrupts the storyline and starts a background section with habitual action: *wa(y)-yiqtol* + *wa-qatal*.¹⁵ A more common strategy when starting a habitual background complex is to begin with a discourse discontinuity *yiqtol(u)* clause (type *X-yiqtol(u)*, Isaksson 2021, 217ff.), as in (12) and (13), or a *qōṭēl* clause, and continue with *wa-qatal* clauses.¹⁶

3.0. Evaluation of Khan's Contribution to the Problem of *wa-qatal*

3.1. Summary of Achievements

- Khan's application of Bybee's construction theory to the *wa-qatal* clause-type is completely new. Since *wa-qatal* is a construction that has not developed into a verbal morpheme, it is not a 'tense', but a clause-type. The meanings of *wa-qatal* are not a function of its component parts, *wa* + *qatal*.

¹⁵ The storyline *wa(y)-yiqtol* before *wa-qatal* is represented by a bi-clausal (thetic) cleft construction in 1 Sam. 1.2, introduced by *wayhī*, which should probably be analysed as mono-clausal syntax with an initial focus marker *wayhī* (Khan 2019, 15–18).

¹⁶ For *wa-haya* introducing background, see Isaksson (1998).

- The development of *wa-qatal* into a full-blown future and habitual construction took place in several steps, which Bybee calls *schematisations* or *extensions* (of usage and meaning).
- The birth of the *wa-qatal* construction took place in the context of linking between two clauses: PROTASIS + *wa-QATAL*, where the capitalised parts are subject to extension. The *wa-* in the construction is invariable.
- The process that resulted in the *wa-qatal* construction with future and habitual meanings was an internal Classical Hebrew, or at least post-Archaic, development. It is not attested in Archaic Hebrew poetry (Notarius 2013).
- *Wa-qatal* did not develop into a grammatical morpheme, probably because of the initial connective *wa-*, which in all uses has retained its force as a conjunction. As a matter of fact, *wa-qatal* is phonetically unreduced.

3.2. Hesitancies

3.2.1. The Missed Interaction Between *wa-qatal* and *yiqtol(u)*

Khan does not fully acknowledge the close interaction between *wa-qatal* and long *yiqtol(u)* in the process. The long *yiqtol(u)* is an old imperfective formation (Huehnergard and Pat-El 2019, 9), and it is a common phenomenon in the world's languages for habitual meanings to be expressed via imperfective gram (Carlson 2012).¹⁷

¹⁷ Khan (2021a, 313) writes that a “habitual predicate is imperfective in aspect.”

Since the development of *wa-qatal* as a construction is internal, statistics from CBH are relevant.¹⁸ If we search for examples of the successive extensions of the *wa-qatal* construction, we should expect to find traces of such steps in the CBH texts. CBH texts exhibit a great number of conditional linkings. If we scrutinise them, it becomes clear that *yiqtol(u)* clauses dominate in protases, and are also very frequent in apodoses:

Table 1: Statistics of *yiqtol(u)* and *wa-qatal* in protases and apodoses

	Protases	Apodoses
<i>yiqtol(u)</i>	61%	27%
<i>wa-qatal</i>	2.5%	48%
Total in corpus	478	463

The dominant predicate in protases is *yiqtol(u)*, with 61 percent. This means that when an apodosis *wa-qatal* began to develop as a construction, protases with a *yiqtol(u)* predicate had high frequency. From the beginning, the *wa-qatal* construction was most frequently associated with *yiqtol(u)*.

In apodoses, half of the cases start with *wa-qatal*. It is significant that 27 percent have a *yiqtol(u)* predicate. Since the phenomenon ‘*waw* of apodosis’ can be feasible only in the construction *wa-qatal*, the term is unwarranted. The *wa-* in *wa-qatal* is a

¹⁸ All statistics are from my corpus, consisting of the Pentateuch and the book of Judges, see Isaksson (2021, 207). The archaic sections are excluded. In the following I take for granted that statistics from this corpus are also generally relevant for CBH (cf. Joosten 2016, 329), though I am aware that the large sections of legal material in the Pentateuch might make the statistics less than fully representative of the living usage of the classical language.

normal invariable conjunction *wa-* ‘and’ (pace Khan 2021a, 315). In other types of apodoses, not least those with a *yiqtol(u)* predicate, the rule is asyndesis.¹⁹

Since asyndesis is otherwise the rule in a CBH apodosis, the question must be raised as to why *wa-qatal*, and not, for example, *Ø-qatal*, increased in apodosis frequency and became a construction.²⁰ In Amarna Canaanite, a futural apodosis with *qatal* could be preceded by *wa-* or be asyndetic, though the *wa-qatal* clause-type was more frequent (Baranowski 2016a, 173–78). In Ugaritic, a futural *qatal(a)* in apodosis is as a rule syndetic with a proclitic *wa-* (Troppner 2012, 717). This comparative evidence suggests that a *wa-qatal* apodosis with future meaning had already become a chunk, though possibly not a construction, in early Northwest Semitic. There must have been a reason for this strong tendency.

This is a question Khan does not discuss (2021a, 315). To approach an answer, it is necessary to consider the ancient Canaanite usage of *wa-qatal* in modal sequences. As the second or third clause in a modal sequence, *wa-qatal* may occur with future time reference, and in such uses the *wa-* seems necessary: IMP + *wa-*

¹⁹ Of 242 non-*wa-qatal* apodoses in the corpus only five have an initial *wa-*: Gen. 13.9 (2x); Exod. 8.22; Num. 16.22, Judg. 6.13.

²⁰ In my CBH corpus a futural *Ø-qatal* apodosis is extremely rare. The only possible instance is שְׁכַלְתִּי ‘I am/will be bereaved’ (Gen. 43.14), which is syntactically linked to a temporal clause with the conjunction *ka-’āšer*. The other instances of *Ø-qatal* apodoses express anterior (as in Exod. 22.14) or performative meanings (as in Deut. 4.26). On one occasion a *qatal* morpheme in an apodosis expresses future meaning in an archaic oath formula: כִּי אֲמַנְקֶמְתִּי בָכֶם ‘I swear that I won’t stop until I get my revenge on you’ (Judg. 15.7).

qatal + *wa-qatal*, e.g., ‘Kill your leader and then you will be like us and you will be at peace’ (EA 74:23–29, similarly EA 123:33–35; Baranowski 2016a, 162); IMP + *wa-yaqtula* + *wa-qatal*, e.g., ‘Send back word to me, or I will form an alliance with ‘Abdi-Aširta like Yapa-Hadda and Zimrid[d]a so that I stay alive’ (EA 93:9–13; Baranowski 2016a, 164). In a similar way, an apodosis in Amarna Canaanite may consist of the series *wa-yaqtul* + *wa-qatal* + *wa-qatal*, e.g., ‘I will abandon the city and depart and my life will be safe while I do as I please’ (EA 82:41–46) or *wa-yaqtul* + *wa-qatal* (EA 73:11–14; Baranowski 2016a, 174, 176). In the case that *wa-qatal* takes part in a modal series, there seems to be no alternative: a clause within a modal sequence should by default signal discourse continuity.²¹ This ancient *wa-qatal* in a modal sequence with intentional future meaning probably established *wa-qatal*, rather than *Ø-qatal*, as a chunk and a construction in apodosis function in CBH. In this way, CBH *wa-qatal* preserves a more archaic usage of the old resultative *qatal* than does CBH *qatal*, which has developed into a gram for anterior and past perfective meanings. The *wa-qatal* usage in modal series, where *wa-qatal* has a meaning of intentional future, is not a Hebrew innovation. Such a function of *qatal*, which Baranowski (2016a, 162) calls “modal *qatal*” and which occurs only in the *wa-qatal* clause-type, has influenced the frequency of *wa-qatal* as apodosis with future time reference, both in Amarna and in CBH.

²¹ On the iconic discourse continuity of *wa-VERB* constructions see Hornkohl (2019, 555). For *wa-qatal* in CBH modal sequences, see Dallaire (2014, §2.5.2), and later in this article.

3.2.2. A Missed Meaning in CBH Apodoses

Khan does not note that obligation is by far the most frequent meaning in CBH apodoses. This is a meaning that is found also in the imperfective *yaqtulu* in Amarna Canaanite. Baranowski regards it “a pragmatic use of its future meaning” (2016a, 150).

Table 2. Meanings in *yiqtol(u)* and *wa-qatal* apodoses in the corpus²²

	<i>yiqtol(u)</i> in apodosis	<i>wa-qatal</i> as apodosis
Obligation	78%	67%
Future	16%	31%
Permission	4%	1.5%
Habitual present	1%	—
Ability	1%	0.5%
Counterfactual	—	0.5% ²³
Total number	123	221

If we want to discuss the development of *wa-qatal* on the basis of its use in apodoses, the obligational meaning must be recognised. As can be seen in Table 2, modal obligation is by far the most frequent meaning of an apodosis in CBH.

Also in this case (obligation), it is necessary to recognise the influence of the long *yiqtol(u)*. The table indicates that there seems to be a strong semantic correlation between *wa-qatal* as apodosis and *yiqtol(u)* as apodosis. The internal Hebrew construction *wa-qatal* was from the beginning semantically conditioned by the imperfective meanings of *yiqtol(u)*.

²² Temporal linkings are not included, since the temporal clause expresses something expected, not a condition. My statistics concerning conditional sentences in the corpus are fairly complete, which means that the percentage numbers are significant.

²³ Judg. 16.17. Brockelmann (1908–13, II, §432): “Irreal gedachte Bedingungen.”

Table 2 also shows that habitual meanings are extremely rare in a conditional linking. Habituality is never expressed by a *wa-qatāl* apodosis in the corpus. Khan's argument that a *wa-qatāl* in 'dependence' position (as apodosis) easily extends to habitual meaning is not plausible in the light of Table 2. Habitual meanings are not easily acquired at all in conditional linkings.

The habitual meanings of *wa-qatāl* are found outside the realm of conditional constructions in CBH, and in nearly all examples of (past) habitual *wa-qatāl* there is a preceding habitual *yiqṭol(u)* clause. This shows that early in the schematisation of *wa-qatāl*, it was perceived, and used, as a simple-clause (a *wa-VERB* type) substitute for *yiqṭol(u)* in the absence of an initial focused element or negation (Hornkohl 2019, 555). Crosslinguistically, habituality is a normal meaning for an imperfective formation like *yiqṭol(u)*. My conclusion is that *yiqṭol(u)* has heavily influenced the meanings of the construction *wa-qatāl* during its step-by-step development: obligation, future, habituality.²⁴

²⁴ In spite of Khan's significant contribution to our understanding of *wa-qatāl*, and though conscious of my lack of expertise in NENA dialects, I am not convinced that *bət-qatāl* in NENA is a relevant typological parallel to *wa-qatāl*. My main arguments against this supposition are: (1) Khan regards *bət-qatāl* as a typological parallel to both narrative *wa(y)-yiqṭol* and future *wa-qatāl*, which is unconvincing, because, in such a case, CBH would have had only one *wa-VERB* clause-type, and this could function in all TAM contexts; but in fact CBH had two *wa-VERB* clause-types, *wa(y)-yiqṭol* and *wa-qatāl*, functioning in different TAM contexts; (2) *bət-qatāl* lacks a connective, which is attached to both *wa-qatāl* and *wa(y)-yiqṭol*; (3) Khan regards *wa(y)-yiqṭol*, like *bət-qatāl*, a construction in Bybee's sense, but it is not: the meanings of *wa(y)-yiqṭol* can be de-

3.3. A Suggestion for Future Research

It is commonly accepted today that the West Semitic *qatal(a)* conjugation has developed from a resultative construction (Huehnergard 1987, 225, 227; Cook 2012, 203; Huehnergard and Pat-El 2019, 7, 18 fn. 6). Such constructions “predicates the **condition** or **state** that is the result of the action of the verb” (Huehnergard 2011, 221, his emphasis).

Qatal’s prototypical meaning—expressing the result of a previous action or state—made *wa-qatal* a natural choice for the expression of an apodosis. To this must be added the late Bronze age Northwest Semitic custom of using *wa-qatal* in modal sequences with final meaning of (Renz 2016, §2.1.2.3.4; 649 fn. 267).

It is probable, considering the comparative Northwest Semitic evidence, that *wa-qatal* as apodosis was a chunk already in the Late Bronze Age languages. Though we might also expect $\emptyset$ -*qatal* with its prototypical resultative meaning to be used as apodosis, this asyndetic clause-type was used only occasionally as apodosis in Amarna and seemingly not at all in Ugaritic. Already in this early stage, both Ugaritic and Amarna Canaanite attest to the use of *wa-qatal* in modal sequences with prototypical result and final meanings. In such domains only *wa-qatal*, the continuity alternative (type *wa-VERB*), is attested, not $\emptyset$ -*qatal*.

duced from its component parts: *wa-* which is a normal Semitic connective, and the short ‘preterite’ *yiqtol*, which is inherited from Proto-Semitic (Baranowski 2016b; Isaksson 2021; for the archaic poetry: Notarius 2013, 78, 280; Khan 2021a, 320).

The diachronic semantic development of *wa-qatal* in Iron Age Hebrew was one of bleaching: from a clause expressing finality, to a clause that continues a volitive (imperative or jussive) with further instructions. Also without an initial volitive, *wa-qatal* can continue *yiqtol(u)*, not only in instructions (obligational meaning), but in all imperfective functions. Unfortunately, the diachronic steps in the semantic bleaching of *wa-qatal* are poorly attested in the meagre material of the pre-exilic Hebrew inscriptions (Renz 2016, §5.2).²⁵ However, the expected range of meanings of *wa-qatal* in modal sequences can be detected in the richer CBH textual material.

As apodosis *wa-qatal* was gradually extended to other types of environments, (1) with extended range of the preceding clause-type: subordinate clauses (temporal and causal) and, gradually, main clauses before *wa-qatal*; but also (2) with extended meanings of *wa-qatal* itself, from result to plain future and obligation.

Example (16) illustrates the result meaning of *wa-qatal* in CBH, often at the end of a modal sequence.

(16) $\emptyset$ -IMP + *wa-qatal* + *wa-qatal*

הַקָּרֵב אֶת־מִטָּה לִּי וְהַעֲמִדְתָּ אֹתוֹ לִפְנֵי אֶהֱרֹן הַכֹּהֵן וְשִׁרְתּוֹ אִתּוֹ:

‘Bring the tribe of Levi and station them in the presence of Aaron the priest, **so that they may serve** him.’ (Num. 3.6; Levine 1993, 152)

²⁵ Renz’ note 308 does not support that *wa-qatal* is attested with a sense of finality in the Hebrew pre-exilic inscriptions; his example of a final meaning is often otherwise interpreted: Arad 24:14–15 (Renz 2016, 659 fn. 308, §4.2.1.2; cf. Dobbs-Allsopp et al. 2005, 49).

In (16) the first *wa-qatal* in the sequence is an additional instruction (obligation), while the second has final force.²⁶

The later usage of *wa-qatal* as an additional instruction after the volitive in modal sequences is much more frequent in CBH. In such cases it carries connotations different from the initial volitive (Revell 1989, 23). The *wa-qatal* clause is not perceived as subordinate, but there remains in many cases a sense of intention, expressing the goal of the action in the initial volitive(s). An example is (17):

(17) Ø-O.noun-IMP + *wa-qatal* + *wa-qatal* + *wa-qatal*

כָּל־הַחַיָּה אֲשֶׁר־אַתָּה מְכַל־בָּשָׂר בְּעוֹף וּבַבְּהֵמָה וּבְכָל־הָרֶמֶשׂ הָרֶמֶשׂ עַל־
הָאָרֶץ הוֹצֵא אִתָּךְ וְשָׂרְצוּ בָאָרֶץ וּפָרוּ וְרָבוּ עַל־הָאָרֶץ:

‘Bring out with you every living thing that is with you of all flesh—birds and animals and every creeping thing that creeps on the earth—they shall swarm on the earth, and be fruitful and multiply on the earth.’ (Gen. 8.17)

In (17) the *wa-qatal* clauses follow a pausal stop and express the intended result of the command in the imperative. They cannot be analysed as additional instructions.²⁷

²⁶ Other examples of *wa-qatal* expressing finality in modal sequences: Exod. 8.12; 18.19; 19.23; Num. 4.19 (Garr 1998, lxxxiii: result from a preceding situation); 7.5; 8.7; Judg. 16.5.

²⁷ Other examples of *wa-qatal* clauses that have a nuance of intention in modal series: Gen. 1.14 (Dallaire 2014, 147, purpose); 6.21; 19.2; 30.32; 31.44; 43.14; 45.9b–10; 45.19; 47.29; 47.30; Exod. 3.16; 4.21; 8.12; 18.19, 22; 19.23 (intended result); 19.24; 30.34–35; Num. 3.6 (first *wa-qatal*), 41; Deut. 28.8, 22; Judg. 11.37; 16.5; 19.13 (Dallaire 2014, 147); 20.32.

Baranowski observes a relative rarity of *wa-qatal* in modal sequences in Amarna (2016a, 160). This is not the case in CBH, where *wa-qatal* is frequent. And while the choice of *wa-qatal* in a modal sequence in Amarna may be due to the lexically stative meaning of the verbs (Baranowski 2016a, 162), in CBH all lexical types are represented. In this respect, the frequency of *wa-qatal* in modal sequences and its wide semantic range represent an extension compared to ancient Canaanite, and the latest steps of the same development can be detected in the pre-exilic Hebrew inscriptions (Renz 2016, 649).

My hypothesis is that the preponderance of *wa-qatal* as against $\emptyset$ -*qatal* as first clause in apodoses is due to the influence from its use in modal sequences, where *wa-* before *qatal* was preferred, because *wa-qatal* was a discourse continuity clause (type *wa-VERB*; Isaksson 2024, 395–461). The construction *wa-qatal* is specifically a clause-type without negation and without initial focused element, the Semitic unmarked declarative word order (Pat-El 2019, 86). If a negated clause is needed, or a constituent is to be inserted before the verb in the coding of the apodosis, another clause-type must be used in CBH. As Table 1 indicates, the substitute predicate was a *yiqtol(u)* morpheme in CBH. When the apodosis was negated, most frequently *lō yiqtol(u)* was used, and as soon as a focused constituent, like an object noun phrase, was inserted before the verb, *X-yiqtol(u)* was used instead of *wa-qatal*. As a rule, such *yiqtol(u)* apodoses were asyndetic. In (18) a negated apodosis is illustrated.

(18) אִם-לֹא יֵרֵד אֶחֱיִיכֶם הַקָּטָן אִתְּכֶם לֹא תִסְפֹּן לְרֵאוֹת פָּנַי:

‘Unless your youngest brother comes down with you, **you will not** see my face **again**.’ (Gen. 44.23)

In (18) the apodosis is of the type $\emptyset$ -*lō-yiqṭol(u)*. The future time reference implies a prohibition (a negated obligation). In the example, a *wa-qṭal* apodosis is replaced by an asyndetic clause. An example with a focused initial constituent is found in (19).

- (19) אִם-עֶבֶד יִגַּח הַשּׂוֹר אֶזְ אִמָּה בָּסֶף | שְׁלֹשִׁים שֶׁקֶלִים יִתֵּן לְאֹדֹנָיו וְהַשּׂוֹר יִסָּקֵל:
 ‘If the bull gores a male or female slave, the owner **must pay thirty shekels of silver** to the master of the slave, and the bull is to be stoned to death.’ (Exod. 21.32)

In (19) the apodosis has the pattern $\emptyset$ -*O.noun-yiqṭol(u)* (where *O.noun* means ‘object noun phrase’). In this example, too, the apodosis is asyndetic. The meaning is obligation. The amount of money that the owner must pay has focused position in the legal statement (italicised in the gloss).

Wa-qṭal as a construction and clause-type is basically a clause that follows another clause. It is a clause-type involved in linkage, and this fact should be accounted for when the steps of schematisation are investigated systematically. In this classification the cases when the preceding clause has a *yiqṭol(u)* predicate turn out to be of special importance. There is a close connection between *yiqṭol(u)* and *wa-qṭal* already in conditional sentences, and it is not surprising that *wa-qṭal* as a continuity clause-type in the overwhelming number of cases continues a main line *yiqṭol(u)* clause, whatever the meaning of this *yiqṭol(u)* may be (Isaksson 2024, 395–461).

References

- Baranowski, Krzysztof J. 2016a. *The Verb in the Amarna Letters from Canaan*. Languages of the Ancient Near East 6. Winona Lake, IN: Eisenbrauns.
- . 2016b. 'The Biblical Hebrew *wayyiqtol* and the Evidence of the Amarna Letters from Canaan'. *Journal of Hebrew Scriptures* 16: 1–18.
- Brockelmann, Carl. 1908–1913. *Grundriß der vergleichenden Grammatik der semitischen Sprachen*. 2 vols. Berlin: Reuther und Reichard. Reprint, Hildesheim: Olms, 1982.
- Bybee, Joan L. 2010. *Language, Usage and Cognition*. Cambridge: Cambridge University Press.
- . 2015. *Language Change*. Cambridge Textbooks in Linguistics. Cambridge: Cambridge University Press.
- Bybee, Joan L., Revere D. Perkins, and William Pagliuca. 1994. *The Evolution of Grammar: Tense, Aspect, and Modality in the Languages of the World*. Chicago: University of Chicago Press.
- Carlson, Greg N. 2012. 'Habitual and Generic Aspect'. In *The Oxford Handbook of Tense and Aspect*, edited by Robert I. Binnick, 828–51. Oxford Handbooks. Oxford: Oxford University Press.
- Cohen, Eran. 2014. 'The Domain: A Formal Syntactic Unit above Sentence Level'. In *Strategies of Clause Linking in Semitic Languages: Proceedings of the International Symposium on Clause Linking in Semitic Languages 5–7 August 2012 in Kivik, Sweden*, edited by Bo Isaksson and Maria Persson, 233–52. *Abhandlungen für die Kunde des Morgenlandes* 93. Wiesbaden: Harrassowitz.

- Cook, John A. 2012. *Time and the Biblical Hebrew Verb: The Expression of Tense, Aspect, and Modality in Biblical Hebrew*. Linguistic Studies in Ancient West Semitic 7. Winona Lake, IN: Eisenbrauns.
- Cristofaro, Sonia. 2003. *Subordination*. Oxford Studies in Typology and Linguistic Theory. Oxford: Oxford University Press.
- Dallaire, Hélène. 2014. *The Syntax of Volitives in Biblical Hebrew and Amarna Canaanite Prose*. Winona Lake, IN: Eisenbrauns.
- Dobbs-Allsopp, F. W., J. J. M. Roberts, Choon L. Seow, and R. E. Whitaker. 2005. *Hebrew Inscriptions: Texts from the Biblical Period of the Monarchy with Concordance*. New Haven, CT: Yale University Press.
- Garr, W. Randall. 1998. 'Driver's *Treatise* and the Study of Hebrew: Then and Now'. In *A Treatise on the Use of the Tenses in Hebrew and Some other Syntactical Questions*, by S. R. Driver, xviii–lxxxvi. Biblical Resource Series. Grand Rapids, MI: Eerdmans.
- Gogel, Sandra Landis. 1998. *A Grammar of Epigraphic Hebrew*. Resources for Biblical Study 23. Atlanta: Scholars Press.
- Haiman, John. 1978. 'Conditionals are Topics'. *Language* 54/3: 564–89.
- Halliday, Michael A. K. 2004. *An Introduction to Functional Grammar*. Edited by Christian M. I. M. Matthiessen. 3rd revised edition. London: Arnold.
- Hornkohl, Aaron D. 2019. 'Pre-modern Hebrew: Biblical Hebrew'. In *The Semitic Languages*, edited by John Huehnergard and Na'ama Pat-El, 533–70. Routledge Language Family Series. London and New York: Routledge.
- Huehnergard, John. 1987. 'Stative', Predicative Form, Pseudo-Verb'. *Journal of Near Eastern Studies* 46: 215–32.

- . 2011. *A Grammar of Akkadian*. 3rd edition. Harvard Semitic Studies 45. Winona Lake, IN: Eisenbrauns.
- Huehnergard, John, and Na'ama Pat-El. 2019. 'Introduction to the Semitic Languages and Their History'. In *The Semitic Languages*, edited by John Huehnergard and Na'ama Pat-El, 1–21. Routledge Language Family Series. London and New York: Routledge.
- Isaksson, Bo. 1998. "Aberrant' Usages of Introductory *wəhāyā* in the Light of Text Linguistics'. In "Lasset uns Brücken bauen..." Collected Communications to the XVth Congress of the International Organization for the Study of the Old Testament, Cambridge 1995, edited by Klaus-Dietrich Schunck and Matthias Augustin, 9–25. Beiträge zur Erforschung des Alten Testaments Und des Antiken Judentums 42. Frankfurt am Main: Peter Lang.
- . 2015. 'The Importance of Word Order for the Biblical Hebrew Verbal System'. Paper read at the *SBL Annual Meeting Atlanta, 21–24 November 2015*.
- . 2021. 'The Biblical Hebrew Short *yiqṭol* and the "Consecutive Tenses"'. In *New Perspectives in Biblical and Rabbinic Hebrew*, edited by Geoffrey Khan and Aaron D. Hornkohl, 197–240. Cambridge Semitic Languages and Cultures 7. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/OBP.0250.09>
- . 2024. *The Verb in Classical Hebrew: The Linguistic Reality behind the Consecutive Tenses*. Cambridge Semitic Languages and Cultures 27. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/OBP.0414>

- Joosten, Jan. 2016. 'Diachronic Linguistics and the Date of the Pentateuch'. In *The Formation of the Pentateuch: Bridging the Academic Cultures of Europe, Israel, and North America*, edited by Jan Christian Gertz, Bernard M. Levinson, Dalit Rom-Shiloni, and Konrad Schmid, 327–44. Tübingen: Mohr Siebeck.
- Khan, Geoffrey. 2019. 'Copulas, Cleft Sentences and Focus Markers in Biblical Hebrew'. In *Ancient Texts and Modern Readers: Studies in Ancient Hebrew Linguistics and Bible Translation*, edited by Gideon R. Kotzé, Christian S. Locatell and John A. Messarra, 14–62. *Studia Semitica Neerlandica* 71. Leiden and Boston: Brill.
- . 2020. *The Tiberian Pronunciation Tradition of Biblical Hebrew: Including a Critical Edition and English Translation of the Sections on Consonants and Vowels in the Masoretic Treatise Hidāyat al-Qāri' "Guide for the Reader"*. 2 vols. *Cambridge Semitic Languages and Cultures* 1. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/OBP.0163>
- . 2021a. 'The Coding of Discourse Dependency in Biblical Hebrew Consecutive *Weqatal* and *Wayyiqtol*'. In *New Perspectives in Biblical and Rabbinic Hebrew*, edited by Aaron D. Hornkohl and Geoffrey Khan, 299–354. *Cambridge Semitic Languages and Cultures* 7. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/OBP.0250.12>
- . 2021b. 'Verbal Forms Expressing Discourse Dependency in North-Eastern Neo-Aramaic'. In *Studies in the Grammar*

- and *Lexicon of Neo-Aramaic*, edited by Geoffrey Khan and Paul M. Noorlander, 143–93. Cambridge Semitic Languages and Cultures 5. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/OBP.0209.04>
- KTU = Dietrich, Manfred, Oswald Loretz, and Joaquín Sanmartín. 1976. *Die keilalphabetischen Texte aus Ugarit*. Alter Orient und Altes Testament 24. Kevelaer: Butzon und Bercker and Neukirchen-Vluyn: Neukirchener.
- Levine, Baruch A. 1993. *Numbers 1–20*. The Anchor Yale Bible 4A. New Haven & London: Yale UP. Reprint, 2008.
- Notarius, Tania. 2013. The Verb in Archaic Biblical Poetry: A Discursive, Typological, and Historical Investigation of the Tense System. *Studies in Semitic Languages and Linguistics* 68. Leiden and Boston: Brill.
- Pat-El, Na'ama. 2019. 'The Semitic Language Family: A Typological Perspective'. In *The Semitic Languages*, edited by John Huehnergard and Na'ama Pat-El, 80–94. Routledge Language Family Series. London and New York: Routledge.
- Renz, Johannes. 2016. 'Alt oder spät? Die Abfolge *wa*-Perfekt als Element der althebräischen Verbalsyntax im Kontext des nordwestsemitischen Verbalsystems. Eine Problemanzeige aus der Perspektive der nordwestsemitischen Epigraphik'. *Zeitschrift für die alttestamentliche Wissenschaft* 128: 433–67; 626–67.
- Revell, E. J. 1989. 'The System of the Verb in Standard Biblical Prose'. *Hebrew Union College Annual* 60: 1–37.
- Schüle, Andreas. 2000. *Die Syntax der althebräischen Inschriften: Ein Beitrag zur historischen Grammatik des Hebräischen*. Alter Orient und Altes Testament 270. Münster: Ugarit-Verlag.

- Sivan, Daniel. 1998. 'The Use of *QTL* and *YQTL* Forms in the Ugaritic Verbal System'. In *Past Links: Studies in the Languages and Cultures of the Ancient Near East Dedicated to Professor Anson F. Rainey*, edited by Shlomo Izre'el, Itamar Singer, and Ran Zadok, 89–103. Israel Oriental Studies 18. Winona Lake, IN: Eisenbrauns.
- . 2001. *A Grammar of the Ugaritic Language*. 2nd edition. Handbook of Oriental Studies. Section 1: The Near and Middle East 28. Leiden: Brill.
- Smith, Mark S. 1991. *The Origins and Development of the waw-consecutive: Northwest Semitic Evidence from Ugarit to Qumran*. Harvard Semitic Studies 39. Atlanta: Scholars Press.
- Tropper, Josef. 2012. *Ugaritische Grammatik*. 2nd revised edition. Alter Orient und Altes Testament 273. Münster: Ugarit-Verlag.

THE ORIGINS OF *WAYYIQTOL*: A FIRST-PERSON ACCOUNT

Aaron D. Hornkohl

In what promises to become a groundbreaking study published in 2021, the impact of which is yet fully to be felt (cf. Hornkohl 2023, 373–84, and Isaksson’s treatment in the present volume), the honouree proposed a potentially paradigm-shifting theory on the genesis of *wayyiqtol*.¹ Building on his own work on the phenomenon of secondary gemination in biblical reading traditions (Khan 2018a, 341–47; 2020, I:524–30), on Kantor’s (2020) study of Greek and Latin transcriptional evidence for the late differentiation of *wayyiqtol* and *we-yiqtol*, and on Robar’s (2013) argument against core preterite semantics for *wayyiqtol*, Khan (2021, 319–40) argues that the Masoretic distinction between *wayyiqtol* and *we-yiqtol* owes to secondary disambiguation of a formerly semantically undifferentiated Iron Age *w-yiqtol* syntagm by means

¹ §§1.0–2.0 of the present article are based, with slight revision, on Hornkohl (2023, 374–80). Limitations of space preclude exhaustiveness of the voluminous bibliography related to *wayyiqtol*; beyond the standard reference grammars, see Smith (1991); Bloch (2007); Robar (2013); Hornkohl (2014, 159–80); and Gzella (2018).

of gemination² innovated in the interests of orthoepy.³ Basically, the idea is that preterite *wayyiqtol* is a secondary schematisation of originally volitive/purposive *w-yiqtol*, which latter semantic value is preserved in Masoretic *we-yiqtol*. After summarising the supporting evidence for this view and the argument itself, the present article will examine developmental trends in first-person *w-yiqtol* morphology and assess the extent to which they are consistent with Khan's hypothesis for the origins of *wayyiqtol*.

1.0. Supporting Evidence

1.1. Semantic Gemination

Secondary gemination has been shown by Khan (2018a, 341–47; 2020, I:524–30) to be one means of disambiguating perceived homophones in BH recitation traditions. Words with identical

² Notwithstanding the modern convention of transcribing *shewa* as an *e*-class vowel (e.g., *a*, in some standard transcription systems), since the default realisation of *shewa* in Tiberian BH was as short *a*, identical to the realisation of *pataḥ*, the chief distinction between Tiberian *wayyiqtol* and *we-yiqtol* was one of gemination, not vowel quality (Kantor 2020, 59, 66–91; Khan 2020, I:305; 2021a, 332).

³ Broadly speaking, orthoepy refers to correct pronunciation. In the specific context of biblical reading traditions, such careful realisation sometimes resulted, as might be expected, in the preservation of old pronunciations against the encroachment of new ones (e.g., the safeguarding of distinctly realised phonemes and syllables in the face of slurring). Perhaps more surprisingly, it also occasioned innovative ways of disambiguating meaning, though, crucially, such innovations seem to have taken advantage of existing variants (see Khan 2018b).

forms but different meanings could be distinguished via the elongated realisation of a consonant in the case of one of the meanings. Since the gemination is marked by *dagesh* in some biblical traditions, it is sometimes referred to as ‘semantic *dagesh*’. Khan collects numerous examples from biblical (Tiberian, Babylonian, Samaritan) and non-biblical (rabbinic) traditions. Examples from Tiberian Hebrew include אָבִיר ‘powerful (divine)’ versus אֲבִיר ‘powerful (human)’, עֲצָבִים ‘toils’ versus עִצְבִּים ‘idols’, and, probably, הִרְעִים ‘make thunder (divine)’ versus הִרְעִים ‘vex, irritate (human)’. Though innovative and secondary from the perspective of pre-existing reading traditions, Khan (2020, 525) argues that “[t]he gemination in these pairs of forms most likely originates in existing variant morphological patterns that have been exploited to avoid homophony.”

1.2. Transcriptional Evidence

In a detailed survey of Greek and Latin transcriptional evidence relevant to the development of *wayyiqtol*, Kantor adduces compelling evidence of diachronic evolution in the form’s phonetic realisation. In the late Second Temple Period, writes Kantor (2020, 99–100),

The conjunction *waw* was **usually pronounced identically** before a preterite *yiqtol* and non-preterite *yiqtol* form, namely, with no full vowel or following gemination. Nevertheless, the conjunction *waw* was also **frequently pronounced distinctly** before a preterite *yiqtol* form, being vocalised with a full vowel and (probably) gemination.... (emphasis in the original)

Subsequently, in the early Byzantine Period, “The conjunction *waw* was ***always pronounced distinctly*** before a preterite *yiqtol* form (as opposed to before a non-preterite *yiqtol*), being vocalised with a full vowel and (probably) gemination....” Extrapolating back along the diachronic trajectory, Kantor argues that in Iron Age BH “the conjunction *waw* was ***pronounced identically*** before a preterite *yiqtol* and non-preterite *yiqtol* form, probably with the original etymological */a/ vowel,” meaning “that up to some point in the Second Temple period, *yiqtol* in the sequence **w-yiqtol* was a polysemous form, indicating either past or non-past (usually jussive) semantics according to context” (emphasis in the original).

Significantly, Kantor (2020, 104–5) follows Khan (1991, 241; 2013, 43) in positing secondary morphological disambiguation of previously undifferentiated *w-yiqtol* into preterite *way-yiqtol* and non-preterite *we-yiqtol* by means of gemination as the most plausible explanation for the gemination in Masoretic *way-yiqtol*.

While one cannot definitively exclude the possibility that the Tiberian reading tradition preserves an Iron Age distinction between geminated past *waw-yiqtol* (> *wayyiqtol*) and singleton non-past *waw-yiqtol* (> *we-yiqtol*) by gemination, several lines of argumentation combine to suggest otherwise: (a) the absence of any such distinction in the Samaritan reading tradition,⁴ (b) the partial, but increasing use of the distinction in the period of the

⁴ For an alternative means of distinguishing preterite *waw-yiqtol* in the Samaritan reading tradition, i.e., the replacement of *w-yiqtol* with *w-qatal* in I-y forms, see Khan (2021, 331); Hornkohl (2023, 448–51).

Greek and Latin transcriptions, (c) the reality of secondary semantic gemination across multiple reading traditions, and (d) multiple cases of dissonance in the Masoretic biblical tradition involving early consonantal orthography vocalised according to a characteristically later reading tradition.⁵ Such considerations are arguable evidence that the disambiguation in question took place after the Samaritan and Jewish traditions had diverged, was in the process of taking hold at the time the transcriptions were made, but had become solidly established before the division of the Masoretic Tiberian, Babylonian, and Palestinian branches.

1.3. Non-preterite *wayyiqtol*

Robar (2013; 2015, 78–112; 2021) builds a multi-pronged argument against *wayyiqtol*'s consensus preterite classification. She sees *wayyiqtol* as a narrative present of unspecified time reference that takes its TAM (Tense-Aspect-Mood) semantics from the context. While Khan's theory differs from Robar's at important points, he is favourable of her approach and agrees that certain *wayyiqtol* semantic values are incompatible with core preterite semantics (Khan 2021, 320 fn. 14, 328–29 and fn. 26). In place of fundamental perfective past semantics, he proposes a broader realis value (Khan 2021, 332).

⁵ For recent studies on this topic and further bibliography see Joosten (2015); Hornkohl (2020a; 2020b; 2023); Khan (2020, I:56–85).

2.0. The Development of *wayyiqtol*

Synthesising the aforementioned studies and additional research, Khan (2021, 319–40) employs Construction Grammar (Bybee 2010) to explain the development of *wayyiqtol* by means of the recognised mechanisms of reanalysis and schematisation. Khan improves upon existing accounts of *wayyiqtol*'s development in line with its semantic range, pragmatics, and status as the sole standard remnant of archaic preterite short *yiqtol* (< Proto-Semitic *yaqtul*).

Khan argues that preterite *yiqtol*'s preservation almost exclusively after *waw* is due to syntactic similarity to a “discourse dependent” (Khan 2021, 320ff.) modal short *yiqtol* in a (normally) purpose/result *w-yiqtol* construction, which made preterite *w-yiqtol* ripe for reanalysis. In this way, the short *yiqtol*'s originally distinct preterite and modal purpose/result semantics became fused in a semantically undifferentiated *w-yiqtol* construction.⁶ The core semantics of the resulting *w-yiqtol* had effectively been reduced to the “common denominator” of temporal posteriority relative to preceding context (Khan 2021, 326), which was further schematised to one of broader “topical cognitive relevance” (Khan 2021, 340).

Later, in some Second Temple traditions, the realis (preterite) and irrealis (volitive, often purpose/result) senses of *w-yiqtol* were disambiguated via gemination of the preformative in realis

⁶ Khan (2021a, 319 fn. 13) explicitly sidesteps the question of whether the ancient Hebrew preterite and volitional short *yiqtol* values are themselves reflexes of a single (Huehnergard 1988) or distinct PS *yaqtul* forms (Hetzron 1969; Rainey 1986).

(mostly preterite) *w-yiqtol*, resulting in a new distinction between realis (mainly preterite) *wayyiqtol* and irrealis (volitional, often purpose/result) *we-yiqtol*.

3.0. Addressing Potential Concerns

Beyond elegantly explaining preterite *yiqtol*'s nearly exclusive clause-initial preservation after *waw*, Khan's proposed Iron Age preterite-volitive/purpose *w-yiqtol* fusion helps to illuminate *wayyiqtol*'s semantic range: by acknowledging its mixed preterite-modal parentage, the form is revealed to have genetics consistent with non-past and/or non-perfective semantics, such meanings reflecting the archaic tenseless, aspect-free character of *way-yiqtol*'s volitive/purpose *waw-yiqtol* ancestor. The earlier preterite and volitive semantics, however, gave way in pre-Tiberian BH to a broader sense of temporal consecution and discourse dependency. According to this analysis, any old preterite and non-preterite values did not persist, but had to be inferred from context.

Even so, such a radical reimagining of the pre-Tiberian BH verb system invites scrutiny. For example, one might ask how the disambiguation of preterite and volitive/purposive⁷ *w-yiqtol* forms in proto-Tiberian BH related to the development of the semantically equivalent, but pragmatically distinct *X + qaṭal* sequence (Hornkohl 2018; Isaksson in the present volume). More generally, a potential area of scholarly doubt might revolve around the not trivial question of how the pre-Tiberian BH verb system 'worked' given a semantically undifferentiated *w-yiqtol*

⁷ For comments on the distinction between purely volitive and purposive semantics, see JM 116 note (1).

form, i.e., whether and how users disambiguated preterite and volitive/purposive senses of a *w-yiqtol* emptied of all but the barest of semantic values (temporal posteriority > discourse dependency). Finally, even if *w-yiqtol* may have lost its preterite semantics on the way to becoming *wayyiqtol*, it may well have reacquired strong preterite associations by dint of its use as the default narrative TAM construction. Given reader comfort with the morphological, phonological, graphic, and semantic distinction between *wayyiqtol* and *we-yiqtol* in Tiberian BH, doubts and knee-jerk resistance to the viability of a system with no such disambiguation are understandable.

In this connection, several points can be made. The first is that readers of at least one biblical reading tradition with ancient roots—that of the Samaritan Pentateuch—manage regularly to distinguish preterite and volitive/purposive *w-yiqtol* sequences with no phonological or graphic aid. That the interpretive tradition indeed draws a semantic distinction from forms despite their formal identity, is clear from the Samaritan Aramaic and Arabic translations.

Yet, as some might attribute the largely undifferentiated phonology of Samaritan *w-yiqtol* to a secondary departure from an earlier stage of disambiguation (notwithstanding the evidence from the Greek and Latin transcriptions, adduced above, in §1.2), it is worth noting that the semantics of the vast majority of *w-yiqtol* sequences in BH are readily intelligible from context and, specifically, from the preceding verb form. Khan himself (2021, 326) notes an important correlation: “In the attested corpus of Biblical Hebrew... purpose and result clauses with jussives have

future main clauses, whereas past *wayyiqtol* is generally preceded by a past clause.” In other words, preceding context must commonly have sufficed for the disambiguation of past versus volitive/purpose/result semantics of *w-yiqtol* forms. Indeed, according to the extant Masoretic tradition (= MT), there seem to be relatively few instances in which an ancient reader unaided by distinguishing phonology might have been required to read a *w-yiqtol* form against the TAM value of the immediately preceding verb form. Khan (2021a, 328) cites as potentially ambiguous the *w-yiqtol* form in (1), arguing that the extant *wayyiqtol* form may have originally been intended as a volitive/purposive *w-yiqtol*.

- (1) ...למה אמרת אחתי הוא ואקח אותה לי לאשה.
 ‘Why did you say “She is my sister,” **so that I took** her for my wife?...’ (Gen. 12.19)

As Hornkohl (2023, 380–81) observes, however, the regular first-person distinction between volitive/purposive *w-yiqtol* augmented with $\bar{d}$ (ואקטלה) and preterite *w-yiqtol* with no such augmentation (ואקטל), especially in the Pentateuch (see below, §4.1.1), renders this scenario unlikely. Whatever the case, *we-yiqtol* forms after past TAM forms are rare.⁸ Conceding the comparatively late semantic differentiation of *w-yiqtol*, Hornkohl (2023, 382–83) views the preservation of volitive/purposive semantics after perfective past forms as evidence of a semantically sensitive and nuanced interpretive tradition of great historical depth.

⁸ Consider Lev. 9.6; 1 Kgs 13.33; 2 Kgs 19.25; Isa. 41.26; Lam. 1.19. See JM (§§116b note (1), e); Joosten (2012, 154–55).

4.0. Factoring in First-person Morphology

The overwhelming majority of the approximately 15,000 *way-yiqtol* forms in the MT are in the third-person; see Table 1 for the frequency of *wayyiqtol* and *we-yiqtol* forms.⁹

Table 1: Frequency of *wayyiqtol* and *we-yiqtol* forms in the Masoretic text according to grammatical person

Person	<i>wayyiqtol</i>	<i>we-yiqtol</i>
1st	722 (5%)	557 (38%)
2nd	315 (2%)	78 (5%)
3rd	14,072 (93%)	842 (57%)

Since Tiberian *wayyiqtol* and volitive/purpose/result *we-yiqtol* both contain a prefix conjugation form that developed from Proto-Semitic short, i.e., consonant-final, *yaqtul*, this means that—apart from gemination and, in some cases, syllable stress—the majority of *wayyiqtol* forms are formally indistinguishable from *we-yiqtol* forms. The same goes for the far rarer cases of second-person morphology. Indeed, unless syllable stress once distinguished preterite and modal forms (see above, fn. 6), second- and third-person preterite and modal *waw* + *qaṭal* forms may always have been formally identical.

4.1. Distribution of *w-yiqtol* Morphology

When it comes first-person forms, however, a different situation obtains. According to the evidence most reflective of early typol-

⁹ The figures are according to searches of the Groves-Wheeler Westminster Hebrew Morphology database (2020) using the Accordance software (version 13.4.2) and include cases of *ketiv* and *qere*.

ogy, namely, the written (i.e., consonantal) component of the Tiberian tradition in the Torah,¹⁰ preterite *w-yiqtol* and volitive/purposive *w-yiqtol* were morphologically distinct in the first person. The following sections present tables showing the incidence of the relevant forms in the MT and in cognate, extra-biblical, and non-Masoretic biblical sources as well as discuss the data (see Appendix for citations).

4.1.1. The Pentateuch

Table 2: First-person *w-yiqtol* morphology in the Masoretic Pentateuch

	preterite		volitive/purposive	
	ואקטל	ואקטלה	ואקטלה	ואקטל
Genesis	39	3	44	0
Exodus	8	0	11	0
Leviticus	8	0	0	0
Numbers	5	1	6	0
Deuteronomy	41	0	6	1
Torah	101	4	67	1

According to the written component of the Masoretic Torah, in the first person a rigid distinction between preterite and volitive/purposive *w-yiqtol* morphology obtains. The dominant preterite form is *ואקטל* (101 of 105 cases), with extremely rare cases

¹⁰ On the typological antiquity of the Hebrew in the Masoretic Torah, see Elitzur (2015; 2018a; 2018b; 2019; 2022) and Hornkohl (2024). Circumstantial evidence ostensibly indicating the early crystallisation of the Torah's textual and linguistic traditions include, inter alia, its 3rd-century BCE translation into Greek, its comparatively infrequent incidence of *ketiv-qere* dissonance (Barr 1981, 32–33; Tov 2004a, 204 fn. 25); the disproportionate representation of Torah texts among the palaeo-Hebrew DSS (Tov 2004b, 246); and the occurrence in the Judean Desert of long scrolls apparently containing multiple books of the Torah (Tov 2004b, 75). See, further, Hornkohl (2024, 15–17)

of $\bar{a}$ augmentation (4 cases). Conversely, ואקטלה with $\bar{a}$ augmentation is the rule when it comes to volitive/purposive forms (67 of 68 cases).

4.1.2. The Prophets

Table 3: First-person *w-yiqtol* morphology in the Masoretic Prophets

	preterite		volitive/ purposive			preterite		volitive/ purposive	
	ואקטל	ואקטלה	ואקטל	ואקטלה		ואקטל	ואקטלה	ואקטל	ואקטלה
Josh.	20	1	0	0	Ezek.	65	3	0	2
Judg.	9	5	11	3	Hos.	1	0	4	3
Sam.	18	7	31	11	Amos	7	0	2	0
(1 Sam.	14	2	17	5)	Obad.	0	0	1	0
(2 Sam.	4	5	14	6)	Jon.	0	0	2	0
Kgs	17	0	15	6	Mic.	2	0	2	0
(1 Kgs	14	0	6	3)	Hab.	0	0	1	0
(2 Kgs	3	0	12	4)	Hag.	1	0	1	1
Isa.	13	0	18	17	Zech.	30	1	0	3
(1–39	6	0	12	8)	Mal.	2	0	1	1
(40–55	5	0	9	9)	Proph.	236	19	105	55
(56–66	2	0	1	7)	Fmr	65	13	57	20
Jer.	51	2	16	8	Lat.	172	6	48	35

In the MT Prophets, the morphological distinction between first-person preterite and volitive/purposive *w-yiqtol* forms remains perceptible, but is maintained less strictly than in the MT Penta-teuch. Preterite *w-yiqtol* forms are still normally ואקטל , i.e., without augmentation (217 of 236 cases). This is especially true of the Latter Prophets (172 of 178 cases; compare 65 of 78 cases in the Former Prophets).

In the case of volitive/purposive *w-yiqtol*, while lengthened ואקטלה morphology with $\bar{a}$ unambiguously marks as modal most volitive/purposive forms (just under two-thirds of the time), in a sizeable minority of the cases (55 of 160), unaugmented morphology obtains. Again, though, there is a discernible difference

between textual blocks: in the Former Prophets, nearly three-quarters of the cases (57 out of 77) end in $-\ddot{a}$; cf. the Latter Prophets, where forms with and without $-\ddot{a}$ are more evenly matched (48 against 35).

4.1.3. The Writings

Table 4: First-person *w-yiqtol* morphology in the Masoretic Writings

preterite		volitive/ purposive		preterite		volitive/ purposive	
	ואקטל	ואקטלה	ואקטלה	ואקטל		ואקטל	ואקטלה
Pss	9	12	54	9	Qoh.	0	1
(119)	1	6	17	2)	Dan.	7	10
(–119)	8	6	37	7)	Ezra	4	17
Job	9	6	10	8	Neh.	36	31
(prose	0	4	0	0)	Chron.	7	0
(poetry	9	2	10	8)	(1 Chr.	2	0
Prov.	0	0	1	0	(2 Chr.	5	0
Ruth	0	0	2	1	Writ.	73	77
Song	0	0	2	0	Non-LBH +	18	8
Lam.	1	0	3	2	LBH +	55	69
						30	8

Noticeably distinguishing the MT Writings from both the MT Torah and Prophets is the Writings' high incidence of preterite $ואקטלה$ morphology with $-\ddot{a}$ augmentation (77 out of 150 cases). As LBH+¹¹ accounts for 69 of the 77 cases of $ואקטלה$, and as nearly 80 percent of the eligible forms in LBH+ end in $-\ddot{a}$, one may take this as preliminary evidence (see below, §4.1.4) of a diachronic dimension in first-person *wayyiqtol* morphological variety. But this is not the whole story. The non-LBH+ Writings,

¹¹ LBH+ is comprised of the core LBH books of Esther, Daniel, Ezra, Nehemiah, and Chronicles—all dated by their content to the post-Restoration period—along with Ps. 119, the prose sections of Job (1–2 and 42.7–17), and Qohelet—each of which exhibits striking concentrations of distinctively post-exilic linguistic features.

with over 30 percent preterite *ואקטלה* forms, also show a comparatively high incidence, perhaps indicating a genre-based correlation between *ואקטלה* and poetry.

When it comes to volitive/purposive *w-yiqṭol*, the Writings, with 77 percent augmented *ואקטלה*, most closely resemble the Former Prophets, with 74 percent augmented *ואקטלה*. Unlike the Torah, both corpora show sizeable minorities of unaugmented volitive/purposive *ואקטל* forms.

4.1.4. Cognate, Extra-biblical, Non-Masoretic Biblical Material

Table 5: First-person *w-yiqṭol* morphology in cognate, extra-biblical, non-Masoretic biblical material

	preterite		volitive/purposive	
	ואקטל	ואקטלה	ואקטלה	ואקטל
Mesha ^c	12	0	0	0
Tel Dan	3	0	0	0
Non-biblical DSS	4	24	59	13
Samaritan Pentateuch	70	34	47	23
Biblical DSS	30	18	65	32
Ben Sira ¹²	4	3	3	0

Iron Age Cognate Material

In typological agreement with the Masoretic Pentateuch, Iron Age Moabite and Aramaic material has no first-person preterite *w-yiqṭol* morphology with $-\bar{a}$ augmentation, showing only *ואקטל*. This is significant, given the apparently routine orthographic representation of final vowels in the relevant corpora (on Moabite,

¹² The figures for Ben Sira differ from those in Hornkohl (2023, 412) due to the ambiguity of some forms' TAM values.

see Hornkohl 2023, 312). Neither corpus contains examples of first-person volitive/purposive *w-yiqtol*.

The Non-biblical Dead Sea Scrolls

As Second Temple compositions (rather than copies of earlier material), the evidence of the NBDSS is likely to furnish the most authentic representation of Second Temple linguistic conventions. Their fragmentary nature, though, necessitates caution (in the case of first-person *w-yiqtol* forms, especially as there are many instances of broken endings. In the NBDSS, augmented *ואקטלה* morphology prevails for both preterite semantics (24 of 28 cases) and volitive/purposive semantics (56 of 65 cases; cf. the case of the Masoretic Former Prophets, above, §4.1.2, Table 3). This has been explained as the result of a wholesale morphological reorganisation whereby clause-initial position became associated with *ואקטלה* morphology (Qimron 1997; 2018, 165–69).

The Samaritan Pentateuch

Erosion of morphological distinction is also conspicuous in the case of the Samaritan Pentateuch as compared to the corresponding Masoretic material. Though favouring non-augmented preterite *ואקטל* and augmented volitive/purposive *ואקטלה*, SH exhibits significant minorities of the respective alternants (preterite *ואקטלה* 34 of 104 and volitive/purposive *ואקטל* 23 of 70 cases, respectively; cf. Masoretic Pentateuch 4 of 105 and 1 of 69 cases, respectively). Notably, there is no difference between the written

Ben Sira

In the admittedly small sample set afforded by the Ben Sira manuscripts, first-person preterite *w-yiqtol* forms show a mix of וַאֲקַטֵּל and וַאֲקַטְלָה forms, whereas volitive/purposive semantics are represented exclusively by וַאֲקַטְלָה forms.

4.1.5. Summary

Examination of the incidence of first-person *w-yiqtol* morphosemantics in the ancient Hebrew and cognate sources examined above reveals a clear diachronic dimension. In typologically early material, morphology disambiguates semantics: preterite וַאֲקַטֵּל and volitive/purposive וַאֲקַטְלָה are kept rigidly distinct. According to later material, there is something of a conflation of the formerly dedicated forms. In the case of preterite semantics, the early preference for non-augmented וַאֲקַטֵּל morphology gives way to increasingly frequent וַאֲקַטְלָה forms, with a proliferation of preterite וַאֲקַטְלָה noticeable in Second Temple material.

Volitive/purposive semantics undergoes the reverse switch: early וַאֲקַטְלָה to later mixed usage of וַאֲקַטְלָה and וַאֲקַטֵּל. But there are significant differences compared to the case of preterite *w-yiqtol*. First, the shift from augmented וַאֲקַטְלָה to non-augmented וַאֲקַטֵּל morphology is not as clearcut: despite increased use of וַאֲקַטֵּל, וַאֲקַטְלָה remains dominant in pre-rabbinic Hebrew. Second, the common use of וַאֲקַטֵּל alongside וַאֲקַטְלָה apparently begins far earlier than the Second Temple Period, since it already characterises Tiberian CBH books beyond the Pentateuch. It is worth mentioning that the latter development is in line with another,

perhaps related, distinction that separates the Tiberian Penta-teuch (and Iron Age cognate sources) from the rest of the MT and late extra-biblical and biblical material, namely, the shift from short to long preterite *w-yiqtol* morphology in the case of III-y (ואבן > ואבנה), II-w/y (ואקום > ואקום), and *hif'il* verbs (ואבדל > ואבדיל), as seen in both the written and pronunciation components of the tradition (see Hornkohl 2023, 419–21; 2024, 52–54).

4.2. Discussion

On the basis of the data, it is possible to add some detail relevant to Khan's theory on the genesis of *wayyiqtol*, especially in terms of the supposed historical depth of the developmental processes. According to Khan, Iron Age BH was characterised by a semantically undifferentiated *w-yiqtol*. Indeed, notwithstanding awareness of previous scholarship postulating a convergence of the preterite and directive–volitive *yiqtol* paradigms in LBH (Bergsträsser 1918–1929, II:§5d; Talshir 1986), Khan (2021, 321–22) argues explicitly that “this had taken place already in Classical Biblical Hebrew.” Among his pieces of evidence is the sporadic appearance in the Masoretic Torah of preterite *w-yiqtol* in the ואקטלה form normally associated with volitive/purposive semantics (Khan 2021, 327–28).

On the assumption that *wayyiqtol* is due to secondary schematisation of originally volitive/purposive *w-yiqtol*, one can understand why Khan sees the sporadic CBH incidence of preterite ואקטלה as evidence of the process's historical depth. Consider the semantic similarity of the following examples, (2) and (3) hypothetical, and (4) authentic:

- (2) אֶגְרֹשׁ אוֹתָם מִפְּנֵיכֶם וְאַתְּנָה לָכֶם אֶת־אֶרְצָם*
 *‘I will drive them out before you **in order to give** you their land’ (Judg. 6.9b, adapted)
- (3) וְאֶגְרֹשׁ אוֹתָם מִפְּנֵיכֶם וְאַתְּנָה לָכֶם אֶת־אֶרְצָם*
 *‘And I drove them out before you **in order to give** you their land’ (Judg. 6.9b, adapted)
- (4) וְאֶגְרֹשׁ אוֹתָם מִפְּנֵיכֶם וְאַתְּנָה לָכֶם אֶת־אֶרְצָם
 ‘And I drove them out before you **and I gave** you their land’ (Judg. 6.9b)

The use of *w-yiqtol* in (3) serves as a developmental bridge between the prototypical FUTURE/MODAL + (DEPENDENT) PURPOSIVE sequence in (2) and the prototypical PERFECTIVE PAST + (DEPENDENT) PERFECTIVE PAST sequence in (4). It takes little imagination to comprehend how uses like (3) could be inferred to mean (4)—and how a subsequent desire for semantic differentiation might eventually lead to secondary phonological/morphological differentiation. In this way Khan explains the intermittent early appearance of preterite וַאֲקַטֵּל, which in the Second Temple Period multiplies. This interpretation of the data is also not inconsistent with the situation in the more common third-person and rarer second-person forms, where there was less morphological variation.

While there is consensus that preterite וַאֲקַטֵּל incorporates augmented cohortative *yiqtol*, one of Khan’s innovations is the linking of preterite וַאֲקַטֵּל to the first-person *jussive* with short *yiqtol* morphology. Khan (2021, 335–36) finds support for this view in Amarna Canaanite, where all grammatical persons appear in all three prefix forms: *yaqtulu*, *yaqtul*, and *yaqtula*. He further follows Baranowski (2016, 166–68) in positing a special

dependent purposive role for the Amarna Canaanite short *yaqtul*, which is to be distinguished from the directive–volitive modality of the longer *yaqtula* (pace Moran 1960; Dallaire 2014, 131–32).

Khan's main focus is on the development of *wayyiqtol* from a formerly purposive *w-yiqtol* sequence that came to be construed as a construction signalling preterite semantics. His developmental scheme is consistent with the diachronic data on וַאֲקַטְלָה: sporadic in typologically early material, common, but by no means dominant, in poetry and late texts.

Khan says less about the diachrony of volitive/purposive *w-yiqtol* morphological variety. In light of the situation in Amarna Canaanite, with first-person modal forms manifesting in both the short jussive and augmented cohortative patterns, their incidence and distribution in BH is intriguing. For while short *yaqtul* jussives are well documented in the first person in Canaanite, the BH incidence of such forms, as gauged on the basis of III-y, II-w/y, and *hif'il* verbs, is negligible (JM 114g).¹⁵ Not only this, but a diachronically sensitive survey of the evidence reveals some unexpected details when it comes to the use and non-use of volitive/purposive forms with and without $\bar{a}$ augmentation. First, the Masoretic Torah presents just one case of volitive/purposive וַאֲקַטְלָה (Deut. 10.2), against 67 cases of volitive/purposive וַאֲקַטְלָה.

¹⁵ Potential cases include וְלֹא־נִשְׁאָר (1 Sam. 14.36, despite the indicative negative particle), וַאֲרָא (Isa. 41.28), וַאֲחִזֶּק (Isa. 42.6), and וַאֲטַ (Hos. 11.4). Other short first-person *yiqtol* forms should perhaps be analysed as archaic preterites: וְלֹא־חָחַז (Job 23.9), וְלֹא־טַט (Job 23.11). Allegedly relevant cases of אֶסֶף are to be construed as *qal* forms of the *yaf'el* pattern (Huehnergard 2005; Hornkohl 2023, 245).

This is significant, because it has been shown on the basis of a series of linguistic details, that the written tradition of the Tiberian Pentateuch preserves the earliest typological phase of BH (Hornkohl 2024). The lack of clear-cut cases of short jussive ואקטל in this material, thus, implies that the process by which short jussive ואקטל ceded its role of encoding dependent volitive/purposive semantics to the augmented cohortative ואקטלה was by the time of CBH a *fait accompli*.

Second, against expectations, the pre-CBH expression of dependent volitive/purposive semantics via non-augmented ואקטל —which, again, is all but absent from the CBH of the Pentateuch—is found in Masoretic CBH beyond the Pentateuch, where it comprises minorities, sometimes sizeable, of the relevant forms. Of course, this should not be interpreted as denoting a re-emergence of the short first-person jussive, since the forms in question merely lack $\bar{a}$ augmentation, rather than exhibit unambiguous short morphology (as should be evident in the case of weak and *hif'il* verbs). Rather, as Khan himself (2021, 337–38) observes, in addition to the proposed *w-yiqtol* merger, there was a more general reduction in *yiqtol* morphological variation. Analogical pressure resulted in the unification of the short, long, and augmented patterns into a single undifferentiated *yiqtol* formally identical to the standard indicative *yiqtol* derived from Proto-Semitic *yaqtulu*. This process is uncharacteristic of the linguistic tradition preserved in the Masoretic Pentateuch, but more or less typical of the traditions of all other corpora, biblical and extra-

biblical, Masoretic and non-Masoretic.¹⁶ The culmination of the process is seen in RH, where *yiqṭol* morphological diversity is preserved only in quotations from the Bible or in allusions thereto.

References

- Barr, James. 1981. "A New Look at Kethibh-Qere." *Oudtestamentische Studiën* 21: 19–37.
- Bergsträsser, Gotthelf. 1918–1929. *Hebräische Grammatik*. 2 vols. Leipzig: Vogel.
- Bloch, Yigal. 2007. 'From Linguistics to Text-Criticism and Back: *Wayyiqṭol* Constructions with Long Prefixed Verbal Forms in Biblical Hebrew'. *Hebrew Studies* 48: 141–70.
- Ben-Ḥayyim, Ze'ev. 1977. *The Words of the Pentateuch*. Vol. 4 of *The Literary and Oral Tradition of Hebrew and Aramaic amongst the Samaritans*. Jerusalem: The Academy of the Hebrew Language. [Hebrew]
- Bybee, Joan L. 2010. *Language Usage and Cognition*. Cambridge: Cambridge University Press.
- Dallaire, Hélène. 2014. *The Syntax of Volitives in Biblical Hebrew and Amarna Canaanite Prose*. Linguistic Studies in Ancient West Semitic 9. Winona Lake, IN: Eisenbrauns.
- Elitzur, Yoel. 2015. 'The Divine Name ADNY in the Hebrew Bible: Surprising Findings'. *Liber Annuus* 65: 87–106.

¹⁶ The linguistic uniqueness of the Masoretic Torah in this connection may be regarded as a further example of the difference between CBH₁ and CBH₂, as recently proposed by Hornkohl (2024).

- . 2018a. ‘Diachrony in Standard Biblical Hebrew: The Pentateuch vis-à-vis the Prophets/Writings’. *Journal of Northwest Semitic Languages* 44: 81–101.
- . 2018b. ‘The Interface between Language and Realia in the Preexilic Books of the Bible’. *Hebrew Studies* 59: 129–47.
- . 2019. ‘The Names of God and the Dating of the Biblical Corpus’. In *The Believer and the Modern Study of the Bible*, edited by Tova Ganzel, Yehudah Brandes, and Chayuta Deutsch, 428–42. Boston: Academic Studies Press.
- . 2022. ‘Emergence and Disappearance of Words and Expressions in Pre-Exilic Biblical Hebrew’. *Revue Biblique* 129: 481–504.
- Gzella, Holger. 2018. ‘Untypical Wayyiqtol Forms in Hebrew and Early Linguistic Diversity’. In *The Unfolding of Your Words Gives Light: Studies on Biblical Hebrew in Honor of George L. Klein*, edited by Ethan C. Jones, 21–37. University Park, PA: Eisenbrauns.
- Hetzron, Robert. 1969. ‘The Evidence for Perfect *y^laqtul and Jussive *yaqt^lul in Proto-Semitic’. *Journal of Semitic Studies* 14: 1–21.
- Hornkohl, Aaron D. 2014. *Ancient Hebrew Periodization and the Language of the Book of Jeremiah*. Studies in Semitic Languages and Linguistics 74. Leiden: Brill.
- . 2023. *The Historical Depth of the Tiberian Reading Tradition*. Cambridge Semitic Languages and Cultures 17. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers.
<https://doi.org/10.11647/OBP.0310>

- . 2024. *Diachronic Diversity in Classical Biblical Hebrew*. Cambridge Semitic Languages and Cultures 29. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/OBP.0433>
- Huehnergard, John. 1988. ‘The Early Hebrew Prefix Conjugations’. *Hebrew Studies* 29: 19–23.
- . 2005. ‘Hebrew Verbs I-w/y and a Proto-Semitic Sound Rule’. In *Memoriae Igor M. Diakonoff*, edited by Leonid Kogan, Natalia Koslova, Sergey Loesev, and Serguei Tishchenko, 457–74. Babel und Bibel 2. Winona Lake, IN: Eisenbrauns.
- JM = Joüon, Paul, and Takamitsu Muraoka. 2006. *A Grammar of Biblical Hebrew*. Subsidia Biblica 27. Rome: Pontifical Biblical Institute Press.
- Joosten, Jan. 2012. *The Verbal System of Biblical Hebrew: A New Synthesis on the Basis of Classical Prose*. Jerusalem Biblical Studies 10. Jerusalem: Simor.
- . 2015. ‘The Tiberian Vocalization and the Hebrew of the Second Temple Period’. In *Hebrew of the Late Second Temple Period: Proceedings of a Sixth International Symposium on the Hebrew of the Dead Sea Scrolls and Ben Sira*, edited by Eibert Tigchelaar and Pierre Van Hecke, 25–36. Studies on the Texts of the Desert of Judah 114. Leiden: Brill.
- Kantor, Benjamin. 2020. ‘The Development of the Hebrew Wayyiqṭol (“Waw Consecutive”) Verbal Form in the Light of Greek and Latin Transcriptions of Hebrew’. In *Studies in Semitic Vocalisation and Reading Traditions*, edited

- by Aaron D. Hornkohl and Geoffrey Khan, 55–129. Cambridge Semitic Languages and Cultures 3. Cambridge: University of Cambridge and Open Book Publishers. <https://doi.org/10.11647/OBP.0207>
- Khan, Geoffrey. 1991. ‘Morphological Markers of Individuation in Semitic Languages and Their Function in the Semitic Tense System’. In *Proceedings of the Fifth International Hamito-Semitic Congress: Band 2, Cushitic, Egyptian, Omotic, Semitic*, edited by Hans G. Mukarovsky, 235–44. Vienna: Afro-Pub.
- . 2013. *A Short Introduction to the Tiberian Masoretic Bible and Its Reading Tradition*. 2nd edition. Piscataway, NJ: Gorgias.
- . 2018a. ‘How Was the *Dageš* in Biblical Hebrew דָּגֵשׁ Pronounced and Why Is It There?’. *Journal of Semitic Studies* 63/2: 323–51.
- . 2018b. ‘Orthoepy in the Tiberian Reading Tradition of the Hebrew Bible and Its Historical Roots in the Second Temple Period’. *Vetus Testamentum* 68: 378–401.
- . 2020. *The Tiberian Pronunciation Tradition of Biblical Hebrew: Including a Critical Edition and English Translation of the Sections on Consonants and Vowels in the Masoretic Treatise Hidāyat al-Qāri’ ‘Guide for the Reader’*. 2 vols. Cambridge Semitic Languages and Cultures 1. Cambridge: University of Cambridge and Open Book Publishers. <https://doi.org/10.11647/OBP.0163>
- . 2021. ‘The Coding of Discourse Dependency in Biblical Hebrew Consecutive *Weqatal* and *Wayyiqtol*’. In *New*

- Perspectives in Biblical and Rabbinic Hebrew*, edited by Aaron D. Hornkohl and Geoffrey Khan, 299–354. Cambridge Semitic Languages and Cultures 7. Cambridge: University of Cambridge and Open Book Publishers. <https://doi.org/10.11647/OBP.0250>
- Moran, William L. 1960. ‘Early Canaanite Yaqtula’. *Orientalia* 29: 1–19.
- Rainey, Anson F. 1986. ‘The Ancient Hebrew Prefix Conjugation in the Light of Amarnah Canaanite’. *Hebrew Studies* 27: 4–19.
- Robar, Elizabeth. 2013. ‘Wayyiqtol: An Unlikely Preterite’. *Journal of Semitic Studies* 58: 21–42.
- . 2015. *The Verb and the Paragraph in Biblical Hebrew: A Cognitive-Linguistic Approach*. Studies in Semitic Languages and Linguistics 78. Leiden: Brill.
- . 2021. ‘The Rise of Wayyiqtol.’ In *New Perspectives in Biblical and Rabbinic Hebrew*, edited by Aaron D. Hornkohl and Geoffrey Khan, 241–74. Cambridge Semitic Languages and Cultures 7. Cambridge: University of Cambridge and Open Book Publishers.
- Smith, Mark S. *The Origins and Development of the Waw-consecutive: Northwest Semitic Evidence from Ugarit to Qumran*. Harvard Semitic Studies 39. Winona Lake, IN: Eisenbrauns.
- Talshir, David. 1986. ‘Al Yihude Tahbir be-Lashon ha-Miqra ha-Me’uheret’. In *Proceedings of the Ninth World Congress of Jewish Studies*, part 4, vol. 1, 5–8. Jerusalem: The World Union of Jewish Studies.
- Tov, Emanuel. 2004a. ‘The Ketiv-Qere Variations in Light of the Manuscript Finds in the Judean Desert’. In *Text, Theology*

and Translation: Essays in Honor of Jan de Waard, edited by Simon Crisp and Manuel Jinbachian, 199–208. Swindon: United Bible Societies.

———. 2004b. *Scribal Practices and Approaches Reflected in the Texts Found in the Judean Desert*. Studies on the Texts of the Desert of Judah 54. Atlanta: Society of Biblical Literature and Leiden: Brill.

Appendix

Masoretic Tradition

Pentateuch

Preterite—ואקטל: Gen. 3.10, 10, 12, 13; 12.19; 16.5; 20.6, 13; 24.39, 42, 42, 45, 47, 47, 48, 48; 26.28; 27.33; 31.10, 11; 32.5; 39.14, 15, 18; 40.11, 11, 11; 41.12, 21, 24; 42.31; 43.7, 21; 44.20, 22, 24, 26, 28; Exod. 3.8, 17; 4.23; 6.5; 19.4, 4; 31.3; 32.24; Lev. 7.34; 17.14; 18.25; 20.23, 24, 26; 26.13, 13; Num. 8.18; 20.15, 16; 21.30; 31.50; Deut. 1.9, 15, 15, 19, 19, 19, 20, 23, 29, 43; 2.1, 1, 8, 8, 13, 26, 34, 34; 3.4, 6, 8, 23, 29; 9.9, 15, 17, 18, 20, 21, 21, 21, 25, 26, 26; 10.3, 5, 5; 22.14; 26.7; 29.4, 7; **ואקטלה**: Gen. 32.6; 41.11; 43.21; Num. 8.19; **volitive/purposive—ואקטלה**: Gen. 11.3, 7; 12.2, 3; 13.9, 9; 17.2; 18.5, 30, 32; 19.5, 32; 22.5; 23.4, 13; 24.56, 57; 26.28; 27.4, 7, 25, 41; 29.21, 27; 30.25, 26, 28; 32.10; 33.12, 12; 34.12; 35.3; 42.34; 43.4, 8, 8; 44.21; 45.18; 46.31, 31; 47.16; 49.1; 50.5, 5; Exod. 3.18; 4.18; 5.3; 8.4; 9.28; 14.4, 12, 17; 20.19; 24.12; 33.5; Num. 9.8; 11.13; 14.4; 21.16; 22.19; 23.3; Deut. 5.31; 13.7, 14; 31.28, 28; 32.1; **ואקטל**: Deut. 10.2

Prophets

Preterite—ואקטל: Josh. 2.11; 7.7; 9.24; 14.7; 22.26, 28; 24.3, 3, 3, 4, 4, 5, 5, 6, 8 (q), 8, 10, 11, 12, 13; Judg. 2.1, 1; 6.8, 9, 9; 10.10; 12.2; 19.18; 20.6; 1 Sam. 1.15; 10.14, 18; 12.1, 10; 13.12, 12; 15.20, 20, 24;

24.11; 25.35; 28.21, 21; 2 Sam. 1.7, 8 (*q*), 10, 10; 1 Kgs 2.8, 42; 3.17, 21, 21; 8.16, 20, 20, 21; 14.8; 18.13; 19.10, 14; 21.6; 2 Kgs 6.29, 29; 10.13; Isa. 6.5, 8, 8, 11; 8.3; 24.16; 41.9; 45.4; 48.5; 50.7; 51.16; 64.4, 5; Jer. 1.6, 11, 13; 2.7; 3.7, 8, 19; 4.10; 5.7; 7.13, 13, 25; 8.6, 13; 11.5, 8; 13.2, 5, 7, 7, 7; 14.13; 15.17; 18.3; 23.38; 24.3; 25.3, 17; 31.18; 32.8, 10, 10, 10, 10, 11, 12, 16; 35.3, 4, 5, 5, 8, 10, 10, 11, 11, 15, 17; 42.21; 44.4, 17; Ezek. 1.24, 28, 28; 2.2; 3.2, 12, 14, 15, 15 (*q*), 15, 23, 23, 23; 4.14; 8.5, 8, 10; 9.8, 8; 10.20; 11.13, 13, 13, 25; 16.6, 6, 6, 8, 8, 8, 8, 9, 12, 27, 50; 20.5, 5, 5, 7, 8, 11, 13, 18, 21, 26, 29; 21.5; 22.26, 30, 31; 23.43; 24.18, 20; 28.18; 31.15, 15; 36.18, 19, 21; 37.3; 39.23, 24; 43.3, 6; 44.4; Hos. 3.3; Amos 2.9, 10, 11; 7.2, 5, 8; 8.2; Mic. 3.1; 6.4; Hag. 1.11; Zech 1.9; 2.1, 2, 4, 5, 6; 3.5; 4.2 (*q*), 4, 5, 11, 12, 13; 5.1, 1, 2, 6, 9, 10; 6.1, 1, 4; 11.7, 8, 9, 10, 10, 12, 13, 14; Mal. 1.2, 3; **ואקטלה**: Josh. 24.8 (*k*); Judg 6.9, 10; 10.12; 12.3, 3; 1 Sam. 2.28; 28.15; 2 Sam. 4.10; 7.9; 12.8, 8; 22.24; Jer. 11.18; 32.9; Ezek. 3.3; 9.8; 16.11; Zech. 11.13; **volitive/purposive—ואקטלה**: Judg. 1.3; 6.39; 9.29; 11.6, 37; 16.28; 18.5; 19.11, 13, 28; 20.13; 1 Sam. 9.5, 9; 11.3, 14; 12.7; 14.1, 6, 12, 36; 15.16; 17.10, 44; 26.11; 27.5; 28.7, 7, 22; 2 Sam. 3.21, 21; 12.8; 14.7, 32; 15.14; 16.9; 17.1, 1, 3, 5; 18.19; 20.16, 21; 1 Kgs 13.7; 18.1; 19.20; 20.25; 21.2; 22.7; 2 Kgs 3.11; 4.22, 22; 5.5; 6.2, 19; 7.4, 9, 9, 13; 18.23; 19.23; Isa. 1.18, 24, 25, 25, 26; 2.3, 5; 5.19; 8.2; 18.4; 25.9; 36.8; 41.22, 22, 23, 23, 23; 43.28; 49.20; 51.23; 55.3; 56.12; Jer. 4.5; 5.5; 6.5, 10; 7.3; 8.14; 9.1, 1; 17.14; 18.18; 20.10, 10; 31.18; 33.3; 46.16; 51.10; Hos. 2.9; 6.1, 3; 14.3; Amos 8.5, 5; Obad. 1; Jon. 1.7, 7; Mic. 1.8; 4.2; Hab. 2.1; Hag. 1.8 (*q*); Mal. 3.7; **ואקטל**: Judg. 16.20, 26; 19.11; 1 Sam. 7.5; 11.14; 12.3, 3; 20.11; 2 Sam. 10.12; 15.7; 17.2; 19.27, 27, 38; 1 Kgs 11.21; 12.9; 20.31; 2 Kgs 4.10; 6.13; 19.23, 24; Isa. 1.25; 7.6; 10.13, 13; 14.13; 37.24, 24, 25; 41.23 (*k*) (?), 26; 42.6, 14; 43.4, 28; 44.19; 46.4; 49.5; 57.17, 18; 63.5, 5, 6, 6; 64.4; Jer. 3.19; 5.1; 8.14; 17.14; 35.11; 40.4; 42.12; 51.9; Ezek. 2.1; 13.15; Hos. 5.14; 13.8, 11; Hag. 1.8 (*k*); Zech. 1.3; 8.10; 11.5; Mal. 1.4

Writings

Preterite—ואקטל: Ps. 18.24; 20.9; 44.21; 55.7; 73.13; 77.11; 95.10; 119.52; 139.11; Job 5.3; 19.10; 29.18; 30.19; 31.34; 32.6; 38.10, 10, 11; Lam. 3.18; Dan. 8.3, 16; 8.27, 27; 10.5, 9; 12.7; Ezra 8.21, 32, 32; 10.2; Neh. 1.5; 2.1, 2, 3, 4, 5, 7, 9, 11, 12, 14, 15, 15, 15, 17, 18, 20, 20; 4.3, 3, 7, 7, 8, 8, 9, 13; 5.7, 9 (*q*), 12; 6.4; 7.1, 3 (*q*), 5, 5; 13.7, 15; 1 Chron. 17.8, 10; 2 Chron. 6.6, 6, 10, 10, 11; **ואקטלה:** Ps. 3.6; 7.5; 69.12, 21; 73.16; 90.10; 119.55, 59, 106, 131, 147, 158; Job 1.15, 16, 17, 19; 19.20; 29.17; Qoh. 1.17; Dan. 8.13, 15, 17; 9.3, 4, 4; 10.16, 16, 19; 12.8; Ezra 7.28; 8.15, 16, 17, 17, 23, 23, 24, 25, 26, 28, 31; 9.3, 3, 5, 5, 6; Neh. 1.4; 2.1, 6, 9, 13; 5.7, 7, 8, 13; 6.3, 8, 11, 12; 7.5; 12.31; 13.7, 8, 9, 9, 10, 11, 11, 13, 17, 17, 19, 19, 21, 21, 22, 30; **volitive/purposive—ואקטלה:** Ps. 2.3, 8; 7.18; 9.3; 21.14; 26.6; 27.6, 6; 31.8; 34.4; 39.14; 40.6; 41.11; 42.5; 43.4; 50.7, 7, 21; 51.18; 55.3, 7; 57.8; 66.16; 77.2; 80.4, 8, 20; 81.9; 86.12; 90.14, 14; 95.6; 108.2; 118.24; 119.15, 17, 18, 27, 34, 44, 45, 46, 48, 63, 73, 88, 115, 117, 125, 134, 146; 139.8; 145.1, 2; Job 6.10; 9.27; 10.20; 13.13; 15.17; 16.4, 6; 23.5, 7; 30.26; Prov. 27.11; Ruth 2.2; 4.4 (*q*); Song 1.4; 3.2; Lam. 3.40, 40; 5.21 (*q*); Dan. 1.12; Neh. 5.2, 2, 3; 6.2, 7, 10; 1 Chron. 13.3; 19.13; 21.2; 2 Chron. 1.10, 10; 18.6; **ואקטל:** Ps. 4.9; 51.9; 55.13, 13; 59.17; 90.12; 119.47, 48, 163; Job 3.11, 13; 13.19; 23.15; 29.25, 25; 31.17; 41.3; Ruth 4.4 (*k*); Lam. 3.8; 5.21 (*k*); Neh. 10.32; 2 Chron. 7.14, 14; 10.9; 14.6; 20.9

Cognate, Extra-biblical, Non-Masoretic Biblical Material

Mesha^c

Preterite—ואקטל: KAI 181 1.11, 11, 12, 13, 14–15, 15, 16, 17, 18, 20, 30, 32

Tel Dan

Preterite—ואקטל: KAI 310 1.5, 6, 9

Non-biblical Dead Sea Scrolls

Preterite—ואקטל: 4Q364 f26bii + e.1, 2; 4Q386 f1ii.2; 4Q391 f36.2; **ואקטלה:** 1QH^a 12.37; 14.9, 10; 15.23; 17.9, 10; 1Q49 f1.1; 4Q381 f45a + b.1, 1, 2; 4Q385 f2.9; 4Q385a f1a–bii.6, 7; f15i.5; 4Q387 f1.7; 4Q389 f2.4, 5; f6.1; 4Q390 f1.6, 6; 4Q437 f2ii.13; 4Q504 f1–2Rv.17; 11Q5 28.5; 11Q19 65.8; **volitive/purposive—ואקטלה:** 1QS 10.16; 1QpHab 6.13; 1QM 13.13, 13; 1QH^a 4.29; 5.37; 7.24, 26, 36; 8.22, 29; 9.25; 11.21, 21; 12.23; 13.35; 17.8, 13, 14; 18.33, 36; 19.8, 9, 20; 20.6; 21.5, 7; 22.13; fA8.2; 4Q171 f1–2ii.6; 4Q179 f1ii.2; 4Q185 f4ii.3; 4Q216 2.12; 7.8; 4Q266 f1a–b.5; 4Q299 f26.2; f59.7; 4Q300 f8.4; 4Q379 f18.3; 4Q381 f15.3; f33ab + 35.5; f45a + b.1; f47.3; 4Q382 f23.1; 4Q389 f2.7; 4Q391 f20.2; 4Q426 f1ii.3; 4Q427 f1.3; f2.2; f3.3; f8i.9; 4Q438 f3.1; 4Q443 f1.6; 4Q511 f42.7; f7 + 5ii.7; 11Q19 29.8; 54.10, 21; 55.4; **ואקטל:** 1QH^a 19.20; 4Q222 f2.3; 4Q368 f3.4; 4Q372 f1.23, 25; 4Q378 f6ii.6; 4Q381 f33ab + 35.3; f45a + b.1, 1, 2; f47.2; 4Q521 f2iii.1; 11Q19 59.7

Samaritan Pentateuch

Preterite—ואקטל: Gen. 3.10, 10, 12, 13; 12.19; 16.5; 20.6, 13; 24.39, 42, 42, 45, 47, 47, 47, 48, 48; 26.28; 27.33; 31.10, 11; 32.5; 39.14, 15, 18; 40.11, 11, 11; 41.11 (≠ MT), 12, 21, 24; 42.31; 43.7, 21 (≠ MT), 21; 44.20, 22, 24, 26; Exod. 4.23; 19.4, 4; 31.3; 32.24; Lev. 7.34; 17.14; 18.25; 20.23, 24, 26; 26.13; Num. 8.18; 20.15, 16; 31.50; Deut. 1.9, 15, 15, 19, 20, 23, 29; 2.1; 3.8, 29; 9.9; 26.7; 29.4, 7; **ואקטלה:** Gen. 32.6 (= MT); Exod. 3.8, 17; 6.5; Lev. 26.13; Num. 8.19 (= MT); Deut. 1.19, 19, 43; 2.1, 8+ (MT —), 8, 8, 13, 26, 34, 34; 3.4, 6, 23; 9.15, 17, 18, 20, 21, 21, 21, 25, 26, 26; 10.3, 5, 5; 22.14; **volitive/purposive—ואקטלה:** Gen. 11.3; 12.2; 18.30, 32; 19.32; 23.4, 13; 24.56; 26.28; 27.7, 41; 30.25, 26, 28; 33.12, 12; 35.3; 42.34; 43.4, 8, 8; 44.21; 46.31; 49.1; 50.5, 5; Exod. 3.18; 4.18; 5.3, 17; 6.9+; 8.23; 14.4, 12, 17; 20.18+; 33.5; Num. 9.8; 22.19; 23.3; Deut. 5.28; 10.2 (≠ MT); 13.7, 14; 31.28, 28; 32.1; **ואקטל:** Gen. 12.3; 18.5; 19.5; 22.5; 24.57; 27.4, 25; 29.21, 27;

30.37+ (MT —); 32.10; 34.12; 45.18; 46.31; 47.16; Exod. 8.4; 9.28; 20.18b; 24.12; Num. 11.13; 14.4; 21.16, 30

Biblical Dead Sea Scrolls

Preterite—ואקטל: 1QIsa^a 5.25; 6.1; 7.20; 19.13; 38.10; 1Q8 17.6; 19.16; 4Q1 f9.4, 5; 4Q3 f1ii.18 (≠ MT Gen. 41.10); 4Q31 2.12; 4Q35 f1.11; f5–6.7; 4Q56 f27.3; f36.2; 4Q60 f9–10.2; 4Q70 f3+4i+5–7.8; f21–22i.2, 5; 4Q72 f23–24.4; 4Q112 f14.13; f15.18 (≠ MT Dan. 10.19); 5/6Hev1b f6–7.10; Mur1 f5ii.1; 14.34; Mur88 21.38; Mas1d 2.3, 8; 3.5; **ואקטלה**: 1QIsa^a 6.2 (≠ MT Isa. 6.8), 5 (≠ MT Isa. 6.11); 34.12 (≠ MT Isa. 41.9); 40.10 (≠ MT Isa. 48.5); 42.8 (≠ MT Isa. 50.7); 51.20 (≠ MT Isa. 64.5); 4Q13 f3ii+5–6i.8 (≠ MT Exod. 3.17); 4Q51 3a–e.25; 9e–i.16; f61ii+63–64a–b+65–67.3; 4Q80 f8–13.19 (≠ MT Zech. 4.4); f14–15.4 (≠ MT Zech. 5.10); 4Q83 f19ii–20.31; 4Q113 f16–18i+19.5 (≠ MT Dan. 8.3); 11Q5 9.1; 11.2; 12.4; 13.9; 20.2 (≠ MT Ps. 139.11); **volitive/purposive—ואקטלה**: 1QIsa^a 1.21, 29; 2.10, 14; 14.28; 29.11; 31.2 (≠ MT Isa. 37.24), 3 (≠ MT Isa. 37.25); 33.6 (≠ ואמר MT Isa. 40.6); 34.29, 29; 35.1, 2; 35.4, 5 (≠ MT Isa. 41.26), 16 (≠ MT Isa. 42.6), 24 (≠ MT Isa. 42.14); 37.6 (≠ MT Isa. 43.28); 37.25 (≠ MT Isa. 44.19); 39.10 (≠ MT Isa. 46.4); 41.2 (≠ MT Isa. 49.5), 20; 43.13; 46.26; 47.17 (≠ MT Isa. 57.17); 51.2 (≠ MT Isa. 63.6), 2 (≠ MT Isa. 63.6); 53.23 (≠ MT וַעֲצֹרְתִי Isa. 63.5); 1Q8 18.5 (≠ MT Isa. 43.4); 24.30; 25.2 (≠ MT Isa. 57.18); 27.14 (≠ MT Isa. 63.5), 14 (≠ MT Isa. 63.5), 15 (≠ MT Isa. 63.6), 15 (≠ MT Isa. 63.6); 4Q1 f22ii+26.9 (≠ MT וַיִּבְרָחָה Exod. 5.8); 4Q11 f10ii.4; 4Q29 f5–8.5; 4Q38 f1.4; 4Q57 f44–47.13; 4Q59 f1.3; f4–10.1; 4Q70 f29.4; 4Q135 f1.7; 4Q137 f1.56; 11Q5 7.1, 3, 4; 8.8, 8, 10, 11 (≠ MT Ps. 119.47), 12; 10.7; 11.11, 13; 12.7; 13.15; 16.8, 9; XQ2 1.13; Mur88 10.11, 11; 12.5; 13.21; **ואקטל**: 1QIsa^a 1.28 (≠ MT Isa. 1.24), 1.29 (≠ MT Isa. 1.25); 5.6 (≠ MT Isa. 5.19); 6.20; 9.28, 28; 17.7; 20.8 (≠ MT Isa. 25.9); 31.2; 32.7 (≠ ואמר MT Isa. 38.15); 37.6 (≠ MT Isa. 43.28); 45.22 (≠ MT Isa. 55.33); 46.26 (≠ MT וַאֲקַחְהָ Isa. 56.12); 47.17 (≠ MT הַסֵּתֶר Isa. 57.17), 18; 51.1, 1, 19; 1Q8 25.1; 4Q56 f31ii.2; 4Q58 11.24 (≠ MT הַסֵּתֶר Isa. 57.17), 24; 4Q85

f15ii-16.27 (≠ MT Ps. 50.21); 4Q99 f1.4; 4Q101 f1-2.2; 11Q5 8.12; 11.13 (≠ MT וְאַשְׁטָה Ps. 119.117); Mur2 f1i.2

Ben Sira

Preterite—ואקטל: 51.9 (SirB 20v.5); 51.10 (SirB 20v.5); 51.14 (SirB 21r.12); 51.19 (SirB 21r.17); **ואקטלה:** 51.8 (SirB 20v.3); 51.12 (SirB 20v.11); 51.12 (SirB 20v.11); **volitive/purposive—ואקטלה:** 42.15 (Mas1h 5.1); 42.15 (SirB 12r.6); 51.18 (11Q5 21.15)

FRONTING IN THE PROTASES OF ׀

CONDITIONALS

Christo H. J. van der Merwe

Geoffrey Khan has been interested in the interpretation of word order (especially, the functional value of moving a clause constituent from its canonical position to another position in a clause) since the beginning of his career. In 2020, he co-authored an article with me in which we seek to provide a more comprehensive model for the interpretation of fronting in Biblical Hebrew (BH) verbal clauses. One of the main theses of our study reads as follows: “A key feature of our model is the recognition that fronting constructions include both categorical sentences, which make a predication about a base of predication, and alsothetic sentences, which present a unitary situation” (Khan and van der Merwe 2020, 347). That study, which limited its data set to 1 Samuel, makes a distinction between (i) narrow constituent focus constructions, (ii) selecting topic constructions, and (iii)thetic constructions.

The purpose of the present exploratory research is to employ insights of the theoretical framework of the above-mentioned study to investigate fronting in a very specific type of construction in the entire Tanakh, viz. the protasis of conditionals introduced by ׀. Why this focus on the protasis of conditionals

introduced by ׀? First, all instances of this clause type in the Tanakh are given to relatively straightforward identification and collection on the basis of their formal features.¹

Second, the protases of conditionals always involve the establishment of a specific alternative or alternatives—a key concept in the identification of topic selection and narrow constituent focus. The alternatives might be (1) *if (protasis) A, then (apodosis) B*, or (2) *if not A, then B*. The alternatives might also be *if A¹ and if Aⁿ, then B*. See example (7).

Third, given the nature of the protases of conditionals referred to above, it is reasonable to assume that the most prototypical function of fronting in protases with finite verbs is the selection of alternative topics. The question is: is the notion of “selecting topic constructions” as defined in Khan and Van der Merwe adequate to describe the function of fronting in the protases of conditionals—in particular the selection of alternative topics? Khan and Van der Merwe (2020, 370) state “In categorical sentences with a fronted constituent that fall into this category both the fronted constituent *and* the following predication contain a focus. The focused fronted entity establishes the topic that acts as the base of predication” (italics added) (e.g., וַיֵּקָם וַיֵּלֶךְ, וַיְהוֹנָתָן בָּא הָעִיר ‘He got up and left; *but Jonathan*—went into the city’ 1 Sam. 21.1). The dilemma is that in protases with a fronted

¹ In some instances, however, the function of ׀ is difficult to interpret, e.g., Ps. 131.2; Job 36.29. A few instances are excluded from this investigation on text-critical grounds, i.e., Deut. 32.30; Ruth 3.12; Job 30.24; Prov. 24.11; Ezek. 35.6; Hos. 12.12.

non-verbal constituent, that constituent is the only focus of the clause. See examples (22)–(40).

This, fourthly, leads one to the question: is the fronting in protases introduced by ׀ rather a type of narrow focus? According to Khan and Van der Merwe (2020, 362) “a construction with a fronted constituent in narrow focus is used where the speaker/writer informs the reader of the identity of a variable in a pre-supposition in the common ground.” A typical example of narrow focus can be found 1 Sam. 26.6b מִי־יֵרֵד אִתִּי אֶל־שָׂאוּל אֶל־הַמַּחֲנֶה בֵּאֵר. 26.6b “*Who* will go down with me into the camp to Saul?” Abishai said, “*I* will go down with you.” For Khan and Van der Merwe, this example is an instance of non-exhaustive completive focus. Other types of narrow focus are exhaustive completive, restricting, selective, replacing, expanding, and scalar focus (2020, 236–369).

The primary research questions of this study are as follows: can the fronted constituent of the clause immediately following ׀ be regarded as a type of narrow focus? If yes, what type of narrow focus is it? If not, given the realities referred to in the two paragraphs above, can anythetic constructions be identified? Since a protasis may consist of more than one clause, and since fronted constituents may on occasion be restricted to the second or third clauses, a secondary research question is: what is the function of the fronting in those instances?² It is assumed that in

² In about 13 percent (40/303) of the cases, the apodosis has a fronted non-verbal constituent. These instances are listed in italics. Space constraints preclude systematic discussion of the function of the fronting.

order to address our research questions, a profile of the distribution and frequency of possible relevant syntactic configurations of the protases of ׀ conditionals in the Hebrew Bible is needed. For this purpose, the first formal pattern to distinguish is the distinction between protases that are initiated by *yiqtol* and those that are initiated by *qatal* forms. Since some protases contain only one clause and others more than one clause, the second formal feature to distinguish is whether a protasis consists of one (Type 1) or more than one clause (Type 2)? This feature has been regarded as relevant, since a second or subsequent clause in a protasis has the potential to commence with a non-verbal constituent. A third formal feature, of which only the distribution has been explored, is how often apodoses with finite verbs are verb-initial or not—in other words, whether the apodosis has a fronted non-verbal constituent or not.

Since BH conditionals typically refer to something that has not yet happened, the overwhelming majority of the protases have a *yiqtol* form of the verb. For this reason, I commence with ׀ *yiqtol* protases and then proceed to consider ׀ *qatal* constructions. In each case, the secondary research question, namely, the function of fronting clauses not immediately following ׀ in Type 2 constructions, is addressed (typically in footnotes). The results of this investigation and the frequency patterns are discussed in §1.0.

Although in the initial stages of the investigation, a distinction between of ׀ X *yiqtol* and of ׀ X *qatal* constructions is made, and certain preliminary conclusions are formulated in §1.3, the differences between protases with *qatal* and *yiqtol*

turned out to be of no significance for the role of fronting in the protases of conditionals. For this reason, in §2.0 the only formal feature of the protases to receive systematic consideration is whether the construction has a fronted non-verbal constituent or not.

1.0. Verb-initial protases

1.1. ׀ *yiqtol* (303x)

In a pilot study, it became apparent that protases that commence with infinitive absolute constructions have some unique features. For this reason, instances of Type 1 and Type 2 with an infinitive absolute construction are treated separately as Type 3.

1.1.1. Type 1 V(X): *If A, then B* (190x)³

This instance of the category typically refers to a positive condition to be met by a (mainly⁴) discourse-active entity (1). This is by far the most frequently occurring pattern of use. Often a negative condition is involved (2). The protasis as a rule precedes the apodosis. However, the protasis also occasionally follows the apodosis. A positive (3) or negative condition (4) may be involved in the latter case.

³ In about 17 percent (32/190) of the cases, the apodosis has a fronted non-verbal constituent.

⁴ For exceptions, cf. Amos 3.6a, 6b; 6.9; Ps. 7.13; Prov. 6.28; Job 14.14; Song 8.7; Eccl. 11.3ab.

- (1) אִם-אֶמְצָא בְּסוֹדֹם חֲמִשִּׁים צְדִיקִים בְּתוֹךְ הָעִיר וְנִשְׁאַתִּי לְכָל-הַמָּקוֹם בַּעֲבוּרָם
 ‘If I find at Sodom fifty righteous in the city, I will forgive
 the whole place for their sake.’ (Gen. 18.26)⁵
- (2) וְאִם-לֹא תֵאָבֶה הָאִשָּׁה לָלֶכֶת אַחֲרָיִךְ וְנִקִּיתִי מִשְׁבַּעְתִּי זֹאת
 ‘But if the woman is not willing to follow you, then you
 will be free from this oath of mine.’ (Gen. 24.8)⁶

⁵ 98x: Gen. 13.16b; 30.31; Exod. 12.4, 22.6b; 29.34 Lev. 2.14; 13.57; Num. 12.6b; 22.18ab–b; 24.13; 36.4; Deut. 30.4; Josh. 2.20; Judg. 4.8ab; 13.16aa, ab–ac; 15.7b; 16.7b; 21.21; 2 Sam. 10.11a; 15.25b, 1 Kgs 1.52ab–ac; 2.4b–c; 3.14; 12.27; 13.8ab–ac; 2 Kgs 2.10ba; 7.4aa, bb, bc; Isa. 1.18ba, bb; 10.22; 21.12ba; 53.10ab–ab; Jer. 15.19ab (may also be Type 2); 22.24b–c; 31.36; 33.20ab–21a; Hos. 9.12; Amos 3.6a, b; 5.22; 6.9; 9.2a, 2b, 3a, 3b, 4; Nah. 3.12; Hag. 2.13ab; Hab. 2.3ba; Pss 27.3a, 3a–b; 50.12; 68.14; 132.12; 137.5; Job 8.18; 9.3; 9.20a; 14.7, 14; 16.6a; 17.13; 22.23; 27.14; 31.13–14; 33.5; Prov. 1.10; 3.24a; 4.12b; 6.28; 27.22; Song 5.8b; 8.7b; Ruth 3.13aa; 4.4ba, bb; Eccl. 4.10a, 11, 12; 8.17c; 10.11; 11.3aa; Neh. 1.9b; 2.5ab; 3.35; 13.21ab; 1 Chron. 19.12; 28.9ba, bb; 2 Chron. 15.2cb, cc; 20.9. In Gen. 38.17 and Judg. 13bb the apodoses are elided.

⁶ 37x: Gen. 4.7ab–ac; 34.17; 44.23, 32b; Exod. 13.13ab; 22.7; 34.20ab; 40.37; Lev. 5.7, 11; 12.8; 25.54; 27.27b; Num. 19.12b; 32.23, 30; 33.55; Deut. 24.1; 25.7; 28.15, 58–59; Judg. 4.8b; 14.13; Isa. 7.9b; Jer. 12.17; 13.17; 17.27; 22.5; 26.4b–6; 38.18; Pss 7.13a; 59.16b; Job 36.12; Song 1.8; Ruth 3.13ab; 4.4bb.

- (3) וְלֹא אֲסִיף לְהִנָּיֵד רֶגֶל יִשְׂרָאֵל מִן־הָאָדָמָה אֲשֶׁר נָתַתִּי לְאַבוֹתָם בְּקִי אִם־
 יִשְׁמְרוּ לַעֲשׂוֹת כְּכֹל אֲשֶׁר צִוִּיתִים וּלְכָל־הַתּוֹרָה אֲשֶׁר־צִוָּה אֹתָם עַבְדִּי מֹשֶׁה:
 ‘And I will not cause the feet of Israel to wander any more
 out of the land that I gave to their ancestors, **if only they**
will be careful to do according to all that I have com-
manded them, and according to all the law that my servant
Moses commanded them.’ (2 Kgs 21.8b)⁷
- (4) אֶת־שְׁנֵי בְנֵי תָמִית אִם־לֹא אָבִיאָנוּ אֵלֶיךָ
 ‘You may kill my two sons **if I do not bring him back to**
you.’ (Gen. 42.37ab–ac)⁸

1.1.2. Type 2 V(X): If A^1 and A^n , then B (58x)⁹

The most frequent instances of this configuration are those where the protasis consists of more than one clause, but only the verb of the first clause is preceded by אם (5). In a number of instances, a second clause and/or subsequent clauses of the protasis have a fronted constituent, i.e., *X yiqtol* (6).

Although the majority of these instances refer to positive conditions, a few negative ones are also attested (7).¹⁰ Typically, actions representing stages or different aspects of the same

⁷ 18x: Gen. 15.5; 18.28b, 30b; 34.15; 1 Sam. 25.22; 1 Kgs 8.25ab–bb; 20.10ab–b; 2 Kgs 18.23b; Isa. 36.8b; Jer. 2.28ab; Ps. 81.9; Prov. 1.10–14; 1 Chron. 22.13; 28.7; 2 Chron. 6.16ab–bb; 30.9bb–bc; 33.8.

⁸ 5x: Josh. 2.14; 7.12b; Prov. 4.16a, 16b. In Ps. 137.6a two separate conditions are referred to.

⁹ In about 16 percent (9/58) of the cases, the apodosis has a fronted non-verbal constituent.

¹⁰ In only one instance (Deut. 11.28) does the protasis follow the apodosis.

event¹¹ are predicated of discourse-active entities in categorical sentences. Relatively often, the apodosis entails more than one action.¹²

- (5) אִם-תֹּאבֹדוּ וְשָׁמַעְתֶּם טוֹב הָאָרֶץ תֹּאכְלוּ:
 ‘If you are willing and obedient, you shall eat the good of the land.’ (Isa. 1.19)¹³
- (6) וְאִם לֹא יִכְבְּסוּ וּבִשְׂאוּ לֹא יִרְחֹץ וְנִשְׂא עוֹנָו
 ‘But if they do not wash themselves or bathe *their body*, they shall bear their guilt.’ (Lev. 17.16)¹⁴

¹¹ Isa. 58.9–10 is an exception, where different actions required by the discourse-active entity are referred to.

¹² E.g., Lev. 13.53–54; 26.21–22; Deut. 19.8–9; 30.17–18; 1 Kgs 6.12–13; Isa. 58.13–14.

¹³ 30x: Gen. 28.20b–22; 32.9; Lev. 13.21, 53–54; 14.43–44; 26.21–22; Num. 32.29; Deut. 19.8–9; 30.17–18; 1 Sam. 17.9a; 2 Sam. 11.20–21; 1 Kgs 6.12–13; 9.4–5; 11.38; Isa. 1.20; 58.13–14; Jer. 2.22; 15.19aa (may also be Type 1); 37.10; Job 11.10; 20, 12–14; 36.11; Eccl. 6.3; 2 Chron. 6.22–23, 24–25; 7.19–20; 10.7. In 1 Sam. 12.14 the apodosis is elided. Job 31.5–40 requires further investigation.

¹⁴ 10x: 1 Kgs 6.12–13; 9.4–5; Job 14.8–9; 20.6–7; 31.7–8; 34.14–15; 2 Chron. 7.17–18. In Ps. 89.31–33 a second, third, and fourth clause have a fronted constituent. In each instance, alternative topics are selected. In Job 27.16–17 a different point of comparison is fronted. A feature shared by all these examples is that in the first clause (without a fronted constituent) a set of related topics is (potentially) triggered. In the subsequent clause(s) one (or more) of these accessible topics is (are) fronted. What is predicated about them is slightly different from, but closely related to, the predication in the first clause of the protasis, e.g., in (6) Lev 17.16aa, the predication is ‘not wash’, and in 16ab, it is ‘not bathe’. In other words, these constructions may be explained by means of what Khan and Van der Merwe (2020, 370) refer to as “selecting a

- (7) וְהָיָה אִם-לֹא יֵאֱמִינוּ לָךְ וְלֹא יִשְׁמְעוּ לְקוֹל הָאֵת הָרִאשׁוֹן וְהֵאֱמִינוּ לְקוֹל הָאֵת
הַשֵּׁנִי:

If they will not believe you or heed the first sign, they may believe the second sign (Exod. 4.8).¹⁵

In a few instances each clause of the protases is preceded by אם (8). In these cases, it can be argued that events of relatively significant difference are involved.¹⁶ In a few rare instances in the parallel lines of poetic texts, אם is totally absent in the second protasis + apodosis pair (9).

- (8) אִם-תַּעֲנֶנָּה אֶת-בָּנֹתַי וְאִם-תִּקַּח נָשִׁים עַל-בָּנֹתַי אֲנִי אִישׁ עֹמְנוּ רָאָה אֱלֹהִים
עַד בֵּינִי וּבֵינֶךָ:

‘If you ill-treat my daughters, or if you take wives in addition to my daughters, though no one else is with us, remember that God is witness between you and me.’ (Gen. 31.50)¹⁷

topic.” I will refer to this function of fronting in this paper as “selecting alternative topics.” See also Van der Merwe, Naudé and Kroeze (2017, 501).

¹⁵ 6x: Exod. 4.9; Deut. 20.12; 1 Sam. 12.15. In Lev. 26.14–16, 26.15 specifies 26.14 with two אם X *yiqtol*s. In each instance alternative topics are selected. Cf. also (6).

¹⁶ Obad. 1.4 is an exception.

¹⁷ 8x: Num. 32.20–22; Mal. 2.2; Job 31.16–22 (in 20–21 *qatals* follow אם), 24–28 (in 24 a *qatal* follows אם), 29–30. Prov. 2.1–5. In Prov. 2.3, the second אם is followed by an X *yiqtol*. A similar construction occurs in Obad. 1.4aa.

- (9) אַם-אַפֿק שְׁמַיִם שָׁם אַתָּה וְאַצִּיעָה שְׁאוֹל הַנֶּגֶד:
 ‘If I ascend to heaven, you are there; if I make my bed in Sheol, you are there.’ (Ps. 139.8)¹⁸

1.1.3. Type 3 V(X): V = Infinitive Absolute Construction (55x)¹⁹

A distinctive feature of this category is the use of an infinitive absolute construction in clause-initial position in the protasis.²⁰ These protases number 40x of Type 1 (10) and 13x of Type 2 (11).

- (10) אַם-חָבֵל תְּחַבֵּל תְּחַבֵּל שְׁלֵמַת רֵעֶךָ עַד-בֹּא הַשָּׁמֶשׁ תִּשְׁיָבֶנּוּ לוֹ:
 ‘If ever you take your neighbour’s cloak in pledge, you shall return it to him before the sun goes down.’ (Exod. 22.25)²¹

¹⁸ 4x: Job 9.20b; 16.6b; Prov. 3.24b.

¹⁹ In about 9 percent (5/55) of the cases, the apodosis has a fronted non-verbal constituent.

²⁰ In two instances (Exod. 22.22 and Josh. 23.12–13), both protasis and apodosis are introduced by infinitive absolute constructions. In only one case (Song 8.7b), the apodosis alone is introduced with an infinitive absolute construction.

²¹ 40x: Exod. 19.5; 21.5–6, 22.22; Lev. 7.18; 13.7, 22, 27, 19.7; 20.4–5; 27.10b, 31, 33b; Num. 21.2; 30.13, 15, 16; Deut. 11.13, 22; 28.1; Judg. 11.30b–31; 16.11ab–b; 1 Sam. 12.25; 20.6, 7b, 9, 21b; 2 Sam. 15.8b; 18.3; 1 Kgs 20.39bb–bc; 22.28ab–ac; Jer. 12.16; 17.24–25; 22.4; 38.17; 42.10; Est. 4.14. In Deut. 15.5 and Zech. 6.15b, the protasis follows the apodosis. See perhaps also Lam. 5.22.

- (11) וְאִם שָׁכַב יִשָּׁכַב אִישׁ אֶתָּהּ וְתָהִי נִדְתָּהּ עָלָיו וְטָמֵא שְׁבַע יָמִים וְכָל־הַמִּשְׁכָּב
אֲשֶׁר־יִשָּׁכַב עָלָיו יִטָּמֵא:

‘If it indeed/ever happens that any man lies with her, and her impurity falls on him, he shall be unclean seven days; and every bed on which he lies shall be unclean.’ (Lev. 15.24)²²

Crucial for purposes of this study is, first, that in (10)–(11) (and the cases listed in the footnotes) some action or event Y is predicated of a discourse-active entity X by means of a categorical sentence (or sentences). In nearly all instances, the factuality of the action or event is profiled.²³

Second, only one instance of a protasis with an infinitive absolute construction and fronted non-verbal constituent is attested: (12). I have been unable to establish the function of this fronting.²⁴

²² 13x: Exod. 15.26; 23.22; Lev. 13.12–13, 35; 14.48; Num. 30.7–8; 35.26–27; Deut. 8.19; Josh. 23.12–13; Judg. 14.12; 1 Kgs 9.6; Jer. 7.5–7. Typically, protasis clauses that follow an initial clause introduced by an infinitive absolute construction are verb initial. Exod. 15.26 is an exception. Even more exceptional is Jer. 7.5–7: not only is the second clause of the apodosis also introduced by an infinitive absolute construction (as well as אם), but the third, fourth, and fifth clauses have a fronted constituent—in each case alternative topics are selected to be commented upon.

²³ For a more detailed description of the semantic functions of the infinitive absolute construction, see Van der Merwe, Naudé, and Kroeze (2017, 179–80). The function of the infinitive absolute construction in Lev. 14.48 is unclear.

²⁴ See also the major English translations, e.g., *ESV*, *CEB*, *NRSV*, and *NIV*, and commentaries on Jeremiah, e.g., Holladay (1989, 274), Allen

- (12) וְעַתָּה לִכְן שָׁמְעוּ דְבַר־יְהוָה שְׂאֵרֵי־יְהוּדָה כְּה־אָמַר יְהוָה עֲבָאוֹת אֱלֹהֵי
 יִשְׂרָאֵל אִם־אַתֶּם שׁוֹם תִּשְׁמָוּן פָּנִיכֶם לָבֹא מִצְרַיִם וּבִאתֶם לָגוֹר שָׁם:
 ‘Therefore hear the word of the LORD, O remnant of Judah.
 Thus says the LORD of hosts, the God of Israel: *If you are
 determined to enter Egypt and go to settle there.*’ (Jer.
 42.15)

Third, infinitive absolute constructions are attested only in protases with *yiqtol* verbs.

1.2. ׀ *Qatal* (77x)²⁵

1.2.1. Type 1 V(X): *If A, then B* (53x)²⁶

Instances of this category typically refer to a positive condition to be met by a (mainly²⁷) discourse-active entity (13)–(15). This is, as in cases where ׀ is followed by *yiqtol*, by far the most frequently occurring pattern of use.²⁸ Sometimes a negative condition is involved (16). The protasis as a rule precedes the apodosis.

(2008, 425), and Lundbom (2008, 11). Not one of these translators or commentaries appears to assign a function to the fronting.

²⁵ In about 8 percent (6/77) of the cases, the apodosis has a fronted non-verbal constituent.

²⁶ In about 8 percent (4/53) of the cases, the apodosis has a fronted non-verbal constituent.

²⁷ For an exception, cf. Ps. 41.7.

²⁸ In conditionals in the parallel lines of poetic texts, ׀ is sometimes (3x) absent in the second protasis + apodosis pair (Job 10.15; 35.6; Prov. 9.12).

However, although rare, the protasis may also follow an apodosis (17).

- (13) אם־שִׁכַּבְתִּי ואֲמַרְתִּי מָתִי אֶקוּם
 ‘When I lie down, I say, “When shall I rise?”’ (Job 7.4)²⁹
- (14) ואם־עָמְדוּ בְסוּדִי וַיִּשְׁמְעוּ דְּבָרִי אֶת־עַמִּי
 ‘But if they had stood in my council, then they would have proclaimed my words to my people.’ (Jer. 23.22)³⁰
- (15) וְהָיָה אִם־בָּא אֶל־אִשְׁתּוֹ אָחִיו וַיִּשְׁחַת אֶרְצָהּ לְבִלְתִּי נִתּוֹזֵרֶעַ לְאָחִיו:
 ‘So, whenever he went into his brother’s wife he would waste the semen on the ground, so as not to give offspring to his brother.’ (Gen. 38.9 *ESV*)³¹
- (16) וְהָיָה אִם־לֹא חִפְצָתָהּ בָּהּ וְשָׁלַחְתָּהּ לְנַפְשָׁהּ וּמָכַר לֹא־תִמְכְּרֶנָּה בְּכֶסֶף
 ‘But if you are not satisfied with her, you shall let her go free and not sell her for money.’ (Exod. 21.14)³²
- (17) הָבּוּ מִקְנֵיכֶם וְאֶתַנֶּנָּה לָכֶם בְּמִקְנֵיכֶם אִם־אָפַס כֶּסֶף
 ‘Give me your livestock, and I will give you food in exchange for your livestock, if your money is gone.’ (Gen. 47.16).³³

²⁹ 18x: Exod. 22.2a; Num. 14.8, 30.5; Isa. 28.25; Jer. 14.18aa, ab; Ezek. 43.11; Pss 41.7; 50.18; 94.18; Job 21.6; 35.6, 7; Prov. 9.12; 23.15; 24.14; Lam. 3.32.

³⁰ 13x: Judg. 16.17b; 2 Sam. 15.33; 2 Kgs 7.4ab; Amos 7.2; Ps. 66.18; 73.15; Job 9.15; 10.14, 15; 31.21–22, 33. In Jer. 15.1, the subjects are discourse inactive, but identifiable for the audience.

³¹ 3x: Judg. 6.3; Ps. 78.34.

³² 5x: Exod. 22.10ab; Lev. 25.28; Job 31.20, 31 (part of sequence of protases).

³³ 2x: Prov. 3.30, 30.

A number of instances of a fixed expression are attested (18). The latter constructions always appear in dialogue, where both interlocutors are discourse active. This fixed expression does not occur in texts that are typically associated with LBH.³⁴ Furthermore, it never occurs with a *yiqtol* form of the verb.

- (18) אִם-נָא מְצָאתִי חֵן בְּעֵינֶיכֶם דְּבַרְוּ-נָא בְּאַזְנֵי פִרְעָה לְאִמֹּר:
 ‘If now I have found favour with you, please speak to Pharaoh as follows:’ (Gen. 50.4)³⁵

1.2.2. Type 2 V(X): If A^1 and A^n , then B (24x)³⁶

Like instances of this configuration with a *yiqtol* verb, most frequent are instances where the protasis consists of more than one clause, but only the verb of the first clause is preceded by אִם (19). The overall majority are positive conditions.³⁷ In all these cases, typically, actions representing stages or different aspects of the same event are predicated of discourse-active entities in categorical sentences. In a few instances each clause in the protasis is preceded by אִם (20). However, the reason for the particle’s repetition is unclear.

³⁴ However, see (21) below.

³⁵ 10x: Gen. 18.3; 33.10; 47.29b; Exod. 33.13; Num. 11.15b; 32.5; Judg. 6.17; 1 Sam. 20.29ab–ac; 27.5. In Gen. 30.27, the apodosis has been elided.

³⁶ In about 8 percent (2/24) of the cases, the apodosis has a fronted non-verbal constituent.

³⁷ Gen. 43.9 and Lev. 5.28 are exceptions.

- (19) וְהָיָה אִם-נִשְׁךְ הַנָּחָשׁ אֶת-אִישׁ וְהִבִּיט אֶל-נָחָשׁ הַנָּחָשׁ וַחֲיִי:
 ‘When a snake bit someone, and he looked up to the snake,
 he would live.’ (Num. 21.9)³⁸
- (20) אִם-נִבְלַתְּ בְּהִתְנַשָּׂא וְאִם-זָמַמְתָּ יָדְךָ לִפְהֶךָ:
 ‘If you have been foolish, exalting yourself, or if you have
 been devising evil, put your hand on your mouth.’ (Prov.
 30.32)³⁹

The fixed expression identified in (18), which is rare in LBH, is attested in Est. 5.8a (21) and 7.3a. It is significant, though, that in each of the latter two cases the former fixed expression is coordinated with a second fixed expression that seems to have replaced it in LBH.⁴⁰

- (21) אִם-מָצְאתִי חֵן בְּעֵינֵי הַמֶּלֶךְ וְאִם-עַל-הַמֶּלֶךְ טוֹב לָתֵת אֶת-שְׂאֵלָתִי וְלַעֲשׂוֹת
 אֶת-בְּקִשְׁתִּי יָבוֹא הַמֶּלֶךְ וְהָמָן אֶל-הַמִּשְׁתֶּה אֲשֶׁר אֶעֱשֶׂה לָהֶם
 ‘If I have won the king’s favour, and if it pleases the king to
 grant my petition and fulfil my request, let the king and
 Haman come tomorrow to the banquet that I will prepare
 for them.’ (Est. 5.8a)

³⁸ 17x: Gen. 47.6bb–bc; Num. 5.27, 28; 2 Kgs 7.4aa; Mic. 5.7b; Pss 7.5; 44.21; Job 9.16, 30–31; 31.5–6, 9–10; Prov. 6.1–3. In Ps. 63.6–7, the protasis follows the apodosis of the condition. In Isa. 4.4–5, Job 9.24, and Eccl. 10.10 the second clause of the protases has a fronted constituent, in each case involving the selection of an alternative topic.

³⁹ Also Lev. 5.19 and Ps. 7.4–6.

⁴⁰ See Est. 3.9; 5.4ab–b; 9.13ab–b; Neh. 2.5a; 1 Chron. 13.2.

1.3. Preliminary Conclusions

The following statistical profile of the 380 verb-initial protases can now be perceived.

1. About 80 percent (303) of the protases have *yiqṭol* and 20 percent (77) have *qaṭal* verbs.
2. Of the instances with *yiqṭol* verbs, nearly 25 percent (71/303) are of Type 2. In the case of instances with *qaṭal* verbs, about 31 percent (24/77) are of Type 2.
3. About 13 percent (40/303) of the apodoses with a *yiqṭol* verb have a fronted non-verbal constituent. In the apodoses with *qaṭal* verbs, this configuration is substantially less frequent, viz. about 8 percent (6/77).
4. When the verb is used in an infinitive absolute construction, the finite verb is never a *qaṭal*, and in only one case does the infinitive absolute construction not initiate the clause. The apodoses have a fronted non-verbal constituent in less than 10 percent (5/55) of the instances.
5. In protases that consist of more than one clause (Type 2), 15 instances⁴¹ were identified where some of the non-initial clauses have a fronted constituent. In each of these cases, the selection of an alternative topic can be postulated.
6. A distinction has also been made between positive and negative conditions. Instances where the protases followed the apodoses have also been considered separately.

⁴¹ 12x with a *yiqṭol* as initial verb and 3x with a *qaṭal* as the initial verb.

None of these heuristic distinctions has revealed any significant semantic differences relevant to this study.

If we now turn to protases with ׀X *yiqtol* and ׀X *qatal* configurations, we can focus on the possible function(s) of the fronting. We will not deal with the above-mentioned configurations separately.

2.0. ׀X Verb protases (96x)⁴²

As indicated earlier, unlike in §1.0, the data are not discussed in this section in terms of Type 1 and Type 2 constructions. Of Type 2, 22 instances⁴³ were identified in ׀X verb protases.

When one considers the 96 instances of ׀X verb protases in the Hebrew Bible,⁴⁴ it is possible to postulate the following in the overwhelming majority (85/96, i.e., nearly 89 percent) of the cases: as far as a specific discourse-active event or situation is concerned,⁴⁵ the fronted constituent refers to one or another

⁴² In only about 7 percent (7/96) of the cases does the apodosis have a fronted non-verbal constituent.

⁴³ In Exod. 18.23; 22.1; Lev. 13.23, 28; 26.23–24; Num. 30.11–12; 35.16, 17; Deut. 20.11; 22.25; Judg. 6.3; 1 Sam. 17.9b; 2 Sam. 15.34; 1 Kgs 12.7; Job 19.5 the second and/or later clauses of the apodosis are verb-initial. In Lev. 13.37; 26.3; Num. 16.29; 35.20–21, 22–24; Judg. 9.16–18; and Job 31.39–40 some or all of the non-initial clauses also have a fronted constituent. In each case, the selection of an alternative topic can be postulated.

⁴⁴ Of these instances, 73 have ׀X *yiqtol* and 23 ׀X *qatal*.

⁴⁵ In a few cases the discourse-active event has to be construed from context. See, for example, (37)–(40).

(non-verbal) aspect, for example, a person, thing, or circumstance of the discourse-active event or situation that can be construed as a selection from a set of more than one possible alternatives (or variables).

The closed set of alternatives may consist of only two members, as in (22) and (23). However, in a legal frame the set of alternatives is often more than two. In the case of (24), the rest of the closed set who may sin can be found in Lev. 4.13 (the congregation of Israel) and 4.27 (an individual member of the Israelite community).

- (22) אַם-יִוָּכַל לְהִלָּחֵם אִתִּי וְהָצַנִּי וְהָיִינוּ לְכֶם לַעֲבָדִים וְאִם-אֶנִּי אוֹכֵל-לוֹ וְהָכִיתִיו וְהָיִיתֶם לָנוּ לַעֲבָדִים וְעַבְדֶּתֶם אֹתָנוּ:

‘If he is able to fight with me and kill me, then we will be your servants; **but if I prevail against him and kill him**, then you shall be our servants and serve us.’ (1 Sam. 17.9)⁴⁶

- (23) וְאִם-מִזְבֵּחַ אֲבָנִים תַּעֲשֶׂה-לִּי לֹא-תִבְנֶה אֹתָהּ מִגִּזִּית

‘**But if you make for me an altar of stone**, do not build it of hewn stones.’ (Exod. 20.25)⁴⁷

⁴⁶ 7x: 2 Sam. 10.11b || 1 Chron. 19.12b; 1 Kgs 1.52b. See also 1 Sam. 26.19ba–bb and Job 8.4, 5–6.

⁴⁷ 4x: see also Lev. 4.32; 12.5; 27.22–23 and Job 31.39–40.

- (24) אם הכהן המשיח יחטא לאשמת העם והקריב על חטאתו אֶשֶׁר חָטָא פָּר
בְּזֶבֶק תָּמִים לַיהוָה לְחַטָּאת:

‘If it is *the anointed priest* who sins, thus bringing guilt on *the people*, he shall offer for the sin that he has committed a bull of the herd without blemish as a sin offering to the LORD.’ (Lev. 4.3)⁴⁸

Although at first glance “alternative topics” appear to be selected, as I mentioned earlier in this paper, (22)–(24), like (25)–(40), do not meet the criteria for “the selection of a topic” in a context where “the fronted constituent and the following predication contain a focus” (Khan and Van der Merwe 2020, 370). The alternative(s) that are selected occur in a context “where the speaker/writer informs the reader of a variable in a presupposition in the common ground.” In the case of (23), altars to be built are involved, the alternative variable is the type of altar. In the case of (24), what must be done to people who are sinning is at stake, the alternative variable is the identity of the group of people who have sinned. In terms of Khan and Van der Merwe’s (2020, 366) types of focus, these cases could be labelled as a type of selective focus. Not all are like (22), i.e., prototypical instances of selective focus, since a prototypical instance of this category “involves specifying a member of a presupposed set of possible specific alternatives as the variable within a proposition in the common ground” (Khan and Van der Merwe 2019, 366). In (23) and (24) the member(s) selected do not exclude or contrast with other variables, but present each as a possible alternative.

⁴⁸ 12x: see also Exod. 21.4, 9, 10, 27, 32; Lev. 4.13, 27; Num. 15.27. Outside a legal frame, see Jer. 49.9a; Obad. 1.5 and Zech. 14.18.

Furthermore, selecting topic constructions are typically associated with things and living entities. However, in אִם X verb constructions in protases, the Xs are circumstantial, for example, spatial (25), temporal (26), or modal (27) in nature. The alternative purpose of an event may also be involved (28), as well as what was said in a situation (29). In (30), only the cataphoric reference to the alternative content is fronted.

- (25) וְאִם-בִּשְׂדֵה יִמְצָא הָאִישׁ אֶת-הַנָּעִר הַמֵּאֲרָשָׁה וְהִחְזִיק-בָּהּ הָאִישׁ וְשָׁכַב עִמָּה
וּמֵת הָאִישׁ אֲשֶׁר-שָׁכַב עִמָּה לְבִדּוֹ:

‘But if the man meets the engaged woman *in the open country*, and the man seizes her and lies with her, then only the man who lay with her shall die.’ (Deut. 22.25)⁴⁹

- (26) אִם-בִּמְחֻתָּרֶת יִמְצָא הַגֵּנֵב וְהָכָה וּמָת אִין לוֹ דָּמִים
‘If the thief is caught *while breaking in* and is beaten and dies, the one who killed him won’t be guilty of bloodshed.’
(Exod. 22.1)⁵⁰

- (27) אִם-בְּגִפּוֹ יָבֹא בְּגִפּוֹ יֵצֵא
‘If he comes *in single*, he shall go out single.’ (Exod. 21.3).⁵¹

⁴⁹ 8x: Lev. 6.21b; Num. 13.23, 28, 41; 30.11–12; 2 Sam. 15.34; 17.13.

⁵⁰ 6x: Num. 30.9; 1 Kgs 12.7. In Exod. 21.21; Lev. 25.52; and Eccl. 11.8 the temporal adjunct that is fronted refers to duration.

⁵¹ 14x: Lev. 7.12; Num. 10.4; 15.24; 16.29; 35.16, 17, 20–21, 22–24; and Judg. 9.16–18 (3x), 19.

- (28) וַיֹּאמֶר אִם-לְשָׁלוֹם יֵצְאוּ תִפְשׂוּם חַיִּים וְאִם לְמִלְחָמָה יֵצְאוּ תִפְשׂוּם:
 ‘He said, “*If they have come out for peace*, take them alive;
if they have come out for war, take them alive.”’ (1 Kgs
 20.18).⁵²
- (29) וְהָיָה אִם-שָׁלוֹם תַּעֲנֶנּוּ וּפְתַחְתֶּהּ לָךְ וְהָיָה כָּל-הָעָם הַנִּמְצָא-בָּהּ יִהְיוּ לָךְ לְעָמָס
 וְעֶבְדֶּיךָ
 ‘If they answer you, “Peace” and open their gates, then all
 the people in it shall serve you at forced labour.”’ (Deut.
 20.11).⁵³
- (30) אִם-כֶּפֶה יֹאמֶר נִקְדִּים יִהְיֶה שְׂכָרְךָ וְיִלְדוּ כָל-הָעֹצָן נִקְדִּים וְאִם-כֶּפֶה יֹאמֶר
 עֲקָדִים יִהְיֶה שְׂכָרְךָ וְיִלְדוּ כָל-הָעֹצָן עֲקָדִים:
 ‘If he said *thus*, “The speckled shall be your wages,” then all
 the flock bore speckled; and if he said *thus*, “The striped shall
 be your wages,” then all the flock bore striped.”’ (Gen.
 31.8).⁵⁴

In most of the cases listed in (24)–(30), the set of alternatives is closed, or can be construed as a closed set of possible alternatives. Each of them can also be labelled as a type of ‘selective’ focus.

In a few instances, the narrow focus involved could be regarded as a restrictive focus (31)–(33), since it “selects the only possible candidate from the supposed open set” (Khan and Van der Merwe 2020, 366).

⁵² 1 Chron. 12.18bb (2x).

⁵³ 4x: Prov. 2.3 (part of 2.1–5). In Jer. 5.2, the content of what is said represents an extreme alternative, namely, a solemn oath. In other words, “Even if they say, ‘as surely as the LORD lives,’ they still swear falsely.” See also Jer. 23.38.

⁵⁴ 7x: 1 Sam. 14.9, 10; 20.7a, 22; 2 Sam. 15.26.

- (31) אִם־יְהוָה | לֹא־יִבְנֶה בַּיִת שָׁא | עֲמָלּוֹ בּוֹנֵיו בֶּן אִם־יְהוָה לֹא־יִשְׁמְרֶנּוּ שָׁא | שְׂקָד שׁוֹמֵר

‘Unless the LORD builds the house, those who build it labour in vain. Unless the LORD guards the city, the guard keeps watch in vain.’ (Ps. 127.1)⁵⁵

- (32) וְאִם־שָׁלַשׁ־אֵלֶּה לֹא יַעֲשֶׂה לָּהּ וַיֵּצֵאָה חֲנֹם אֵין בָּסָף |
‘And if he does not do these three things for her, she shall go out without debt, without payment of money.’ (Exod. 21.11)

- (33) וַיֹּאמֶר הַכֹּהֵן חֲרֹב גִּלְיָת הַפְּלִשְׁתִּי אֲשֶׁר־הָבִיתָ | בְּעֵמֶק הָאֵלֶּה הִנֵּה־הִיא לִוְיָהּ |
בְּשִׁמְלָהּ אַחֲרֵי הָאֶפֹּד אִם־אַתָּה תִּקַּח־לָךְ קֶחַ כִּי אֵין אַחֲרֶיהָ זֹלָתָהּ בָּזָה |
‘The priest said, “The sword of Goliath the Philistine, whom you killed in the valley of Elah, is here wrapped in a cloth behind the ephod; if you will take that, take it, for there is none here except that one.”’ (1 Sam. 21.10).⁵⁶

In a few instances it is not immediately obvious whether restrictive narrow focus should be postulated, or rather a selection from a set of alternative topic-like entities.⁵⁷ In (34), for example,

⁵⁵ See also Exod. 18.23. In the case of Num. 22.20b, reference is made to the exclusive reason for someone coming to the addressee, i.e., “If the sole reason for the men was coming to summon you, then....”

⁵⁶ In Lev. 26.18, 23–24, and 27 reference is made via a fronted cataphoric pronoun to extreme measures God took to persuade his people.

⁵⁷ In Num. 20.17 Moses asks the Edomites to allow the Israelites to pass through their land and promises that they will not pass through any field or drink of the water from their wells. The Edomites refuse their request. The Israelites then come up with a more realistic promise in v. 19: 19: בְּמַסְלָה נַעֲלֶה וְאִם־מִמֶּיֶד נִשְׁתָּה אֲנִי וּמִקְנִי וְנִתְתִּי מִכָּרָם | ‘Only on the highway we will keep, and if we drink your water, we or our livestock, we will pay you its price.’ It is possible to argue that the Edomites refuse to

which is very similar to (6), it appears as if a series of alternative topics are selected. However, it can also be argued that the condition is that exclusively the Lord's statutes and commands must be kept, like his Sabbaths—not those of the idols (Lev. 26.1). Although not so evident as in (34), but nevertheless possible, it is reasonable to regard (35) as a similar instance of restrictive focus. A formal feature that is shared by (31), (34), and (35) is that אם is repeated before each clause in the protasis⁵⁸

- (34) אם־בְּחֻקֹּתַי תֵּלְכוּ וְאֶת־מִצְוֹתַי תִּשְׁמְרוּ וְעִשִּׂיתֶם אֹתָם:
 ‘If you follow *my statutes* and keep *my commandments* and observe them faithfully, ...’ (Lev. 26.3)
- (35) כֹּה־אָמַר יְהוָה צְבָאוֹת אם־בְּדַרְכֵי תֵלֵךְ וְאִם אֶת־מִשְׁמְרֹתַי תִּשְׁמֹר וְגַם־אֶתֶּהָ תִּדְּרִן אֶת־בֵּיתִי וְגַם תִּשְׁמֹר אֶת־חֲצֵרִי
 ‘Thus says the LORD of hosts: “If you will walk *in my ways* and if you keep *my requirements*, then you shall rule my house and have charge of my courts.”’ (Zech. 3.7)

comply out of fear that the Israelites and their livestock would eat from their land and drink from their wells. In their reply, the Israelites acknowledge by implication that it would be hard to pass through a land without drinking water. Between the alternatives, food and water, one, i.e., water, is selected for comment. However, it can also be argued, that the Israelites first committed themselves to travel ‘*only* on the highway’, and then pledge ‘if any whatsoever of the Edomites’ water’ is drunk by them or livestock, they will pay for it. In the latter instance a type of restrictive focus or perhaps even scalar focus (Khan and Van der Merwe 2020, 378–79) could be postulated.’

⁵⁸ Ps. 89.31–32 is not easy to explain. Its repetition of אם is not exactly the same as in (31), (34), and (35).

Instances of fronting where the verb of a protasis is הָיָה are rare. In (36), an instance of narrow restrictive constituent focus can be postulated. The condition is: “If this matter has been from the king, and nobody else, then...”

- (36) אִם מֵאֵת אֲדֹנֵי הַמֶּלֶךְ נִהְיָה הַדָּבָר הַזֶּה וְלֹא הוֹדַעְתָּ אֶת-עַבְדִּיךָ
 “If this matter has been *from my lord the king*, you did not make it known to your servant” (1 Kgs 1.27).⁵⁹

In a few cases, the function of the fronted constituent most probably is indeed that of narrow selective focus. However, the discourse-active predication and other possible variables have to be construed from the preceding context. In (37), it can be argued that God may cause disaster to strike someone so that he/she dies (Job 9; 13; 17). However, in verse 23, it is the alternative of an instance where a disaster (and not God) causes someone’s death. In (38), it may be argued that “money” and not something else, for example, an animal (verse 13), is lent to God’s people. In (39), it might be argued that the role of God as creator of the normal order of things is discourse active. The narrow selective focus of the protasis is that “if it is *something new* that God created.” In (40), a “ransom” can be construed as an alternative “punishment” to that of the death penalty that is imposed on the guilty party referred to in Exod. 21.29.

⁵⁹ In two other instances with הָיָה, alternatives can be postulated. In Exod. 21.23, it is a serious injury as alternative to a less serious one; and in Deut. 22.20, it is when a claim is true, as alternative to a false claim. Each case represents an instance of selective narrow focus.

- (37) אם־שׁוּט יָמִית פֶּתְאֵם לְמִסַּת נְקִיִּים יִלְעָג
 ‘When *disaster* brings sudden death, he mocks at the calamity of the innocent.’ (Job 9.23)
- (38) אם־בָּסַף | תִּלְוֶה אֶת־עַמִּי אֶת־הָעֲנִי עִמָּךְ לֹא־תִהְיֶה לוֹ בְּנִשָּׁה לֹא־תִשְׁיָמוּן עָלָיו
 נֶשֶׁךְ:
 ‘If you lend *money* to my people, to the poor among you, you shall not deal with them as a creditor; you shall not exact interest from them.’ (Exod. 22.24)
- (39) ואם־בְּרִיאָה יִבְרָא יְהוָה וּפִצְתָּהּ הָאֲדָמָה אֶת־פִּיהָ וּבִלְעָה אֹתָם וְאֶת־כָּל־אֲשֶׁר
 לָהֶם וַיֵּרְדּוּ חַיִּים שְׂאֵלָה וַיִּדְעֻם כִּי נֶאֱצָו הָאֲנָשִׁים הָאֵלֶּה אֶת־יְהוָה:
 ‘But if the LORD creates *something new*, and the ground opens its mouth and swallows them up, with all that belongs to them, and they go down alive into Sheol, then you shall know that these men have despised the LORD.’ (Num. 16.30)
- (40) אם־כֶּפֶר יוֹשֶׁת עָלָיו וְנָתַן פִּדְיוֹן נִפְשׁוֹ כָּל־אֲשֶׁר־יוֹשֶׁת עָלָיו:
 ‘If a *ransom* is imposed on the owner, then the owner shall pay whatever is imposed for the redemption of the victim’s life.’ (Exod. 21.30)

In (41)–(44), like in (12), I have failed to identify any possible alternative variables to construe.

- (41) ואם־בְּעֵינָיו עֲמִד הַנֶּתֶק וְשָׁחַר צֶמַח־בּוֹ נִרְפָּא הַנֶּתֶק טְהוֹר הוּא
 ‘But if *in his eyes* the itch is checked, and black hair has grown in it, the itch is healed, he is clean.’ (Lev. 13.37)⁶⁰

⁶⁰ See also Job 19.5.

- (42) אִם-רוּחַ הַמוֹשֵׁל תִּעֲלֶה עָלֶיךָ מִקוֹמְךָ אֶל-תֵּנְךָ
 ‘If the anger of the ruler rises against you, do not leave your post.’ (Eccl. 10.4)⁶¹
- (43) אִם-עוֹנוֹת תִּשְׁמְרֶנָּה אֲדֹנָי מִי יַעֲמֹד:
 ‘If you, O Lord, should mark *iniquities*, Lord, who could stand?’ (Ps. 130.3)⁶²
- (44) הִנֵּה אֲנֹכִי מַצִּיג אֶת-גִּזְזֵי הַעֲמָר בַּגֶּרֶן אִם טֵל יִהְיֶה עַל-הַגִּזָּה לְבִדָּה וְעַל-כָּל-
 הָאָרֶץ חֹרֵב וְיָדַעְתִּי כִּי-תוֹשִׁיעַ בְּיָדִי אֶת-יִשְׂרָאֵל
 ‘Look, I am going to lay a fleece of wool on the threshing floor; if there is dew on the fleece alone, and it is dry on all the ground, then I shall know that you will deliver Israel by my hand.’ (Judg. 6.37b)

In one case, the protasis with a fronted constituent follows the apodosis (45). In this case, it is also not possible to postulate a set of alternatives from which the fronted subject could have been selected.⁶³

- (45) וְכָל אֲשֶׁר יִהְיֶה אֵתָּךְ בְּבַיִת דָּמּוֹ בְּרֹאשֵׁנוּ אִם-יָד תִּהְיֶה-בָּו:
 ‘...their blood will be on our head if a hand is laid on them.’
 (Josh. 2.19)

What is significant about some these ‘problematic’ cases is that the fronted constituent is indefinite, for example (37)–(40) and

⁶¹ Also Eccl. 5.7.

⁶² See also Jer. 14.7 and Job 34.32.

⁶³ One of the reviewers suggested that one could postulate an instance of scalar narrow focus, in other words, ‘if *even* a hand is laid on them’. It is indeed possible. For the notion ‘scalar focus’, see Khan and Van der Merwe (2020, 369).

(43)–(45). In the case of (44), like in Judg. 4.20, the indefinite subject may suggest the presence of athetic sentence.⁶⁴

3.0. Conclusions

This exploratory study has a limited scope. It focuses on the function of the fronting in 399 verbal sentences in the protases of conditional clauses that are introduced by ׀⌘. Given the nature of conditional clauses as setting up one or more alternative mental spaces, the study addresses the question of whether one should expect that the fronting of a non-verbal constituent prototypically functions as a type of narrow focus rather than to select alternative topics or mark athetic sentence in the protases of conditionals.⁶⁵ It has been established that this is indeed the case. In 76 percent (73/96)⁶⁶ of the cases of fronting, it can be argued

⁶⁴ “In such constructions the whole sentence is in broad focus with no presuppositional component. They involve only one domain of focus. They present the proposition of the clause as a unitary situation. The fronted items do not serve as the base of predication about which a predication is made” (Khan and Van der Merwe 2020, 378–79).

⁶⁵ According to Atkinson (2021, 189), the fronting of 964 verbal clauses in Samuel–Kings can be explained in 32.5 percent of the cases as topic selection/shift, in 35 percent as a type of narrow focus, and in 32.5 percent asthetic sentences.

⁶⁶ In 24 percent (96 of the 399) of the verbal apodoses in our corpus, a non-verbal constituent is fronted. In comparison with the 14 percent in narrative material and 34 percent in poetic material as established by Lunn (2006, 276–78), the 24 percent of the instances of fronting in apodoses occupy an in-between position. Fronting in the protasis of conditionals also occurs significantly more frequently than in the apodosis, namely, 13 percent versus 24 percent.

that a type of selective narrow focus is involved and in 12.5 percent (12/96) cases restrictive narrow focus. In cases where not the first, but a second or/and third clause of a protasis has a fronted constituent, it can be argued, almost as a rule, that an alternative topic has been selected.

In 11.5 percent (11/96) of the cases, it has not been possible to construe the selection of any alternative. In only two of these instances, it is possible thatthetic sentences are involved.

A secondary research question, which was only partially investigated, is that of the distribution of verbal clauses with fronting in the apodoses of the conditionals in our corpus. It was established that with $\text{𐤏𐤍 } yiq\text{ṭ}ol$ constructions, on average about 13 percent of the cases, the apodosis has a fronted non-verbal constituent. By contrast, a lower occurrence of fronting (8 percent) is attested in $\text{𐤏𐤍 } qat\text{al}$ constructions as well as $\text{𐤏𐤍 } X$ verb constructions.

Apart from establishing the functions of fronting in the above-mentioned apodoses, a number of parameters have not been taken into account in this exploratory study. These include, for example, the relevance of the diachronic layers of BH, the literary genres of the texts, and any distinctions between content, generic, speech act, and epistemic conditions (cf. Bivin 2017).

References

- Allen, Leslie C. 2008. *Jeremiah: A Commentary*. The Old Testament Library. Louisville, KY, and London: Westminster John Knox.

- Atkinson, Ian T. 2021. 'In Pursuit of a More Comprehensive Framework for Fronting in Classical Biblical Hebrew Prose'. PhD dissertation, Stellenbosch University.
- Bivin, William E. 2017. 'The Particle ׀ and Conditionality in Biblical Hebrew Revisited: A Cognitive Linguistic Account'. PhD dissertation, Stellenbosch University.
- Holladay, William L. 1989. *Jeremiah 2: A Commentary on the Book of the Prophet Jeremiah, Chapters 26–52*. Hermeneia. Minneapolis, MN: Fortress Press.
- Khan, Geoffrey A., and Christo H. Van der Merwe. 2020. 'Towards a Comprehensive Model for Interpreting Word Order in Classical Biblical Hebrew'. *Journal of Semitic Studies* 65/2: 347–90.
- Lundbom, Jack R. 2004. *Jeremiah 37–52*. Anchor Yale Bible Commentary 21C. New York: Doubleday.
- Lunn, Nicolas P. 2006. *Word-Order Variation in Biblical Poetry*. Bletchley, UK: Paternoster.
- Van der Merwe, Christo H., Jacobus. A. Naudé, and Jan H. Kroeze. 2017. *A Biblical Hebrew Reference Grammar*. 2nd edition. London: Bloomsbury.

CONSIDERATIONS FOR THE DESIGN OF DEPENDENCY TREEBANKS FOR LINGUISTIC RESEARCH IN BIBLICAL HEBREW*

Robert S. D. Crellin

Geoffrey Khan's contributions to the linguistic study of Biblical Hebrew (BH) have been wide ranging. As a brief glance at his recent bibliography shows, his interests span the full range of the linguistic study of the language, for instance:

* The present contribution was completed as part of ongoing research on the CROSSREADS project. CROSSREADS has received funding from the European Research Council (ERC) under the Horizon 2020 research and innovation programme (grant agreement no. 885040). Syntax trees were drawn using software written by the present author in Python. The software converts the XML of these tree-banks into DOT (see <https://graphviz.org/doc/info/lang.html>). The resulting DOT file is compiled to PNG format using the Graphviz compiler in Dependency2Tree (<https://github.com/boberle/dependency2tree/>, last commit 2020) and Graphviz (<https://graphviz.org/>). I would like to record my gratitude to the editors and to the anonymous reviewers for their comments and advice, which has certainly improved this paper. In addition, I wish to thank Daniel Swanson for kindly sharing an advance copy of Swanson and Tyers (2022).

- Phonology (Khan 2020a; 2020b)
- Morphology (Khan 2013)
- Syntax (Khan 2019)
- Information structure (Khan 2019)

These topics are addressed not only in their own terms, but also together, in terms of the relationship between them, for instance:

- Phonology and morphology (Khan 2013)
- Morphology and information structure (Khan 2021)
- Syntax and information structure (Khan 2019)

The present chapter is inspired by Geoffrey Khan's multi-stratal engagement with BH to consider how recent advances in treebanking can help us better understand BH in the future.

Although treebanking efforts in ancient (and of course modern) languages are accelerating apace, there has been relatively little evaluation of the different principles and frameworks it is possible to adopt. It is relatively rare for treebank authors to provide in-depth discussion of the reasons for choosing a particular formalism. I could find no overt discussion of the rationale for choosing AGLDT (= Prague) in Vierros (2018) for PapyGreek, in Gorman (2020) for the Gorman treebanks, and in Keersmaekers et al. (2019) for the Pedalion trees; or for choosing Universal Dependencies in Zeldes and Abrams (2018), Luukko et al. (2020), and Swanson and Tyers (2022). Unusual, therefore, are Haug and Jøhndal (2008) and Bamman and Crane (2006), who provide detailed reasoning for the design of the PROIEL and ALDT annotation schemes, respectively. The lack of explanation or discussion of this kind is particularly conspicuous in the case

of treebanks that adopt Universal Dependencies (e.g., Zeldes and Abrams 2018; Luukko et al. 2020; Swanson and Tyers 2022), in light of criticism that the Universal Dependencies formalism has received (see below).

The present contribution aims to address this lack, at least in the context of ancient languages, and BH in particular. Special attention is paid to Universal Dependencies. This is in light of the facts both that it is fast becoming a *de facto* standard for the creation of dependency treebanks and that it has received considerable criticism regarding its design in linguistic terms.

The contribution has been written in the context of constructing a treebank, for the corpus of ancient inscriptions from ancient Sicily (Prag 2022). This corpus primarily comprises inscriptions written in Greek and Latin. However, a small subset are written in other languages, including the Semitic languages Punic and Hebrew. As such, the treebank is multilingual.

The contribution is written for anyone considering constructing a treebank for linguistic research, to bring together some of the general issues that need to be addressed in any treebanking project.

1.0. Importance of Corpora for the Study of Ancient Languages

Since for historical languages, like BH, our only recourse is to written records, the linguistic study of these languages is inherently reliant on corpora (Haug 2015, 187). Crucially, unlike living languages, there is no native speaker intuition to guide un-

derstanding of the underlying structure of the languages in question (Haug 2015, 187). Our understanding of these languages is therefore reliant on two sources: the original documents themselves and language theory (Haug 2015, 187).

2.0. Treebanks

A powerful way to bring together a given corpus with our general understanding of how languages work is to compile “structured corpora that are annotated for the assumptions that go into the research based on them” (Haug 2015, 192). Such corpora are often referred to by the term `TREEBANK`.

The last twenty years have seen a blossoming of such tree-banked corpora of the world’s languages. These vary in what they cover. Most consist of morphological and syntactic layers. It is the tree-like representation of syntactic and semantic structures that gave rise to the term `TREEBANK` (<https://en.wikipedia.org/wiki/Treebank>).

Additional layers are often included. For example, the Prague Dependency Treebank (Prague Dependency Treebank) includes a `TECTOGRAMMATICAL` layer, which brings together syntactic, semantic, and information structural features (Hajič et al. 2017, 563). Pragmatic Resources for Old Indo-European Languages (PROIEL) includes a layer describing information structure (Haug, Eckhoff, and Welo 2014).

2.1. Treebanks of Historical Languages

2.1.1. Syntactic Treebanking of Ancient Languages

In earlier years treebanks often used phrase structure grammars, e.g., the Penn Treebank (see Marcus, Santorini, and Marcinkiewicz 1994). With the growth of Natural Language Processing applications, including machine translation and question answering, (typed) dependency grammars have been preferred in recent years. Part of the reason for this is that in typed dependency grammars, the grammatical relations between elements (usually words, i.e., units demarcated by spaces) are directly specified, rendering computation of the relationship more straightforward. By contrast, in Phrase Structure Grammars this information must be derived from the structure as a whole, or specified separately (see further de Marneffe, MacCartney, and Manning 2006).

2.1.2. Phrase Structure Grammar Treebanks

Two Phrase Structure Grammar treebanks for ancient languages known to the present author are both for BH:¹

¹ An anonymous reviewer suggested the inclusion of *Biblical Hebrew Grammar Visualised* (Andersen and Forbes 2012). For the assertion that the grammars are phrase structure grammars, see p. 6. The reviewer also pointed out that “Holmstedt’s and Andersen and Forbes’ databases of BH, which are those used within the standard BH software programmes (Accordance Logos).” These are to my knowledge not Open Access databases; I, unfortunately, do not have access to them, and cannot bring them into the discussion.

- the Biblia Hebraica Stuttgartensia Amstelodamensis (BHSA), is provided by the Eep Talstra Centre for Bible and Computer (ETCBC; see <https://github.com/ETCBC/bhsa>), and is encoded in the Text-Fabric format (see <https://github.com/annotation/text-fabric>; see further Kingham and Van Peursen 2018).
- Clear Bible Macula Phrase Structure Grammar trees (see <https://github.com/Clear-Bible/macula-hebrew>).

2.1.3. Dependency Grammar Treebanks

Dependency treebanks have been built or proposed for the following old Semitic languages:

- Qurʾanic Arabic (QADT) (Dukes, Atwell and Sharaf 2010, using traditional Arabic grammar, إعراب);
- Akkadian (Luukko et al. 2020, using Universal Dependencies);
- Ancient Hebrew-PTNK (Swanson and Tyers 2022, using Universal Dependencies);
- Ugaritic (Zemánek 2007, using Prague Dependencies).

Apart from Swanson and Tyers' treebank (discussed below), the Ugaritic Treebank (Zemánek 2007) is of particular relevance for the present study, given the structural similarities of Ugaritic and Hebrew. Unfortunately, however, it appears to have been developed no further than the pilot stage.

Old Indo-European languages have also seen intensive treebanking efforts:

- Ancient Greek and Latin Dependency Treebank (AGLDT, Celano, Crane, and Almas 2014);

- Pragmatic Resources in Old Indo-European languages (PROIEL, Haug and Jøhndal 2008);
- PapyGreek (Vierros and Henriksson 2021);
- Corpus of the Epigraphy of the Italian Peninsula in the 1st Millennium BCE (CEIPoM, Pitts 2022);
- Pedalion treebanks (Keersmaekers et al. 2019);
- Gorman treebanks (Gorman 2020).

All but PROIEL use the AGLDT flavour of the Prague dependency formalism (Bamman and Crane 2006; Bamman and Crane 2011). PROIEL uses its own formalism, described in Haug and Jøhndal (2008), Haug et al. (2009), and Haug (2010).

In contrast to their Phrase Structure Grammar counterparts, efforts to build dependency treebanks of BH are in their infancy. Swanson and Tyers (2022) describe the initial construction of a syntax treebank for ancient Hebrew following the Universal Dependencies formalism. To my knowledge this is the only dependency treebank currently available for ancient Hebrew. However, Swanson and Tyers (2022) do not discuss explicitly their reasons for choosing Universal Dependencies over other Dependency Grammar formalisms.

In the present survey I focus on Dependency Grammar treebanks for two reasons: (1) this is the most active area of development for treebanks of historical languages, generally; (2) relatively little work has been done to develop Dependency Grammar treebanks of BH. These two reasons combined make it a good moment to survey the field and glean what might be useful for the development of Dependency Grammar treebanks for BH.

2.2. Designing a Treebank of Biblical Hebrew: Design Criteria

The design of a BH treebank will be affected by the primary applications of the project. In what follows we will see several examples of how this kind of consideration might play out in the design of a BH treebank.

It is possible to conceive of a wide range of possible applications for a treebank of BH: from automatically generating first drafts of Bible translations into a new language, to linguistic research into the distribution of particular syntactic phenomena. I will argue that a particular application (whether machine translation or linguistic research) is likely to benefit most from a treebank designed with this application in mind.

3.0. Dependency Grammar

3.1. Relatedness

Although elements of Dependency Grammar have been seen in the work of earlier scholars (see Kahane and Osborne 2015, xxx) and even in the Arabic grammatical tradition (Dukes, Atwell, and Sharaf 2010, 1822, with references), modern Dependency Grammar is generally seen as having its origin with Lucien Tesnière (Tesnière 1959, translated into English in Tesnière 2015).

The fundamental insight of Dependency Grammar is that “particular occurrences of minimal units are directly related to one another” (Hays 1964, 511). Tesnière (2015, §3) puts the matter as follows:

Each word in a sentence is not isolated as it is in the dictionary. The mind perceives **connections** between a word and its neighbours. The totality of these connections forms the scaffold of the sentence. (bold type original)

Tesnière does not define exactly what is meant by the notion of ‘dependency’. This is to say, he does not “produce a falsifiable definition” of the term (Kahane and Osborne 2015, lxi). Perhaps in consequence of this ambiguity, Dependency Grammar formalisms have interpreted the notion of dependency in different ways. The three key formalisms for our purposes are:

- Prague Dependencies
- Pragmatic Resources in Old Indo-European Languages (PROIEL)
- Universal Dependencies

It is beyond the scope of this brief article to elaborate on the detailed differences between these formalisms. I will instead focus on one key difference, which is the different interpretations of the notions of dependency that they embody:

1. Dependency as a representation of surface syntactic relations (Prague Dependencies analytical layer; PROIEL syntactic layer);
2. Dependency as a representation of syntax-semantic relations (Prague Dependencies tectogrammatical layer; Universal Dependencies).

To illustrate how this works in practice, let us consider the treatment of definite direct objects in *בָּרָא אֱלֹהִים אֶת הַשָּׁמַיִם* (Gen. 1.1), in which *אֶת הַשָּׁמַיִם* is a definite direct object headed by the

particle אֵת.² A surface-syntactic analysis (Figure 1, facing page) differs from a syntax-semantic one (Figure 2, facing page) in that the syntax-semantic analysis prioritises the semantic relationship of the verb (בָּרָא) and the direct object (הַשָּׁמַיִם), but minimises the structural feature that this relationship is mediated by a particle (אֵת).³ The surface-syntactic analysis, by contrast, prioritises the relatedness of the verb (בָּרָא) and the particle אֵת which heads the direct object phrase.

² The labels used in the examples provided in this section are taken from Universal Dependencies. The rules for structuring the relations do not always follow those of Universal Dependencies, for purposes of showing the different structuring rules that the respective surface-syntactic and syntax-semantic analyses imply. Trees that follow Universal Dependencies are labelled ‘Universal Dependencies’, while those which have been modified are labelled ‘modified Universal Dependencies’. ‘Modified Universal Dependencies’ is an adaptation purely for the present context to illustrate the difference between surface-semantic and syntax-semantic representations.

³ The Hebrew text of Gen. 1.1, Gen. 1.11, and Gen. 1.20 used in this section was sourced from the Unicode/XML Leningrad Codex, version UXLC 1.9, <https://tanach.us>. For version history, see <https://www.tanach.us/Pages/Supplements.html>.

Figure 1: Surface-syntactic dependency analysis of בָּרָא אֱלֹהִים אֶת הַשָּׁמַיִם





Figure 2: Syntax-semantic dependency analysis of בָּרָא אֱלֹהִים אֶת הַשָּׁמַיִם



The syntax-semantic analysis of בָּרָא אֱלֹהִים אֶת הַשָּׁמַיִם (Figure 2) captures well its structural similarity in semantic terms to examples involving indefinite direct objects, e.g., תִּדְשָׁא הָאָרֶץ דְּשָׂא (Gen. 1.11; Figure 3): in both cases the direct object participant is directly dependent on the main verb. By contrast, the surface-syntactic analysis (Figure 1) captures the structural similarity between בָּרָא אֱלֹהִים אֶת הַשָּׁמַיִם and sentences with prepositional phrase verbal complements e.g., וַעֲוִי יַעֲזֹבֶנּוּ עַל-הָאָרֶץ (Gen. 1.20; Figure 4, facing page): in both cases the main verb heads a particle mediating the relationship with the nominal, but the similarity with sentences involving indefinite direct objects (Figure 2) is much less obvious.

Figure 3: Surface-syntactic dependency analysis of תִּדְשָׁא הָאָרֶץ דְּשָׂא עֵשֶׂב





Figure 4: Surface-syntactic dependency analysis of $\text{וְעוֹהֵי יְעוֹפָק עַל־הָאָרֶץ}$



3.2. Universal Dependencies

Universal Dependencies is fast becoming the dependency formalism of choice for new treebanks and has recently been used for several projects annotating historical language corpora (Zeldes and Abrams 2018, Coptic; Luukko et al. 2020, Akkadian; Swanson and Tyers 2022, Hebrew). The PROIEL and AGLDT corpora have additionally been converted to Universal Dependencies.

While dependency grammars after Tesnière have tended to hew close to the structure of the surface syntax, per e.g., Figure 1 (Osborne and Maxwell 2015; Osborne and Gerdes 2019, 5), Universal Dependencies prioritises semantic relations (de Marneffe et al. 2021, 257). It follows that, in principle, all function words are subordinated to their objects, auxiliaries to their content word

counterparts, and copulas to their predicate nominals (for a full list see Osborne and Gerdes 2019, 4–5). Universal Dependencies therefore runs counter to the tradition of dependency grammars that have arisen since Tesnière (Osborne and Maxwell 2015).

3.2.1. Universal Dependencies: A Compromise between Surface- and Syntax-semantic Representations

Given Universal Dependencies’s prominence, it is worth considering in some detail the criticisms that have been voiced. Universal Dependencies has been criticised for its prioritisation of sentence-semantics over surface-syntactic structure (Osborne and Maxwell 2015; Gerdes and Kahane 2016; Osborne and Gerdes 2019). However, while this decision lies outside the mainstream of dependency grammars after Tesnière, the present author sees no problem with this, provided the semantics-first principle is adopted consistently.

Universal Dependencies is (syntactically) monostratal (de Marneffe et al. 2021, 268), and therefore represents a compromise between a representation of the surface syntax and the underlying syntactic-semantic relationships. It is a necessary consequence of this that neither of these will be represented consistently, as the designers recognise (de Marneffe et al. 2021, 268): “...UD representations end up looking like a hybrid of deep and surface-oriented representations, but where the tree structure is primarily determined by predicate-argument structure.”

In other words, Universal Dependencies trees are structured primarily in terms of semantic relations, but because Universal Dependencies is monostratal, they also include as nodes elements of

surface syntax. The problem with Universal Dependencies from a purely linguistic perspective, therefore, is not so much its departure from the representation of surface syntax in favour of semantic relations, but that it represents no single linguistic layer consistently (Osborne and Gerdes 2019, 10–12).

To understand why Universal Dependencies is the way it is, it is worth observing that Universal Dependencies is far from motivated by purely linguistic Considerations (see, e.g., de Marneffe, MacCartney, and Manning 2006). The sometimes-conflicting goals of Universal Dependencies are outlined as follows (abbreviated from <https://universaldependencies.org/introduction.html>). Universal Dependencies sets out to be:

1. ...satisfactory on linguistic analysis grounds for individual languages.
2. ...good for linguistic typology...
3. ...suitable for rapid, consistent annotation by a human annotator.
4. ...easily comprehended and used by a non-linguist...
5. ...suitable for computer parsing with high accuracy.
6. [Able to] support well downstream language understanding tasks (relation extraction, reading comprehension, machine translation, ...). (ellipsis original)

Only goals 1 and 2 are explicitly linguistic in character; the others are user-oriented (3, 4) and computational (5, 6). Indeed, goal 4 might be argued to run directly counter to a purely linguistic objective. It is not at all surprising, therefore, that inconsistencies, in purely linguistic terms, are inherent in the annotation scheme.

3.2.2. Prague Dependencies: Separating Surface-syntax and Semantics

An alternative approach is to split the treebank into multiple layers, as is done by the Prague Dependency Treebank. Prague dependency grammar consists of two layers above the morphological and textual, namely the ANALYTICAL and the TECTOGRAMMATICAL (Hajič et al. 2017, 557–58).

The analytical layer describes the surface syntax of sentences as a dependency tree (Hajič et al. 2017, 560–62). The nodes of the tree are the words of the sentence, that is, elements separated by blank spaces, along with the punctuation (on which see further below). The tree’s edges (for the most part) represent the grammatical relation holding between a syntactic head and a dependent, e.g., SUBJECT, DIRECT OBJECT, etc. The surface-syntactic nature of the annotation is shown, for example, in the fact that prepositions head their objects and modals head their content verbs (although this does not apply in the case of non-modal auxiliaries, on which see Osborne and Maxwell 2015, 247).

Complementing the surface-syntactic layer is the tecto-grammatical layer, which represents “the underlying dependency structure of the sentence” (Hajič et al. 2017, 563; see further 563–72; cf. de Marneffe et al. 2021, 268), that is, the syntactic-semantic layer (Fučíková et al. 2015, 62; Hajič et al. 2017, 556). At this layer of representation nodes correspond to content words, with function words viewed as “complex features” of these content words (Hajič et al. 2017, 563). This is to say that function words are not nodes in their own right.

While the Prague Dependency Treebank arguably represents linguistic layers more consistently, it also suffers from linguistic incoherence elsewhere. As discussed below, both Prague Dependencies and Universal Dependencies include punctuation marks in their trees. However, there are good reasons for not seeing these as syntactic in nature. This different status of punctuation marks is noted in passing by Hajič et al. (2017, 560–61), who state, in reference to the Prague dependency formalism: “Most of the edges represent dependency relations, while others stand for various linguistic or technical phenomena, e.g. coordination, apposition, punctuation, etc.”

3.2. Implications and Applications

It is not the purpose of the present paper to argue for one or another approach. Rather, my goal is to consider how the subject of a particular research project affects the kind of formalism one might want to adopt. It is clear from the preceding discussion that the goals of the designers of a system, e.g., for machine translation, will likely not fully align with those of the theoretical linguist (for similar observations along these lines, see also Haug 2015, 194). In the following, I consider three applications of treebanks to open questions in BH research, and how these affect the features of the treebank.

4.0. Application of Treebanks to Biblical Hebrew Research

4.1. Syntax-semantics Interface

It has been observed in the general linguistic literature that the selectional restrictions between the verb and the patient/theme argument are greater than those between the verb and the agent (for some discussion and illustration see Crellin 2016, 90–94). This is to say that the theme/patient argument has the potential to disambiguate verbal senses in a way that the subject cannot.⁴ A study concerned with such selectional restrictions may be more interested in the semantic structure of the verb's arguments than in the syntactic mechanism by which the grammatical relations are structured in the surface syntax, such as through function words like *תָּא* (cf. discussion above). For such a study, therefore, a formalism that prioritises semantics/lexical content over surface syntax, such as Universal Dependencies, or the semantic layer of Prague Dependencies, may be a better choice than one that does not, such as the surface syntactic layer of Prague Dependencies, or PROIEL.

4.2. Surface Syntactic Structure and Word Order


When comparing BH texts with texts written in an Old Indo-European language, such as Latin or Greek, an important issue to

⁴ For the disambiguating role of other sentence participants in general, see, e.g., Katz and Fodor (1963).

consider is the relationship between word order and surface syntax. In Latin and Greek, it is frequently the case that constituents are broken up with elements of other constituents (Bamman and Crane 2006). This state of affairs breaks the *projectivity* condition, which “requires each dependency subtree to cover a contiguous region of the sentence: a word and its transitive dependents must span a contiguous sequence in the linear order” (Mambrini and Passarotti 2013, 178).

The non-projectivity of Greek can be seen in the first two lines of the *Iliad* (text per Munro and Allen 1920), analysed in Figure 5 (following the analysis in Mambrini and Passarotti 2013, 178), where *μῆνιν* [anger.ACC] is head of both *Ἀχιλλῶς* [Achilles.GEN] and *οὐλομένην* [accursed.ACC], but these dependencies do not “span a contiguous sequence in the linear order,” as required by the projectivity condition (Mambrini and Passarotti 2013, 178).

Figure 5: Dependency analysis of *Iliad* 1.1–2 according to AGLDT



By contrast, BH is much more projective than Latin and Greek. Its projectivity may be observed in the dependency (AGLDT) analysis of Gen. 1.1 in Figure 6 (facing page), where all subtrees of a given node are represented in the linear order as contiguous sequences.⁵

In situations of language contact, as seen, for example, in New Testament Greek, it is in principle possible that crosslingual influence may be seen in the relative levels of projectivity observed. Ponti (2016, 543) observes that the level of projectivity (a surface-syntactic phenomenon) in later varieties of Greek (Postclassical) is higher than in earlier varieties (Classical, Archaic). At least in the case of the Greek New Testament, however, a likely projective influence on the language is that of Hebrew (and Aramaic). Ponti does not mention this possibility. In order to establish the extent to which crosslingual influence plays a role in the development towards projectivity in Greek, it would be possible to use dependency treebanks of BH, the Greek New Testament, and other varieties of Greek, to compare directly the levels of projectivity. Such an analysis could be conducted on the basis of a single surface-syntactic annotation layer.


⁵ The Hebrew text of Gen. 1.1 used in this section was sourced from the Unicode/XML Leningrad Codex, version UXLC 1.4, <https://tanach.us>, accessed 17 June 2022.

The accent systems in the Hebrew Bible have been an area of particular interest to Geoffrey Khan (see most recently Khan 2020b). Ancient punctuation systems are known to follow different principles from their modern counterparts (Wingo 1972 for epigraphic Latin; Morpurgo Davies 1987, for epigraphic ancient Greek; Zemánek 2007, 214, for Ugaritic; Crellin 2022 for epigraphic Northwest Semitic). These principles have been argued to be prosodic in nature (e.g., Morpurgo Davies 1987; Devine and Stephens 1994; Crellin 2022).

While it has been argued that Masoretic punctuation provides a syntactic analysis of the sentence (Aronoff 1985), a growing body of literature points to the roots of the Masoretic punctuation system being in the prosody of BH rather than directly in the syntax

(Dresher 1994; Khan 2020b; Pitcher 2020; 2021; 2023; Crellin 2022).⁶ Figure 7 provides an analysis of Gen. 1.1 in prosodic terms (see Park 2020, 15, Table 5, for the hierarchical status of disjunctive accents in Hebrew; see also the analysis at <https://www.tanakhml.org/d21.php2xml?sfr=1&prq=1&psq=1&lvl=99>).

Figure 7: Prosodic tree analysis of Gen. 1.1⁷



Surface-syntax and prosody have been shown to be related crosslinguistically, and some of the implications of this for BH have been explored over the past few decades (see, e.g., Dresher 1994; Crellin 2022 for examples, and references to the general

⁶ I am grateful to an anonymous reviewer for the references to Sophia Pitcher’s work. I have not had time to engage with these works since being made aware of them, but include them here for completeness.

⁷ Abbreviations in Figure 7: U = Utterance; φ = Major Phrase; φ = Minor Phrase; C = Conjunctive; D = Disjunctive. The subscript numbers relate to the strength of the division: the lower the number, the stronger the division. See, e.g., Dresher (1994).

linguistic literature). However, this research has primarily concerned the relationship between prosody and Phrase Structure Grammar, particularly through the phenomenon of *EDGE ALIGNMENT* (for edge alignment, see, e.g., Selkirk 2014 [1996]; for the application to BH, see, e.g., Crellin f.c.). To the best of my knowledge, the relationship between Dependency Grammar and prosody has not been explored for BH. A dependency treebank could be very helpful for such a project. In contrast to many current approaches, however, I suggest that a treebank built for this purpose for BH is best separated into two layers, one surface-syntactic, the other for prosody/punctuation.

Both the Prague Dependencies and Universal Dependencies formalisms allow for, and, indeed, expect, punctuation to be included in the (surface) syntactic layer of annotation. In two treebanks of Latin and Greek, AGLDT and PapyGreek, modern editorial punctuation has been included in the syntactic layer in this way. This is problematic, since this punctuation is introduced to facilitate reading by modern readers (Haug et al. 2009, 27; Reuben Pitts, §3.3, <https://reubenjpitts.github.io/Corpus-of-the-Epigraphy-of-the-Italian-Peninsula-in-the-1st-Millennium-BCE/vademecum>).⁸

The likely non-syntactic status of ancient punctuation means that its place is not properly in the syntactic layer. There is, therefore, a good case for separating it from the surface-syntactic layer of annotation, as is done in PROIEL (see Haug et al. 2009, 27) and CEIPoM

⁸ It is not clear that punctuation as it is used in modern texts written in European languages relates directly to syntax or indeed to anything linguistic (Krahn 2014, 63–74; Neef 2015, 711–12; see also Crellin 2022, 7).

(<https://reubenjpitts.github.io/Corpus-of-the-Epigraphy-of-the-Italian-Peninsula-in-the-1st-Millennium-BCE/vademecum>).

5.0. Conclusion

I observed that relatively few treebank authors provide an in-depth justification for using the particular formalism they adopt. Since dependency treebanking of BH is in the early stages, I set out to provide an overview, first, of existing treebanking efforts for ancient languages, and then to survey the implications of adopting any one of the three Dependency Grammar formalisms that have been used for treebanking ancient languages. This included a more in-depth consideration of the criticisms that have been made of Universal Dependencies, which is becoming a standard. Finally, I considered the application of treebanking to three areas of BH linguistic research—the syntax-semantics interface, projectivity and the syntax-phonology interface as interpreted through Masoretic punctuation.

References

- Andersen, Francis I., and A. D. Forbes. 2012. *Biblical Hebrew Grammar Visualized*. Winona Lake, IN: Eisenbrauns.
- Bamman, David, and Gregory Crane. 2006. ‘The Design and Use of a Latin Dependency Treebank’. In *Proceedings of the TLT 2006*, edited by J. Hajič and J. Nivre, 67–78. Institute of Formal and Applied Linguistics.
- . 2011. ‘The Ancient Greek and Latin Dependency Treebanks’. In *Language Technology for Cultural Heritage: Selected Papers from the LaTeCH Workshop Series*, edited by Caroline

- Sporleder, Antal Bosch, and Kalliopi Zervanou, 79–98. Berlin: Springer.
- Celano, Giuseppe G. A., Gregory Crane, and Bridget Almas (eds). 2014. *The Ancient Greek and Latin Dependency Treebank*. The Perseus Digital Library. https://perseusdl.github.io/treebank_data/
- Crellin, Robert S. D. 2016. *The Syntax and Semantics of the Perfect Active in Literary Koine Greek*. Chichester: Wiley Blackwell. <https://doi.org/10.1111/1467-968X.12080>
- . 2022. *The Semantics of Word Division in Northwest Semitic Writing Systems: Ugaritic, Phoenician, Hebrew, Moabite and Greek*. Oxford: Oxbow.
- . Forthcoming. ‘Main Clause Verbs are Prosodically Weaker than Nouns in Biblical Hebrew Prose Books’. In *The Intertwined World of the Oral and Written Transmission of Sacred Traditions in the Middle East*, edited by G. Khan, A. Fedeli, and J. Lundberg. Cambridge: Open Book Publishers.
- de Marneffe, Marie C., Bill MacCartney, and Christopher D. Manning. 2006. ‘Generating Typed Dependency Parses from Phrase Structure Parses’. *Language Resources and Evaluation Conference* 6: 449–54.
- de Marneffe, Marie C., Christopher D. Manning, Joakim Nivre, and Daniel Zeman. 2021. ‘Universal Dependencies’. *Computational Linguistics* 47/2: 255–308. https://doi.org/10.1162/COLI_a_00402
- Devine, Andrew M., and Laurence D. Stephens. 1994. *The Prosody of Greek Speech*. Oxford: Oxford University Press.

- Dresher, B. Elan. 1994. 'The Prosodic Basis of the Tiberian Hebrew System of Accents'. *Language* 70: 1–52.
- Dukes, Kais, Eric Atwell, and Abdul-Baqee M. Sharaf. 2010. 'Syntactic Annotation Guidelines for the Quranic Arabic Dependency Treebank'. In *Proceedings of the Seventh International Conference on Language Resources and Evaluation (LREC'10)*. European Language Resources Association (ELRA). http://www.lrec-conf.org/proceedings/lrec2010/pdf/278_Paper.pdf
- Fučíková, Eva, Jan Hajič, Jana Šindlerová, and Zdeňka Urešová. 2015. 'Czech-English Bilingual Valency Lexicon Online'. In *Proceedings of the Fourteenth International Workshop on Treebanks and Linguistic Theories (TLT14)*, edited by Markus Dickinson, Erhard Hinrichs, Agnieszka Patejuk, and Adam Przepiórkowski, 61–71. Warsaw: Polish Academy of Sciences. https://pure.knaw.nl/ws/portalfiles/portal/1712331/2015_Wouden_TLT14_proceedings.pdf#page=68
- Gerdes, Kim, and Sylvain Kahane. 2016. 'Dependency Annotation Choices: Assessing Theoretical and Practical Issues of Universal Dependencies'. In *Proceedings of the 10th Linguistic annotation workshop held in conjunction with ACL (LAW-X 2016)*. <https://halshs.archives-ouvertes.fr/halshs-01509118/document>
- Gorman, Vanessa B. 2020. 'Dependency Treebanks of Ancient Greek Prose'. *Open Humanities Data* 1/1: 1–3. <https://doi.org/10.5334/johd.13>

- Hajič, Jan, Eva Hajičová, Marie Mikulová, and Jiří Mírovský. 2017. 'Prague Dependency Treebank'. In *Handbook of Linguistic Annotation*, edited by Nancy Ide and James Pustejovsky, 555–94. Dordrecht: Springer.
- Haug, Dag T. T. 2010. 'PROIEL Guidelines for Annotation'. <http://dev.syntacticus.org/proiel-annotators-handbook-v1.pdf>
- . 2015. 'Treebanks in Historical Linguistic Research'. In *Perspectives on Historical Syntax*, edited by Carlotta Viti, 197–202. Amsterdam: John Benjamins. <https://doi.org/10.1075/slcs.169.07hau>
- Haug, Dag T. T., and Marius L. Jøhndal. 2008. 'Creating a Parallel Treebank of the Old Indo-European Bible Translations.' In *Proceedings of the Second Workshop on Language Technology for Cultural Heritage Data (LaTeCH 2008)*, edited by Caroline Sporleder and Kiril Ribarov, 27–34. European Language Resources Association. http://www.lrec-conf.org/proceedings/lrec2008/workshops/W22_Proceedings.pdf#page=31
- Haug, Dag T. T., Hanne Eckhoff, and Eirik Welo. 2014. 'The Theoretical Foundations of Givenness Annotation'. In *Information Structure and Syntactic Change in Germanic and Romance Languages*, edited by Kristin Bech and Kristine Eide, 17–52. Amsterdam and Philadelphia: John Benjamins. <https://doi.org/10.1075/la.213.02hau>
- Haug, Dag T. T., Marius L. Jøhndal, Hanne Eckhoff, Eirik Welo, Mari Hertenberg, and Angelika Müth. 2009. 'Computational and Linguistic Issues in Designing a Syntactically Annotated Parallel Corpus of Indo-European Languages'. *Traitement Automatique des Langues* 50/2: 17–45.

- Hays, David. 1964. 'Dependency Theory: A Formalism and some Observations'. *Language* 40/4: 511–25.
- Kahane, Sylvain, and Timothy Osborne. 2015. 'Translators' Introduction'. Introduction to *Elements of Structural Syntax*, by Lucien Tesnière, xxix–lxxiii. Amsterdam: John Benjamins.
- Katz, Jerrold J., and Jerry A. Fodor. 1963. 'The Structure of a Semantic Theory'. *Language* 39/2: 170–210.
- Keersmaekers, Alex, Wouter Mercelis, Colin Swaelens, and Toon Van Hal. 2019. 'Creating, Enriching and Valorising Treebanks of Ancient Greek: The Ongoing Pedalion-project'. In *Proceedings of the 18th International Workshop on Treebanks and Linguistic Theories (TLT, SyntaxFest 2019)*. Association for Computational Linguistics. <https://doi.org/10.18653/v1/W19-7812>
- Khan, Geoffrey. 2013. 'Pronominal Suffixes'. In *Encyclopedia of Hebrew Language and Linguistics*, edited by Geoffrey Khan, et al., 3: 267–72. Leiden: Brill.
- . 2019. 'Copulas, Cleft Sentences and Focus Markers in Biblical Hebrew'. In *Ancient Texts and Modern Readers: Studies in Ancient Hebrew Linguistics and Bible Translation*, edited by Gideon R. Kotzé, Christian S. Locatell, and John A. Messarra, 14–62. Leiden: Brill.
- . 2020a. 'Remarks on Syllable Structure and Metrical Structure in Biblical Hebrew'. *Brill's Journal of Afroasiatic Languages and Linguistics* 12/1: 7–30.
- . 2020b. *The Tiberian Pronunciation Tradition of Biblical Hebrew*. Cambridge Semitic Languages and Cultures 1. Cambridge: University of Cambridge Faculty of Asian and

- Middle Eastern Studies and Open Book Publishers.
<https://doi.org/10.11647/OBP.0163>
- . 2021. ‘The Coding of Discourse Dependency in Biblical Hebrew Consecutive Weqaṭal and Wayyiqṭol’. In *New Perspectives in Biblical and Rabbinic Hebrew*, edited by Aaron D. Hornkohl and Geoffrey Khan, 299–354. Cambridge Semitic Languages and Cultures 7. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers.
<https://doi.org/10.11647/OBP.0250.12>
- Kingham, Cody, and Wido Van Peursen. 2018. ‘The ETCBC Database of the Hebrew Bible’. *Journal for Semitics* 27/1: 1–13.
<https://doi.org/10.25159/1013-8471/2974>
- Krahn, Albert E. 2014. ‘A New Paradigm for Punctuation’. PhD dissertation, University of Wisconsin, Milwaukee.
- Luukko, Mikko, Aleksi Sahala, and Sam HardwickLindén Krister. 2020. ‘Akkadian Treebank for Early Neo-Assyrian Royal Inscriptions’. In *Proceedings of the 19th International Workshop on Treebanks and Linguistic Theories*. Association for Computational Linguistics. <https://doi.org/10.18653/v1/2020.tlt-1.11>
- Mambrini, Francesco, and Marco Passarotti. 2013. ‘Non-projectivity in the Ancient Greek Dependency Treebank’. In *Proceedings of the Second International Conference on Dependency Linguistics (DepLing 2013)*. Matfyzpress.
<https://aclanthology.org/W13-3720.pdf>
- Marcus, Mitchell P., Beatrice Santorini, and Mary A. Marcinkiewicz. 1994. ‘Building a Large Annotated Corpus

- of English: The Penn Treebank'. In *Using Large Corpora*, edited by Susan Armstrong, 273–90. Cambridge, MA: MIT Press.
- Morpurgo Davies, Anna. 1987. 'Folk-linguistics and the Greek Word'. In *Festschrift for Henry Hoenigswald: On the Occasion of his Seventieth Birthday*, edited by George Cardona and Norman H. Zide, 263–80. Tübingen: Narr.
- Munro, David B., and Thomas W. Allen (eds). 1920. *Homeri Opera*, Vol. 1, 3rd edition. Oxford: Oxford University Press.
<http://www.perseus.tufts.edu/hopper/text?doc=Perseus%3atext%3a1999.01.0133>
- Neef, Martin. 2015. 'Writing Systems as Modular Objects: Proposals for Theory Design in Grapholinguistics'. *Open Linguistics* 1: 708–21. <https://doi.org/10.1515/opli-2015-0026>
- Osborne, Timothy, and Daniel Maxwell. 2015. 'A Historical Overview of the Status of Function Words in Dependency Grammar'. In *Proceedings of the Third International Conference on Dependency Linguistics (Depling 2015)*. Uppsala: Uppsala University. <https://aclanthology.org/W15-2127.pdf>
- Osborne, Timothy, and Kim Gerdes. 2019. 'The Status of Function Words in Dependency Grammar: A Critique of Universal Dependencies (UD)'. *Glossa: a journal of general linguistics* 4/1: 1–28. <https://doi.org/10.5334/gjgl.537>
- Park, Sung J. 2020. *The Fundamentals of Hebrew Accents: Divisions and Exegetical Roles Beyond Syntax*. Cambridge: Cambridge University Press. <https://doi.org/10.1017/9781108801782>

- Pitcher, Sophia L. 2020. 'A Prosodic Model for Tiberian Hebrew'. PhD dissertation, University of the Free State, Bloemfontein.
- . 2021. 'Towards a Prosodic Model for Tiberian Hebrew: An Intonation-based Analysis'. *Stellenbosch Papers in Linguistics Plus* 63: 1–27. <https://doi.org/10.5842/63-0-934>
- . 2023. 'The Medieval Prosodic Orthography of the Tiberian Masoretic Reading Tradition'. *Journal of Semitic Studies* 68/2. <https://doi.org/10.1093/jss/fgad009>
- Pitts, Reuben. 2022. 'Corpus of the Epigraphy of the Italian Peninsula in the 1st Millennium BCE (CEIPoM)'. *Journal of Open Humanities Data* 8/1: 1–4. <https://doi.org/10.5334/johd.65>
- Ponti, Edoardo M. 2016. 'Divergence from Syntax to Linear Order in Ancient Greek Lexical Networks'. In *Proceedings of the Twenty-ninth International Florida Artificial Intelligence Research Society Conference*. <https://www.aaai.org/ocs/index.php/FLAIRS/FLAIRS16/paper/view/12820/12627>
- Prag, Jonathan R. W. (ed.). 2022. *I. Sicily*. <https://doi.org/10.5281/zenodo.4021517>
- Selkirk, Elizabeth. 2014 [1996]. 'The Prosodic Structure of Function Words'. In *Signal to Syntax: Bootstrapping from Speech to Grammar in Early Acquisition*, edited by James L. Morgan and Katherine Demuth, 187–214. New York: Psychology Press.
- Swanson, Daniel G., and Francis M. Tyers. 2022. 'A Universal Dependencies Treebank of Ancient Hebrew'. In *Proceedings of*

- the 13th Language Resources and Evaluation Conference*. European Language Resources Association. <https://aclanthology.org/2022.lrec-1.252>
- Tesnière, Lucien. 1959. *Éléments De Syntaxe Structurale*. Paris: C. Klincksieck.
- . 2015. *Elements of Structural Syntax*. Amsterdam: John Benjamins.
- Vierros, Marja. 2018. ‘Linguistic Annotation of the Digital Papyrological Corpus: Sematia’. In *Digital Papyrology II: Case Studies on the Digital Edition of Ancient Greek Papyri*, edited by Nicola Reggiani, 105–18. Berlin: De Gruyter. <https://doi.org/10.1515/9783110547450-006>
- Vierros, Marja, and Erik Henriksson. 2021. ‘PapyGreek Treebanks: A Dataset of Linguistically Annotated Greek Documentary Papyri’. *Journal of Open Humanities Data* 7: 1–6. <https://doi.org/10.5334/johd.55>
- Wingo, E. O. 1972. *Latin Punctuation in the Classical Age*. The Hague and Paris: Mouton.
- Zeldes, Amir, and Mitchell Abrams. 2018. ‘The Coptic Universal Dependency Treebank.’ In *Proceedings of the Second Workshop on Universal Dependencies (UDW 2018)*. Association for Computational Linguistics. <https://doi.org/10.18653/v1/W18-6022>
- Zemánek, Petr. 2007. ‘A Treebank of Ugaritic’. In *Proceedings of the Sixth Workshop on Treebanks and Linguistic Theories (TLT2007)*, edited by K. De Smedt, J. Hajič, and S. Kübler, 213–18. <https://dspace.ut.ee/bitstream/handle/10062/4840/213-218-zemanek.pdf?sequence=1&isAllowed=y>

NOTES ON THE RECIPROCAL FUNCTION OF *NIF'AL* IN BIBLICAL HEBREW*

Ambjörn Sjörs

1.0. Introduction

Reciprocal constructions in Biblical Hebrew (BH) have recently gained considerable attention, in particular reciprocal anaphoric expressions (Bar-Asher Siegal 2020; Staps 2020), e.g., וַיֹּאמְרוּ אִישׁ אֶל-אָחִיו ‘they said to one another’ (Exod. 16.15). In addition to these, mutual situations in BH can also be expressed morphologically by the verb. It is widely assumed that the N-stem (*nif'al*), for example, can express mutuality (GKC §51d; JM §51c), e.g., וְהִנֵּה שְׁנֵי-יִשְׂרָאֵלִים עֹבְרִים יַחְדָּם ‘behold, two Hebrews **were struggling together**’ (Exod. 2.13¹).

Needless to say, the N-stem does not only express mutual situations, and for purpose of interpretation, it is reasonable to

* This article is dedicated with the warmest feelings of gratitude to Prof. Geoffrey Khan, a bottomless fountain of wisdom, encouragement, and generosity. I am forever grateful for his inspiration and support. I would also like to acknowledge an anonymous peer reviewer and Prof. Aaron Hornkohl for many valuable comments on this article, and Ben Kantor for discussing some morphological details of the N-stem.

¹ All English translations of biblical texts are according to the *English Standard Version*, unless otherwise specified.

ask what linguistic features inform mutual meaning. It has previously been suggested that mutual meaning is conditioned by the lexical semantics of a given verb (Klein 1992, 293–94; Jenni 2012, 240). The mutual meaning of the input (G-stem), however, is not always obvious; compare, for example, שָׁפֵט ‘judge, decide’ versus נִשְׁפָּט ‘plead, dispute’ and יַעֲזֹז ‘advise, plan’ versus נִעְזָז ‘consult’. Moreover, some reciprocal N-verbs lack a corresponding input in BH, e.g., נָצַח ‘struggle’ and נִדְּבַח ‘argue’, and their lexical semantics must be established on the basis of stems other than the G-stem and/or comparative material.

The purpose of this investigation is to advance knowledge on the reciprocal function of the N-stem by investigating the factors that condition its mutual meaning.

1.1. Mutual Situations

On the semantic level, a mutual situation is a situation in which there are at least, and prototypically, two participants who each perform two identical semantic roles (e.g., agent and patient) in an identical reverse relation to each other (Haspelmath 2007, 2088; Nedjalkov 2007, 6–7).

Mutual situations may or may not involve several different sub-events; compare, for example, *Mary and John told each other a secret* and *Mary and John kissed*. In the former example, the situation consists of two telling events and two secrets, and the two sub-events can be conceptualised sequentially. In the latter example, the mutual situation is conceptualised as just one event (under normal circumstances), and the two kisses are presented as simultaneous and virtually indistinguishable. The former kind

of situation may be called a *multiplex* mutual event, and the latter *uniplex* (Haspelmath 2007, 2106–9).

Languages frequently express uniplex and multiplex mutual events with different reciprocal constructions. Uniplex mutual events are often expressed using so-called *lexical reciprocals*, also known as *allelic predicates*, which are predicates that express a mutual situation by themselves, without being derived in a regular way from a non-mutual base. Lexical reciprocals exist in all languages and typically fall into a limited number of semantic classes of predicates (Haspelmath 2007, 2105), such as verbs of competition (*fight, quarrel*), verbs of joint action (*communicate, consult*), and verbs of connecting (*combine, unite, mix*).

Multiplex mutual events, in turn, are always expressed with *grammatical reciprocals* (Haspelmath 2007, 2109), i.e., constructions that can be derived by means of morphological or syntactic modifications, or by a combination of them, from an input that lacks mutual meaning (Nedjalkov 2007, 10).

Uniplex mutual events are also frequently expressed with so-called *lexicalised reciprocals*, also known as *reciprocal dependents*, which are predicates with reciprocal morphology and mutual meaning that lack a corresponding unmarked non-mutual input. While lexicalised reciprocals always express uniplex mutual events (Haspelmath 2007, 2109), they may have historically expressed multiplex events. The Norwegian lexicalised reciprocal *se-s* 'meet', for example, comprises *se* 'see' and an old reflexive-reciprocal marker *-s*, and can be reconstructed as 'see each other'. Through language change, however, it lexicalised as 'meet', and

a situation described by *se-s* can only be interpreted as a simultaneous event with low distinguishability between the participants and sub-events (Kemmer 1903, 111).

The existence of reciprocal constructions in language can be thought to be motivated by a communicative need to present a mutual situation from the viewpoint of the entire set of participants in a single coherent situation (Haspelmath 2007, 2019). At the same time, uniplex mutual events can sometimes be expressed via so-called discontinuous reciprocal constructions (in contrast to simple constructions), in which one of the participants is mentioned as a non-subject. This construction may be used to assign asymmetric discourse prominence to the participants, which can be conceptualised in terms of figure-ground alignment. In a uniplex mutual event, such as *The bicycle collides with the building*, for example, the subject and the oblique object have the same thematic roles, but *the bicycle* is conceptualised as a figure, and the oblique object as ground (Gleitman et al. 1996). The discontinuous reciprocal construction may also be used to assign different degrees of agency or volition to the participants (Dimiatriades 2007, 398–402).

Moreover, in so-called mutual antipassive constructions, one of the participants may be omitted altogether, e.g., *He fights*. In these constructions, the identification of a reciprocant is backgrounded and not crucial in the communicative context (Lichtenberk 2000). At the same time, mutual antipassive constructions can be construed as involving a plurality of participants, because the syntactically omitted reciprocant can remain semantically implied by the meaning of the verb phrase.

1.2. The N-Stem and the Reciprocal Middle

The N-stem in (Classical) BH primarily expresses the middle and medio-passive voice of the G-stem (Gzella 2009; Van Wolde 2019). This grammatical function is a consequence of the fact that the N-stem historically is a morphological modification used to derive verbs from adjectives, specifically the verbal adjective *qatil*-, which itself is mostly middle and passive (Testen 1998, 137–38; Kouwenberg 2010, 300).

In typological perspective, middle marking tends to occur with a similar set of semantic classes of verbs across languages (Kemmer 1993, 16–20). Using examples from BH to illustrate the recurring morphology, these semantic classes include, among others: translational and non-translational motion, e.g., נָמַלֵּט ‘flee’ and נָהַפֵּךְ ‘turn’; mental situations (emotion, cognition, perception), e.g., נִבְהַל ‘be dismayed’, נִדָּע ‘become known’, and נִרְאָה ‘appear’; emotive speech actions, e.g., נָלֹן ‘grumble’; and mutual events, e.g., נָלַחַם ‘fight’ (Van Wolde 2019).

Since the same form-meaning pairing is found in language after language, the middle voice can be viewed as a network of functions that are conceptually related by universal human experience. In Kemmer’s view (1993, 109–23), the semantic commonality of middle situation types is the human speaker’s conceptualisation of the relative elaboration of events, i.e., the distinguishability of the participants and sub-events. The reciprocal middle, for example, is characterised by a low degree of internal event complexity relative to an ordinary transitive event, and can be used by the speaker to ‘turn down’ the distinguishability between the participants and sub-events in a mutual situation. Thus, since

there is a low degree of distinguishability between the relations that constitute the mutual situation, the middle voice lends itself to describe uniplex mutual events.

1.3. Aim and Method

The aim of this investigation is to systematically describe the linguistic features that inform the mutual meaning of the N-stem in BH, including both the syntactic and semantic properties of the reciprocal construction. It will do so by investigating the N-verbs classified as reciprocal by Klein (1992), whose corpus comprises some 4100 verb forms in the N-stem. According to Klein's (1992, 286–87) analysis, 224 verb forms (5.5 percent) describe mutual situations. These verb forms are distributed over eleven roots, but it may be noted that 167 of the total number of tokens involve the verb נָלַחַם 'fight'.

It is also worth noting that Klein's list excludes verbs that express what Kemmer (1993) calls collective situations, e.g., נִאָסַף 'gather', נִבְקַע 'cleave', נִזְעַד 'assemble by appointment', נִקְבַּץ 'gather', and נִפְרָד 'separate'. For the analysis of these verbs as describing collective situations, see Garr (2021).

2.0. Analysis

The reciprocal N-verbs are presented in order of frequency, beginning with the most common. The verbs formed on דָּבַר, אָוִית, and מָלַךְ, whose interpretation is problematic, are presented last.

2.1. נָלַחַם 'fight'

Two voices can be reconstructed for the G-stem of **lhm*. An active voice can be reconstructed on the basis of Classical Arabic *laḥama* 'fit, join (TR)' (WKAS L 341), and a middle voice on the basis of Syriac *lhem*, *nelḥam* 'fit, suit' (Payne Smith 1903, 240).² Thus, the mutual meaning of the N-stem can be connected with the lexically reciprocal verb **lhm* G 'fit, join', which can express that two participants take part in the action of the verb (e.g., 'they fit together'). In BH, it has taken on the secondary sense of hostile conjoining, i.e., 'fight'.³

The N-verb נָלַחַם is attested in 167 examples. In the majority of these, one of the reciprocants is expressed as an oblique argument (Staps 2018), e.g., מִמֶּנּוּ שָׁבִי | וַיִּלָּחֶם בְּיִשְׂרָאֵל וַיִּשָּׁב 'he fought against Israel, and took some of them captive' (Num. 21.1).⁴ In this example, the discontinuous construction may be used to assign different degrees of agency or volition to the participants, so

² In BH, the G-stem is attested four times and only in Psalms (35.1a, 1b; 56.2, 3), e.g., אֶת־לִחְמִי לָחֶם 'fight against those who fight against me' (Ps. 35.1). For the possible connection between **lhm* 'fit' and לָחֶם 'bread, food', see Krotkoff (1969).

³ For the semantic development, compare BH נִאָּבַק 'wrestle' (Gen. 32.25, 26) and Jewish Babylonian Aramaic אִבַּק 'attach, cling' (Sokoloff 2002, 76), and BH נִפְתַּל 'wrestle' (Gen. 30.8) and Classical Arabic *fatala* 'twist' (Lane 2334). As indicated by Jastrow (1903, 8), אִבַּק may be a biform of חִבַּק.

⁴ The most frequently used preposition is בְּ-, which may reflect the historical background of the verb as 'fit (with, in)'.

that the subject position assigns both instigation and participation to its referent, while the oblique position assigns only participation to its referent, e.g., ‘**he attacked** the Israelites’ (NIV).

The N-verb *נלחם* is also frequently used in the sense of ‘fight’ without mentioning a reciprocant. In many cases, such a reciprocant is inferable, e.g., *וַיִּלָּחֶמוּ פְּלִשְׁתִּים וַיִּגְּפוּ יִשְׂרָאֵל* ‘So the Philistines **fought**, and Israel was defeated’ (1 Sam. 4. 10). Other times, *נלחם* may be thought of as antipassive, e.g., *אֲדָהְיֶה-לִּי לְבֹן-אֲדָהְיֶה לְיְהוָה מִלְחָמוֹת יְהוָה* ‘Only be valiant for me **and fight** the LORD’s battles’ (1 Sam. 18.17). In this case, the identification of a reciprocant is backgrounded and not crucial in the communicative context.

In only two examples, the subject participants are mentioned by the verb:

- (1) *תְּנוּ-לִי אִישׁ וְנִלָּחֶמָה יַחַד*
‘Give me a man, **that we may fight** together.’ (1 Sam. 17.10)
- (2) *וְסִכְסַכְתִּי מִצְרַיִם בְּמִצְרַיִם אִישׁ-בְּאַחִיו וְאִישׁ בְּרֵעֵהוּ*
‘And I will stir up Egyptians against Egyptians, **and they will fight**, each against another and each against his neighbour...’ (Isa. 19.2)

In both examples, the situation described by *נלחם* can be interpreted as a mutual event. In the middle voice, this mutual situation has low event elaboration, i.e., there is zero distinguishability between the participants and sub-events.

In (1), the situation can be interpreted as a uniplex mutual event, in which the fighting and its participants are presented as simultaneous and virtually indistinguishable. The adverb *יחד* is used to explicitly express that it is the subject participants that

are the reciprocants, rather than someone implied or inferred (see above). In (2), the anaphoric pronominal phrases pull apart the uniplex mutual event and distinguish its different sub-events and participants. The reason may be contrastive focus, i.e., to contrast the fact that the Egyptians fight each other against the implicit idea that they fight against others.

2.2. נָעַץ 'consult'

The etymological background of *wʿʒ is unclear (Kogan 2015, 203–4), but it is possible to reconstruct both an active and a middle function in the G-stem. Evidence for the active function is provided by Classical Arabic *waʿaẓa* 'exhort, admonish, warn, give advice' (Lane 2953), and BH נָעַץ 'advise, counsel' (BDB 419). Evidence for the middle function is provided by BH נָעַץ 'plan, decide' (HALOT 421), which may be thought of as a mental middle, e.g., 'deliberate, think over (in order to reach a decision)'.⁵ When there is a plurality of participants, such a situation may be interpreted as mutual, e.g., אֵל מְשֻׁאֲמוֹתָם | נָעֲצוּ לְהַדִּיחַ 'They only consult to cast him down from his excellency' (Ps. 62.5 KJV). In other words, the middle G-stem can be 'take advice' both in the sense of 'deliberate, think over' (of an individual), and in the sense of 'consult, discuss' (of a plurality of participants). Thus, the mutual meaning of the N-stem can be straightforwardly connected with נָעַץ in the sense of 'consult, discuss'.

⁵ For the same kind of polyfunctionality, see Akkadian *malāku* 'give advice' and 'ponder, deliberate, come to a decision' (CAD M/1 154–56).

נוֹעַץ is attested 22 times. In four examples (Isa. 45.21; Ps. 71.10; 83.6; Neh. 6.7), the verb form is finite and plural without an explicitly mentioned subject, e.g.,

- (3) הִגִּידוּ וְהִגִּישׁוּ אֶף יוֹעֲצֵי יְהוָה
 ‘Declare and present your case; **let them take counsel** together!’ (Isa. 45.21)

These verb phrases describe uniplex mutual events and there is zero distinguishability between the participants and sub-events. The adverb יַחְדָּו, which is used in all four examples, may be viewed as explicitly indicating that the subject participants are the reciprocants (Bar-Asher Siegal 2020, 167–68), rather than someone implied or inferred.

In nine examples, the verb form is singular, but the verb phrase involves a reciprocant mentioned by a prepositional phrase: אִתּוֹ ‘with’ (1 Kgs 12.6 || 2 Chron. 10.6; 1 Kgs 12.8 || 2 Chron. 10.8; Isa. 40.14), עִמּוֹ ‘with’ (1 Chron. 13.1; 2 Chron. 32.3), and אֵלָיו (2 Kgs 6.8; 2 Chron. 20.21). These discontinuous reciprocal constructions can be interpreted in terms of figure-ground alignment: the subject position assigns discursive topicality and a higher degree of agency or volition to its referent.

In six examples, the verb form has a plural subject that is explicitly mentioned (1 Kgs 12.6 || 2 Chron. 10.6; 1 Kgs 12.9 || 2 Chron. 10.9; 30.2, 23), e.g.,

- (4) וַיֹּעֲצֵן הַמֶּלֶךְ וְשָׂרָיו וְכָל־הַקָּהָל בִּירוּשָׁלַם לַעֲשׂוֹת הַפֶּסַח
 ‘For the king and his princes and all the assembly in Jerusalem **had taken counsel** to keep the Passover’ (2 Chron. 30.2)

In these constructions, נִזְעַן is followed by a verb phrase that mentions the decision reached via consultation. Thus, נִזְעַן can be also be translated as ‘decide’ (HALOT 422), i.e., ‘consult (in order to reach a decision)’.

When the verb form is singular and no participant other than the subject is mentioned (1 Kgs 12.28; 2 Chron. 25.17), נִזְעַן can be interpreted as antipassive, e.g., וַיִּזְעַן הַמֶּלֶךְ וַיַּעַשׂ שְׁנֵי עֲגֻלֵי זָהָב, ‘So the king **took counsel** and made two calves of gold’ (1 Kgs 12.28). In the relevant examples, the verb phrases are followed by *wayyiqtol*s, which recount the decision reached on the basis of consultation.

2.3. נִשְׁפָּט ‘plead, dispute’

The G-stem of **ṭpṭ* can be reconstructed as active ‘judge, decide’ and as middle ‘process, litigate’. The evidence for active G **ṭpṭ* comes from BH שָׁפַט ‘judge, decide’ (BDB 1047), e.g., יְהוָה יִשְׁפֹּט ‘**May** the LORD **judge** between you and me!’ (Gen. 16.5). As shown by the use of the prepositional phrase בֵּין ... וּבֵין ‘between’, the situation of deciding and discriminating can be thought of as an object-oriented mutual situation, in which the subject manipulates two objects in a mutual relationship. The evidence for middle G **ṭpṭ* comes from the Aramaic of the Aḥiqar proverbs: [m]h *yšṭṭwn* ‘qn ‘m šh ‘Why **should** wood **strive** with fire?’ (TAD C:1.1.88). In this case, the subject manipulates itself in a mutual relationship with another participant. The BH deverbal noun מִשְׁפָּט in the sense of ‘process, procedure, litigation’ (BDB 1048) can also be thought to reflect a middle function

is unwilling to be a reciprocant. This interpretation lends itself to one example where את is unambiguously the differential object marker: הִנְנִי נִשְׁפָּט אוֹתְךָ עַל-אֲמָרְךָ לֹא חָטָאתִי 'Behold, I will **bring** you **to judgment** for saying, "I have not sinned."' (Jer. 2.35).⁶

In four examples, no participant other than the subject is mentioned. The examples in Psalms (9.20; 37.33; 109.7) can be interpreted as medio-passive of active שָׁפַט 'judge, decide' (BDB 1047). The example in Isaiah can be interpreted as antipassive with a reciprocant whose identity is generic: אִין-קִרָא בְּצִדֵּק וְאִין נִשְׁפָּט בְּאִמּוּנָה 'No one enters suit justly; no one **goes to law** honestly' (Isa. 59.4).

2.4. נִכַּח 'argue'

The G-stem of יכ"ח is not attested in BH, but its meaning can be reconstructed as 'be firm, right' (Jastrow 1903, 577). Support for this reconstruction is provided by the C-stem הִכִּיחַ 'decide, adjudge, prove' (BDB 406), which can be interpreted as a factitive derivation ('correct') of the erstwhile G-stem (Nöldeke 1910, 191). Morphemes that mean 'right' also mean 'straight, level, equal' in many languages (Buck 1949, 895), which presupposes a mutual situation between two entities opposite each other; cf. BH נִכַּח 'what is situated straight ahead' and נִכַּח 'what is opposite' (HALOT 699). Thus, the mutual meaning of the N-stem can be connected with a lexical reciprocal G יכ"ח 'be opposite'. The meaning 'argue' may have lexicalised from a specialised use of 'be opposite' in the sense of 'oppose, be in opposition'.

⁶ Jeremiah also attests the use of נִשְׁפָּט לְ- (Jer. 25.31), which may be used to similar effect.

The N-verb נִזְכָּח is attested three times. In one example, the verb form is plural and codes both reciprocants: לְכוּ־נָא וְנִזְכָּחַה יְהוָה 'Come now, **let us reason together**, says the LORD' (Isa. 1.18). In another example, there is a plurality of participants but one of them is expressed by a prepositional phrase headed by עִם 'with': שָׁם יִשְׂרָאֵל נִזְכָּח עִמּוֹ 'There an upright man **could argue** with him' (Job 23.7).

In a third example, the N-stem can be interpreted as medio-passive of יָצַח in the sense 'be right', but the text is problematic: הִנֵּה הוּא־לִי בְּסוּת עֵינַיִם לְכָל אֲשֶׁר אֶתָּד וְאֵת כָּל וְנִזְכָּחַת 'Look, this is a covering of the eyes (viz. a compensation) for you, before all who are with you and with everyone (else), **and you are hereby set right**' (Gen. 20.16, my translation: AS).⁷

2.5. נָצַח 'struggle'

The G-stem of נָצַח is not attested in BH, but its meaning can be reconstructed as 'quarrel, contend' on the basis of the deverbal noun מִצָּח 'strife, contention' (BDB 663). The G-stem with this meaning is attested in Aramaic, e.g., Samaritan Palestinian Aramaic G *nṣy* 'quarrel' (Tal 2000, II:543), and Jewish Babylonian Aramaic G *nṣy* 'quarrel' (Sokoloff 2002, 771).⁸ Thus, the mutual

⁷ The proposed emendation in *BHS* is to read וְאֵת כָּל נִבְחַת or וְאֵת כָּל וְנִבְחַת. The Samaritan version has וְנִבְחַת וְנִבְחַת.

⁸ This meaning of נָצַח is presumably connected with נִצָּח 'plumage'. According to medieval Arabic lexicographers, for example, the meaning of Classical Arabic L *nṣy* 'quarrel' properly means the grasping of one another by the scruff (*Lisān* 4447); compare, for example, Spanish *pelear* 'quarrel' and *pelo* 'hair' (Buck 1949, 1371). The BH C-verb הָצַח 'have a

meaning of the N-stem can be connected with a lexical reciprocal G נָצַח 'contend, quarrel'.

נָצַח is attested five times and the verb form is always plural. In three examples, the subject is explicitly mentioned and is dual (Exod. 2.13; Lev. 24.10; 2 Sam. 14.6), e.g., וְהָיָה שְׁנֵי־אֲנָשִׁים עִבְרִים, נָצְחוּ 'behold, two Hebrews were **struggling together**' (Exod. 2.13). In a fourth example, duality is not explicit, but may be considered implied. The Septuagint, for example, translates וְכִי־יִנָּצוּ אֲנָשִׁים 'When men **strive together**' (Exod. 21.22) as ἐὰν δὲ μάχωνται δύο ἄνδρες 'when two men **fight**'. In the fifth example, the verb phrase is marked by reciprocal morphemes: כִּי־יִנָּצוּ אֲנָשִׁים יַחְדָּו אִישׁ וְאָחִיו 'If two men get into a hand-to-hand **fight**' (Deut. 25.11 *NET*). The use of syndeton (instead of a preposition) in אִישׁ וְאָחִיו is unique, and it is not self-evident that the phrase expresses a multiplex event. Rather, it is possible that it draws attention to the fact that it is a fight between men (Staps 2020, 62 fn. 3).

Thus, the situation described by נָצַח can be interpreted in all examples as a uniplex mutual event. In the middle voice, this situation has low event elaboration, i.e., there is zero distinguishability between the participants and sub-events.

2.6. נִפְגַּשׁ 'meet'

The G-verb נִפְגַּשׁ 'meet, encounter' (BDB 803) is transitive as a rule, and the object is mentioned as either a noun phrase (Gen. 33.8; 1 Sam. 25.20; Isa. 34.14; Jer. 41.6) or a pronominal suffix

fight with (לָחַם)' (*HALOT* 715) can be analysed as a denominative derivation of a noun of this root, such as נֻפָּח 'plumage'.

(Gen. 32.18; Exod. 4.24, 27; 2 Sam. 2.13; Hos. 13.8).⁹ See, for example

- (6) אֶפְגַּשְׁם כְּדָב שְׂכֹל וְאֶקְרַע סְגֹר לָבָם
 ‘I will fall upon them like a bear robbed of her cubs; I will tear open their breast’ (Hos. 13.8)
- (7) וּפְגָשׁוּ צִיִּים אֶת־אֲיִים וְשָׁעִיר עַל־רֵעֵהוּ יִקְרָא
 ‘And wild animals shall meet with hyenas; the wild goat shall cry to his fellow’ (Isa. 34.14)

In Hos. 13.8, the verb phrase describes a transitive event with one agent and one patient. In Isa. 34.14, the verb phrase has been interpreted as describing a mutual situation by the *ESV*, perhaps informed by the mutual situation expressed in the subsequent clause.

It is possible that the two meanings ‘meet’ and ‘encounter’ reflect two inflections, e.g., active ‘happen on, encounter’ and middle ‘meet (by chance)’. It is also possible to interpret פָּגַשׁ ‘meet’ as expressing an asymmetric mutual situation, in which the subject is figure and the complement ground.

In the N-stem, which is attested three times (Ps. 85.11; Prov. 22.2; Prov. 29.13), the subject is explicitly mentioned in all examples and is always dual, e.g., חֲסֵד־וָאֱמֶת נִפְגְּשׁוּ ‘Steadfast love

⁹ In one example, the verb is complemented by a prepositional object headed by *ב־* (Prov. 34.14). It is not clear whether *אֵת* in Isa. 34.14 should be identified with the comitative preposition or the differential object marker, but while there is no conclusive evidence for constructions with the former, the latter is unambiguously attested twice (1 Sam. 25.20; Jer. 41.6). The frequent reference to the object as a pronominal suffix also indicates preference for direct over oblique object marking.

and faithfulness **meet**' (Ps. 85.11). This can be interpreted as a uniplex mutual event, i.e., the situation is conceptualised as only one simultaneous event. The middle voice modifies the situation so that it receives low event elaboration, and there is zero distinguishability between the participants and sub-events.

2.7. נָדוֹן 'dispute, contend'

The G-stem of נָדוֹן is primarily 'judge, plead the cause' (BDB 192). In addition to this active function, it is also possible to posit a middle function on the basis of the deverbal noun מִדּוֹן 'strife, contention' (BDB 193); compare also וְלֹא־יִוָּכַל לִדְוֹן עִם שְׂתַקְיָהּ [ק'; כ'] 'he is not able to dispute with one stronger than he' (Eccl. 6.10). Accordingly, it appears that G נָדוֹן can be 'argue' both in the sense of 'plead the cause' and in the sense of 'dispute, contend'. Thus, the mutual meaning of the N-stem can be connected with G דָּוָן 'dispute, contend'.

The N-stem of נָדוֹן is attested once: וַיִּשְׂרְאֵל גַּם אִישׁ לְאֹהֲלָיו: וַיָּהִי כִלְהֵעָם נָדוֹן בְּכָל־שִׁבְטֵי יִשְׂרָאֵל 'Israel had fled, each man to his own tent, and all the people **were in dispute** among all the tribes of Israel' (2 Sam. 19.9–10, my translation: AS). In the N-stem, this mutual situation has low event elaboration, i.e., there is zero distinguishability between the participants and sub-events.

2.8. נָחַרַב 'fight'

Two voices can be reconstructed for the G-stem of **hrb*. The active voice is evidenced by Classical Arabic *ḥaraba* 'despoil, plunder' (Lane 540), and perhaps by BH חָרַב 'attack, smite' (BDB

352).¹⁰ The middle voice is evidenced by Classical Arabic *ḥariba* ‘be despoiled, plundered’ and ‘be angry’ (Lane 540). Both voices are also evidenced by Sabaic *ḥrb* G ‘plunder, pillage’ (Bron 2012, 85) and ‘wage war’ (Beeston 1982, 69), the latter of which can be derived from middle ‘plunder each other’.¹¹ Thus, the mutual meaning of נָחַרְב can be derived from the lexically reciprocal G **ḥrb* ‘plunder each other, wage war’.

The N-verb נָחַרְב is attested in one example: דָּם זֶה הַחֶרֶב וַיָּכּוּ אִישׁ אֶת־רֵעֵהוּ ‘This is blood; the kings **have** surely **fought together** and struck one another down’ (2 Kgs 3.23). This can be interpreted as a uniplex mutual event: in the middle voice, the situation has low event elaboration and there is zero distinguishability between the participants and sub-events.

2.9. דב"ר

The N-verb נָדָבַר is attested four times. It is an open question whether נָדָבַר expresses mutuality, but it may be noted that none

¹⁰ The G-stem of חר"ב in BH is attested in the imperatives חָרֵב (Jer. 50.21) and חָרְבוּ (Jer. 50.27), but it is possible that the relevant verb forms should be derived from **ḥaraba*, i.e., an active inflection of stative חָרַב ‘be waste, desolate’ (BDB 351). For the existence of an active and a middle inflection of the **ḥrb*, see Classical Arabic *ḥaraba* ‘reduce to ruin’ and *ḥariba* ‘be ruined’ (Lane 715).

¹¹ The G-stem identification of Sabaic *ḥrb* ‘wage war’ is deduced from the fact that its infinitive is not suffixed by *-n*.

of the ancient versions translate it with reciprocal grammatical constructions.¹²

- (8) ואתה בן־אדם בְּנִי עַמֶּךָ הַנִּדְבָּרִים בְּךָ אֶצֶל הַקִּירוֹת וּבַפֶּתַח הַבָּתִּים וְדָבַר־
חֶד אֶת־אַחַד אִישׁ אֶת־אָחִיו

‘As for you, son of man, your people **who talk together** about you by the walls and at the doors of the houses, say to one another, each to his brother’ (Ezek. 33.30)

- (9) חֲזָקוּ עָלַי דְּבָרֵיכֶם אֲמַר יְהוָה וְאַמְרֹתֶם מֶה־נִּדְבָּרְנוּ עָלַי: אֲמַרְתֶּם... אֲנִי
נִדְבָּרוּ יְרֵאֵי יְהוָה אִישׁ אֶת־רֵעֵהוּ

“Your words have been hard against me”, says the LORD. But you say, “How **have we spoken** against you?” You have said... Then those who feared the LORD **spoke** with one another.’ (Mal. 3.13–16)

- (10) גַּם יֵשְׁבוּ שָׂרִים בִּי נִדְבָּרוּ
‘Even though princes sit **plotting** against me’ (Ps. 119.23)

In Ezek. 33.30, the verb phrase **וְדָבַר־חֶד אֶת־אַחַד** ‘one **said** to the other’ is an elaboration of **הַנִּדְבָּרִים**, but it is not self-evident that the participle phrase itself expresses mutuality. The Targum, for example, translates it by רִנָּן ‘murmur’. Thus, it is possible that the N-stem is used for emotive speech action; compare, for example, גָּלוּז ‘grumble’ and נָאֲנָה ‘groan’. Likewise, the situation expressed by **נִדְבָּרוּ** in Mal. 3.16 is mutual, but it is not self-evident if mutuality is expressed by the anaphoric phrase **אִישׁ אֶת־רֵעֵהוּ**, the N-

¹² The Septuagint translates as *λαλέω* ‘talk, speak’ and *καταλαλέω* ‘speak evil’, the Peshitta as *my* ‘think, meditate’ (Ezek. 33.30; Ps. 119.23) and *mr* ‘say’ (Mal. 3.13), and the Targum as *מלל* and *סגי למללא* ‘talk a lot’ (Mal. 3.13). For **דָּבַר בִּי** ‘speak evil of’ (D-stem), see, for example, Num. 12.1; 21.7; Job 19.18.

verb, or both. The *KJV* translates נִדְבַר in both Mal. 3.13 and 3.16 as ‘speak much, often’.

2.10. או"ת

The morphological analysis of the verb forms וַיֵּאָזְזוּ ‘they agreed’ (2 Kgs 12.9), יֵאָזְזוּ לָנוּ ‘they will agree with us’ (Gen. 34.22), יֵאָזְזוּ לָכֶם ‘we will agree with you’ (Gen. 34.15), and יֵאָזְזוּהָם לָהֶם ‘let us agree with them’ (Gen. 34.23) is ambiguous; they may reflect either the N-stem (*yē’ōt- < *yi’āt < *yin’awit) or the G-stem (*yē’ōt- < *yi’āt < *yi’wat-). The fact that the object complement is introduced by -לְ, while oblique reciprocants of reciprocal N-verbs are usually headed by עִם or אֶת, may indicate that the relevant forms are G-verbs.

2.11. מל"ך

The N-stem of מל"ך is attested once: וַיִּמְלֹךְ לִבִּי עָלַי ‘My heart **deliberated**’ (Neh. 5.7, my translation: AS). Since no other participant is mentioned, this N-verb can be interpreted as a mental middle derived from G מל"ך in the sense of ‘advise, counsel’ (‘take advise’). Since the G-stem with this meaning is unattested in BH, but common in Aramaic, it is likely that the meaning of the input of נִמְלֵךְ in Nehemiah results from Aramaic influence (Wagner 1966, 77). Moreover, since מל"ך is primarily ‘rule, dominate’ and ‘possess, own’ in West Semitic (Kogan 2015, 91–92), it is possible that the meaning ‘advise’ in Aramaic results from Akkadian influence (Kogan 2015, 419 fn. 1202). Incidentally, *namluk-* is one of a few reciprocal N-verbs in Akkadian still in use in the Neo-Assyrian and Neo-Babylonian period (Kouwenberg 2010, 295).

3.0. Summary and Conclusions

The investigation has shown that N-verbs that express mutual situations have, or can be thought to have had, an input with mutual meaning, i.e., an input that is a lexical reciprocal: נָלַחַם can be derived from **lhm* G 'fit', נִזְעַץ from **w'z* G 'take advise, discuss', נִשְׁפַּט from **špt* G 'process, litigate', נִזְכַּח from **ykh* G 'be opposite', נִצָּח from **nsy* G 'contend, quarrel', נִפְגַּשׁ from *pgš* G 'meet', נִדָּן from **dyn* G 'dispute, contend', and נִחָרַב from **hrb* G 'wage war'. It has also been suggested that נִדְבַּר may be an emotive speech action middle, that נִמְלֵךְ may be a mental middle, and that the verb forms derived from אָוַת may be G-verbs.

When the G-stem has both active and middle meaning, the reciprocal N-verb can most straightforwardly be connected with the middle G-stem; נִשְׁפַּט, for example, can be derived from **tapiṭ*- 'process, litigate'. Since both the (middle) G-stem and the N-stem of these roots express mutual situations or formerly did so, it is possible that the N-stem was used when the speaker intended to present a mutual situation from the viewpoint of the entire set of participants in a single coherent situation. Indeed, N-verbs that are lexicalised reciprocals (e.g., נִזְכַּח and נִצָּח) may have been so frequently used in the N-stem to express the mutual meaning of their roots that the G-stem itself was lost.

When the N-verb is used in simple reciprocal constructions, the verb phrase is frequently either marked by a reciprocal adverb or the subject is explicitly mentioned and usually dual. The reciprocal adverbs יַחְדָּו and יַחַד may be used to explicitly express that it is the subject participants that are the reciprocants, rather

than someone implied or inferred. The selection of sociative morphemes (יָחַד and יְחָדִי) over anaphoric pronominal phrases in uniplex mutual events may be motivated by the low event-elaboration—see examples (1), (3), (5). Anaphoric pronominal phrases, in turn, may be used for contrastive focus—see example (2) and Deut. 25.11 in §2.5). The discontinuous reciprocal construction, finally, can be used to assign different degrees of discourse prominence to the reciprocants and/or different degrees of agency or volition (e.g., נִנְכַּח).

The investigation has also shown that mutual situations expressed by N-verbs are usually uniplex mutual events. An avenue for further research is contrasting mutual situations expressed by the N-stem with mutual situations expressed by the Dt-stem (*hitpa^{el}*). If the Dt-stem can be analysed as a pluractional and detransitive derivation of the G-stem, it can be hypothesised that mutual situations expressed by the Dt-stem are multiplex mutual events.

References

- Bar-Asher Siegal, Elitzur. 2020. *The NP-Strategy for Expressing Reciprocity: Typology, History, Syntax and Semantics*. Typological Studies in Language 127. Amsterdam: John Benjamins.
- BDB = Brown, Francis, Charles Briggs, and Samuel Driver. 1906. *A Hebrew and English Lexicon of the Old Testament*. Oxford: Clarendon.
- Beeston, Alfred. 1982. *Sabaic Dictionary: English-French-Arabic*. Louvain-la-Neuve: Peeters.

- Bron, François. 2012. 'Une nouvelle inscription sabéenne du règne de Laḥay'athat Yarkham, roi de Saba' et dhū-Ray-dān'. *Semitica* 54: 81–89.
- Buck, Carl D. 1949. *A Dictionary of Selected Synonyms in the Principal Indo-European Languages*. 4th printing. Chicago: University of Chicago Press.
- CAD = Gelb, Ignace, Benno Landsberger, Leo Oppenheim, and Erica Reiner. 1956–2006. *The Assyrian Dictionary of the Oriental Institute of the University of Chicago*. Chicago: The Oriental Institute of the University of Chicago.
- Dimitriades, Alexis. 2007. 'Irreducible Symmetry in Reciprocal Constructions'. In *Reciprocals and Reflexives: Theoretical and Typological Explorations*, edited by Ekkehard König and Volker Gast, 375–409. Trends in Linguistics 192. Berlin: Mouton de Gruyter.
- Garr, W. Randall. 2021. 'Reflexivity: The Cases of the *Niphal* and *Hithpael*'. *Journal of Near Eastern Studies* 80/2: 341–56.
- GKC = Kautzsch, Emil (ed.). 1910. *Gesenius' Hebrew Grammar*. Translated by Arthur E. Cowley. 2nd edition. London: Oxford University Press.
- Gleitman, Lila, Henry Gleitman, Carol Miller, and Ruth Ostrin. 1996. 'Similar, and Similar Concepts'. *Cognition* 58: 321–76.
- Gzella, Holger. 2009. 'Voice in Classical Hebrew against Its Semitic Background'. *Orientalia* 78/3: 292–325.
- HALOT = Koehler, Ludwig, and Walter Baumgartner. 1994–2000. *The Hebrew and Aramaic Lexicon of the Old Testament*. Leiden: Brill.

- Haspelmath, Martin. 2007. 'Further Remarks on Reciprocal Constructions'. In *Reciprocal Constructions*, edited by Vladimir Nedjalkov, 4:2088–115. Typological Studies in Language 71. Amsterdam: John Benjamins.
- Jastrow, Marcus. 1903. *A Dictionary of the Targumim, the Talmud Babli and Yerushalmi and the Midrashic Literature*. London: Luzac.
- Jenni, Ernst. 2012. *Studien zur Sprachwelt des Alten Testaments III*. Stuttgart: Kohlhammer.
- JM = Joüon, Paul, and Takamitsu Muraoka. 2006. *A Grammar of Biblical Hebrew*. 2nd edition. Subsidia Biblica 27. Rome: Pontifical Biblical Institute.
- Kemmer, Suzanne. 1993. *The Middle Voice*. Amsterdam: John Benjamins.
- Klein, George. 1992. 'The Meaning of the Niphal in Biblical Hebrew'. PhD dissertation, Annenberg Research Institute.
- Kogan, Leonid. 2015. *Genealogical Classification of Semitic: The Lexical Isoglosses*. Berlin: De Gruyter.
- Kouwenberg, Norbert. 2010. *The Akkadian Verb and Its Semitic Background*. Languages of the Ancient Near East 2. Winona Lake, IN: Eisenbrauns.
- Krotkoff, George. 1969. '*Laḥm* "Fleisch" and *leḥem* "Brot"'. *Wiener Zeitschrift für die Kunde des Morgenlandes* 62: 76–82.
- Lane = Lane, Edward. 1863–1893. *An Arabic-English Lexicon*. London: Williams and Norgate.
- Lichtenberk, Frantisek. 2000. 'Reciprocals Without Reflexives'. In *Reciprocals: Forms and Functions*, edited by Zygmunt

- Frajzyngier and Traci Curl, 31–62. *Typological Studies in Language* 41. Philadelphia: John Benjamins.
- Lisān* = Al-Kabīr, ‘Abd Allāh ‘Alī, Muḥammad Aḥmad Ḥasab Allāh, and Hāshim Muḥammad al-Shadhilī. 1981. *Lisān al-‘arab li-Ibn Manẓur*. Cairo: Dār al-Ma‘ārif.
- Nedjalkov, Vladimir. 2007. ‘Overview of the Research: Definitions of Terms, Framework, and Related Issues’. In *Reciprocal Constructions*, edited by Vladimir Nedjalkov, 1:3–114. *Typological Studies in Language* 71. Amsterdam: John Benjamins.
- Nöldeke, Theodor. 1910. *Neue Beiträge zur semitischen Sprachwissenschaft*. Strassbourg: Trübner.
- Payne Smith, Jessie. 1903. *A Compendious Syriac Dictionary*. Oxford: Clarendon.
- Sokoloff, Michael. 2002. *A Dictionary of Jewish Babylonian Aramaic of the Talmudic and Geonic Periods*. *Dictionaries of Talmud, Midrash and Targum* 3. Ramat-Gan: Bar-Ilan University Press.
- Staps, Camil. 2018. ‘A Case Study of Reciprocal Middles in Biblical Hebrew: The Niphal of נִחַל’. *Orientalia* 87/2: 159–83.
- . 2020. ‘Prepositions and the Grammaticalization of Ancient Hebrew Bipartite Reciprocal Markers’. *Journal of Semitic Studies* 65/1: 61–84.
- TAD* = Porten, Bezalel, and Ada Yardeni. 1986–1999. *Textbook of Aramaic Documents from Ancient Egypt*. Jerusalem: The Hebrew University of Jerusalem, Department of the History of the Jewish People.

- Testen, David. 1998. 'The Derivational Role of the Semitic N-Stem'. *Zeitschrift für Assyriologie* 88: 127–45.
- Tal, Abraham. 2000. *A Dictionary of Samaritan Aramaic*. Handbuch der Orientalistik I: Der Nahe und Mittlere Osten 50: 1–2. Leiden: Brill.
- Van Wolde, Ellen. 2019. 'The Niphal as Middle Voice and Its Consequence for Meaning'. *Journal for the Study of the Old Testament* 43/3: 453–78.
- Wagner, Max. 1966. *Die lexikalischen und grammatikalischen Aramaismen im alttestamentlichen Hebräisch*. Beiheft zur Zeitschrift für die alttestamentliche Wissenschaft 96. Berlin: Töpelmann.
- WKAS = Kramer, Jörg, Helmut Gätje, Anton Spitaler, and Manfred Ullmann. 1970–. *Wörterbuch der klassischen arabischen Sprache*. Wiesbaden: Harrassowitz.

HEALED BY ‘HIS WOUND(S)’, ‘HIS BRUISING’, OR ‘IN HIS COMPANY’?: ISAIAH 53.5 AND *DAGESH MAVHIN**

Benjamin Kantor

1.0. The Philological Problem of חֲבֵרָה in Isaiah 53.5

Most conventional or traditional translations of Isa. 53.5 read something like the following:

- (1) וְהוּא מִחֲלָל מִפְּשָׁעֵנוּ מִדָּבָר מְעֹנֵתֵינוּ
 מוֹסֵר שְׁלוֹמֵנוּ עָלָיו וּבְחֲבֵרָתוֹ נִרְפָּא-לָנוּ:
 ‘And he was pierced for our transgressions,
 crushed for our iniquities,
 the chastisement of our peace was upon him,
 and by his wounds we are healed.’
-

* I would like to thank Randall Buth for first drawing this issue to my attention many years ago and Geoffrey Khan for discussing this idea with me over the years. I would also like to thank those in attendance at the 2022 SBL Annual Meeting in Denver, Colorado, for their feedback on an earlier version of this paper that I presented there. I am also grateful to the two reviewers who offered helpful feedback on an earlier iteration of this paper. Their constructive comments have made this final version of better quality. Any remaining errors are only my own.

There is, however, one potential philological problem with this translation. The word translated as ‘wounds’ (*NIV*; *ESV*) or ‘stripes’ (*KJV*) may not—at least according to the Tiberian-pointed Masoretic Text—mean ‘wounds’ or ‘stripes’ at all.

1.1. The Lexeme חַבּוּרָה ‘wound’ in the Bible

In the Hebrew Bible, the consonantal sequence חב(ו)רה is normally vocalised with a geminated *bet* as the lexeme חַבּוּרָה/חַבְרָה ‘wound, stripe’. Indeed, aside from the verse under consideration, wherever the sequence חב(ו)רה is used to refer to ‘wound(s)’ or ‘stripe(s)’ (6x), it has *dagesh forte* in the *bet*:

- (2) כִּי אִישׁ הִרְגֹתִי לְפָצְעִי וְיֹלֵד לְחַבְרָתִי:
‘for I killed a man for my wound, and a young man **for my stripe**’ (Gen. 4.23)
- (3) כְּוִיָּה תַחַת כְּוִיָּה פָצַע תַּחַת פָּצַע חַבּוּרָה תַּחַת חַבּוּרָה:
‘burn for burn, wound for wound, **stripe** for **stripe**’ (Exod. 21.25)
- (4) פָּצַע וְחַבּוּרָה וּמִכָּה טְרִיָּה
‘wound **and stripe** and a fresh blow’ (Isa. 1.6)
- (5) הַבְּאִישׁוֹ נִמְקוּ חַבּוּרָתִי
‘**my stripes** stink and rot’ (Ps. 38.6)
- (6) חַבְרוֹת פָּצַע תִּמְרֹק (ק'; כ': תִּמְרִיק) בִּרְעַ
‘**stripes** that wound cleanse away evil’ (Prov. 20.30)

As noted, the only case of a noun represented by the consonantal sequence חב(ו)רה without a *dagesh* occurs in our passage

in Isa. 53.5.¹ It is, of course, possible that the Hebrew Bible admits two morphological or phonological byforms for the word ‘wound’, namely חבוּרָה and חִבוּרָה. The pattern קטוּלָה is itself quite rare in Biblical Hebrew (BH) (Huehnergard 2015, 55); the pattern קטוּלָה is much more common, also overlapping with the feminine singular passive participle in the *qal*. There are at least some other pairs that may exhibit parallel byforms, whether in קטוּל or קטוּלָה, e.g., אֲשָׁרִי ‘my steps’ (Ps. 17.5) versus אֲשָׁרִי ‘my step’ (Job 31.7); שְׁכוּלָה ‘bereaved’ (Isa. 49.21) versus וְשָׁכְלָה ‘and bereaved’ (Song 4.2) (Fox 2003, 201).

While such parallels could, at least theoretically, shed light on the form in Isa. 53.5, the form וּבְחִבְרָתוֹ is unlikely to reflect a mere byform of חבוּרָה without some semantic nuance or distinction of its own. If such were the case, the apparent byform חִבוּרָה would be attested only here. By contrast, the parallel examples of אֲשֶׁר- and שְׁכוּלָה(ו) cited above attest to their byforms without gemination many times throughout the Bible. It would thus be hard to explain why the lone case of the byform חִבוּרָה—without any apparent semantic distinction—occurs only here in Isa. 53.5, especially when the more regular form חבוּרָה occurs in Isa. 1.6.

¹ Note, however, the non-similar sounding form חִבְרָה, which occurs once in the phrase לְחִבְרָה ‘in company’ (Job 34.8). This same noun may also occur in the Samaritan Pentateuch (and oral reading) in וחברתם = [wa:ba:ra:'timma] ‘and their company’ (Gen. 49.7).

1.2. The Lexemes חַבּוּרָה ‘wound’ and חַבּוּרָה/חַבּוּרָה ‘company; association’ in Rabbinic Hebrew

A separate lexeme חַבּוּרָה (or חַבּוּרָה), with a distinct meaning, is, however, attested in Rabbinic Hebrew (RH). In MS Kaufmann of the Mishna, for example, the form without *dagesh* consistently has the meaning ‘company’ or ‘association’, e.g., לֹא יַעֲשֶׂנוּ דָּמִים עָלַי חַבּוּרָה ‘he may not charge its value against the association’ (m. Pesah. 7.3); שְׁתֵּי חַבּוּרוֹת שֶׁהָיוּ אוֹכְלוֹת ‘two associations which were eating’ (m. Ber. 7.5).² The form with *dagesh*, on the other hand, has the meaning ‘wound’ or ‘stripe’, as in the Bible, e.g., זָרַק חַבּוּרָה לַעֲשׂוֹת ‘he threw [it] to inflict a wound’ (m. Shabb. 11.6).³

1.3. Summary of the Philological Problem

According to the vocalisation traditions reflected in the Lenin-grad Codex (L) and RH,⁴ then, it seems that at face value the vocalisation of the form וּבְחַבְרָתוֹ in Isa. 53.5 reflects a reading like ‘and in his association’, ‘and in his company’, or ‘and by union with him’. While it is possible that חַבּוּרָה could reflect a mere

² See also m. Eruv. 6.6; m. Pesah. 7.3, 13; 8.6–7; 9.8–10; m. Beṣa 2.3. Although MS Kaufmann has *holem*, note that חַבּוּרָה/חַבּוּרָה are presumably byforms in Rabbinic Hebrew (possible due to the *resh*); the form with *shureq* is typical in Hebrew lexica (Jastrow 1926; *Milon Even-Shoshan*). Note also that the Babylonian tradition of RH often has *shureq* here, e.g., חַבּוּרוֹת (m. Ber. 7.5; Yeivin 1985, 917).

³ See also m. Shabb. 11.6; m. Beṣa 2.8; m. BabaQ. 8.1, 3, 5; m. Sanh. 11.1; m. Shevu. 5.5. Translations in consultation with Neusner (1988).

⁴ There is some variation in the presence of *dagesh* in the lexeme חַבּוּרָה in the Babylonian tradition of RH (Yeivin 1985, 962–63).

byform of חַבּוּרָה ‘wound’, it seems unlikely that such a (phonological?) byform without any semantic distinction of its own would be attested in just this one verse when the result would actually be homophonous with a distinct lexeme meaning ‘company’ or ‘association’. After all, the word חַבּוּרָה ‘company; association’ would have been known to the early tradents of pre-Tiberian reading traditions. Indeed, it would be reasonable to expect a rendering like ‘and by his wound’, ‘and by his bruise’, or ‘and by his stripe’ to have been passed down in the reading tradition with the vocalisation וּבְחַבְרָתוֹ**.

2.0. Isaiah 53.5 in Modern Translations and Commentaries

Why, then, is the rendering ‘and by his wound(s)’ or the like nearly universal in major translations and commentaries? There are likely two factors at play. First, interpreters have probably afforded more weight to what rendering would best fit the wider context of the verse than to strict adherence to the vocalisation of the Tiberian tradition. Second, it is plausible that the Septuagint’s rendering has exerted significant influence on the course of interpretive history.⁵ These two explanations, of course, are not

⁵ The Septuagint translates וּבְחַבְרָתוֹ as τῷ μῶλωπι αὐτοῦ ‘by his wound’. Elsewhere in the Septuagint, the lexeme μῶλωψ is only ever used to translate what the Tiberian vocalisation tradition vocalises as חַבּוּרָה (Gen. 4.23; Exod. 21.25; Ps. 37.6; Isa. 1.6). In fact, the only place where חַבּוּרָה is not translated with μῶλωψ is in Prov. 20.30, where the phrase חַבְרוֹת פָּצַע ‘blows that wound’ is rendered as ὑπώπια καὶ συντρίμματα ‘bruises and fractures’. The Septuagint rendering may indeed reflect a reading tradition that pronounced וּבְחַבְרָתוֹ as /wa-v-habbu:ra:θo:/ (i.e.,

mutually exclusive. In any case, however we explain it, this interpretation is nearly universal among translators and commentators.

2.1. Modern Translations

In a survey of over thirty English Bible translations' renderings of the phrase *וּבְחֶבְרֹתוֹ* in Isa. 53.5, *all of them* exhibit the rendering 'and by his wound(s)' or some synonymous expression. None of them exhibit a rendering such as 'and in his company':⁶

- *NIV, NASB, CSB, HCSB, NHEB, WEB, CPDV*: 'and by his wounds'
- *ESV*: 'and with his wounds'
- *GWT*: 'from his wounds'
- *NET*: 'because of his wounds'
- *KJV, AKJV, ASV, JPS* (1917), *AFV, DBT, ERV, WBT*, Geneva (1587), Bishops' Bible (1568), Coverdale (1535): 'and with his stripes'
- *NKJV*: 'and by His stripes'
- *BSB*: 'and by His stripes'
- *SLT*: 'and in the marks of his stripes'
- *ISV, Douay-Rheims*: 'and by his bruises'
- *YLT*: 'and by his bruise'
- *NASB* (1977), *NASB* (1995), *LSV*: 'and by His scourging'
- Amplified Bible: 'and by His stripes (wounds)'
- *NLT*: 'he was whipped'

the equivalent of *וּבְחֶבְרֹתוֹ*) with gemination. This interpretive tradition seems to be reflected in the New Testament as well (see 1 Pet. 2.24).

⁶ Survey conducted online at <https://biblehub.com/parallel/isaiah/53-5.htm>.

- *CEV*: ‘by taking our punishment’
- *GNT*: ‘by the blows he received’

Nor do any of these translations appear to footnote the possibility of alternative renderings such as ‘and in his company’, ‘and in his association’, or ‘and by union with him’. This philological crux is thus not apparent in the English translations surveyed.

2.2. Modern Commentaries

A similar pattern is found in modern scholarship and commentaries on this passage. Most modern commentators interpret the phrase as ‘and by his wounds’ or the like, with no comment on the philological difficulty of a lack of *dagesh* in the *bet*. This is the case, for example, in the commentaries of Westermann (1969, 254) in *The Old Testament Library*, Blenkinsopp (2002, 345) in *The Anchor Bible Commentary* series, and many others as well.⁷

There are, however, some notable exceptions to this trend. Goldingay and Payne (2006, 307–8), in *The International Critical Commentary* series, specifically refer to the lexeme in question in v. 5 as ‘*ḥabburāh*’ (with a double *bb*!). Nevertheless, they do not comment on the fact that the form in the MT is without a *dagesh*; rather, they follow the conventional interpretation of ‘wound’. And yet, without connecting it to the vocalisation of the MT, they

⁷ See also Buttrick (1956, 622–23); Duhm (1968, 399); McKenzie (1968, 130–31, 134–35); Herbert (1975, 107, 112); Beuken (1983, 187, 217–18); Watts (1987, 224, 226, 231); Grimm (1990a, 83; 1990b, 412–13); Hanson (1995, 163–64); Berges (1998, 403–5); Koole (1998, 253–54); Oswalt (1998, 384, 387–89); Childs (2001, 407, 414–16); Schmidt (2013, 226, 230–31).

note that the Targum's rendering (ובדנתנהי לפתגמוהי) 'and in that we attach ourselves to his words'; see fn. 9) may point to the more common meaning of 'uniting' or 'joining' for the root חב"ר.

Baltzer, in the *Hermeneia* commentary series, renders Isa. 53.5 differently from all other commentators. He translates וּבְחֶבְרֵתוֹ נִרְפָּא־לָנוּ as 'and through his fellowship/invocation we have received healing'. Despite the unconventional translation, however, Baltzer does not base his rendering on the absence of *dagesh* in the term חֶבְרֵתוֹ. Rather, by appealing to alternate meanings associated with the root חב"ר, he suggests two possible interpretations (2001, 392–429, especially 411–12):

1. First, drawing on examples in which חב"ר refers to '(snake) charming' (e.g., Deut. 18.11; Ps. 58.6), he suggests that the phrase might be rendered as something like 'and through his (snake) charming we received healing'. This would be an allusion to the bronze serpent in Num. 21.4–9 and the exclusive healing ability of Moses in such a context. It might also be set against other contemporary cultic practices and invocations.
2. Second, he suggests that the root חב"ר might better be regarded as referring to 'community' in this context, albeit without any reference to the lack of *dagesh* in the word. Instead, he calls up words like חֶבֶר 'community', חָבֵר 'companion', and חֶבֶר 'fellow-guildsman'. This leads him to the possible alternative rendering of 'through fellowship with him we received healing'. Similarly, this 'community' or 'guild' of the Servant is to be distinguished from contemporary foreign cults and guilds.

While Baltzer touches on literary arguments that may shed light on alternative interpretations of the word חֲבֵרָתוֹ (וּבְ), his philological arguments actually find further support in the vocalisation of the sequence וּבַחֲבֵרָתוֹ in Tiberian Hebrew and the attestation of this word in RH.

There does appear to be more interaction with the exceptional lack of *dagesh* among commentators writing in Modern Hebrew. Paul, for example, writing in the *Miqra le-Yisra'el* series, notes that “this is the lone occurrence in which the *bet* of the word חֲבֵרָה is without a *dagesh*” (translation mine). Nevertheless, he explains the phrase וּבַחֲבֵרָתוֹ נִרְפָּא-לָנוּ as ‘and because of his wounds, we have been healed’ (translation mine) (Paul 2008, 368). In the English version of his commentary, however, published as part of the *Eerdmans Critical Commentary* series (2012), he expounds on this point. After noting that “in every other occurrence... the letter *beth* has a *dagesh* in this word,” he suggests that perhaps the Masoretes “omitted it in order to interpret the word as ‘his company’, thereby tempering the gravity of the servant’s condition” (Paul 2012).

Ḥakham, in his Hebrew commentary on Isaiah in the *Da‘at Miqra* series (1984), presents a similar picture. Although he regards the form in Isaiah as a case of the lexeme חֲבֵרָה ‘wound’, he specifically notes how the lack of *dagesh* in וּבַחֲבֵרָתוֹ (Isa. 53.5) contrasts with the presence of *dagesh* in פָּצַע וְחֲבֵרָה ‘bruise and wound’ (Isa. 1.6). When commenting on the exceptional vocalisation, he writes the following in a footnote:

The pointing חֲבֵרָתוֹ (*havurato*) with *bet rafa* is intended out of respect for Israel. Its purpose is to hint at the fact that they are not really bruised or wounded, but that they are

good friends (*ḥaverim ṭovim*) and their society (*ḥevratam*) brings healing to the world. And this same meaning comes through in Targum Jonathan, who renders [the phrase] וכדנציית לפתגמוהי חובנא ישתבקון לנא [as] ובחברתו נרפא לנו 'and when we obey his words, our iniquities will be atoned for us'. That is, when we attach ourselves (*nithaber*) to him and obey his teaching, our iniquities will be atoned for and we will be healed from our blows (Ḥakham 1984, 570–71, translation mine).

It is difficult to know exactly how to take Ḥakham's explanation in the footnote, since he treats the word as חבירה 'wound' in the main body of the commentary. His argument appears to be that, while the original intention of the biblical author was 'wound' or 'stripe', the oral reading tradition eventually revocalised this word as 'connection' or 'association' to draw attention to the positive aspects of union with Israel. An oral realisation implying Israel's bruising was thereby avoided. This could be compared to cases like the end of Job 2.9, where the euphemistic phrase בִּרְדָּא אֱלֹהִים וּמָתָּ: 'bless God and die!' is written in the consonantal text, but 'curse God and die!' is intended—and thus the unanimous translation. Given that the euphemism of Job 2.9 is found already in the consonantal text,⁸ however, there may be better examples for comparison. Note, for instance, cases where לִרְאוֹת—normally vocalised as a *qal* verb 'to see'—is vocalised as לְהִרְאוֹת 'to appear' (cf. לְהִרְאוֹת) when פְּנֵי יְהוָה 'the face of YHWH' would otherwise be the object of the *qal* verb (Exod.

⁸ There is thus no incongruence between the written and reading traditions.

34.24; Deut. 31.11; see Hornkohl 2023, 56–58). Such an explanation might thus satisfy our earlier question about the uniform rendering of modern translations, while at the same time acknowledge that the vocalisation without *dagesh* should mean something different.

In any case, like Paul, Ḥakham admits that the meaning of חֲבוּרָה should be expected to differ from that of חִבּוּרָה, yet concludes that the different meaning was not actually the original intention of the biblical author. Rather, it serves as a sort of respectful way to minimise the hurt and suffering of Israel and/or the Servant. Also, like Goldingay and Payne, Ḥakham sees significance in the Targum. In fact, the relevance of the Targum for the history of interpretation of this passage is touched on by a number of scholars, even if it does not necessarily impact their reading of the MT. Nevertheless, because Targum Jonathan plays an important role in this study, we will presently turn to its rendering of this passage in greater detail.

3.0. Targum Jonathan and וּבַחֲבֵרְתּוֹ as ‘and in his company’

While, as noted above, few modern translations and commentaries take וּבַחֲבֵרְתּוֹ as ‘and in his company’, there may be evidence of this interpretation already in late antiquity. In Targum Jonathan, the phrase וּבַחֲבֵרְתּוֹ נִרְפָּא לָנוּ is rendered as וּבְדִנְתָּנְהִי לְפִתְגְמוּהִי חוּבְנָא ‘and in that we attach ourselves to his

words, our debts will be forgiven to us'.⁹ The rendering *וּבְדַתְנֵהִי* 'and in that we attach ourselves' is presumably based on a reading of *וּבַחֲבֵרְתּוֹ* that sees in it the root *חב"ר* with the meaning of 'connection' rather than 'wound'. This might imply an interpretation that read *וּבַחֲבֵרְתּוֹ* as containing the RH lexeme *חֲבוּרָה/חֲבוּרָה* 'company; association' rather than the BH lexeme *חֲבוּרָה* 'wound'.

Although multiple Targum scholars appear to be aware of the possibility that the *meturgeman* worked on the basis of an alternate meaning of the root *חב"ר*, none seem to identify the connection with the vocalisation of the Masoretic Text. Kim (2008, 89), for example, rather than drawing on the RH parallel *חֲבוּרָה/חֲבוּרָה* 'union, association', appeals instead to the term *חֲבֵרָה* 'company':

The Targum seems to have achieved [the interpretation of 'by our devotion to his words'] by altering the vocalization of *בְּחֲבֵרְתּוֹ* to *בְּחֲבֵרְתּוֹ* [*sic!*] ('in his company'—through which we gather around him and he is with us), taking the root from *חֲבֵרָה* 'company, companion' (Job 34.8).

While his interpretation of the Targum seems to be on the right track, it does not actually require us to assume that the *meturgeman* had in mind such an alternative vocalisation. For an ancient (or medieval) reader acquainted with various traditions and forms of Hebrew—not just its biblical traditions—the form *חֲבֵרְתּוֹ* would already mean 'his company'.

⁹ See Chilton (1997, 253) for translation, especially the rendering of *וּבְדַתְנֵהִי* as 'and in that we attach ourselves'. Jastrow (1926) glosses the *itpe'el* form of *נָה"י*, namely *אֶתְנֵהִי*, as 'to follow eagerly'.

Also important to note here is the fact that the theme of the suffering of the Servant is entirely absent. In fact, the phrase *וּבְדִנְתָּהּ לְפִתְגְמוֹהִי חוּבָנָא יִשְׁתַּבְּקוּן לָנָא* in the Targum is part of a wider interpretive vision of the Messiah rebuilding the Temple (Chilton 1997, 253–54). Because the Targum probably has its origins between 70–132 CE, one can imagine why the vision of a triumphant Messiah would have been important. After the destruction of the Temple in 70 CE, the idea that the Messiah would come and restore it to its former glory would be most welcome.¹⁰

If the more ‘original’ vocalisation—or at least that of some ancient communities—had been (the equivalent of) *וּבְחִבְרָתוֹ* ‘and by his wound’,¹¹ one wonders if such a socio-historical background might have given rise to the vocalisation in the MT. Schorch (2006; 2009) has argued that the parabiblical traditions

¹⁰ For more on the social and historical background of this passage in the Targum, see Bruce (1982, 63); Chilton (1997, 253–54; 1999, 135; 2007, 243–44); Evans (2004, 102–3); Kim (2008, 87–89); Huizenga (2009, 196–97); Flesher and Chilton (2011, 171, 189–90); Shepherd (2014, 97–100).

¹¹ In the Dead Sea Scrolls, in addition to a text that looks like the MT (1Q8 23.15), there is also one manuscript that reflects a plural form of the noun: *וּבְחִבּוּרֵינוּ נִרְפָּא לָנוּ* ‘and by his wounds we are healed’ (1QIsa^a 44.11). Though less likely, it is also possible that such an orthography reflects a singular form, since *יִ*- can sometimes be used to reflect just the vowel /o/. Nevertheless, given the likely plural number of the word, the interpretation of ‘wounds’—rather than ‘associations’—appears to be reflected. One might tentatively suggest, then, that the scribe of 1QIsa^a pronounced the sequence *וּבְחִבּוּרֵינוּ* as something like /wa-v-habbu:ro:θaw/ (i.e., the equivalent of *וּבְחִבְרֵיתִי* with *dagesh*).

of various Second Temple Jewish and Samaritan communities exerted influence on their oral readings of the text, apart from any deliberate effort to alter its meaning.

Therefore, as a parabiblical or interpretive tradition about a Messiah who would come and rebuild the Temple developed among certain Jewish communities, this might have predisposed them to vocalise certain words in this passage differently than other communities. When they came to the consonantal sequence *ובחברתו*, they might have envisioned healing and restoration in the ‘company’ of the Messiah more instinctively than through the ‘wound’ of the Messiah. As such, they read the sequence *ובחברתו* as /wa-v-ḥāvu:ra:θo:/ ‘and in his company; and in his association’ (i.e., the equivalent of *ובְּחֶבְרֵתוֹ*) in light of their parabiblical tradition. While such a hypothesis is speculative, it might explain the unique vocalisation of the MT.

Such an interpretive tradition, however, by no means reflects the majority reading in late antiquity nor in the Middle Ages. Its explanatory power is thus limited. It, therefore, behoves us to seek a new explanation that can best account for both the strong interpretive tradition sensitive to the context of the verse and the precise vocalisation of the Tiberian reading tradition.

4.0. New Explanation: *Dagesh Mavḥin*

Indeed, while it may be possible to simply read (with Targum Jonathan?) the phrase *ובחברתו* as containing the RH lexeme *חֶבְרָה/חֲבֻרָה* ‘company; association’, there may be a better philological explanation that adheres closer to the overall sense of the

passage. For this, we may turn to a phenomenon attested in various BH reading traditions known as *dagesh mavḥin* ‘*dagesh* to distinguish meaning’. This particular morphophonological phenomenon, on which Geoffrey Khan, the honouree of this *Festschrift*, has helped advance our understanding significantly, can shed further light on the phrase וּבְחֶבְרֹתוֹ in Isa. 53.5, both in the Tiberian vocalisation of the MT and in the history of its interpretation.

4.1. Background on *Dagesh Mavḥin*

Beginning students of BH learn that there are two types of *dagesh*: (1) דגש חזק ‘strong *dagesh*’, which serves to indicate gemination (or ‘doubling’) of a consonant (e.g., מָסַפֵּר [masap^lpe:ɛɾ]) and (2) דגש קל ‘weak *dagesh*’, which indicates the plosive pronunciation of a letter בגדכפ"ת (e.g., מִסְפָּר [mis^lʔkɛ:ɾ]). As one delves deeper into the various reading traditions of BH, however, one encounters other types of *dagesh*. Of particular note for our present purposes is a subclass of ‘strong *dagesh*’ that has come to be termed *dagesh mavḥin* or ‘*dagesh* to distinguish meaning’. In short, *dagesh mavḥin* is the (often secondary) gemination of a consonant to distinguish otherwise homophonous words.¹²

In the Tiberian tradition, *dagesh mavḥin* is often used to distinguish ‘profane’ or ‘common’ nouns from ‘holy’ or ‘divine’ nouns. Note, for example, that while the noun אֲבִיר ‘mighty’ without *dagesh* is used in reference to God, the noun אֲבִירִי is used in

¹² On the phenomenon of secondary gemination for purposes of distinguishing meaning, see Khan (2018). For the employment of *dagesh* to distinguish meaning in the Babylonian Masoretic biblical tradition, see Yeivin (1985, 354–63, 909–12, 940, 1132–33); Khan (2018, 342–44).

reference to people, e.g., אֲבִיר יַעֲקֹב ‘Mighty One of Jacob’ (Gen. 49.24), but cf. אֲבִיר הָרָעִים ‘chief of the shepherds’ (1 Sam. 21.8). Similarly, the noun עֲצָבִים without *dagesh* means ‘toils’, but the noun עֲצָבִים with *dagesh* means ‘idols’, e.g., הָעֲצָבִים ‘the toils’ (Ps. 127.2), but cf. הָעֲצָבִים ‘the idols’ (2 Chron. 24.18) (Khan 2018).

In the Babylonian tradition, similar distinctions are found. Note the difference between כְּהֲנָיִם [ko:h(a)ni:m] (Job 12.19) in reference to priests generally, but הַכְּהֲנָיִם [hakko:han'ni:m] (Zeph. 1.4) in specific reference to pagan priests. Similarly, the form לְעֵמָל [l(ʔ)-ʕm:l] without *dagesh* may be rendered as ‘for/to service (of the LORD)’ (Job 5.7), while the form עֵמָל [ʕm:l] with *dagesh* is interpreted as meaning ‘trouble’ (Job 4.8) (Yeivin 1985, 441, 940; Khan 2018).

In the Samaritan tradition, a form like [ɑ:'da:ni] without *dagesh* refers to the one true God, but a form like [ɑ:'danni] with *dagesh* refers to a human master, e.g., [ɑ:'da:ni] ‘Lord (divine)’ (Gen. 15.2), but [ɑ:'danni] ‘master, sir’ (Gen. 23.6). Similarly, a proper noun may be without *dagesh*, but a common noun with *dagesh*, e.g., [w'ja:mən] ‘and Yamin’ (Gen. 46.10), but cf. [ʔ'jammən] ‘(to the) right’ (Num. 20.17) (Ben-Hayyim 1977; Florentin 1996, 228–35; Khan 2018).

Finally, a similar phenomenon is attested in RH. Of particular note is the tendency to use *dagesh mavhin* to distinguish between the ‘concrete’ (or ‘physical’) and the ‘abstract’. Note, for example, that חֲתִיכָה and חִתִּיכָה may be used for the abstract concept of ‘cutting’ versus the concrete physical meaning of ‘a piece (of something)’, respectively, e.g., וַחֲתִיכֶת ‘and cutting off of’ (m.

Pesah. 6.1), but cf. חֶתֶיכָּה ‘a portion; a piece’ (m. Ker. 5.4). Similarly, in the Yemenite tradition of RH, גְּבִינָה without *dagesh* may be used for the abstract process of making cheese, but גְּבִנָּה with *dagesh* for cheese itself (Khan 2018, 344–45). In fact, the abstract noun in each of these examples may simply constitute what we would refer to in post-biblical Hebrew grammar as the שם פעולה ‘verbal noun’ of the root.

Note that various scholars, most notably Khan (2018), have appealed to *dagesh mavḥin* to explain other phenomena and philological cruxes in BH. In his view, the anomalous *dagesh* in the form בָּתִּים ‘houses’ originally came into being to distinguish the word from a hypothetical (but plausible) participle form */ba:ti:m/ (or */ba:ti:n/) ‘spending the night’ in an earlier stage of Northwest Semitic (Khan 2018). Kantor, expanding on an idea posited originally by Khan, has argued that the *dagesh* in the prefix consonant of the wayyiqṭol verbal form came about in the late Second Temple period to distinguish the form’s ‘past’ semantics from the ‘non-past’ semantics of the polysemous yiqṭol form (Kantor 2020; see also Khan 2021, 319–40).

The mechanism of change that brings about *dagesh mavḥin* is not always clear. In some cases, the form must have originally been polysemous and the gemination developed secondarily merely to distinguish the forms. In other cases, one particular meaning of an originally polysemous form might have been pulled via analogy into a similar-sounding morphological byform. In still other cases, there may have originally been two separate patterns, but they were configured so that the one with

gemination tended to align with certain semantic categories. A combination of such factors is also possible.

However such near-homophonous pairs distinguished only by *dagesh* came about—it is unlikely to have been the same process in all cases—the important point is the resulting synchronic situation. Across the BH reading traditions, there are numerous pairs of words distinguished only by gemination of one of the root letters, which tends to occur in the latter member of contrasting semantic category pairs like the following: (i) ‘holy’ versus ‘profane’, (ii) ‘divine’ versus ‘common’, (iii) ‘monotheistic’ versus ‘pagan’, (iv) ‘abstract’ versus ‘concrete’.

4.2. *Dagesh Mavhin* and Isaiah 53.5

Returning to the near-homophonous pair of חֲבוּרָה and חִבּוּרָה, then, we may tentatively posit that the latter member of this pair constitutes an instance of *dagesh mavhin*. As was the case in the typology of the examples from RH mentioned above, the noun with the more abstract meaning is without *dagesh* (i.e., חֲבוּרָה), whereas the noun with the more concrete physical meaning is with *dagesh* (i.e., חִבּוּרָה).

While it may be tempting to see the lexemes identified above, namely חֲבוּרָה ‘company; association’ and חִבּוּרָה ‘wound’, as fitting this paradigm, such a pair would not actually satisfy the typical criteria for *dagesh mavhin*. After all, in the RH *comparanda* cited above, there is a high degree of polysemy in each pair. In the pair חֲתִיכָה ‘cutting’ versus חִתִּיכָה ‘a piece (cut from something)’, the semantics of ‘cutting’ are at the core of each lexeme from the root חת"ך. The same applies to the pair גְּבִינָה ‘making

cheese' versus גִּבְנָה 'cheese'. In each case the root גִּב"ן has a base semantic association with 'cheese'. There is not, however, any apparent polysemy that would connect the distinct lexemes חֲבוּרָה 'company; association' and חֲבוּרָה 'wound'.

Rather, based on analogy with the pairs חֲתִיכָה 'cutting' versus חֲתִיכָה 'piece cut off' and גִּבְיָה 'making cheese' versus גִּבְנָה 'cheese', we should perhaps posit the following hypothetical pair: חֲבוּרָה '(process of) wounding; bruising' versus חֲבוּרָה '(physical) wound; bruise'. While this theoretical pair would fit quite nicely with the RH examples of *dagesh mavḥin* to distinguish concrete from abstract, it requires positing the existence of a lexeme, namely חֲבוּרָה '(process of) wounding; bruising', that is unattested elsewhere in ancient or medieval Hebrew literature. Though somewhat speculative, such a hypothesised lexeme would also fit well within the wider context of the verse. Moreover, though largely overlooked in modern scholarship, numerous of the medieval Hebrew grammarians appear to have interpreted the form וַיַּחֲבֹרְתוּ of Isa. 53.5 in this way (i.e., as a verbal noun) as well. It is thus to their writings that we turn presently.

4.3. Medieval Grammarians on Isaiah 53.5 and the Implications for *Dagesh Mavḥin* in חֲבוּרָה

As implied by the discussion above, seeing *dagesh mavḥin* in the lexeme חֲבוּרָה 'wound; bruise' would imply that the form וַיַּחֲבֹרְתוּ without *dagesh* found in Isa. 53.5 has the more abstract meaning. Just such an interpretation notably appears to be reflected in at least some of the medieval Hebrew grammarians.

In Jonah ibn Janāḥ's (ca 990–ca 1050 CE) famous lexicon, *Kitāb al-uṣūl*, we find the following comments on the lexeme חבורה (Neubauer 1968, 208–9):

חבורה [תחת חבורה]. הבאישו נמקו חבורותי. חבורות פצע כלֵה גرح
 وخدش. ومنه عندی ובחבורתו נרפא לנו. وهو اسم الفعل لا اسم الجرح
 نفسه على زنة [אין קול ענות גבורה]. אין קול ענות חלושה. משפט
 הבכורה... فكأنه قال وبחבור אתו.

הבאישו. 'wound for wound' (Exod. 21.25). חבורה תחת חבורה
 חבורות פצע. 'my wounds stink and rot' (Ps. 38.6). נמקו חבורתי
 'stripes that wound' (Prov. 20.30). [The meaning] in all of
 [these cases] is 'wound' and 'abrasion'. In this sense I [may
 also cite] 'and by his חבורה we are healed' (Isa. 53.5), in which [חבורה] is the verbal noun (*ism al-fiʿl*)—not the noun [referring to the physical] wound it-
 self—after the pattern of 'it is not the sound of crying out in triumph' (Exod. 32.18), 'אין קול ענות גבורה', 'it is not the sound of crying out in defeat' (Exod. 32.18), 'חלושה', 'right of being firstborn' (Deut. 21.17)... so it is as if it said 'and in bruising him'.
 (translation mine)

While Ibn Janāḥ clearly sees the semantics of חבורה as related to 'wound' and 'abrasion' in all of these passages, he makes the point that in the case of 'and in bruising him' in Isa. 53.5 we are dealing with 'the verbal noun' and 'not the noun [referring to the physical] wound itself'. His conclusion that 'and in bruising him' is equivalent to 'and in bruising him' clearly highlights the nuanced implications of reading it as a verbal noun rather than referring to a physical wound. Though Ibn Janāḥ does not explicitly impute the semantic distinction to the absence of *dagesh*, his comments certainly appear to be consistent

with seeing an abstract versus concrete distinction in חִבּוּרָה ‘(process of) wounding; bruising’ versus חִבּוּרָה ‘wound; bruise’.

A similar reading appears in Judah ibn Balaam’s (1000–1070 CE) commentary on Isaiah (Goshen-Gottstein 1992, 214):

מוסר שלומנו עליו ובחבורתו נרפא לנו – מענאה אן הד׳א אלולי אלפאצ׳ל
למא תחמל אלדאב אלוארדה עליה עלי סביל אלמחנה אד׳ כאן לא ד׳נב
לה פכאן כל אדב כאן ילזמנא נחן וסלמנא מנה קד חל בה ונזל עליה וכאן
בג׳רחה שפאנא. ובחבורתו אסם פעל.

‘the chastisement of our peace was upon him, and by his wound(s) we are healed’ (Isa. 53.5) – Its meaning is that this honourable Servant, in bearing the punishments coming upon him by way of trial, though he had committed no offence, [brought it about that] we escaped intact every punishment that should have fallen on us, [so that] it has befallen him and has come down upon him [instead]. And by his wound(ing) we are healed. [The phrase] וּבְחִבּוּרָתוֹ is a verbal noun (*ism fiʿl*). (translation mine)

The identification of the word חִבּוּרָה in the phrase וּבְחִבּוּרָתוֹ as an اسم فعل ‘verbal noun’ implies that Ibn Balaam also regarded it as the more abstract ‘(process of) wounding; bruising’ rather than the more concrete ‘wound; bruise’.

4.4. The Chronology of *Dagesh Mavhin* in חִבּוּרָה

If the form חִבּוּרָה ‘wound, stripe’ came to be secondarily distinguished from חִבּוּרָה ‘(process of) wounding; bruising’ by means of *dagesh* in the *bet*, one might wonder if such a distinction was even present in ancient times at all. After all, if the distinguishing gemination was introduced relatively late in חִבּוּרָה ‘wound’, earlier polysemy could have given rise to a variety of interpretations of

the verse, some of which we may encounter in the ancient versions. Nevertheless, though late innovation may be the case with some instances of *dagesh mavhin*, the variety of processes by which *dagesh mavhin* can come about do not require it (see above in §4.1). Indeed, gemination of *bet* in the word חבורה ‘wound, stripe’ is attested in multiple reading traditions of BH as far back as we can trace:

Babylonian (Yeivin 1985, 962–63)

חֲבֻרוֹת ‘wounds’ (Prov. 20.30)

חֲבֻרוֹתַי ‘my wounds’ (Ps. 38.6)

Samaritan (Ben-Hayyim 1977)

labbu:ra:ti ‘for my wound’ (Gen. 4.23)

ṣab'bu:ra 'ta:t ṣab'bu:ra ‘stripe for stripe’ (Exod. 21.25)

Because gemination of /bb/ is attested in both the ‘Jewish’ and the ‘Samaritan’ branches of BH, we may reasonably posit that the form חבורה ‘wound, stripe’ is at least as old as the late Second Temple Period.¹³

Along the same lines, however, one might question how relevant the concept of *dagesh mavhin* is for the original interpretation of Isa. 53.5. While gemination of /bb/ in חבורה ‘wound’ might be as old as the late Second Temple period, the typological evidence for gemination distinguishing ‘physical/concrete’ versus ‘abstract’ adduced above is from RH. Moreover, the relevance of this phenomenon for the interpretive history of Isa. 53.5 does

¹³ The nominal pattern *qatūla is more common than *qattūla (see discussion above in §1.1).

not appear to be evidenced before the medieval Hebrew grammarians of the eleventh century. It is thus possible that seeing *dagesh mavḥin* as distinguishing חִבּוּרָה ‘bruise; wound’ from חִבּוּרָה ‘bruising; wounding’ is a later interpretive innovation.

Now while the ‘verbal-noun’ interpretation may not be attested explicitly in antiquity, we may be able to find some examples of gemination to distinguish ‘physical/concrete’ versus ‘abstract’ beyond just RH. After all, Khan’s (2018) argument regarding the form בָּתִּים ‘houses’ is that already in Northwest Semitic gemination came to distinguish (the more physical/concrete form) **battin* ‘houses’ from (the more abstract/participial/verbal hypothesised form) **batin* ‘spending the night’. Moreover, even though some of the clearest examples of *dagesh* to mark the more concrete entity—e.g., גִּבְנָה ‘cheese’ versus גִּבְנָה ‘making cheese’—are attested in RH, we may find some similar pairs in the Bible as well. Note that the *dagesh* in the form הַמִּקְרָה ‘the roof; the rafter’ (Eccl. 10.18) may be regarded as distinguishing the physical entity from the more abstract participial/verbal action in הַמִּקְרָה ‘the one who lays the beams’ (Ps. 104.3).¹⁴ In Babylonian Hebrew, a *dagesh* may distinguish נָא ‘raw’ (Exod. 12.9) from the interjection נָא ‘please’ without *dagesh*. Similarly, a *dagesh* may distinguish the form עָלָהּ [ʕa:lːa:hɔ:] ‘its (FS) leaf’ from something like עָלֶיהָ [ʕa:lːa:hɔ:] ‘upon her’ (see Yeivin 1985, 357–58, 965). One might even regard *dagesh mavḥin* for marking ‘human/profane’ over against ‘divine’ as loosely related to the ‘physical’ versus ‘abstract’ use attested in RH.

¹⁴ I would like to thank Ben Rothstein for bringing this example to my attention.

5.0. Conclusions: Exegetical Ramifications

The purpose of this article is not to overturn the traditional interpretation of Isa. 53.5. In fact, though perhaps requiring a slightly nuanced modification of our interpretation of **וּבְחִבְרָתוֹ** from ‘and by his wound(s)’ to ‘and by/in his bruising’, a careful analysis of the vocalisation tradition has yielded a rendering largely concentric with traditional interpretations. Rather, the main point of this article has been to draw attention to the fact that the Tiberian vocalised form **וּבְחִבְרָתוֹ** is not what we would expect for the simple meaning ‘and by his wound(s)’ and subsequently to lay out possible suitable explanations for this philological crux.

In the end, we have argued that, as is common in various Hebrew traditions in similar contexts, *dagesh mavhin* may distinguish the more physical concrete **חִבְרָה** ‘wound, stripe’ from the more abstract **חִבְרָה** ‘(process of) wounding; bruising’ in a near-homophonous pair. The form without *dagesh* in Isa. 53.5, then, would reflect the more abstract noun of the pair. Exegetically, this may imply that the text envisions the process of physical suffering endured by the Servant as bringing healing rather than focusing on the specific physical wounds themselves. Though often overlooked by modern scholars, this verbal-noun interpretation, based on a precise reading of the Tiberian vocalisation, already appears among the medieval Hebrew grammarians of al-Andalus such as Ibn Janāḥ and Ibn Balaam. At the same time, however, we should be careful to note that this use and grammatical understanding of *dagesh mavhin* is more common in post-biblical Hebrew and among the medieval grammarians. It thus remains a

question to what extent such an interpretation belongs with the original language of the text and not merely later reception history.

Indeed, we cannot totally rule out the possibility that at least some ancient Jewish communities read *ובחברתו* in Isa. 53.5 as reflecting the RH lexeme *חִבּוּרָה/חִבּוּרָה* ‘company; association’. Such a reading may in fact underlie the interpretive tradition behind Targum Jonathan. The vocalisation without a *dagesh* in Tiberian may even reflect the influence of a parabiblical tradition like that of the community in which the Targum developed. From an exegetical standpoint, this would imply that by following the teachings of the Servant and becoming his disciple, one might receive healing. Other interpretations based on taking *ובחברתו* as ‘and in his community’ or ‘and in his company’ are also possible. While it lies beyond the scope of this paper to fully flesh out what exegetical ramifications such a reading might have, we refer the reader to the commentary of Baltzer (2001; see above, §2.2) as an example of at least one possible interpretation.

Nor can we ultimately rule out the suggestion of scholars like Paul and Hakham, who argue that the vocalisation may have shifted from *חִבּוּרָתוּ* to *חִבּוּרָתוּ* out of respect for Israel and/or the Servant. As such, this vocalisation should be compared to other reverent mismatches in the Bible, like *בָּרַךְ אֱלֹהִים* ‘bless God!’ when the intended meaning is actually ‘curse God!’ or *לִרְאוֹת אֶת־פְּנֵי יְהוָה* ‘to appear before the LORD’ when the original meaning might have been ‘to see the face of the LORD’ (see above in §2.2). The underlying meaning, however, would still be *חִבּוּרָתוּ* ‘his wound’ rather than *חִבּוּרָתוּ* ‘his company’.

We should also note that in the late Second Temple Period, there may have been other reading traditions according to which this text was realised as (the equivalents of) *וּבְחִבְרָתוֹ* or *וּבְחִבְרָתָיו*, including that of the Septuagint translators and that of (some of) the Dead Sea Scrolls. In such cases, the traditional rendering referring to the physical wound(s) of the Servant would be the most apt translation. Indeed, wherever *חבורה* is attested with plural morphology, the ‘verbal-noun’ interpretation would presumably be excluded, or at least less likely. This point underscores the importance of taking into account multiple oral reading traditions of BH when interpreting the Bible.

Nevertheless, while allowing for a variety of possible explanations,¹⁵ we have argued that positing a distinction between *חִבְרָה* ‘(process of) wounding; bruising’ and *חִבְרָה* ‘(physical) wound; bruise’ is at least one way of respecting the Tiberian vocalisation within its wider interpretive context. It would also constitute one more example of the well-established phenomenon of *dagesh mavhin* attested in various reading traditions of Hebrew.

References

- Baltzer, Klaus. 2001. *Deutero-Isaiah: A Commentary on Isaiah 40–55*. Hermeneia. Minneapolis, MN: Fortress Press.
- Ben-Hayyim, Ze’ev. 1977. *The Literary and Oral Tradition of Hebrew and Aramaic Amongst the Samaritans*, vol. IV: *The*

¹⁵ It may even be appropriate to allow for multiple interpretations *intended* by the original author of the text. For more on this concept in the Hebrew Bible, see Paran (1973).

- Words of the Pentateuch*. Jerusalem: The Academy of the Hebrew Language. [Hebrew]
- Berges, Ulrich. 1998. *Das Buch Jesaja*. Biblische Gestalten 22. Freiburg: Herder.
- Beuken, Willem A. M. 1983. *Jesaja: Deel II B*. De Prediking van het Oude Testament. Nijkerk: Callenbach.
- Blenkinsopp, Joseph. 2002. *Isaiah 40–55: A New Translation with Introduction and Commentary*. Anchor Bible Commentary 19A. New York: Doubleday.
- Bruce, Frederick F. 1982. 'The Background to the Son of Man Sayings'. In *Christ the Lord: Studies in Christology Presented to Donald Guthrie*, edited by Harold H. Rowdon, 50–70. Leicester: Inter-Varsity Press.
- Buttrick, George Arthur. 1956. *The Interpreter's Bible*, vol. V: *The Book of Ecclesiastes; The Song of Songs; The Book of Isaiah; The Book of Jeremiah*. New York: Abingdon Press.
- Childs, Brevard S. 2001. *Isaiah*. Old Testament Library. Louisville, KY: Westminster John Knox Press.
- Chilton, Bruce. 1997. 'The Temple in the Isaiah Targum'. In *Jesus in Context: Temple, Purity, and Restoration*, edited by Bruce Chilton and Craig A. Evans, 251–62. *Arbeiten zur Geschichte des antiken Judentums und des Urchristentums* 39. Leiden: Brill.
- . 1999. 'The Targumim and Judaism of the First Century'. In *Judaism in Late Antiquity 3: Where We Stand—Issues and Debates in Ancient Judaism*, edited by Jacob Neusner and Alan Jeffery Avery-Peck, 115–50. *Handbook of Oriental*

- Studies, Section 1 The Near and Middle East 40. Leiden: Brill.
- . 2007. 'Targum, Jesus, and the Gospels'. In *The Historical Jesus in Context*, edited by Amy-Jill Levine, Dale C. Allison, Jr, and John Dominic Crossan, 238–55. Princeton Readings in Religions. Princeton, NJ: Princeton University Press.
- Duhm, Bernhard. 1968. *Das Buch Jesaia*. Göttinger Handkommentar zum Alten Testament: Die prophetischen Bücher 1. Göttingen: Vandenhoeck & Ruprecht.
- Evans, Craig A. 2004. 'Targumizing Tendencies in Matthean Redaction'. In *When Judaism and Christianity Began: Essays in Memory of Anthony J. Saldarini*, edited by Alan Jeffery Avery-Peck, Daniel Harrington, and Jacob Neusner, 93–116. Leiden: Brill.
- Flesher, Paul V. M., and Bruce Chilton. 2011. 'Targum Jonathan of the Prophets: Its Development as Revealed by the Targum of Isaiah'. In *The Targums: A Critical Introduction*, edited by Paul V. M. Flesher and Bruce Chilton, 169–98. Waco, TX: Baylor University Press.
- Florentin, Moshe. 1996. 'Iyunim be-Torat ha-Šurot shel 'Ivrit ha-Shomronim: Bidulim Semantiyim be-'Emša'im Morfolo-giyim'. *Leshonenu* 59/3: 217–41.
- Fox, Joshua. 2003. *Semitic Noun Patterns*. Harvard Semitic Studies 52. Winona Lake, IN: Eisenbrauns.
- Goldingay, John, and David Payne. 2006. *Isaiah 40–55*, vol. 2. International Critical Commentary. London: T&T Clark.
- Goshen-Gottstein, Moshe. 1992. *Perush R. Yehuda 'ibn Bal'am le-Sefer Yish'ayahu*. Ramat-Gan: Bar-Ilan University Press.

- Grimm, Werner. 1990a. *Das Trostbuch Gottes: Jesaja 40–55*. Stuttgart: Calwer Verlag.
- . 1990b. *Deuterojesaja: Deutung – Wirkung – Gegenwart: Ein Kommentar zu Jesaja 40–55*. Calwer Bibelkommentare. Stuttgart: Calwer Verlag.
- Ḥakham, Amos. 1984. *Sefer Yish‘ayahu*. Da‘at Miqra. Jerusalem: Mossad Harav Kook.
- Hanson, Paul D. 1995. *Isaiah 40–66*. Interpretation: A Bible Commentary for Teaching and Preaching. Louisville, KY: John Knox Press.
- Herbert, Arthur S. 1975. *The Book of the Prophet Isaiah: Chapters 40–66*. The Cambridge Bible Commentary on the New English Bible. Cambridge: Cambridge University Press.
- Hornkohl, Aaron. 2023. *The Historical Depth of the Tiberian Reading Tradition of Biblical Hebrew*. Cambridge Semitic Languages and Cultures 17. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/OBP.0310>
- Huehnergard, John. 2015. ‘Biblical Hebrew Nominal Patterns’. In *Epigraphy, Philology, and the Hebrew Bible: Methodological Perspectives on Philological and Comparative Study of the Hebrew Bible in Honor of Jo Ann Hackett*, edited by Jeremy M. Hutton and Aaron D. Rubin, 25–64. Atlanta: SBL Press.
- Huizenga, Leroy. 2009. ‘The Suffering Servant and Matthean Christology’. In *The New Isaac: Tradition and Intertextuality in the Gospel of Matthew*, edited by Leroy Huizenga, 189–208. Leiden: Brill.

- Jastrow, Marcus. 1926. *A Dictionary of the Targumim, the Talmud Babli and Yerushalmi, and the Midrashic Literature; with an Index of Scriptural Quotations*. New York: Choneb.
- Kantor, Benjamin. 2020. 'The Development of the Hebrew way-yiqtol ('Waw Consecutive') Verbal Form in Light of Greek and Latin Transcriptions of Hebrew'. In *Studies in Semitic Vocalisation and Reading Traditions*, edited by Aaron D. Hornkohl and Geoffrey Khan, 55–132. Cambridge Semitic Languages and Cultures 3. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/OBP.0207.02>
- Khan, Geoffrey. 2018. 'How Was the *Dageš* in Biblical Hebrew םִתְּנָה Pronounced and Why Is It There?' *Journal of Semitic Studies* 43/2: 323–51.
- Kim, Jintae. 2008. 'Targum Isaiah 53 and the New Testament Concept of Atonement'. *Journal of Greco-Roman Christianity and Judaism* 5: 81–98.
- Koole, Jan L. 1998. *Isaiah: Part 3: Volume 2: Isaiah 49–55*. Historical Commentary on the Old Testament. Leuven: Peeters.
- McKenzie, John L. 1968. *Second Isaiah: Introduction, Translation, and Notes*. The Anchor Bible Commentary 20. Garden City, NY: Doubleday.
- Neubauer, Adolf. 1968. *The Book of Hebrew Roots by Abu 'l-Walīd Marwān ibn Janāḥ (Rabbī Yônāḥ)*. Amsterdam: Philo Press.
- Oswalt, John N. 1998. *The Book of Isaiah: Chapter 40–66*. New International Commentary on the Old Testament. Grand Rapids, MI: Eerdmans.

- Paul, Shalom. 2008. *Yish'aya: 40–66*. Miqra le-Yisra'el. Tel-Aviv: 'Am 'Oved.
- . 2012. *Isaiah 40–66: Translation and Commentary*. Eerdmans Critical Commentary. Grand Rapids, MI: Eerdmans.
- Paran, Moshe. 1973. 'Le-Mishne Hora'a ba-Miqra'. *Beer-Sheba* 1: 150–61.
- Schmidt, Uta. 2013. *Zukunftsvorstellungen in Jesaja 49–55: Eine textpragmatische Untersuchung von Kommunikation und Bildwelt*. Neukirchen-Vluyn: Neukirchener Theologie.
- Schorch, Stefan. 2006. 'The Septuagint and the Vocalisation of the Hebrew Text of the Torah'. In *XII Congress of the International Organisation for Septuagint and Cognate Studies, Leiden 2004*, edited by Melvin K. Peters, 41–54. Leiden: Brill.
- . 2009. 'Communio lectorum'. In *Die Textualisierung der Religion*, edited by Joachim Schaper, 167–84. Tübingen: Mohr Siebeck.
- Shepherd, David. 2014. 'When He Comes, Will He Build It?: Temple, Messiah and Targum Jonathan'. *Aramaic Studies* 12: 89–107.
- Steiner, Richard C. 2007. 'Variation, Simplifying Assumptions, and the History of Spirantization in Aramaic and Hebrew'. In *Sha'arei Lashon: Studies in Hebrew, Aramaic and Jewish Languages Presented to Moshe Bar-Asher*, edited by Aharon Maman, Steven E. Fassberg, and Yochanan Breuer, 52–65. Jerusalem: Bialik Institute.
- . 2011. 'Ḥ > Ḥ in Assyria and Babylonia'. In *A Common Cultural Heritage: Studies on Mesopotamia and the Biblical*

World in Honor of Barry L. Eichler, edited by Grant Framge et al., 195–206. Bethesda, MD: CDL Press.

Watts, John D. W. 1987. *Isaiah 34–66*. Word Biblical Commentary 25. Waco, TX: Word Books.

Westermann, Claus. 1969. *Isaiah 40–66: A Commentary*. The Old Testament Library. Philadelphia: Westminster Press.

Yeivin, Israel. 1985. *Masoret ha-Lashon ha-Ivrit ha-Mishtaqqet ba-Niqud ha-Bavli*. Jerusalem: The Academy of the Hebrew Language.

WHY DO PSALMS, PROVERBS, AND JOB USE DIFFERENT ACCENTS?

Elizabeth Robar

Before scribes used accents and pausal forms, they used spaces. Gentry and Meade (2020) have shown that in an old tradition represented by a Masada Psalms scroll (first century BCE), spacing is the strategy used to divide the text into sense units. The same sense units are delimited by pausal forms and accents in the Aleppo Codex, with spaces sometimes used non-linguistically (e.g., dividing elements of a construct chain). Gentry and Meade (2020, 130) conclude that “the pausal forms and accents are the key terminal markers in A[leppo] and the spacing is only a memory of a past scribal technique.”

This simultaneously marks an evolution in the technique used to mark sense units (from spacing to pausal forms and accents) and a united tradition determined to preserve those same sense units. After discussing the similarities between Greek Sinaiticus and Vaticanus and MasPs^a in terms of stichometry, Gentry and Meade conclude that

five hundred years after the original translation, B and S have largely preserved the terminal markers [indicating sense units] of a Hebrew parent text like MasPs^a. The evidence suggests that the original translation into Greek followed the stichometric layout in poetic texts and even in the earliest texts had spaces corresponding to the reading

tradition, and that this tradition was preserved for some time. (Gentry and Meade 2020, 138)

The main sense units were preserved across the evolution of scribal technique, translation into Greek, and change in writing medium from scroll to codex. The sense units superseded any single tradition and were rather embedded into all traditions.

1.0. The Three Books

Within the Tiberian tradition, the Masoretic accentuation became the most prominent way of preserving sense units. There are two traditions of accentuation, one for the Three (Psalms, Proverbs, and Job)¹⁴⁵ and one for the other (21) books. The former tradition is heuristically called the ‘poetic accents’ and the latter the ‘prose accents’.

The historical basis for this division is not entirely clear, but the unique position of at least the Psalms seems to have ancient roots. By the first century CE,¹⁴⁶ the gospel of Luke reports Jesus referring to τῷ νόμῳ Μωϋσέως καὶ τοῖς προφήταις καὶ ψαλμοῖς ‘the Law

¹⁴⁵ Also known as ספרי אמ"ת ‘books of *’emet* (‘truth’), *’alef* for איוב ‘Job’, *mem* for משלי ‘Proverbs’, and *tav* for תהלים ‘Psalms’.

¹⁴⁶ 4QMMT^d (4Q397), known as *Miqṣat Ma‘aṣe Ha-Torah* ‘Some Works of the Torah’—most likely composed around the end of the second century BCE or beginning of the first century CE (Kratz 2020, 21–23)—also appears to refer to a tripartite canon: [כתב]נו אליכה שתבין בספר מושה׳ [ו] בספר [י] ‘We have written to you that you might understand the book of Moses, the books of the Prophets and David’ (4Q397 f14–21.10).

of Moses, the Prophets and the Psalms' (Luke 24.44), possibly indicating Psalms' central importance within Judaism's sacred texts, or its name as an *incipit* to represent the *Ketuvim* 'Writings'.¹⁴⁷

This distinction extended throughout multiple stages of (what became) the Masoretic tradition. Revell (1977, 183) concluded that the Palestinian fragments containing the three books differed from one another significantly: "the accentuation of the three books was not standardised to nearly the same extent as was that of the 21 books." He proposed as a possible reason that there was a "much greater variety of chant" used for the text of the three books (183).¹⁴⁸ The most compelling piece of evidence for the distinction is a Masoretic list found in T-S NS 287.38.¹⁴⁹ This manuscript is unique, including passages from both the 'prose' and 'poetic' sections in the list. Like the Tiberian system, this MS testifies

¹⁴⁷ Beckwith (1985, 111) argues in favour of a reference to a tripartite canon; McDonald (2017, 277–86) cautions that the evidence is too meagre, but acknowledges the Psalms' privileged place, nonetheless. Just as the first word of the Hebrew Bible was used as the title for entire books (e.g., בראשית, *berašit*), so the first book (e.g., 'Isaiah') of a section may have been used as a title for the entire section (e.g., Latter Prophets). Cf. the gospel of Mark's use of 'Isaiah' to represent a prophetic text actually from the book of Malachi: Καθὼς γέγραπται ἐν τῷ Ἡσαΐα τῷ προφήτῃ (Mark 1.2), followed by citing Mal. 3.1.

¹⁴⁸ Revell here relies on the testimony of R. Petachia of Ratisbon who—while travelling around the Middle East towards the end of the 12th century—noted the following while visiting Babylonian synagogues: ויש בחור שיש לו קול נעים ואומר מזמור בקול נעים... ויש מסורות באיזה ניגונים '[When] there is a young man who has a pleasant voice, he recites (lit., 'says') a Psalm in his pleasant voice... tradition determines the melodies [with which he recites the Psalm]' (he-Hasid 2012, 46 [text]).

¹⁴⁹ Described in Revell (1969).

to two different sets of accents, one for verses from the ‘prose’ books, and one for those from the ‘poetic’ books. For example, the sign for *revia*‘ is a prepositive circle for verses from the ‘three books’, e.g., אֲשַׁמְעָה ‘Let me hear’ (T-S NS 287.38 recto ln 2) || MT אֲשַׁמְעָה (Ps. 85.9), whereas in verses from the prose books, it is a vertical stroke above the accented syllable, e.g., הָמָן ‘Haman’ (T-S NS 287.38 verso ln 14) || MT הָמָן (Est. 3.6).

This distinction extended beyond the Tiberian tradition. In the Babylonian tradition, though identical signs are used both for the ‘prose’ and ‘poetic’ books, Ronit Shoshany (2022, 112) has recently demonstrated that they were not used identically.

The early eleventh-century Karaite grammarian ‘Abū al-Faraj Hārūn claims that the poetic books are derived from (פרוע *furū*‘ ‘secondary, derivatives, branches’) or complement the books of the Torah (אצול *uṣūl*‘ ‘primary, foundations, trunks’), and this derivation or complementation correlates with their distinctive accents. He considers this a traditional view, not a new one (Khan 2020, 2:38–39).

By the end of the Masoretic period, Psalms, Proverbs, and Job had come to be distinguished both in their contents and in their reading tradition, although the relationship between the two—if there is one—remains unclear. What is clear, however, is that the accents aided the reading and the reception of the text in some way. To understand likely options, we will briefly survey the relationship between ‘sound’¹⁵⁰ and sacred scripture across multiple religious traditions.

¹⁵⁰ The recent interest in the role of ‘sound’ within comparative religion is reflected in, e.g., Laack (2015), Coward (2013; 2019) and Cuffel et. al. (2019, §17).

2.0. Sound and Sacred Scripture

In Hinduism the chanting of sacred texts (*mantra*) possesses magical qualities that provide the devotee with an *experience* of the Divine. The *mantra* refers to what Otto (1958, 5–7, 190–93) would call “numinous sounds,” sounds that reflect the “holy.” The actual words of the sacred Vedas (*śruti*) are afforded this power due to their origin:

The language of Veda itself is *Śruti*, a rhythm not composed by the intellect but heard, a divine Word that came vibrating out of the Infinite to the inner audience of the man who had previously made himself fit for the impersonal knowledge. (Aurobindo 1998, 10)¹⁵¹

The manner of chanting the *Qurʾān*, too, is also primarily geared towards an *experience*. *Qurʾān* recitation is regulated by a series of detailed rules known as *Tajwīd*, largely phonetic rules concerning nasality (*ḡunna*), assimilation (*ʾidḡām*, *ʾixfāʾ*, and *ʾiqlāb*), pharyngealisation (*tafxīm*), as well as regulation of syllabic duration (*madd*) (Nelson 2011). In the Islamic tradition, the application of *Tajwīd* produces the very sound of the revelation as it was given to the Prophet Muhammad by Gabriel (Nelson 1985, 14). Although the art of reading in the Islamic tradition was concerned with clearly conveying the *meaning* of the text, conveying the accuracy of sound was more fundamental, which falls into the category of *experience*.

¹⁵¹ This section is based on Coward (2019, 1–18).

This tension between *meaning* and *experience* also characterised the reading of scripture in early Syriac Christianity. Music and sung poetry were the lifeblood of early Syriac liturgy (Harvey 2020a). Hymns, prayers, supplications, and preaching were all sung in either an ornate style called *madrāshā*, characterised by a variety of metres and melodies, or *memrā*, which was much simpler with regard to metre and melody (Harvey 2020b). These liturgical settings were the only time that congregants encountered scripture, through both the cycle of lections and quotes in homilies (Brock 2006). Practices of scripture reading varied according to time and place, most clearly seen in Syriac biblical manuscripts, which testify to a developing system of accents. Segal (1953, 58–77) indicates that, before the seventh century, accents used may have been those indicating punctuation in addition to vocal inflection. From the seventh to tenth centuries, the accents developed differently between the Eastern and Western traditions. The data from the Eastern tradition tend to reflect greater emphasis on the musical performance of the accents (viz., an experience), whereas the Western data reflect the rhetorical value of some accents (viz., facilitating understanding) (see Segal 1953, 80–81). According to Harvey (2020a, 376), the value of music was “*affective*: it made an impact on those who sang and those who heard.”

In the Latin-speaking West, scripture was read in the style of plainchant, also known as Gregorian chant. The origins of this style remain unknown, and sources containing actual musical information do not appear until ca 900 CE (Crocker 1990, xv). In contrast to what had gone before, Crocker contends Gregorian

chant was *not* primarily aimed at conveying clearly the words and meaning of the text. Crocker (1995, 44) writes:

the fact is that the chant fails to communicate its words to the world, even to the faithful. The chant really does not project the words in a way that is immediately perceptible to most listeners... the chant cannot be said to communicate either the sound or the sense of the words with anything like the effectiveness claimed or to be expected for a style allegedly derived from the words... the plurality of pitches by itself hinders the pronunciation as well as the recognition of syllable integrity, and the melodic contours break up the phonetic flow of the words with beautiful but irrelevant distractions. And of course the melismata simply force a suspension of attempts to perceive verbal syntax.

The traditions of reading and chanting sacred texts briefly outlined above may suggest a continuum. At one end are traditions which are primarily concerned with affording an *experience*, such as the Hindu Vedas and, to a lesser extent, Gregorian chant. On the other end are reading traditions that are primarily concerned with affording an *understanding* of the words and syntax and, consequently, the ‘plain’ meaning of the text.¹⁵² Early Syriac texts would probably fall into this category. The recitation of the *Qur’ān* and pre-classical Byzantine recitation would probably fall somewhere in between these two extremes.

¹⁵² Although not discussed above, Revell (1976) argues that biblical texts from the Second Temple Period and shortly after—the Naḥal Ḥever scrolls, the Greek uncial codices, and texts that contain the Samaritan Pentateuch—reflect this type of reading.

3.0. Experiential and Propositional Knowledge

We may draw a meaningful connection between the spectrum outlined above and some recent proposals in Cognitive studies. Vervaeke et. al. (2009) have argued for the importance of relevance realisation for various problems of cognition. The heart of relevance realisation is “to be able to usefully ignore information in a contextually sensitive manner so as to enable our actions” (Vervaeke and Ferraro 2013, 28). Stated positively, managing information flow—and thereby not being overwhelmed by combinatorial explosion when trying to act in the world—involves discerning patterns. Patterns between events afford us *procedural* knowledge (‘knowing how’); causal patterns between facts afford us *propositional* knowledge (‘knowing that’); and the relationship between patterns and facts affords us *perspectival* knowledge (‘knowing what it is like’) (Vervaeke and Ferraro 2013, 29–30). A fourth type of knowing is *participatory*, how “nature’s unfolding truth emerges only with the active participation of the human mind” (Tarnas 2010, 434). Another way to think about this final type of knowledge is the level of understanding achieved when one is able to integrate a piece of information into one’s worldview (see Lazic 2021, 7).

Although philosophical debates rage concerning the nature of understanding (Baumberger et. al. 2017), one aspect, of course, is the integration of all these types of knowledge (Lazic 2021, 7). In the context of reading traditions the different traditions seemingly attempt to achieve understanding by initially engaging one of these types. Those traditions that afford the listener an *experience* engage the perspectival types of knowledge

(e.g., knowing *what it was like* to be the seer when he received the Veda and *what it was like* to hear the angel Gabriel deliver the suras), with the assumption that consciousness of this knowledge will manifest itself in speech and action (hence the value of meditative practices). Those that facilitate *understanding* engage the propositional, with the result that a proper understanding may then be applied and give rise to the other types of knowledge.

The fundamental thesis of this article is that the poetic accents, the accents of the Three Books, are *not* primarily intended to convey propositional knowledge. A fine-grained exegetical analysis (representing propositional knowledge) diverges from the interpretation presented by the accents, suggesting that the accents have a different purpose from (primarily) preserving and conveying propositional knowledge. Our hypothesis is that there was a shift in the accents as *reading* aid to the accents as *chanting* aid, a shift which was for some reason exaggerated in the Three Books. It is in the nature of chanting, then, that we seek a set of priorities that diverge from those of propositional knowledge.

4.0. Data and Analysis

Masoretic scholars have derived detailed rules about how the accents work, both in the prose and poetic systems. The most distinctive feature about the poetic accents is how often they ‘break the rules’, or how often the rules are “not put into effect because of very precise rules of transformation” (Dotan 2007, 640). In such *transformations*, expected disjunctive accents are replaced by conjunctive accents. Traditional understanding of

the transformations has been that they thereby accommodate musical needs: too many disjunctive accents would be less musical, so regular rules were applied in certain environments to replace disjunctive accents with conjunctive accents, making the reading more amenable to musical intent. The ‘musical’ intent of the transformations we here align with ‘chanting’ aid.

This study hypothesises that pursuing the application of these rules for transformation may reveal the distinctive purpose of the poetic accent system. Two kinds of environments will be addressed: (1) conjunctive accents present in *accordance* with expected transformations; and (2) conjunctive accents present in *contrast* to expected transformations. In both environments, the analysis will focus on the relationship between the exegetical analysis (*propositional* knowledge) and the effect of the conjunctive accents in the verses (seeking possible *experiential* knowledge). Exegetical analysis will deal extensively with linguistic prominence.

4.1. Linguistic Prominence

Linguistic prominence tends to fall into the category of either theme, topic, or focus. Thematic prominence confirms the larger concerns of the author, connecting this passage with those larger concerns. Topical prominence makes explicit the current concern of the author. Focal prominence makes explicit the main concern of the current clause. In many of the following examples, the effect of an additional prosodic break will be to suggest a kind of prominence, according to one of these categories.

(1a) יוֹשֵׁב בַּשָּׁמַיִם יִשְׁחַק

‘The one enthroned in heaven laughs.’ (Ps. 2.4, rendered without prominence)

When focal prominence is the intent, as is often the case with fronted constituents, one might gloss the effect in English with a cleft structure, as *it is [fronted constituent] that [verb]*. In the case of Ps. 2.4, focal prominence could be rendered as *it is the one enthroned in heaven who laughs*. The purpose would be to identify *who* is the one who is laughing.

If topical prominence is the intent, as is also often the case with fronted subjects, one might gloss the effect as *as for [fronted subject], it [verb]*. If Ps. 2.4 were rendered with topical prominence, it would be *as for the one enthroned in heaven, he laughs*. There is no need in this case to identify the one enthroned in heaven, for this participant is already known. The question is, instead: what about the one enthroned in heaven? What does he do?

Lastly, when thematic prominence is in view, there is no gloss for the immediate clause to render the prominence, precisely because it identifies the topic of the larger passage rather than the immediate clause, and it prompts the reader to ensure he is reading the entire passage within the right context of this theme. If Ps. 2.4 were to be considered as encoding thematic prominence, it would indicate that the entire section of the psalm is about *the one enthroned in heaven*, in contrast to other themes (e.g., others enthroned elsewhere, or an event before or after the enthronement in heaven). The purpose of thematic

prominence is on a larger scale than focal and topical prominence, for it refers to entire sections of the text.

(1b) יוֹשֵׁב בַּשָּׁמַיִם יִשְׁחַק

‘It is the one enthroned in heaven *who* laughs.’ (Ps. 2.4, rendered with focal prominence)

‘As *for* the one enthroned in heaven, he laughs.’ (Ps. 2.4, rendered with topical prominence)

‘The one enthroned in heaven laughs [*and N.B. that he is the theme of the larger section*].’ (Ps. 2.4, rendered with thematic prominence)

4.2. Poetic Peaks and Accent Level

In an extensive exegetical (linguistic, literary, and poetic) analysis carried out for a handful of Psalms (Pss 1–6), the poetic peaks (points of prominence within each psalm) have been found to correlate with the levels of embedding within the accent system. That is, nearly every verse has accents from levels I (*siluq*), II (*revia*‘ *mugrash*, *’atnah*, and/or *’ole ve-yored*), and III (*dehi*, *revia*‘, and *tsinor*). Many poetic verses have no accents from domain IV (*pazer* and *legarme*), however. Poetic peaks tend to correlate with instances of accents from level IV.¹⁵³

When transformations are disregarded, the correlation is even higher. That is, without transformations, the poetic accents (in terms of how many domains are employed) seem motivated

¹⁵³ Whereas the length of the verse would normally be the primary factor in the number of accent levels present, poetic prominence seems to override this at times, e.g., Ps. 2.2, 5, 8.

by concerns very similar to those of poetic and literary prominence. With transformations, however, the correlation drops. The motivation for the transformations does *not* align with the concerns of poetic and literary prominence. This misalignment is the focus of the present analysis.

A working hypothesis is that the greater the number of hierarchical levels employed, the more nuanced the intonation of a given verse. The more nuanced the intonation, the more readily prominence may be noted.¹⁵⁴ There will be no direct correspondence between specific accents and prominence noted, but rather a density of nested accents, which is taken to reflect intonational contour and interest, and thus correlate with the possibility of prominence.

4.3. Expected Transformations

4.3.1. Psalm 2

(1a) יוֹשֵׁב בַּשָּׁמַיִם יִשְׁחַק

‘The one enthroned in heaven laughs’ (Ps. 2.4)

The domain of *ʾatnaḥ* (domain II) would normally be divided by a *deḥi* (domain III), but the expected *deḥi* is here transformed into conjunctive *munah*. The result is that the *one enthroned in heaven* receives no intonational prominence. This may be compared to the prose example in (2), in which the first constituent

¹⁵⁴ Because poetic verses vary in length far less than prose verses, we disregard verse length as a factor. This was prompted by observations such as those above in fn. 153.

is also fronted (presumably as topic) and *also* set off by a strong disjunctive accent (*zaqef gadol*).

(2) וְהָעָם לֹא יַעֲלוּ עִמּוֹ:

‘And as for the people, they shall not go up with him.’

(Exod. 24.2)

Without the transformation from a disjunctive to a conjunctive accent, the *one enthroned in heaven* would potentially receive, as noted above, either focal, topical, or thematic prominence. In the context, focal prominence would be infelicitous; there is no assumption that someone is laughing, with a need to identify *who* is laughing. Topical prominence would require that the idea of *one enthroned in heaven* was already available and expected, with the clause now addressing this topic. A combination of topical and thematic prominence seems most likely, as both announcing the (new) topic of this clause as well as indicating the theme of this section: the one enthroned in heaven, in contrast to those of vv. 1–2, those enthroned on earth.

In linguistic and exegetical terms, therefore, the *munaḥ* diminishes the topical and thematic prominence of the one enthroned in heaven, lessening the explicit contrast between the kings of vv. 1–2 enthroned on *earth* and the king of vv. 3–4, who is enthroned in *heaven*. The implicit contrast remains, of course, but there is one less reinforcing echo of it within the text.

This compares with an exegetical analysis of Psalm 2, which finds the psalm fundamentally to be the interaction between earthly rulers and the heavenly king. The topical and thematic prominence of the heavenly king are therefore paramount to the purpose of the psalm.

4.3.2. Psalm 3

(3) אֵין יְשׁוּעָתָהּ לּוֹ בְּאֱלֹהִים סֵלָה:

‘There is no salvation in God for him. Selah.’ (Ps. 3.3b)

This verse contains many oddities. The presence of transformations is roundly recognised as expected, and there is no doubt that multiple transformations have taken place, with the effect of removing all prosodic breaks apart from the *siluq*. Without transformations, both לּוֹ and בְּאֱלֹהִים would bear disjunctives (e.g., Wickes 1881, 69; Breuer 1989, 297; Price 2010, 181). As the poetic accentuation stands, each has a conjunctive, and יְשׁוּעָתָהּ stands out as bearing the rare *shalsholet qetana*.¹⁵⁵

The prosodic effect is to remove natural stress from the end of the nuclear clause (אֵין יְשׁוּעָתָהּ) plus tightly bound constituent (preposition with exclusively pronominal object, לּוֹ), as well as any natural stress from the end of the entire clause short of the *selah*. A modern reader might dramatise this verse, imagining the derision and mockery with which the original speakers delivered it. In contrast, the MT accentuation neutralises even the syntactic structure. The entire clause and the *selah* are run together as a single undifferentiated prosodic unit.

The reverse of neutralising happens, however, with יְשׁוּעָתָהּ, if we grant with Price that the *shalsholet qetana* attaches special meaning to its passage. Psalm 3 might be exegetically summarised as poetic reversal: from enemies rising up against David

¹⁵⁵ Price (2010, 242) further supposes that the accent attaches some special meaning to the passages in which it occurs. By Price’s (241, 300) count, this accent occurs only eight times in the Hebrew Bible.

and claiming that God has no salvation in store for him (vv. 1–2) to God rising up against David’s enemies, with David declaring that God has great salvation for him (vv. 8–9). The centre section is how David progressed from the beginning to the end, namely calling upon the Lord to be his defence. Any special meaning from the *shalsholet qeṭana* would readily converge with an exegetical reading, in which the question of whether or not God has salvation in store for David is the crux of the psalm.

In this case, whereas the transformations diminish some exegetical nuance (even obscuring the syntax), the *shalsholet qeṭana* possibly retains or even increases another exegetical nuance (in the thematic role of *ישועתה*).

4.3.3. Psalm 6

In Psalm 6, again, the transformations that take place blur what are otherwise significant poetic features within the Psalms. The exegetically significant reversal that grounds the psalm appears between verses 3 and 11.

- (4) *חַנּוּנִי יְהוָה כִּי אֲמַלְל אֲנִי רַפִּיאֲנִי יְהוָה כִּי נִבְהָלָו עַצְמִי:*
 ‘Be gracious to me, LORD, for I am languishing; heal me, LORD, for my bones have become dismayed!’ (Ps. 6.3)
- (5) *יִבְשׁוּ | וַיִּבְהָלוּ מְאֹד כָּל־אֹיְבֵי*
 ‘May all my enemies be ashamed and greatly dismayed!’
 (Ps. 6.11a).

Whereas in v. 3 the psalm’s author is greatly dismayed (*נִבְהָלָו*), in v. 11 it is the enemies who are ashamed and dismayed (*וַיִּבְהָלוּ*). By v. 11, the author’s troubles have been resolved and lament gives way to rejoicing.

In (5) the accents reflect three levels. *ʾAtnah*’s (אֲתָנָה) domain is divided by *dehi* (מֵאֵד) and *dehi*’s domain is divided by *mahpakh legarme* (יִבְשׁוּ |).

Figure 1: Visualisation of accent hierarchy in Ps. 6.11

Domain of <i>ʾatnah</i>		
	Domain of <i>dehi</i>	
		Domain of <i>mapakh legarmeh</i>
כָּל־אֵיבִי אֲתָנָה	וַיִּבְהֶלֹּוּ מֵאֵד דֵּהִי	יִבְשׁוּ מַה־פָּאךְ לֵגַרְמֵה

This contrasts with (4), in which the *munaḥ* on the word נִבְהֶלֹוּ is a transformed *revia*’ *mugrash*, since only one of the two syllables between the accented syllables of נִבְהֶלֹוּ and עֲצָמִי contains a full vowel (Wickes 1881, 69; Breuer 1989, 300; Price 2010, 181). Had נִבְהֶלֹוּ contained its full accent, it would have exhibited a similar level of embedding to that of (5). This entails recognising that the presence of both *ʾole ve-yorēd* and *ʾatnah* in 6.3 create both their own domains and an effectively *additional* domain, at the same level as *ʾatnah*, below labelled ‘from *ʾatnah* to *siluq*’.¹⁵⁶

¹⁵⁶ *Revia*’ *mugrash* cannot be said to be at the same level as *ʾole ve-yorēd* and *ʾatnah*. Wickes (1881, 66) calls it simply a “foretone” and Price (2010, 164) insists it is simply the “near” disjunctive in the last line of a tricolon. For Breuer (1989, 245), *revia*’ *mugrash* is part of the class of “additional disjunctives” (מַפְסִיקִים נֹסְפִים) that, while not of the same rank as *ʾatnah*, puzzlingly, have no rank at all (214). In any case, either *ʾatnah* divides the domain to the left of *ʾole ve-yorēd*, or they both divide the domain of *siluq* into three domains; in either case, *revia*’ *mugrash* divides to the left of *ʾatnah* (245).

Figure 2: Additional domain effectively created from accents ‘ole ve-yorēd and ‘atnaḥ, when ‘ole ve-yorēd and ‘atnaḥ are taken as being of equal rank

<i>Siluq</i>		
(From ‘atnaḥ to siluq)	‘atnaḥ	‘Ole ve-yorēd
כִּי נִבְהִלּוּ עַצְמִי	רַפְּאֲנִי יְהוָה	חֲנֻנִי יְהוָה כִּי אֲמַלֵּל

Figure 3: Additional domains effectively created from accents ‘ole ve-yorēd and ‘atnaḥ, when ‘atnaḥ is considered a lesser domain than ‘ole ve-yorēd

<i>Siluq</i>		
(From ‘ole ve-yorēd to siluq)		‘Ole ve-yorēd
(From ‘atnaḥ to siluq)	‘atnaḥ	
כִּי נִבְהִלּוּ עַצְמִי	רַפְּאֲנִי יְהוָה	חֲנֻנִי יְהוָה כִּי אֲמַלֵּל

If this additional domain is recognised, it provides a complete hierarchy within which to understand the accents. *Siluq* would then simultaneously ‘govern’ the domain of the entire verse *and* also a smaller domain, left over after ‘atnaḥ (and/or ‘ole ve-yorēd) were taken into account.

This would change the usual ‘levels’ of the accents, as the ‘near’ and ‘far’ accents would be understood differently: the ‘far’ to create both domains of their own *as well as* a final domain, between themselves and their own governing accent, the ‘near’ subordinate to that new, additional domain.

Figure 4: Near and Far Accents understood at different levels

Parent Accent (e.g., <i>siluq</i>)		
(From far accent to parent)		Far (e.g., ‘ole ve-yorēd)
(From near to parent)	Near (e.g., <i>revia</i> ‘ <i>mugrash</i>)	
יוֹמָם וּלְיָלָה:	וּבְתוֹרָתוֹ יְהוָה	חֲפָצוֹ

With this understanding, the number of levels in Ps. 6.11 would then be similar to those in Ps. 6.3. Each verse contains three levels, represented by the three shades of grey.

Figure 5: Ps. 6.3b's accent hierarchy presented visually, understanding *munach* as a transformed *revia' mugrash*

<i>Siluq</i>		
(From 'atnah to siluq)		'atnah
	<i>munah' > revia' mugrash</i>	
עֲצָמִי	כִּי נִבְהִלֹי	רָפְאֵנִי יְהוָה

The similar level of embedding indicates a similarity in intonation contour for the two phrases, establishing a prosodic echo of sorts, which would reinforce the poetic feature here: these verses echo one another (albeit with a reversal). In verse 3, the king is in deep dismay, and in verse 11 the enemies experience deep dismay. The shift is from the king's to the enemies' suffering.

The essential point is that this prosodic similarity, reinforcing the exegetically significant thematic prominence, is lost by means of the transformations. With the *munah* chanted as a true conjunctive accent, there is no longer a prosodic connection between verses 3 and 11. Any former exegetical connection is thereby removed.

Figure 6: Visualisation of accent hierarchy in Ps. 6.3b, with the *munah* (a transformed *revia' mugrash*) retained as a conjunctive

<i>Siluq</i>	
(From 'atnah to siluq)	'atnah
עֲצָמִי	רָפְאֵנִי יְהוָה

Transformations also occur in verses 6 and 8:

- (6) כִּי אֵין בַּמּוֹת זִכְרְךָ
‘For in death there is no mention of you.’ (Ps. 6.6a)
- (7) עֵינַי מִכַּעַס עֵינַי
‘My eyes have wasted away from vexation.’ (Ps. 6.8a)

In both instances, the accent appearing before the final word is a transformed *dehi*, most likely since the final syllables in מוֹת and כַּעַס do not constitute their own feet on the level of metrical parsing.¹⁵⁷ With and without transformations, the accent pattern for Ps. 6.6a would be as follows:

Figure 7: Accent hierarchy in Ps. 6.6a, with transformations: understanding *munaḥ* as a transformed *dehi*

'atnaḥ	
	<i>munach > dehi</i>
זִכְרְךָ	כִּי אֵין בַּמּוֹת

Figure 8: Accent hierarchy in Ps. 6.6a, without transformations: keeping *munaḥ* as a conjunctive

'atnaḥ	
כִּי אֵין בַּמּוֹת זִכְרְךָ	


With and without transformations, the accent pattern for Ps. 6.8a would be:

Figure 9: Accent hierarchy in Ps. 6.8a, with transformations: understanding *munaḥ* as a transformed *dehi*

'atnaḥ	
	<i>Munach > dehi</i>
עֵינַי	כִּי אֵין בַּמּוֹת

¹⁵⁷ On the metrical parsing of segolate nouns, see Khan (2020, I:423). On the transformation of *dehi* before *'atnaḥ*, see Wickes (1881, 60, 75); Breuer (1989, 290); Price (2010, 202).

Figure 10: Accent hierarchy in Ps. 6.8a, without transformations: keeping *munaḥ* as a conjunctive



The most common pattern within the poetic verses in Pss 1–6 has two levels: an *'atnaḥ* dividing a first time, and then another level of accents dividing the sections a second time. The presence of transformations in these two verses makes the verses stand out for having *less* intonational interest (fewer accent levels) than is standard.

This compares to the exegetical topography of the psalm, in that verses 7–8 are the poetic peak of the entire psalm, introduced by verse 6. Verses 6 and 8 thus flank the dramatic heart of the psalm, which is a poetic descent into Sheol. Poetic features abound in marking this section, from the absence of the divine name (set forth nearly programmatically in verse 6 as a definition of Sheol), the quantity of rare words (עֵשָׂה, עֵרָשִׁי, אִמָּסָה, אֶתְקָה, עֵשָׂה, all appearing fewer than 10x each in the Hebrew Bible), the proliferation of figurative language (weary sighing, darkness of night, flood of tears causing the bed to float and melt, an eye wasting away), the only tricolon in the psalm (verse 7), and dense alliteration (of gutturals and sibilants).

Whereas the full arsenal of poetic techniques is employed to mark this section as prominent, the transformations remove even the possibility of prominence, rendering the introduction (verse 6) and end (verse 8) intonationally unremarkable. Once again, transformations seem to have ends other than exegetical nuance.

4.4. Unexpected Conjunctive Accents

4.4.1 Psalm 2

(8) יִתְּצֵבּוּ | מַלְכֵי-אֶרֶץ וְרוֹזְנִים נוֹסְדִי-יַחַד

‘The earthly kings take their stand; princes take counsel together’ (Ps. 2.2a)

Scholars disagree over how to analyse the accentuation of (8). Price (2010, 187) claims that a *revia*‘ *gadol* may not serve as a lone disjunctive with *’atnaḥ*, but only as a remote disjunctive, alongside the near disjunctive *deḥi*. Its presence, therefore, requires a *deḥi* (which, if transformed, would become a *munah*).¹⁵⁸

In Ps. 2.2a, however, there is neither *deḥi* nor *munah* that might represent a transformed *deḥi*. Even if the *merkha* somehow stood in for *munah*, the transformation itself would not follow the other conventional conditions in which *deḥi* transforms: one word with a conjunctive must precede the word that would have been accentuated with *deḥi*.

Compare the following: on the right side of the table are verses in which the word preceding *’atnaḥ* is no doubt accentuated with a transformed *deḥi* (transformed into *munah*); the left side of the table consists of situations similar to the one here, where the *merkha* between *revia*‘ *gadol* and *’atnaḥ* is (supposedly) a true conjunctive, not a transformation.

¹⁵⁸ Wickes (1881, 58) does permit the occurrence of *revia*‘ *gadol* in place of *deḥi*, as a lone (near) disjunctive, and Breuer (1989, 248) admits that *’Revīa’ gadol* sometimes comes in place of *deḥi*.

Table 1: Comparison of true conjunctives vs transformed conjunctives preceding *ʾatnah*

No prosodic break (<i>merkha</i> as a true conjunctive, not a transformation)		Prosodic break (<i>munah</i> as transformed <i>dehi</i> , not a true conjunctive)	
אֶרֶץ וְרוֹזְנִים נֹסְדוּ יַחַד	Ps. 2.2	כָּל־יָרֵעַ יַעֲקֹב כְּבָדוֹהוּ	Ps. 22.24
וְהוּא יִשְׁפֹּט־תִּבְלָה בְּצֹדֶק	Ps. 9.9	לֹא יִחַשֵׁב יְהוָה לֹו עוֹן	Ps. 32.2
הַשָּׁמַיִם מְסַפְּרִים כְּבוֹד־אֵל	Ps. 19.2	וְעַתָּה מִה־קִּנְיָתִי אֲדַגִּי	Ps. 39.8
אֶת־עַמּוֹךְ וּבָרָךְ אֶת־נַחֲלָתְךָ	Ps. 28.9	הָאִירֹו בְּרָקִים תִּבְלָה	Ps. 77.19

This quandary is reflected in several medieval manuscripts that accent the word וְרוֹזְנִים with *dehi* and the following word with *munah*, viz., וְרוֹזְנִים נֹסְדוּ (Ginsburg 1913, 2). The exegetical consequence is that the word וְרוֹזְנִים is given less prominence in the MT and more prominence in those manuscripts that accent with either *dehi* or *munah* (if understood as standing in for *dehi*).

Our interest lies in the role of any possible prominence. If focal, one might gloss as *it is princes who take counsel together*. If topical, one might gloss as *as for princes, they take counsel together*. Finally, if thematic, the first section of the psalm should be considered to be *about princes (and their kind)*, presumably in contrast to what the rest of the psalm is about.

This final possibility, thematic prominence, rings true with an exegetical analysis of Psalm 2, already mentioned as the interaction between earthly rulers and the heavenly king. The heavenly king responds to the rebellion of the earthly rulers by installing on Zion his own king, who combines in himself characteristics of both earthly and divine kingship.¹⁵⁹

¹⁵⁹ The new king is physically on Zion (on earth), but aligns with the divine king in perspective and attitude (manner of addressing the rebels). Toward the end of the psalm, the identities of the two are blurred (verses 12a, the subject of יִאֲגָר, and 13, the referent of ‘him’ in הוּא).

Those manuscripts that retain the prosodic break after וְרוֹזְנִים thus make grasping the structure of the psalm a little easier, because ‘(earthly) princes’ are indicated as thematic at nearly the very beginning of the psalm. Those manuscripts that obscure the prosodic break provide no hint to the overall structure. As ever, the question is what would motivate a reading tradition that would detract, however slightly, from indicating the larger structure.

(9) יְהוָה אָמַר אֵלַי בְּנִי אַתָּה

‘The LORD said to me “You are My Son”’ (Ps. 2.7b).

The accentuation of this verse is strange. If *’atnah* is served by two conjunctives, both are expected to be *munah* (Breuer 1989, 288). This, however, is not the case here, where the accents are instead (*tsinoret*-)*merkha*. One reconstructed set of transformations would argue for a break on אֵלַי (between the matrix clause and reported speech),¹⁶⁰ and another for a break on בְּנִי (within the direct speech).¹⁶¹

¹⁶⁰ This is the expected division in any verse containing a clause with a speech verb followed by reported speech (Shoshany 2022, 281). As Breuer (1989, 288 fn. 27) explains, this verse’s accentuation without transformations would have been אָמַר אֵלַי בְּנִי אַתָּה. This division (with a disjunctive accent on אֵלַי) is attested in many late medieval MSS (Ginsburg 1913, 3). After applying transformation rules, we might have expected אָמַר אֵלַי בְּנִי אַתָּה, including *maqef* replaced with a conjunctive. Indeed, this is the accentuation in Ginsburg’s (1913, 3) edition.

¹⁶¹ Price (2010, 204) argues that the *tsinoret-merkha* here serves as a transformed *dehi*, with the break (if one is to be had) falling on the word בְּנִי, not אֵלַי. Although no late medieval MS reflects this reading, in Shoshany’s (2020) sample of 141 instances of a matrix clause con-

By Price's (2010, 243) count, the combination *tsinoret-merkha* that binds the words אֶמְרָאֵלִי appears only eleven times: "The augmentation is not consistent throughout the text, but occurs in only these few instances, suggesting that *Sinnorit* in these cases may attach some special meaning to the passage."

The net result of the poetic accentuation, with *tsinoret-merkha* and an additional *merkha*, makes for no prosodic break after the יְהוָה, while the *tsinoret* may nonetheless attach 'some special meaning' to the passage.

From an exegetical perspective, this is a clear thematic peak, in which the chosen king (who will crush all rebellion) is identified and sanctioned. Verse 7 is the only tricolon in the poem (another indication of a poetic peak), and, in a doubly embedded direct speech, God speaks: but only as cited by the anointed king, not directly from his own mouth. If the Psalm already protects the speech of God by delivering it second-hand, the poetic accentuation removes all prosodic interest, drawing no attention at all to a clear exegetical peak.

4.5. Summary

In each of the examples from Psalms 2, 3 and 6, there are more conjunctive accents than accentuation rules would normally allow. Some are the result of transformations and others remain

taining a speech verb followed by direct/reported speech, the Babylonian differed from the Tiberian system 36 times. In 30 of the occurrences, the Tiberian system divided *within* the direct/reported speech, not, as is generally considered felicitous, between the matrix and complement clause (284). Although this is clearly not the norm within these types of clauses, it may indirectly support Price's claim.

unexplained. In most cases, there are examples of manuscripts other than *Leningradensis* that reflect a version prior to transformations or simply with more expected accentuation. In each case, there is also the presence of some form of linguistic prominence, as derived from an exegetical study.

The working hypothesis was that an increasing number of divisions (and thus the number of hierarchical levels or domains employed) indicates a more nuanced intonation and correlation with linguistic prominence. The corollary is that the fewer divisions (the fewer disjunctives, and the more conjunctives), the less the signalling of linguistic prominence.

The observation is thus repeated that, in each of these examples, although linguistic prominence can be exegetically demonstrated and even aligns with some manuscripts or interpretations of transformations, the MT as it stands subverts expected linguistic prominence.

5.0. Conclusion

Little can be said with certainty, but the hints are tantalising. In the surveyed liturgical traditions, there were competing demands between preserving the sense of the text, as in propositional knowledge, and preserving an embodiment of the text, as in experiential knowledge. The one can be sacrificed for the sake of the other, as in Gregorian chant's almost deliberate obscuring of the meaning of the text.

The poetic accents can by no means be said to obscure the meaning of the text, but it can be said that the effect of transformations (with unexpected conjunctive accents) lessens the effect

of linguistic prominence, which would otherwise lead to a nuanced understanding of the text (especially in terms of themes and macro-structure).

The purpose for lessening this nuance can only be surmised, but the age-old understanding of the poetic accents as a chanting aid (even more so than a reading aid) suggests a possibility. The poetic accents may have willingly sacrificed an amount of exegetical nuance to make the text more amenable to liturgical reading, by which is understood reading such as that linked with regular cadence and rhythm *regardless of* the particular content. The regularity of liturgical reading that honours and preserves a sacred text may have been valued enough to be considered worth sacrificing some details of exegetical nuance.

References

- Aurobindo, Sri. 1998. *The Secret of the Veda*. Pondicherry, India: Sri Aurobindo Ashram Press.
- Baumberger, Christoph, Claus Beisbart, and Georg Brun. 2017. 'What Is Understanding? An Overview of Recent Debates in Epistemology and Philosophy of Science'. In *Explaining Understanding: New Perspectives from Epistemology and Philosophy of Science*, edited by Stephen R Grimm, Christoph Baumberger, and Sabine Ammon, 1–34. New York: Routledge.
- Beckwith, Roger. 1985. *The Old Testament Canon of the New Testament Church*. Grand Rapids, MI: Eerdmans.

- Bin-Nun, Adam. 2020. 'The Masoretic Accentuation of the Hebrew Bible According to the Medieval Treatise *Horayat Haqore* by Ilan Eldar'. *Leshonenu* 82/3: 303–31. [Hebrew]
- Breuer, Mordechai. 1989. *The Biblical Accents in the Twenty-One Books and Psalms, Job, and Proverbs*. Jerusalem: Horev. [Hebrew]
- Coward, Harold. 2013. 'Introduction'. In *Experiencing Scripture in World Religions*, edited by Harold Coward, 1–14. Eugene, OR: Wipf and Stock Publishers.
- . 2019. *Word, Chant, and Song: Spiritual Transformation in Hinduism, Buddhism, Islam, and Sikhism*. Albany, NY: SUNY Press.
- Crocker, Richard. 1990. 'Introduction'. In *The Early Middle Ages to 1300*, edited by Richard Crocker, xv–xx. The New Oxford History of Music. Oxford: Oxford University Press.
- . 1995. 'Gregorian Studies in the Twenty-first Century'. *Plainsong & Medieval Music* 4/1: 33–86.
- Cuffel, Alexandra, Giacinto Di Giacinto, and Volkhard Krech. 2019. 'Senses, Religion and Religious Encounter: Literature Review and Research Perspectives'. *Entangled Religions* 10. <https://doi.org/10.13154/er.10.2019.8407>
- DiCenso, Daniel J. 2018. 'Moved by Music: Problems in Approaching Emotional Expression in Gregorian Chant'. In *Emotion and Medieval Textual Media*, edited by Mary C. Flannery, 19–50. Turnhout: Brepols.
- Dotan, Aron. 2007. 'The Masorah'. In *Encyclopaedia Judaica*, edited by Michael Berenbaum and Fred Skolnik, 13: 603–56. Detroit: Macmillan Reference USA.

- Eldar, Ilan. 1994. *The Study of the Art of Correct Reading as Reflected in the Medieval Treatise Hidāyat al-Qāri*. Jerusalem: The Academy of the Hebrew Language. [Hebrew]
- Fishbane, S. 2007. *Deviancy in Early Rabbinic Literature*. Leiden: Brill.
- Goodman, L. E. 1988. *The Book of Theodicy: Translation and Commentary on the Book of Job*. New Haven, CT, and London: Yale University Press.
- Habib, Joseph. 2021. 'Accents, Pausal Forms and Qere/Ketiv in the Bible Translations and Commentaries of Saadya Gaon and the Karaites of Jerusalem'. PhD dissertation, University of Cambridge.
- Harvey, Susan Ashbrook. 2020a. 'Music as Liturgy: Models from Ancient Syriac Christianity'. *Journal of the International Society for Orthodox Music* 4/2: 371–82.
- . 2020b. 'Holy Sound: Preaching as Divine Song in Late Antique Syriac Tradition'. In *Jewish Roots of Eastern Christian Mysticism*, edited by Andrei A. Orlov, 226–39. Leiden: Brill.
- he-Hasid, Judah b. Samuel. 2012. *The Travels of Rabbi Petachia of Ratisbon Who, in the Latter End of the Twelfth Century Visited Poland, Russia, Little Tartary, the Crimea, Armenia, Assyria, Syria, the Holy Land, and Greece*. Edited by Abraham Benisch. Piscataway, NJ: Gorgias Press.
- Hiley, David. 1993. *Western Plainchant*. Oxford: Clarendon.
- Khan, Geoffrey. 2020. *The Tiberian Pronunciation Tradition of Biblical Hebrew: Including a Critical Edition and English Translation of the Sections on Consonants and Vowels in the Masoretic*

- Treatise Hidāyat al-Qāri* 'Guide for the Reader.' 2 vols. Cambridge Semitic Languages and Cultures 1. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers.
<https://doi.org/10.11647/OBP.0163>
- Kratz, Reinhard G. 2020. 'Introduction'. In *Interpreting and Living God's Law at Qumran: Miqṣat Ma'ase Ha-Torah, Some of the Works of the Torah (4QMMT)*, edited by Reinhard G. Kratz et al., 3–30. Tübingen: Mohr Siebeck.
- Laack, Isabel. 2015. 'Sound, Music and Religion: A Preliminary Cartography of a Transdisciplinary Research Field'. *Method & Theory in the Study of Religion* 27/3: 220–46.
- Lazic, Milan. 2021. 'Identifying Emotions Associated with the Mental States of Understanding'. MA thesis, University of Toronto.
- Lim, Timothy H. 2013. *The Formation of the Jewish Canon*. New Haven, CT: Yale University Press.
- Loopstra, Jonathan. 2015. *An East Syrian Manuscript of the Syriac "Masora" Dated to 899 CE*, vol. 2. Piscataway, NJ: Gorgias Press.
- Martani, Sandra. 2021. 'Recitation and Chant'. In *The Oxford Handbook of Byzantine Literature*, edited by Stratis Papaioannou, 465–79. Oxford: Oxford University Press.
- McDonald, Lee Martin. 2017. *The Formation of the Biblical Canon*, vol. 1. London and New York: Bloomsbury T&T Clark.
- Nelson, Kristina. 1985. *The Art of Reciting the Qur'an*. Austin, TX: University of Texas Press.

- . 2011. ‘Tajwid’. In *Encyclopedia of Arabic Language and Linguistics*, edited by Lutz Edzard and Rudolf Erik De Jong. Leiden: Brill. http://referenceworks.brillonline.com/entries/encyclopedia-of-arabic-language-and-linguistics/tajwid-EALL_COM_0335?s.num=5
- Otto, Rudolf. 1958. *The Idea of the Holy: An Inquiry into the Non-Rational Factor in the Idea of the Divine and Its Relation to the Rational*. Translated by John W. Harvey. 2nd edition. Oxford: Oxford University Press.
- Park, Sung Jin. 2020. *The Fundamentals of Hebrew Accents: Divisions and Exegetical Roles beyond Syntax*. Cambridge: Cambridge University Press.
- Price, James D. 2010. *The Syntax of Masoretic Accents in the Hebrew Bible*. 2nd edition. https://www.jamesdprice.com/images/21_Syntax_of_Accents_rev_ed..pdf
- Qafih, Yosef. 1966. *Psalms with R. Saadya Gaon’s Translation and Commentary*. Jerusalem: n.p. [Hebrew]
- . 1973. *Job with R. Saadya Gaon’s Translation and Commentary*. Jerusalem: n.p. [Hebrew]
- . 1976. *Proverbs with R. Saadya Gaon’s Translation and Commentary (kitāb ṭalab al-ḥikma) and R. Yaḥyā Ṣālih’s (Mahriṣ) Grammatical Notes*. Jerusalem: n.p. [Hebrew]
- Revell, Elizabeth [sic] J. 1969. ‘A New Subsystem of “Tibero-Palestinian” Pointing’. *Proceedings of the World Congress for Jewish Studies* 5: 91–107.
- Revell, E. J. 1976. ‘Biblical Punctuation and Chant in the Second Temple Period’. *Journal for the Study of Judaism* 7/2: 181–98.

- . 1977. *Biblical Texts with Palestinian Pointing and Their Accents*. Missoula, MT: Scholars Press.
- Segal, J. B. 1953. *The Diacritical Point and the Accents in Syriac*. London: Oxford University Press.
- Schiffman, Lawrence H. 2010. *Qumran and Jerusalem: Studies in the Dead Sea Scrolls and the History of Judaism*. Grand Rapids, MI: Eerdmans.
- Shoshany, Ronit. 2022. *Biblical Accentuation in the Babylonian Tradition in Comparison with the Tiberian System*. Jerusalem: The Ben-Zvi Institute. [Hebrew]
- Simon, Uriel. 1991. *Four Approaches to the Book of Psalms: From Saadiah Gaon to Abraham Ibn Ezra*. Translated by Lenn J. Schramm. Albany, NY: State University of New York Press.
- Spanier, Arthur. 1927. *Die massoretischen Akzente: Eine Darlegung ihres Systems nebst Beiträgen zum Verständnis ihrer Entwicklung*. Berlin: Akademie-Verlag.
- Tarnas, Richard. 2010. *The Passion of the Western Mind: Understanding the Ideas That Have Shaped Our World View*. London: Pimlico.
- Vervaeke, John, and Leonardo Ferraro. 2013. 'Relevance, Meaning and the Cognitive Science of Wisdom'. In *The Scientific Study of Personal Wisdom: From Contemplative Traditions to Neuroscience*, edited by Michel Ferrari and Nic M. Westrate, 20–51. New York: Springer.
- Vervaeke, John, T. P. Lillicrap, and Blake A. Richards. 2009. 'Relevance Realization and the Emerging Framework in Cognitive Science'. *Journal of Logic and Computation* 22/1: 79–99.

Wickes, William. 1881. *A Treatise on the Accentuation of the Three So-Called Poetical Books of the Old Testament, Psalms, Proverbs, and Job*. Oxford: Clarendon.

THE PRONUNCIATION OF תִּזְכָּרוֹ (NUM. 15.40) IN RABBINIC SOURCES AND IN LIGHT OF PHOENICIAN*

Gary A. Rendsburg

The breadth of our honouree's scholarship is truly astounding, though the one constant throughout his career has been the pronunciation of Hebrew in its various oral reading traditions, from his early article 'Vowel Length and Syllable Structure in the Tiberian Tradition' (Khan 1987) to the more recent and magisterial two-volume *The Tiberian Pronunciation Tradition of Biblical Hebrew* (Khan 2020). I am, accordingly, very happy to offer this small contribution on the subject to this *Festschrift* in honour of Geoffrey Khan, as a token of our friendship reaching back

* My thanks to the following colleagues for a thorough reading of the pre-final draft and many helpful suggestions: Vincent Beiler (my former MA student, now a recent Cambridge PhD under the tutelage of our honouree), Joshua Blachorsky (my former BA student, now a recent PhD from New York University), and Aaron Rubin (University of Georgia). In addition, both Josh and Vince provided yeoman assistance by tracking down some hard-to-find references in the Bobst Library and Cambridge University Library, respectively. Two additional colleagues are thanked for specific items in fns 12 and 37.

to the 1990–1991 academic year, when we first met in Jerusalem.¹

1.0. Num. 15.40 and the Ensuing Discussion in y. Berakhot 2.3 (4d)

Num. 15.40 reads as follows: לִמְעַן תִּזְכְּרוּ וַעֲשִׂיתֶם אֶת־כָּל־מִצְוֹתַי וְהִיִּיתֶם :קְדוֹשִׁים לֵאלֹהֵיכֶם: ‘so that you may remember, and you shall do all of my commandments, and you shall be holy unto your God’. Because this verse appears within the third paragraph of the traditional recitation of the *Shema*² prayer (in both the Rabbinic and Karaite liturgies),² and because the second word was patient of mispronunciation (see anon), said word received particular attention throughout the ages, especially in the Rabbinic corpus of texts.

¹ Geoffrey spent that year as a fellow of the Institute for Advanced Studies, while I was on sabbatical from my then home institution, Cornell University. Two young scholars, each pursuing his research at the National Library of Israel (then still known as the Jewish National and University Library) on the Giv‘at Ram campus of the Hebrew University: naturally, it did not take us long to meet and share our academic interests with one another. From that point forward, עד היום הזה, our paths have continued to cross, always most fruitfully and collegially.

² Its presence in the Rabbinic liturgy is well-known. For its place in the Karaite liturgy, see <https://opensiddur.org/compilations/liturgical/siddurim/karaite-prayer/karaite-siddur-for-weekdays-and-sabbaths/> (pp. 14, 40, 51, 76).

The earliest source is y. Berakhot 2.3 (4d), which reads as follows (according to MS Leiden [Scaliger 3], fol. 8a; see Figure 1, overleaf):³

ר' לוי ר' אבדימא דחיפא בשם ר' לוי בר סיסי: צריך להתיז "למען תזכרו".
ר' יונה בשם רב חסדא: צריך להתי(ס/ז) "כי לעולם חסדו".

R. Levi, R. Avdima of Ḥaifa, in the name of R. Levi bar Sisi: one must articulate [the *zayin* in] *ləma'an tizkarū*. R. Jonah in the name of R. Ḥisda: one must articulate [the *samekh* in] *kī lā-ʿōlām ḥasdō*.⁴

Per the title of this article, our main concern here is with the dictum "צריך להתיז 'למען תזכרו' 'one must articulate [the *zayin* in] *ləma'an tizkarū*'".⁵ As indicated by the conventional notation,


³ For ease of reading (here and below), I have added double inverted commas (quotation marks) around the quoted biblical passages, colon to offset the reciter(s) of the maxim from the maxim itself, and full stop (period) to indicate the end of a sentence. See the similar techniques used by Sussman (2001, 17).

⁴ At various places in this article, including in the title, I include the Tiberian Masorah and/or transliteration reflecting such, for ease of reading and analysis, though the graphic representation of the oral reading tradition was not created for centuries after the time period under discussion here (that is, the early third century CE, when R. Levi bar Sisi lived).

⁵ For brief comments on our passage, see Weinberg (1985, 138–39) and Miller (2006, 154–55). On the second dictum, see Guggenheimer (2000, 203, fn. 177), with reference to Frankel (1874, *ad loc.*), who called attention to the presence of the root חס"ד 'shame, disgrace', in the *paʿel* form, in various Aramaic dialects, (see, e.g., Sokoloff 2009, 474; 2014, 134): hence, one should be careful to recite חסדו 'his kindness' with sin-


the last letter on the second word in this phrase, להתי(ס/ז), is frustratingly unclear (see Figure 2), though see further below.

Figure 1: MS Leiden (Rome, 1289), fol. 8a (lns 10–11 from bottom).⁶



The rights status of this resource is public domain, per the statement at <https://digitalcollections.universiteitleiden.nl/view/item/937041>.

Figure 2: Close-up of להתי(ס/ז) in MS Leiden, fol. 8a (ln. 10 from bottom)



1.1. Cairo Geniza Documents

For the record, note that two Cairo Geniza documents contain this passage, to wit, C.U.L. T-S F17.20 and C.U.L. T-S F17.7. The former reads as follows, with no significant variants when compared to the Leiden manuscript (see Figure 3, facing page):


ר' לוי ר אבידימה דחיפא בש' ר' לוי בן סיסי: צריך להתיז "למען תזכרו".
ר' יונה בש' רב חסדא: צריך להתיס[!] "כי לעולם חסדו".

gle /s/, and not with double /ss/. One wonders if R. Ḥisda was particularly sensitive to the matter, given his name and the potential for mispronunciation.

⁶ Manuscript available online at <https://digitalcollections.universiteitleiden.nl/view/item/937041>.

Though I do take the opportunity to note what looks like a final *mem* on the word להתיס, one must perforce assume it to be a *sa-mekh* (hence the exclamation mark in the above transcription), as an inspection of the following final *mem* in לעולם (and others on the page) and the following *samekh* in חסדו (and others on the page) makes clear.

Figure 3: C.U.L. T-S F17.20, fol. 1v (left) (FGP no. C97881) (see lns 4–5 for the relevant text)



Used with kind permission granted by the Syndics of the Cambridge University Library.


The second Cairo Geniza document is not a Talmud Yerushalmi manuscript *per se*, but rather one of the few extant manuscripts of Maimonides's *Hilkhot ha-Yerushalmi*, written, in fact, in his own hand (see Figure 4, overleaf). This document was published early on in the history of Geniza research by Louis Ginzberg in his well-known and path-finding book, *Yerushalmi Fragments from the Genizah* (1909, 29–36, esp. 31). The relevant passage once again provides no major textual variants:⁷

⁷ Ginzberg (1909, 31) incorrectly wrote להתיס in the second instance, though the manuscript shows clearly להתיס. In the apparatus Ginzberg noted only the spelling חסדה instead of חסדא.

לוי בר סיסי: צריך להתיז "למען תזכרו". ר' יונה בשם רב חסדה: צריך להתיס "כי לעולם חסדו".

Note, however, the lack of the introductory formula, 'R. Levi, R. Avdima of Ḥaifa, in the name of...'—an issue of no major consequence, though it does point to the more digest-like nature of *Hilkhot ha-Yerushalmi* (as opposed to the full Talmud Yerushalmi text). As the title of his book makes clear, Ginzberg did not realise that he had before him a copy of the long-lost Maimonides, *Hilkhot ha-Yerushalmi*, nor of course he have known at that early stage of Cairo Geniza research that the document was in fact written by the great sage himself. The true identity of T-S F17.7—both its contents and its handwriting—were determined only later, during the 1940s, by Saul Lieberman and Morris Lutzki, based on philological and palaeographical analysis, respectively.⁸

Figure 4: C.U.L. T-S F17.7, fol. 2r (FGP no. C97850) (the arrow points to line 42 of the manuscript page, commencing with the large τ to indicate the new *halakha* section)



Used with kind permission granted by the Syndics of the Cambridge University Library.


⁸ For further details, see Hopkins (1983, 277–82).

1.2. Additional Textual Witnesses

None of the textual witnesses collated by Peter Schäfer and Hans-Jürgen Becker in their *Synopse zum Talmud Yerushalmi* (1991, 58–59) contain any major deviations from the wording in the Leiden manuscript or the Cairo Geniza documents.

That said, there are some interesting variant readings worthy of citation here. For example, to add greater clarification to the key statement by R. Levi bar Sisi, two sixteenth-century Eretz-Israel manuscripts, namely, MS BnF hebr. 1389 (see Figure 5) and MS BL Or. 2822 (see Figure 6, overleaf), both add the letter name זין after להתיז, so that one reads "למען תזכרו" 'one must articulate the *zayin* in *ləma'an tizkarū*' (using the same translation as above, though now with the brackets removed, since the letter *zayin* is expressly stated).


Figure 5: MS Bibliothèque nationale de France hébr. 1389 (Safed, 1542), fol. 17r⁹ (bottom half of the right-hand column)



Used with permission granted by the Bibliothèque nationale de France.

⁹ See <https://gallica.bnf.fr/ark:/12148/btv1b10539966n>. Note that the manuscript includes the important commentary of Solomon ben Joseph Sirillo (d. c. 1558), perhaps as autograph (or at least in part).

Figure 6: MS British Library Or. 2822 (sixteenth century, Safed/Jerusalem), fol. 44r¹⁰ (bottom half of the right-hand column)




© The British Library Board

This reading, with the addition of the letter name זין, clearly must have been ‘in the air’ within Talmudic scholarship in the Ottoman Empire during the sixteenth–seventeenth centuries, for it also finds its way into the printed edition of the Talmud Yerushalmi, Seder Zera‘im (selected tractates), in the work known as *Śede Yehoshua* (Constantinople, 1662): צריך להתזין זין דתזכרו: ‘one must articulate the *zayin* of *tizkərū*’ (see Figure 7, facing page).¹¹

¹⁰ Current numbering is fol. 44r, per the digital presentation at http://www.bl.uk/manuscripts/Viewer.aspx?ref=or_2822. Using the old numbering system, Schäfer and Becker list this folio as p. 38. This manuscript also includes the important commentary of Solomon ben Joseph Sirillo (d. c. 1558), perhaps as autograph (or at least in part).

¹¹ For a description of this early printing, see Schäfer and Becker (1991, xii).

Figure 7: The Gemara section of *Sede Yehoshua*^c (Constantinople, 1662), fol. 15b, with our passage on the next-to-last line.¹²




We also may take the opportunity to note MS Vatican ebr. 133, which is riddled with mistakes at this point in the manuscript (see Figure 8, overleaf).¹³ Note, for example, תזיפה for דחיפה, להתין for להתיוון, and שכרו for תזכרו—all meaningless, but also all understandable misreadings, given the letter forms.

¹² My thanks to David Selis, Leon Charney Doctoral Fellow, Bernard Revel Graduate School of Jewish Studies, Yeshiva University, for taking this photo of the relevant page from the copy of *Sede Yehoshua*^c held by Special Collections at the Mendel Gottesman Library, Yeshiva University (New York), with the shelfmark Strauss Collection, no. 5461.

¹³ In fact, this is true of the entire manuscript: in the words of Ginzberg (1909, vi): הוא מלא שבויים לאלפים 'it is filled with errors unto the thousands'—though as with every manuscript, there are valuable readings nonetheless (though none in our section), which moved Ginzberg to create a listing of such potentially helpful variants on pp. 345–72. See further Richler, Beit-Arié, and Pasternak (2008, 95–96).

Figure 8: MS Vatican ebr. 133 (Ashkenaz, c. 1400), fol. 29r¹⁴



Used with kind permission of the Biblioteca Apostolica Vaticana.

2.0. The Root of the Verb להתיז

Thus far, then, the basic statement from y. Berakhot 2.3 (4d), along with its presentation in Maimonides, *Hilkhoh ha-Yerushalmi*, have been presented. The next issue to address is the key verb להתיז (and the follow-up verb להתיס): what is its root and what is its meaning? The answer to the second question is relatively easy, as the connotation may be garnered from the context: to distinguish the /z/ sound (and to distinguish the /s/ sound)—in short, ‘enunciate, articulate’. But what of the first question: from what root might this verb derive?

From the strict view of morphology, two roots are possible: תו"ז and נת"ז. The former is relatively well attested in Rabbinic Hebrew (RH), including in Tannaitic texts, with the meanings ‘splash’ (*qal*) (e.g., m. Makhshirin 5.2), ‘spurt, squirt’ (*nif'al*) (e.g., m. Hullin 6.6), ‘cut off, decapitate’ (*hif'il*) (e.g., m. Sanhedrin

¹⁴ Available online at https://digi.vatlib.it/view/MSS_Vat.ebr.133.

7.3).¹⁵ And while it is difficult to see the semantic extension from these meanings to ‘enunciate, articulate’, Marcus Jastrow (1903, 2:943), for one, included this meaning (from Amoraic Hebrew, with our passage the only attestation) with those above in the same dictionary entry.

A different tack was taken by the scholars at the Academy of the Hebrew Language, for *Ma’agarim* lists our word להתיז under the root תז"ז, with our passage as the only attestation thereof (see Figure 9).¹⁶ This analysis, of course, implies that our word is a neologism or nonce word—eminently suitable to the singular purpose of R. Levi bar Sisi (and in his wake R. Ḥisda, with slight alteration from להתיז to להתיס).

Figure 9: Results of the search for the root תז"ז at *Ma’agarim* (<https://maagarim.hebrew-academy.org.il/>)

☆ 1 #ר' לוי ר' אבידימא דחיפא בשם ר' לוי בר סיסיא. צריך להתיז "למען תזכרו". #ר' יונה בשם רב חסדא. צריך להתיס(ולו) "כי לעולם חסדו". מראה מקום: פרק ב, משנה ג' דף ד, ע"ד > המסירה: 3, Scaliger, Leiden, Bibliotheek der Rijksuniversiteit, שם החיבור: תלמוד ירושלמי, ברכות מחבר לא ידוע זמן החיבור: בין שנת 400 לשנת 450 סוגה: תלמוד ומדרש
☆ 2 #ר' לוי? ר' אבידימא דחיפא בשם ר' לוי בר סיסיא. צריך להתיז? "למען תזכרו". #ר' יונה בשם רב חסדא. צריך להתיס? "כי לעולם חסדו". מראה מקום: פרק ב, משנה ג' דף ד, ע"ד > המסירה: 20, F 17, Cambridge, University Library, T-S Collection, שם החיבור: תלמוד ירושלמי, ברכות מחבר לא ידוע זמן החיבור: בין שנת 400 לשנת 450 סוגה: תלמוד ומדרש

Above I used the expression “from the strict view of morphology,” if only to observe that in theory at least a third root is possible, namely תז"ז (“in theory,” because the *hif'il* infinitive construct of this root would be להתיז, not להתיז).¹⁷ This verbal root occurs once in the Bible, in the expression וְאֶת־הַנְּטִישׁוֹת הַקִּיר הַתִּי

¹⁵ For a complete survey, see Moreshet (1980, 236–37). For additional insights into the root, see Bar-Asher (2014, 307, 331, 337, fn. 57).

¹⁶ A search under the root תז"ז reveals the same two passages, with attention to the comment by R. Jonah in the name of R. Ḥisda.

¹⁷ See, e.g., Segal (1927, 89); Blau (2010, 310).

‘and the branches, remove and lop off’ (Isa. 18.5).¹⁸ This usage clearly anticipates the aforementioned RH *hif'il* of נָתַח ‘cut off, decapitate’, though we must also posit the interchange of I-*n* (נִ) and geminate (ע"ע) verbs, as observed by scholars previously.¹⁹ Once again, though, one is hard pressed to imagine the semantic extension from any of the meanings of תָּזַח or נָתַח applicable to the statement of R. Levi bar Sisi.²⁰

2.1. The Noun תָּזַח ‘wasp, hornet’

There is one more lead which we need to follow, namely, the noun תָּזַח ‘wasp, hornet’, which occurs a single time in ancient Hebrew (*DCH* 8:617), to wit, in יֵעֲשֶׂה דְּבַשׁ וְתָזַח לֹא ‘and the wasp/hornet shall not make honey’ (4QpsEzek^b [4Q386] f1ii.5).²¹ Quite possibly, the noun תָּזַח is an onomatopoetic creation, evoking the sound of the buzzing produced by these members of the

¹⁸ BDB (1064); *HALOT* (2:1715); *DCH* (8:617). For discussion, see Greenspahn (1984, 166). Of course, one would expect ‘lop off’ to precede ‘remove’, and, in fact, some translations adjust the rendering accordingly. Thus, for example, Alter (2019, 2:680): ‘lop off, take away the slack branches’.

¹⁹ See, e.g., *HALOT* (2:1715); and in greater detail Moreshet (1980, 237 fn. 45*).

²⁰ Unless I have missed the information somewhere, there appears to be no discussion of לָהִיץ in the *‘Arukh*, per Kohut (1926). One would expect to find such in one of the following places: 3:250 (s.v. הִתְזַח), 5:397 (s.v. נָתַח), 8:212 (s.v. תָּזַח); but y. Berakhot 2.3 (4d) makes no appearance in any of these entries.

²¹ For discussion, see Dimant (1998, 513, 516) and Bar-Asher (2012, 150–51).

Apocrita suborder. If such be the case, might this be the source of R. Levi bar Sisi's nonce word להתיז 'enunciate, articulate', with special attention to the proper voiced sibilant pronunciation of the sound /z/ in the word תִּזְכְּרוּ (Num. 15.40)? With no other promising lead, I am inclined to think so.

2.2. The Aramaic Verbal Root נת"ז

A survey of the Semitic languages reveals only one cognate to any of the proposed roots, namely, Aramaic נת"ז, used in three Targumic renderings, including Targum Onqelos to Deut. 1.44 (Cook 2008, 184), as follows:²²

- MT וַיִּרְדְּפוּ אֶתְכֶם כַּאֲשֶׁר תַּעֲשִׂינָה הַדְּבָרִים
 'and they will pursue you, as bees do'
- Tg.O. וַיִּרְדְּפוּ יִתְכוֹן כְּמֵא דְנִתְזוֹ דְּבִרְיָתָא
 'and they will pursue you, as bees **swarm**'

Note how the basic verb עָשָׂה 'do' is glossed with the rarer and more technical נִתְזוֹ 'swarm' (per the context). In theory, this meaning could be related to the RH verb 'splash, spurt, squirt', though I am inclined to see it as an independent verb. Most strikingly, this Aramaic verb connects to the aforementioned Hebrew noun תִּזְיוֹ 'wasp, hornet', once again with onomatopoeitic resonance.

For the record, the other two instances within the Targumim more closely correspond to the different RH connotations, with Job 3.24 meaning 'spurt, squirt' (with reference to water)


²² The Targum Onqelos version is taken from Sperber (2004, 948 [= 1:291]), with the Babylonian vocalisation marks converted to their Tiberian equivalents (see also at *CAL*).

and with 1 Chron. 10.9 meaning ‘cut off’ (with reference to the Philistines decapitating Saul).

2.3. Maimonides, *Mishneh Torah*

I end this section of the article with one further observation: no doubt due to the rareness and opacity of the term להתיז, when Maimonides wrote his *Mishneh Torah* (Code of Jewish Law), with its aim of a simple and accessible Hebrew, he opted for a much more basic Hebrew verb, stating simply: וצריך לבאר זין שלתזכרו ‘and one must pronounce clearly the *zayin* of *tizkərū*’ (see Figure 10).

Figure 10: Bodleian MS Huntington 80, fol. 95v, ln. 5 (Maimonides, *Mishneh Torah*, Hilkhhot Qeri’at Shema²³)



Used with kind permission of the Bodleian Libraries, Oxford.

3.0. Sibilant Interchange

The foregoing excursion into the identification of the root of להתיז is only the forecourt to the discussion adumbrated in the title of this article. Hence, we now move to the pronunciation issue. As many scholars have recognised, the issue with תזכרו (Num. 15.40) was the devoicing of the voiced sibilant /z/ at the onset of the voiceless velar /k/, “due to partial regressive assimilation”

²³ See <https://digital.bodleian.ox.ac.uk/objects/60f5a5d4-8e17-457a-8280-0e0fdd43a1b6/>.

(Kutscher 1965, 30), so that תִּזְכְּרוּ *tizkərū* would be realised as תִּסְכְּרוּ *tiskərū*. Such is noted already by the early grammarians, such as Jonah ibn Janah (1856, 144) and David Qimḥi (1862, 72b), in their basic phonological discussions.²⁴

3.1. The Verbal Root ש"ר 'earn'

According to later medieval rabbinic sources, which codify the instruction from y. Berakhot 2.3 (4d), and then comment upon it, the main concern is that the devoicing of the *zayin* in למען תזכרו *ləma'an tizkərū* would yield a pronunciation identical to that of למען תשכרו *ləma'an tiškərū*, with the resultant meaning 'so that you will earn', as if people would recite the *Shema* for the goal of worldly earnings. In the words of R. Jacob ben Asher (ca 1269–ca 1343), author of the *'Arba'a Turim*: והוי כעבדים המשמשים את הרב ע"מ לקבל פרס 'and be like workers who serve the master in order to receive their salary' ('Orah Hayyim 61.17).

3.2. The Verbal Root ש"ק 'lie'

Another concern, less likely, though possible, is that the mispronunciation of למען תזכרו *ləma'an tizkərū* could lead to the sense of למען תשקרו *ləma'an tišqərū* 'so that you will lie'—produced through an alternative sibilant interchange (along with velar interchange between /k/ and /q/). Once again, in the words of R. Jacob ben Asher: דלא לישתמע תשקרו 'so that it does not sound like *tišqərū*' ('Orah Hayyim 61.17).

²⁴ The latter is summarised in Chomsky (1952, 11, fn. b); see also Bacher (1895, 6, fn. 6).

3.3. The Verbal Root סכ"ר 'dam up, stop up'

And then there is a third concern, which in fact may be the most likely, that the devoicing of the /z/ in למען תזכרו *ləma'an tizkarū* would produce למען תסכרו *ləma'an tiskarū*, derived from the root סכ"ר 'dam up, stop up', the relatively rare Biblical Hebrew verb, but well known from וַיִּסְכְּרוּ מַעֲיֵנֹת תְּהוֹם וְאַרְבַּת הַשָּׁמַיִם 'and the fountains of the deep and the openings of the heaven were stopped up' (Gen. 8.2).²⁵ True, the result is essentially the same as למען תשכרו *ləma'an tiškarū* discussed above, but now the sense is that the reciting of the *Shema'* would create a stoppage or a damming up of God's commandments.²⁶

To the best of my knowledge, only one early rabbinic commentator expressed this concern, namely, the little-known R. Manoaḥ of Narbonne.²⁷ So little is known of R. Manoaḥ that we can only estimate his dates: end of the thirteenth century / first half of the fourteenth century. He is best (or perhaps only) known for his commentary on Maimonides's *Mishneh Torah*, which scholars designate as *Sefer ha-Menuḥa*, though in truth we have no real evidence for the name of the work. A portion of this composition was published (Constantinople, 1718 / Pressburg, 1879), though not the section dealing with the laws of reading the *Shema'*. For


²⁵ The verb also occurs in סכרי שמין בעבכי 'bolt up the heavens in your cloud' (Deir 'Alla 1.6), spoken by the gods addressing feminine Šemeš (Ahituv 2008, 446–47).

²⁶ See Guggenheimer (2000, 203) for a summary of all the options presented here.

²⁷ For a brief summary of his life and work, see Havlin (2007); the most detailed study remains Hurvitz (1965).

that portion of the work, one must consult RSL Moscow MS Guenzburg 123 (fifteenth century, Ashkenaz), available at the National Library of Israel website (see Figure 11). There one learns that R. Manoah indeed related the careless pronunciation of both תִּזְכְּרוּ (Num. 15.40) and וְזָכַרְתֶּם (Num. 15.39) to potential confusion with סבירה ‘damming up, stopping up’, with explicit citation of the aforecited passage in Gen. 8.2.

Figure 11: R. Manoah, *Sefer ha-Menuḥa* (RSL Moscow MS Guenzburg 123, fol. 7r) (fifteenth century, Ashkenaz) (see especially ln. 6 from the bottom of the page)²⁸



Used with permission granted by both the Russian State Library (Moscow) and the Institute of Microfilmed Hebrew Manuscripts, National Library of Israel (Jerusalem).

Scholars are aware of this relatively obscure reference due to the good fortune of R. Manoah's opinion being cited by R. Joseph Qaro (1488–1575), specifically in his halakhic work *Kesef Mishneh* (published in Venice in the year of the author's death),

²⁸ See [https://www.nli.org.il/en/discover/manuscripts/hebrew-manuscripts/view-erpage?vid=MANUSCRIPTS#d= \[\[PNX MANUSCRIPTS990000863000205171-1,FL73163797\]\]](https://www.nli.org.il/en/discover/manuscripts/hebrew-manuscripts/view-erpage?vid=MANUSCRIPTS#d= [[PNX MANUSCRIPTS990000863000205171-1,FL73163797]]).

which in turn constitutes his own commentary to Maimonides's *Mishneh Torah*. There one reads as follows (*Kesef Mishneh*, Qeri'at Shema' 2.9):²⁹

וצריך לבאר זי"ן של תזכרו – ירושלמי שם. והטעם לומר שלא יהא נראה
כאומר למען תשכרו והוי כעובדים את ה' על מנת לקבל פרס. וכתב ה"ר
מנחם או שלא יהא נראה מלשון סכירה כמו ויסכרו מעינות תהום רבה.
וה"ה לזי"ן של וזכרתם:

4.0 Phoenician סכ"ר/זכ"ר 'remember'

Our journey has brought us to the early modern period (in the personage of Joseph Qaro), though at this point, we need to return to an earlier epoch, when Phoenician was still a living language. A data point remarkably relevant to our discussion is the well-nigh universal shift of the basic root זכ"ר 'remember' to סכ"ר in Phoenician and Punic, as witnessed by the following attestations (the sole verbal form is placed first; the remaining entries are different nominal forms):³⁰

(1) ויסכרן מלקרת

'and may Melqart **remember me**' (*KAI* 43.15, Lapethos, Cyprus)

²⁹ Taken from <https://rambam.alhatorah.org/Full/Keriat Shema/2/9#e0n6>.

³⁰ The sources are culled mainly from the indices to the standard reference works: *KAI* (III:17); Tombaek (1978, 228–29); and Krahmalkov (2000, 343–44).

- (2) לִבְנִי לִי לִסְכָּר וְשֵׁם נָעִם
 ‘to be for me **as a memorial** and a good name’ (KAI 18.6 = Umm el-‘Amed, Lebanon, no. 1)³¹
- (3) מִצֵּבֶת סִכָּר בְּחַיִּים
 ‘a **memorial** stele among the living’ (KAI 53.1, Athens, Greece)
- (4) סִכָּר כְּבֹד עַל פַּעֲלַת מַעֲשֵׂרָה
 ‘a **monument** of honour for righteous deeds’ (KAI 123.4–5, Leptis Magna, Libya)³²
- (5) סִכָּר כְּבֹד עַל גַּם אֲדָר
 ‘a **monument** of honour for the noble *gm??*’ (KAI 161.5, Cherchel, Algeria)³³
- (6) סִכָּעַר דְּרָא לְאֵלִים
 ‘the **memorial** of his family forever’ (KAI 165.7–8, Guelaat Bou-Sba, Algeria)
- (7) ז מִצֵּבֶת סִכָּר
 ‘this is the **memorial** stele’ (RES [I:207], no. 250 = Slouschz [1942, 40, no. 23]) = Umm el-‘Amed, Lebanon, no. 5)

³¹ The various inscriptions from Umm el-‘Amed listed here (six in total) are conveniently published in Dunand and Duru (1962, 1:181–96), though three of them also appear in standard collections (KAI, etc.), as indicated. As an aside, note that Umm el-‘Amed, no. 1, was discovered by Ernest Renan already in 1861.

³² The final word is understood as derived from the root יֶשֶׁר ‘upright, righteous’, per KAI (2:130) ‘gerechte’.

³³ For possible interpretations of גַּם, see KAI (2:151); and Krahmalkov (2000, 141).

- (8) ז מצבת סכר
 ‘this is the **memorial** stele’ (Umm el-‘Amed, Lebanon, no. 10)
- (9) ז מצבת סכר
 ‘this is the **memorial** stele’ (Umm el-‘Amed, Lebanon, no. 11)
- (10) סכר אש טנא לאב לי
 ‘a **memorial** which he erected for his father’ (Umm el-‘Amed, Lebanon, no. 16)
- (11) סכר [] א לאשת נעמת מהרת
 ‘**memorial** [] to a good and efficient woman’ (Cooke 1903, 147, no. 56.1, Cherchel, Algeria)
- (12) ובכבד תעצמתי אדר שפח סכ[ר ירח מד] ירח
 ‘and in honour of his great deeds his family has magnified his **memo[ry]** month by] month’ (CIS, no. 6000.7–8, Carthage)³⁴
- (13) לסכר על מאספת עצמי
 ‘as a **memorial** for the collection of my bones’ (RES I:9 [no. 13] = Slouschz [1942, 180, no. 155], Carthage)
- (14) לסכרן בחים
 ‘as a **memorial** among the living’ (Lapethos, Cypros, no. 3, ln. 5; Honeyman 1938, 286)

Finally, for the sake of completeness, consider *Mu Ponnim sucartim* ‘do **you remember** (any) Punic’ (*Poenulus* 1023),³⁵ which

³⁴ The text is broken at the key spot, but the reconstruction seems assured, based on the context (see Krahmalkov 2000, 344–45).

³⁵ I cite the text as presented by Krahmalkov (2000, 343). See also Sznycer (1967, 144).

corresponds to *ecquid commeministi Punice* (Poenulus 985), with the same meaning.

And for further completeness, let us recall Sychaeus, husband of Dido, introduced by Virgil in *Aeneid* 1.343, whose name may derive from the root סכ"ר, the lack of the final /r/ consonant notwithstanding (Levy 1869, 28).

Since, however, the sound /z/ essentially does not occur in Latin, and thus the letter *z* was dropped from the early Latin alphabet (borrowed from Etruscan), both the passage in Plautus's *Poenulus* and the potential derivation of the name Sychaeus from our root are non-probative.

To put the panoply of examples above into perspective, note that in all of Phoenician there are only two instances (to the best of my knowledge) with the *zayin* retained in this root (verb or noun), to wit:

- (15) אש נדר עבדך עבדאסר בן ארש זכרן
 ‘which your servant PN¹ son of PN² vowed **as a memorial**’
 (Naveh 1966, 234, no. 11 = Umm el-‘Amed, Lebanon, no. 14)
- (16) לזכר העלם
 ‘**in memory of** the youth’ (Slouschz 1942, 208, no. 209; Carthage)

As to the dates of all these inscriptions, the majority (if not all) of them are late, from the fifth century BCE onward—though this includes the two examples with *zayin* as the first root letter, in addition to those with *samekh*.

We may expand our database by incorporating Phoenician and Punic personal names (PNs) containing the root סכ"ר / זכ"ר

‘remember’ into the picture. There is no need to enter into the same amount of detail here, however, as the basic reference works may be consulted. Suffice to mention the following: זכר as a personal name in an unprovenanced seal (Levy 1869, 28); four inscribed arrowheads with the names [זכרב]על (Golub 2021, no. 3), זכרבעל (no. 9), זכר (no. 42), [זכרב]על (no. 53); and then examples such as בעלסכר (*RES*, no. 1314), סכר (*CIS*, no. 3751.4), סכרבעל (*CIS*, nos. 1218; 1354.2, 2871.4)—most of these registered in the standard treatment by Frank Benz (1972, 96, 109, 147).

In the case of these PNs, the former five with זכר are all early, while the latter three containing the element סכר are late. Though we should add some commentary regarding the unprovenanced seal, especially since it harks back to the early days of Phoenician studies. During the mid-nineteenth century this small object formed part of the collection of antiquities owned by Viscount Emmanuel de Rougé (1811–1872); it was studied and described by Melchior de Vogüé (1829–1916); and then it was published by M. A. Levy, as follows:³⁶

(17) לאבעד בן זכר

‘(belonging) to PN son of ZKR’ (Levy 1869, 28, no. 13)

Unfortunately, we have no way of firmly establishing the date or provenance of this object, and its whereabouts today are unclear.³⁷ Thus we must rely solely on the palaeographical analysis

³⁶ See also the line drawing at Tafel II, no. 12, between pp. 22–23.

³⁷ I am especially grateful to Matthieu Richelle (Université catholique de Louvain) for his research into the whereabouts of the seal, which

conducted by J. T. Milik (1956, 4), who dated the seal to the eighth–seventh century.

The same holds true for the aforementioned inscribed arrowheads (in fact, of the 63 items in the corpus, only one was found in a controlled excavation; all the others were obtained through the antiquities market), but all scholars agree to an eleventh–tenth century dating for these objects (Golub 2021, 22–23). In light of all the above evidence, we may wish to conclude that the shift of /z/ to /s/ in the root זכ"ר / סב"ר ‘remember’ most likely occurred at a later time, say, the sixth or fifth century BCE.

There is, however, one striking piece of counter-evidence to this conclusion, to wit, the name of the prince of Byblos in the tale of Wenamun, dated to ca 1050 BCE, written in hieratic/hieroglyphic script³⁸ as either $\underline{t}^3-k^3-l-b-^c-r$ (1.16–17) or $\underline{t}^3-k^3-r-b-^c-[x]$ (1.29 [3.7]) (Gardiner 1932, 62, 64),³⁹ typically anglicised as Tjekker-baal (Lichtheim 1973–1980, II:225; Wente 2003, 117–18). As Anson Rainey (1982b, 133–34) astutely noted, the Egyptian sign $\underline{t}$ (and related biliterals, as here with sign G47 [duckling,

confirms its present unknown location. The seal is not recorded in Bordreuil (1986), and thus a home in one of the major Paris repositories is excluded. The standard collection of Avigad and Sass (1997, 270, no. 724) remarks “present location not reported.”

³⁸ Technically hieratic script, hence I use the term ‘hieroglyphic’ here loosely.

³⁹ In the latter version, the third consonant, whether it had been *l* or *r*, was accidentally omitted (hence, my use of *[x]*). Both forms are followed by the recumbant Seth classifier (E21), reflecting the common identification of Seth and Ba‘al in New Kingdom religious texts (Allon 2007).

nestling] representing 𐤊) most frequently correlates with Hebrew/Phoenician *samekh*, and *never* with *zayin* (which is always represented by the Egyptian sign 𐤀 (and related biliterals)).⁴⁰ As such, one must assume that the Egyptian scribe heard /s/ at the onset of the name of the prince of Byblos, rather than /z/, reflecting the root סכ"ר as opposed to זכ"ר.⁴¹

This last point leaves us with an unsettled question regarding the date of the phonological shift, though one may wish to suggest that the shift was present in Byblos at an early stage in the history of Phoenician and then spread southward and westward (across the Mediterranean) at a later stage. Fortunately, regardless of how the issue is to be decided, the question of the date of the phonological shift is not truly germane to the main goal of the present article (see below, §5.0).

Naturally, this shift from /z/ to /s/ in the root סכ"ר / זכ"ר is noted by the standard grammars of Phoenician (Harris 1936,

⁴⁰ For a counter view, see Hoch (1984, 373–74, no. 556). However, Hoch's own data (for which see the charts on pp. 432–33, 436–37) only confirm Rainey's position.

⁴¹ There is yet another relevant item, namely, the patronymic 𐤊-𐤕-𐤌-𐤍 in P. Anastasi III, verso 6.6, perhaps reflecting סכרם (though the final element is unclear), whose son hails from the town of 𐤊-𐤕-𐤌 (an unknown toponym, unless it is a scribal error for 𐤊-𐤕-𐤌 'Gaza'). See Gardiner (1937, 31–31a); and Caminos (1954, 108, 111–12).

29; Friedrich, Röllig, and Amadasi Guzzo 1999, 27, §46a; Krahmalkov 2001, 22).⁴² Moreover, the explanation is readily forthcoming, as recognised first (to the best of my knowledge) by Zellig Harris (1936, 29): “It is the only case of such assimilation of a voiced sound to a voiceless known from Phoenician writing, and must have arisen in forms like יִזְכֹּר, where the *z* immediately preceded the *k*.” Similarly, see the words of Friedrich, Röllig, and Amadasi Guzzo (1997, 27, §46a): “erklären sich vielleicht so, daß die in Imperfektformen wie **īazkur* > *īaskur* in unmittelbarer Berührung mit dem folgenden stimmlosen *k* lautgesetzlich entstandene Aussprache mit stimmlosem *s* in andere Stellungen übertragen wurde.”⁴³

5.0. The Rabbinic Maxim and Phoenician Phonology

By this point the reader of this article should have discovered on his or her own the ultimate connection between the two main portions of my treatment, as adumbrated in the title: (a) the rabbinic maxim to articulate clearly the /z/ in תִּזְכְּרוּ (Num. 15.40), as recorded in y. Berakhot 2.3 (4d), so as not to devoice the sibilant to /s/; and (b) the wealth of Phoenician evidence pointing to this selfsame shift inherent in this selfsame verb.

And now an admission: I have known of these two phenomena for several decades, and have long intended to present this

⁴² See also Lipinski (1997, 123, §14.2). Somewhat oddly, Segert (1976, 65, §33.543.3) mentions the use of *samekh* for original /z/, but he refers only to the Late Punic demonstrative pronoun forms, *s* for *z*, etc.

⁴³ See also Rainey (1982b, 133–34).

material to the academic world via a dedicated scholarly article such as the present one. In my naïveté, I had assumed that I was the first to correlate the two aspects treated herein, from discrete sub-fields within the study of Northwest Semitic languages.

Only upon researching the material for the present article, however, did I learn that, in fact, previous scholars had already noticed the connection between the rabbinic maxim and the Phoenician sound shift. The first appears to have been Zellig Harris (or better: his father), for in a footnote to his Phoenician grammar (Harris 1936, 29, fn. 11), the author states, “Dr. H. H. Harris calls my attention to the Talmudic statement that the word תִּזְכֹּר in Numbers 15.40 should be articulated with special clarity (or with a ‘buzzing’ sound).”⁴⁴ Next one may cite E. Y. Kutscher (1965, 30, with fn. 3), who also connected the two phenomena, apparently independently of Harris, even though he cites his predecessor, albeit a different work.⁴⁵

Most scholars, presumably, have experienced the same: one devises what one thinks is an original contribution—only to learn, upon further reading, that someone else has already stated the same thing. In this case, I am fine with such circumstance, especially since my contribution was anticipated by two of the

⁴⁴ How interesting that Harris should use the term “‘buzzing’ sound” in light of our discussion above regarding תִּזְז ‘wasp, hornet’ (§2.1), a word which, discovered at Qumran, he clearly could not have known.

⁴⁵ That is to say, Kutscher cited Harris (1939, 79), in which Harris mentions “formation of root *skr* from *zkr* ‘remember’,” though without reference to the Talmudic passage in this instance.

giants of Northwest Semitic studies of the past century (Harris and Kutscher).

Though I am not the first to correlate the two phenomena studied herein, this article hopefully still has value, given the detail of research and analysis. Moreover, I also am able to contribute something original, not observed by either Harris or Kutscher. I refer here to the geographical component, namely, the western Galilee and the Plain of Akko.

We began this article with reference to R. Levi bar Sisi, whose dictum is cited by two other rabbinic figures. While we do not know the hometown of R. Levi bar Sisi (a contemporary of R. Judah ha-Nasi), we do know that he served the Jewish community in Simoniya (y. Yevamot 12.6 [13a] // Genesis Rabba 81.2) = biblical Shim'on = Tell Samunieh, located ca 30 km southeast of Haifa (just to the west of the present-day communal settlement of Timrat), attributed to the territory of Zebulun in Josh. 19.15 (under the ghost-word name Shimron, as observed by Anson Rainey 1982a, 140–42; 1998, 73) (see also Ezek. 48.24–25; 2 Chron. 15.9, 34.6).⁴⁶

And then there are the two Amoraim who cite the dictum in the name of R. Levi bar Sisi. We can say little about R. Levi, especially without a patronymic and further identification, though we may observe that he is often associated with R. Joshua

⁴⁶ Note that some LXX manuscripts reflect Shim'on (Συμων), while others reflect Shimron (Σεμρων) (for details, see Margolis 1931, 3:368). For a recent study, see Fulton (f.c.); I am grateful to Deirdre Fulton for furnishing me with a copy of her forthcoming article and for permission to cite it here in advance of publication.

of Sikhnin (Strack and Stemberger 1991, 98), 23 km east of Akko. We can say more about R. Avdima of Ḥaifa (himself a student of R. Levi bar Sisi), since he is associated with a city with deep connections to Phoenician culture—regardless of whether Ḥaifa is identified with Shiqmona or Tell Abu Hawam, since both archaeological sites have yielded material culture objects associated with the Phoenicians (Elgavish 1993; Balensi, Herrera, and Artzy 1993; Artzy, 2008).

In sum, from what we know about these two individuals, R. Levi bar Sisi the teacher and R. Avdima the student, the geography places us at the precise meeting ground of the Hebrew and Phoenician dialects of ancient Canaanite. Indeed, such is true of Mishnaic Hebrew generally, as I have proposed in several studies (Rendsburg 1992; 2003), especially given the compilation of the Mishna (and related texts) in Sepphoris (a bit farther inland, ca 12 km northeast of Shim'on/Simoniya).

And that is how the two discrete portions of this research intersect: for the Jews of the western Galilee and the Plain of Akko, the shift of *tizkərū* to *tiskərū* was very real. The background of R. Levi bar Sisi's comment in y. Berakhot 2.3 (4d) aligns with Phoenician perfectly: both linguistically and geographically.⁴⁷

⁴⁷ One final thought which crossed my mind, though naturally one must assume a singular coincidence: note that, of all the later rabbinic authorities, R. Manoaḥ of Narbonne came closest to the Phoenician reality with his reference to the root סב"ר 'dam up, stop up'. True, Phoenician texts have been found in the Occitan/Provençal region (e.g., *KAI*, nos 69–70) (even if the root סב"ר / זכ"ר 'remember' does not occur in these texts), but they date to one millennium earlier.

References

- Ahituv, Shmuel. 2008. *Echoes from the Past*. Jerusalem: Carta.
- Allon, Niv. 2007. 'Seth Is Baal: Evidence from The Egyptian Script'. *Ägypten und Levante / Egypt and the Levant* 17: 15–22.
- Alter, Robert. 2019. *The Hebrew Bible*. 3 vols. New York: W. W. Norton.
- Artzy, Michal. 2008. 'Tell Abu Hawam'. In *The New Encyclopedia of Archaeological Excavations in the Holy Land*, edited by Ephraim Stern, 5: 1553–54. Jerusalem: Israel Exploration Society.
- Avigad, Nahman, and Benjamin Sass. 1997. *Corpus of West Semitic Stamp Seals*. Jerusalem: Israel Academy of Sciences and Humanities.
- Bacher, Wilhelm. 1895. 'Die Anfänge der hebräischen Grammatik'. *Zeitschrift der Deutschen Morgenländischen Gesellschaft* 49/1: 1–62; 49/3: 335–92.
- Balensi, Jacqueline, Maria D. Herrera, and Michal Artzy. 1993. 'Tell Abu Hawam'. In *The New Encyclopedia of Archaeological Excavations in the Holy Land*, edited by Ephraim Stern, I: 7–14. Jerusalem: Israel Exploration Society.
- Bar-Asher, Moshe. 2012. *Leshonot Rishonim: Studies in the Language of the Bible, the Dead Sea Scrolls, and Aramaic*. Jerusalem: Magnes Press. [Hebrew]
- . 2014. *Studies in Classical Hebrew*, edited by Aaron Koller. Studia Judaica 71. Berlin: Walter de Gruyter.

- BDB = Brown, Francis, S. R. Driver, and Charles A. Briggs. 1906. *A Hebrew and English Lexicon of the Old Testament*. Oxford: Clarendon.
- Benz, Frank L. 1972. *Personal Names in the Phoenician and Punic Inscriptions*. Studia Pohl 8. Rome: Biblical Institute Press.
- Blau, Joshua. 2010. *Phonology and Morphology of Biblical Hebrew*. Linguistic Studies in Ancient West Semitic 2. Winona Lake, IN: Eisenbrauns.
- Bordreuil, Pierre. 1986. *Catalogue des sceaux ouest-sémitiques inscrits de la Bibliothèque Nationale, du Musée du Louvre et du Musée biblique de Bible et Terre Sainte*. Paris: Bibliothèque Nationale.
- Caminos, Ricardo A. 1954. *Late-Egyptian Miscellanies*. Brown Egyptological Studies 1. London: Oxford University Press.
- Chomsky, William. 1952. *David Kimḥi's Hebrew Grammar (Mikhlol)*. New York: Bloch.
- CIS = Ernest Renan, et al. 1881–1962. *Corpus Inscriptionum Semiticarum*, Pars Prima, *Inscriptiones Phœniciaë*. Paris: Reipublicæ Typographeo.
- Cook, Edward M. 2008. *A Glossary of Targum Onkelos*. Studies in the Aramaic Interpretation of Scripture 6. Leiden: Brill.
- Cooke, G. A. 1903. *A Text-book of North-Semitic Inscriptions*. Oxford: Clarendon.
- DCH = David J. A. Clines (ed.). 1993–2011. *The Dictionary of Classical Hebrew*. 8 vols. Sheffield: Sheffield Academic Press / Sheffield Phoenix Press.
- Dimant, Devorah. 1998. '4Q386 ii–iii: A Prophecy in Hellenistic Kingdoms'. *Revue de Qumrân* 18/4: 511–29.

- Dunand, Maurice, and Raymond Duru. 1962. *Oumm el-‘Amed: Une ville de l’époque hellénistique aux échelles de Tyr*. 2 vols. Paris: Librairie d’Amérique et d’Orient Adrien Maisonneuve.
- Elgavish, Joseph. 1993. ‘Shiqmona’. In *The New Encyclopedia of Archaeological Excavations in the Holy Land*, edited by Ephraim Stern, 4: 1373–78. Jerusalem: Israel Exploration Society.
- Frankel, Zacharias. 1874. *Talmud Yerushalmi, Seder Zera‘im*, fasc. 1, *Berakhot, Pe’ah*. Vienna: Winter Brothers.
- Friedrich, Johannes, Wolfgang Röllig, and Maria Giulia Amadasi Guzzo. 1999. *Phönizisch-punische Grammatik*. 3rd edition. Analecta Orientalia 55. Rome: Pontifical Biblical Institute.
- Fulton, Deirdre N. Forthcoming. ‘A Problematic Toponym: Reconsidering (again) Shimron/Shim‘on Traditions’.
- Gardiner, Alan H. 1932. *Late-Egyptian Stories*. Bibliotheca Aegyptiaca 1. Brussels: Édition de la Fondation Égyptologique Reine Élisabeth.
- . 1937. *Late-Egyptian Miscellanies*. Bibliotheca Aegyptiaca 7. Brussels: Édition de la Fondation Égyptologique Reine Élisabeth.
- Ginzberg, Louis. 1909. *Yerushalmi Fragments from the Genizah*. New York: Jewish Theological Seminary.
- Golub, Mitka. 2021. ‘Personal Names on Iron Age I Bronze Arrowheads: Characteristics and Implications’. *Jerusalem Journal of Archaeology* 2: 16–40.
- Greenspahn, Frederick E. 1984. *Hapax Legomena in Biblical Hebrew: A Study of the Phenomenon and Its Treatment Since*

- Antiquity with Special Reference to Verbal Forms*. Society of Biblical Literature Dissertation Series 74. Chico, CA: Scholars Press.
- Guggenheimer, Heinrich W. (ed.). 2000. *The Jerusalem Talmud. First Order: Zeraim—Tractate Berakhot*. Studia Judaica 18. Berlin: Walter de Gruyter.
- HALOT = Koehler, Ludwig, and Walter Baumgartner. 2001. *The Hebrew and Aramaic Lexicon of the Old Testament*. 2 vols. Translated and edited by M. E. J. Richardson. Leiden: Brill.
- Harris, Zellig S. 1936. *A Grammar of the Phoenician Language*. American Oriental Series 8. New Haven, CT: American Oriental Society.
- . 1939. *Development of the Canaanite Dialects*. American Oriental Series 16. New Haven, CT: American Oriental Society.
- Havlin, S. Z. 2007. 'Manoah of Narbonne'. *Encyclopaedia Judaica*. 2nd edition. Edited by Fred Skolnik and Michael Berenbaum, 13: 483. Detroit: Macmillan.
- Hoch, James E. 1994. *Semitic Words in Egyptian Texts of the New Kingdom and Third Intermediate Period*. Princeton, NJ: Princeton University Press.
- Honeyman, A. M. 1938. 'Larnax tēs Lapethou? A Third Phoenician Inscription'. *Le Muséon* 51: 285–98.
- Hopkins, Simon. 1983. 'A New Autograph Fragment of Maimonides' *Hilkhot ha-Yerushalmi*'. *Journal of Semitic Studies* 28/2: 273–96.
- Hurvitz, Eliezer. 1965. 'Rabbenu Manoah, Rabbotav, ve-Ḥibburo "Sefer ha-Menuḥa"'. *Talpiyyot* 9: 136–76, 490–93.

- Ibn Janah, Jonah. 1856. *Sefer ha-Riqma*, translated by Judah ibn Tibbon, edited by B. Goldberg. Frankfurt: n.p.
- Jastrow, Marcus. 1903. *Dictionary of Talmud Babli, Yerushalmi, Midrashic Literature and Targumim*. 2 vols. London: Luzac.
- KAI = Donner, Herbert, and Wolfgang Röllig. 1962–1964. *Kanaanäische und aramäische Inschriften*. 3 vols. Wiesbaden: Harrassowitz.
- Khan, Geoffrey. 1987. 'Vowel Length and Syllable Structure in the Tiberian Tradition'. *Journal of Semitic Studies* 32/1: 23–82.
- . 2020. *The Tiberian Pronunciation Tradition of Biblical Hebrew: Including a Critical Edition and English Translation of the Sections on Consonants and Vowels in the Masoretic Treatise Hidāyat al-Qāri' 'Guide for the Reader'*, 2 vols. Cambridge Semitic Languages and Cultures 1. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers.
<https://doi.org/10.11647/OBP.0163>
- Kohut, Alexander. 1926. *Arukh Completum*. 8 vols. Vienna: Menorah.
- Krahmalkov, Charles R. 2000. *Phoenician-Punic Dictionary*. Orientalia Lovaniensia Analecta 90. Leuven: Peeters.
- . 2001. *A Phoenician-Punic Grammar*. Handbook of Oriental Studies / Handbuch der Orientalistik 1.54. Leiden: Brill.
- Kutscher, Eduard Y. 1965. 'Contemporary Studies in North-Western Semitic'. *Journal of Semitic Studies* 10/1: 21–51.
- Levy, M. A. 1869. *Siegel und Gemmen*. Breslau: Schletter.

- Lichtheim, Miriam. 1973–1980. *Ancient Egyptian Literature*. 3 vols. Berkeley: University of California Press.
- Lipiński, Edward. 1997. *Semitic Languages: Outline of a Comparative Grammar*. Orientalia Lovaniensia Analecta 80. Leuven: Peeters.
- Margolis, Max L. 1931. *The Book of Joshua in Greek*. 4 vols. Paris: Paul Geuthner.
- Milik, Jozef T. 1956. 'An Unpublished Arrow-head with Phoenician Inscription of the 11th–10th Century B.C.'. *Bulletin of the American Schools of Oriental Research* 143: 3–6.
- Miller, Stuart S. 2006. *Sages and Commoners in Late Antique 'Ereš Israel: A Philological Inquiry into Local Traditions in Talmud Yerushalmi*. Texts and Studies in Ancient Judaism 111. Tübingen: Mohr Siebeck.
- Moreshet, Menahem. 1980. *A Lexicon of the New Verbs in Tannaitic Hebrew*. Ramat-Gan: Bar-Ilan University Press. [Hebrew]
- Naveh, Joseph. 1966. 'Phoenician and Punic Inscriptions (1960–1964)'. *Leshonenu* 30/3: 232–39. [Hebrew]
- Qimḥi, David. 1862. *Sefer ha-Mikhlol*. Lyck, Poland: n.p.
- Rainey, Anson F. 1982a. '1. Šimron'. In *'Enšiqlopedya Miqra'it*, edited by Ḥayim Tadmor, 13: 140–2. Jerusalem: Bialik.
- . 1982b. 'Toponymic Problems (cont.)'. *Tel Aviv* 9/2: 130–36.
- . 1998. Review of *Tabula imperii romani: Iudaea-Palaestina, Eretz Israel in the Hellenistic, Roman, and Byzantine Periods*, by Yoram Tsafrir, et al. *Journal of the American Oriental Society* 118/1: 71–73.

- Rendsburg, Gary A. 1992. 'The Galilean Background of Mishnaic Hebrew'. In *The Galilee in Late Antiquity*, edited by Lee I. Levine, 225–40. New York: Jewish Theological Seminary.
- . 2003. 'The Geographical and Historical Background of the Mishnaic Hebrew Lexicon'. *Orient* 38: 105–15.
- RES = Charles Clermont-Ganneau et al. 1900–1968. *Répertoire d'épigraphie sémitique*. 8 vols. Paris: Imprimerie nationale / Académie des inscriptions et belles-lettres.
- Richler, Benjamin, Malachi Beit-Arié, and Nurit Pasternak. 2008. *Hebrew Manuscripts in the Vatican Library: Catalogue*. Vatican City: Apostolic Vatican Library.
- Schäfer, Peter, and Hans-Jürgen Becker. 1991. *Synopse zum Talmud Yerushalmi*, Band I/1–2: *Ordnung Zera'im: Berakhot und Pe'a*. Tübingen: J. C. B. Mohr (Paul Siebeck).
- Segal, Moshe H. 1927. *A Grammar of Mishnaic Hebrew*. Oxford: Clarendon.
- Segert, Stanislav. 1976. *A Grammar of Phoenician and Punic*. München: C. H. Beck.
- Slouschz, Nahum. 1942. *Thesaurus of Phoenician Inscriptions*. Tel-Aviv: Devir / Bialik. [Hebrew]
- Sokoloff, Michael. 2009. *A Syriac Lexicon*. Winona Lake, IN: Eisenbrauns and Piscataway, NJ: Gorgias.
- . 2014. *A Dictionary of Christian Palestinian Aramaic*. *Orientalia Lovaniensia Analecta* 234. Leuven: Peeters.
- Sperber, Alexander. 2004. *The Bible in Aramaic*. Leiden: Brill.
- Strack, H. L., and G. Stemberger. 1991. *Introduction to the Talmud and Midrash*. Edinburgh: T & T Clark.

- Sussman, Yaacov. 2001. *Talmud Yerushalmi: According to Ms. Or. 4720 (Scal. 3) of the Leiden University Library*. Jerusalem: Academy of the Hebrew Language.
- Sznycer, Maurice. 1967. *Les passage puniques en transcription latine dans le "Poenulus" de Plaute*. Études et commentaires 65. Paris: C. Klincksieck.
- Tombback, Richard S. 1978. *A Comparative Semitic Lexicon of the Phoenician and Punic Languages*. Society of Biblical Literature Dissertation Series 32. Missoula, MT: Scholars Press.
- Weinberg, Werner. 1985. 'Observations about the Pronunciation of Hebrew in Rabbinic Sources'. *Hebrew Union College Annual* 56: 117–43.
- Wente, Edward F. 2003. 'The Report of Wenamon'. In *The Literature of Ancient Egypt*, edited by William Kelly Simpson, 116–24. New Haven, CT: Yale University Press.

A CASE FOR DISTRIBUTIVE QUANTIFICATION OF *KOL* IN BIBLICAL HEBREW*

Cynthia L. Miller-Naudé and Jacobus A. Naudé

In a publication that appeared posthumously in 2020, the linguist Edit Doron posits a Distributivity Cycle, a new linguistic concept, which she claims applies to the historical development of Hebrew *kol* (absolute כָּל, construct כָּל־) as a universal quantifier ('all') and a distributive quantifier ('every').¹ The core of her argument is that she rejects an identification of *kol* as a quantifier in pre-modern Hebrew; instead, she sees it as a collective determiner or a

* This work is based on research supported in part by the National Research Foundation of South Africa (Cynthia L. Miller-Naudé UID 95926 and Jacobus A. Naudé UID 85902). The grantholders acknowledge that opinions, findings, and conclusions or recommendations expressed in any publication generated by NRF-supported research are those of the authors, and that the NRF accepts no liability whatsoever in this regard.

¹ We conventionally gloss distributive *kol* with 'every' (rather than 'each' or 'every/each') in this article. English has two lexically differentiated distributive quantifiers, *every* and *each*, whose highly debated syntactic and semantic differences are outside the scope of this article. In a later publication we will examine the extent to which BH *kol* as a distributive quantifier reflects aspects of the English distributive quantifiers *every* and *each*.

free choice determiner. She furthermore rejects the definite article as a determiner in Biblical Hebrew (BH) and does not acknowledge a distributive meaning ('every') for *kol* in BH.

According to Doron (2020, 2), *kol* was originally a noun meaning 'entirety', which grammaticalised into a collective determiner in BH. Although she claims that *kol* followed by a noun phrase (NP) has a collective meaning that is akin to the universal quantifier *all* (in English), she argues that *kol* is unlike 'all' in that it is not quantificational—it "denotes the entirety of a (group) individual rather than quantifying over its members/parts" (Doron 2020, 8). She argues that if *kol* followed by NP occurs under an existential modal, it is then a free choice determiner 'any', but it does not have the meaning 'every' in BH (Doron 2020, 24). In Modern Hebrew, the 'any' (free choice) interpretation of *kol* NP evolved into the distributive interpretation 'every' (Doron 2020, 25–27). By contrast, in BH, distributivity is handled on an ad hoc basis, inter alia by lexical means and floated *kol* (Doron 2020, 20–23).

The view of Doron (2020) is contra the view represented in traditional Hebrew grammars, where the Hebrew quantifier *kol* is described as either a universal quantifier (equivalent to *all* in English) or as a distributive quantifier (equivalent to *each* or *every* in English) (GKC 411, §127b–c; Waltke and O'Connor 1990, 289; JM 485–86; Van der Merwe, Naudé, and Kroeze 2017, 309–11). Her view is also at odds with that of linguist David Gil (1996, 110, fn. 7), who argues that since Hebrew has no distinct lexical counterparts for universal quantification and distributive quanti-

fication (equivalent to the English lexical items *all* and *every*, respectively), the semantic contrast between universal and distributive quantification is expressed structurally: with plural morphology it is interpreted as a universal quantifier and with singular morphology as a distributive quantifier. The structural differentiation of quantification is well attested in antiquity in pre-modern Hebrew (Miller-Naudé and Naudé 2020b; Naudé 2011a; 2011b; f.c.; Naudé and Miller-Naudé 2015; 2022a; 2023) and Hellenistic Greek (Miller-Naudé and Naudé 2021; Naudé and Miller-Naudé 2022b) as well as in some modern languages (Hebrew, Arabic, Malayalam, isiZulu, Maricopa) (Gill 1996).

The views of Doron (2020), therefore, deserve critical examination, especially in light of the innovative linguistic arguments that she raises. In particular, many of Doron's arguments that *kol* in BH is not quantificational are primarily semantically based and, therefore, reductionist. Because language structure is multidimensional, arguments from other components of grammar, for example, phonology, morphology, and syntax, need to be considered to justify or falsify her claims. Specifically, this pertains to the proposed developmental cycle of *kol* as a distributive, and her rejection of the status of the BH definite article as a determiner. In terms of her proposed theory, it must also be determined whether the mechanisms utilised are the most economical and optimal and if they fit the psychological reality of grammatical description and explanation of a natural language like BH. For example, why does Doron (2020, 21–22) analyse floated *kol* as lexically distributive in BH, but consider non-floated *kol* as not distributive at all? What linguistic development

explains why floated *kol* in BH is only distributive in meaning, whereas in Modern Hebrew it is only universal in meaning (according to Francez and Goldring 2022, 341)? She offers no explanation for these facts. In addition, quantifiers across languages do not match in meaning or function; as a result, care must be taken so that there is no interference from the quantification systems of other languages when interpreting the BH system. The alterity of the BH quantification system must be taken into account as far as possible.

The article is organised as follows: In §1.0 we provide an overview of viewpoints concerning the diachronic development of *kol*. In §2.0 we evaluate Doron's arguments that *kol* does not have a distributive sense in BH. §3.0 presents the conclusions.

1.0. Diachronic Development of *kol*

The question of the diachronic development of *kol* has recently become a matter of debate, especially with respect to the question of the cyclic development of *kol*.

David Gil (1996, 110–20) argues that in Hebrew and Arabic the universal quantifier is the more basic and the distributive quantifier develops from it. He demonstrates how various North African dialects of Arabic participate in a quantification cycle—at the beginning of the cycle, the universal and distributive meanings of the quantifier *kull* are syntactically distinct. In the next stage, the syntactic structures and thus the meanings of universal and distributive quantification merge. In the last stage, universal and distributive quantification are again differentiated through the emergence of a new syntactic structure to express distributivity.

The linguist Martin Haspelmath (1995; 1997) identified three main crosslinguistic trajectories for the development of the distributive quantifier ‘every’: (1) from free choice indefinite determiners like ‘any’, (2) from distributive prepositions, or (3) from the universal quantifier ‘all’. The universal quantifier ‘all’ he identified as generally developing from an adjective meaning ‘whole’. Haspelmath identifies Arabic and Hebrew as having a distributive use of the quantifier, which developed out of the universal quantifier and is syntactically differentiated from it. This is the approach to the diachronic development of *kol* that we have accepted (Naudé 2011a; 2011b; f.c.; Miller-Naudé and Naudé 2020b; Naudé and Miller-Naudé 2015; 2022; 2023).

As discussed above, Doron (2020, 2) challenged this view and proposed in its place her Distributivity Cycle as formalised in (1).

(1) The Distributivity Cycle

Adjective/Noun *entire(ity)*

I → collective universal determiner *all*

II → free choice determiner *any*

III → distributive universal determiner *every*

Step I took place in BH—the noun *kol* became grammaticalised as a collective universal determiner with the meaning ‘all’. Step II also took place in BH as *kol* became a free choice determiner with the meaning ‘any’. Both meanings continue throughout the history of Hebrew. Step III, in which *kol* developed into a distributive universal determiner with the meaning ‘every’ from a free choice determiner, occurred only in Modern Hebrew or perhaps as early as Rabbinic Hebrew.

The concept of cyclicity in diachronic change is an extremely important development in historical linguistics (see Van Gelderen 2011).² To evaluate whether Doron's Distributivity Cycle should be accepted for BH, each component of her proposal must be thoroughly examined. In this article, we begin with a critical component of her cycle, namely, her claim that *kol* does not indicate distributivity in BH.

2.0. Distributivity of *kol* in Pre-modern Hebrew

In this section, we describe and critically evaluate the most important arguments advanced by Doron (2020) against a distributive meaning ('every') for *kol* as a quantifier in pre-modern Hebrew, focusing on BH; it is not possible to examine each argument within the confines of this article.

At the outset, it is important to note that Doron uses '*kol* NP' to refer to *kol* before any kind of NP, regardless of whether the NP is singular or plural, definite or indefinite. We will demonstrate throughout this essay that these morphosyntactic differences in the kind of NP that occurs with *kol* are critical for determining the various meanings of *kol*. We will therefore consider the NP that follows *kol* to be singular or plural depending upon the head of the NP. Similarly, we will consider the NP to be definite or indefinite depending upon the definiteness of the NP as a whole; construct phrases are definite if the absolute term (*nomen rectum*) is grammatically definite (as indicated by the definite article, a pronominal suffix, or a proper name).

² For previous studies on cyclic language change in BH, see Naudé, Miller-Naudé, and Wilson (2019; 2022) on the Negative Existential Cycle.

2.1. *Kol* NP as Subject Does Not Allow Scope Ambiguity

In English and many other languages, the universal quantifier ‘all’ as a subject is ambiguous, allowing for two different interpretations depending upon scope. The English sentence *All the artisans made ten curtains* is ambiguous in this way, allowing either universal quantification (i.e., all the artisans as a group made a total of ten curtains) or distributive quantification (i.e., each one of the artisans individually made ten curtains) (Doron 2020, 8). Doron’s claim is that this kind of ambiguity is unknown with *kol* NP—only the non-distributive interpretation is found and thus a distributive interpretation for *kol* must be rejected. As evidence, she cites two biblical verses, which we re-examine here.

The first example is Exod. 36.8, which she condenses to translate “Then all the gifted artisans among them who worked... made ten curtains” (Doron 2020, 8). The complete Hebrew sentence, however, does not support this interpretation:

- (1) וַיַּעֲשׂוּ כָל־חָכָם־לֵב בְּעֹשֵׂי הַמְּלָאכָה אֶת־הַמִּשְׁכָּן עֹשֶׂר יְרֵיעַת שֵׁשׁ מִשְׁזֹר
וּתְבִלֶּת וְאַרְגָּמָן וְתוֹלַעַת שָׁנִי כְּרִבִּים מַעֲשֵׂה חֹשֶׁב עָשָׂה אֹתָם:
‘Then they—**each artisan** (lit. **each wise person of heart**)
among those engaged in the work—made the tabernacle of
ten curtains; (with) twisted linen, and blue, and purple, and
crimson yarns, (with) cherubim, work of a weaver, he made
them.’ (Exod. 36.8)

It is important first to note that the sentence does not say ‘all the artisans’ (with definite plural NP) as Doron claims, but rather a selection of individuals ‘among those doing the work’, each one described as an ‘artisan’, functions as the collective subject of the

plural verb. The sentence also does not make the ten curtains the object of the verb ‘they made’; instead, the object is ‘the tabernacle’ and the ‘ten curtains’ is a secondary object indicating the material of which the tabernacle is made (Waltke and O’Connor 1990, 174, §10.2.3c; see also the translation in Propp 2006, 625). The sentence does not allow scope ambiguity between universal and distributive quantification for these reasons and, therefore, scope ambiguity cannot be used against a distributive meaning of *kol* in general.

Three similar sentences relating to the building of the tabernacle in (2a)–(2c) shed additional light on aspects of the syntactic interpretation of (1):

- (2a) וַעֲשִׂיתָ פָּרֹכֶת תְּכֵלֶת וְאַרְגָּמָן וְתוֹלַעַת שָׁנִי וְשֵׁשׁ מִשְׁזָר מִעֲשָׂה חֹשֶׁב יַעֲשֶׂה אֹתָהּ כְּרֻבִּים:

‘You shall make a curtain_i (with) blue and purple and crimson yarns, and twisted linen, a work of a weaver **one will make it_i** (with) cherubim.’ (Exod. 26.31)

- (2b) וְאֶת־הַמִּשְׁכָּן תַּעֲשֶׂה עֶשֶׂר יְרֵיעֹת שֵׁשׁ מִשְׁזָר וְתְכֵלֶת וְאַרְגָּמָן וְתוֹלַעַת שָׁנִי כְּרֻבִּים מִעֲשָׂה חֹשֶׁב תַּעֲשֶׂה אֹתָם:

‘You shall make the tabernacle of ten curtains_i, (with) twisted linen, and blue, and purple, and crimson yarns, (with) cherubim, a work of a weaver **you will make them_i**.’ (Exod. 26.1)

- (2c) וַיַּעַשׂ אֶת־הַפָּרֹכֶת תְּכֵלֶת וְאַרְגָּמָן וְתוֹלַעַת שָׁנִי וְשֵׁשׁ מִשְׁזָר מִעֲשָׂה חֹשֶׁב עָשָׂה אֹתָהּ כְּרֻבִּים:

‘He made the curtain_i of blue and purple and crimson yarn, and twisted linen, (with) work of a weaver **he made it_i** (with) cherubim.’ (Exod. 36.35)

The objective pronominal suffix *אֹתָם* in (1) could refer to the cherubim (the closer possible antecedent) or to the curtains (the farther possible antecedent). The examples in (2a) and (2c) demonstrate agreement between the objective pronominal suffix *אֹתָהּ* and the noun *פְּרָכָה*. This provides evidence that the objective pronominal suffix *אֹתָם* in (1) also refers to the curtains; the gender mismatch between the pronoun and the antecedent (masculine plural for feminine plural) in (1) is well-attested (see Propp 2006, 406).

The subject of the 3MS verb *עָשָׂה* in (1) must be carefully identified in light of the 3MPL verb *וַיַּעֲשׂוּ* at the beginning of the verse. In (2b), the verse is structured similarly, except that both forms of the verb *עָשָׂה* are inflected with the same person—there is an instruction to Moses in 2MS to make (*תַּעֲשֶׂה*) the tabernacle of ten curtains, which is further elaborated as a 2MS instruction to make (*תַּעֲשֶׂה*) them as the work of a weaver, that is, skilfully. This provides evidence that the two occurrences of the verb *עָשָׂה* in (1) are similarly used to refer to the same subject, while providing two different perspectives on the construction work. The first verb, inflected as 3MPL, highlights the collective endeavour of the selected artisans. The second verb, inflected as 3MS, highlights the highly skilled individual contribution of the artisans within the group earlier described earlier in the verse as *כָּל־חֹכְמֵי־לֵב בַּעֲשֵׂי הַמְּלָאכָה*. The description of the artisanal activities

continues to the end of chapter 36 using only 3MS verbs throughout (example (2c) is included in this passage).³

The second verse that Doron uses as evidence against the distributivity of *kol* is Isa. 2.12 in (3), where she understands the *kol* NP phrase as ‘all the proud and lofty’. However, because the NP is singular and indefinite, we understand the sentence instead to exhibit distributive quantification and not universal quantification:

- (3) כִּי יוֹם לַיהוָה צְבָאוֹת עַל כָּל־גָּאֹה וְרֵם וְעַל כָּל־נִשְׁאָ וְשָׁפֵל:
 ‘For the LORD of hosts has a day against **every proud and arrogant (person)** and against **every lofty (person)**—so that he is brought low.’ (Isa. 2.12)

Although reference is made in the preceding and following verses to a specific day (e.g., Isa. 2.11, 17), in this verse the day is an indefinite and, therefore, non-specific day or time that God has prepared against each proud and lofty person.⁴ The meaning of *kol* is thus distributive before a singular indefinite noun. By way of contrast, in Jer. 1.14 in (4), *kol* precedes a definite plural noun phrase ‘all of the inhabitants of the land’; the meaning of *kol* is the totality of the specific group. The meaning is thus universal and not distributive:

³ In (2a), the 3MS verb (יַעֲשֶׂה) also seems to refer to the activity of an artisan, who is not introduced in the previous context; Propp (2006, 333) translates ‘one shall make’.

⁴ See similarly Ezek. 30.3 with the same expression יוֹם לַיהוָה ‘a day belonging to the LORD’ within a context where a definite day is mentioned before (v. 2) and after (v. 17).

(4) וַיֹּאמֶר יְהוָה אֵלַי מִצָּפוֹן תִּפְתָּח הָרָעָה עַל כָּל־יֹשְׁבֵי הָאָרֶץ:

‘And the LORD said to me: “From the north the disaster will break loose upon **all the inhabitants of the land**.”’ (Jer. 1.14)

In this example, the disaster is predicated as occurring upon ‘all the inhabitants of the land’ as a specific group and not upon individual members of the group. The meaning of *kol* is universal and not distributive.

We agree, then, with Doron that in BH there do not appear to be examples of ambiguous scope with *kol* NP, where both universal (‘all’) and distributive (‘every’) readings are possible (Doron 2020, 8). However, we explain the lack of ambiguity differently—it is not because *kol* disallows distributivity, but because each specific type of NP with which *kol* is associated conveys semantic nuances of universal or distributive quantification, thus precluding the possibility of scope ambiguities. In lacking scope ambiguity, *kol* in BH differs from its parallels in English, Modern Hebrew, and many other languages. As a result, the test of scope ambiguity for determining the distributivity of *kol* must be rejected for BH.

2.2. *Kol* with Singular NP

The second argument of Doron that we consider is that

even when its complement NP is singular, *kol* NP denotes the entirety of a group and functions as subject of collective predicates unlike other languages where NP_{sing} only cooccurs with distributive *every*. (Doron 2020, 9)

This claim can be falsified from various angles.

First, it is possible to demonstrate that *kol* with a singular indefinite NP does have the meaning ‘every’ when the head of the NP is a count noun. We present a selection of six examples.

In (5), *kol* precedes the singular indefinite count noun *šē*. The phrases with *kol* describe the subset of sheep and goats with particular physical characteristics that are to be removed from the flock as a whole.

- (5) אֶעֱבֹר בְּכָל־צֹאֲנֶךָ הַיּוֹם הַזֶּה מִשָּׁם כָּל־שֶׂה וְנֶקֶד וְכָל־שֶׂה־חֹום
בְּבָשָׁבִים וְנֶקֶד וְכָל־צֹאֲנִים וְהָיָה שְׂכָרִי:

‘I will pass through your whole flock today to remove from there every speckled and spotted animal—every dark-coloured sheep among the lambs and spotted and speckled (one) among the goats. Such shall be my wage.’ (Gen. 30.32)

Note that the *kol* NP phrases cannot be interpreted as ‘free choice’ items (see Doron 2020, 24–25) and translated with ‘any’ because Jacob and Laban’s agreement is based on the assumption by both parties that there were such animals in the flock (a fact borne out by Laban’s treachery in v. 35), whereas ‘any’ would imply that perhaps no such spotted animals were present.

In 2 Sam. 20.7–13 in (6), Joab and his men are pursuing Sheba the son of Bichri. After Joab kills Amasa and leaves his body on the road, one of Joab’s men stands by the corpse and calls out to the troops that if they are on the side of Joab and David, they must follow Joab. However, ‘all the people’ (כָּל־הָעָם) stop when they see Amasa’s corpse in the road, so the man moves his corpse to the side, allowing ‘each man [individually]’ (כָּל־אִישׁ) to pass over:

- (6) כְּאַשֶׁר הָגָה מִן־הַמַּסְלָה עָבַר כָּל־אִישׁ אַחֲרֵי יוֹאָב לְרֹדֵף אַחֲרֵי שֶׁבַע בֶּן־בַּכְרִי:
 ‘When he was removed, **each man** crossed over the road after Joab to pursue after Sheba the son of Bichri.’ (2 Sam. 20.13)

The singular indefinite noun with *kol* is the subject of a singular verb; the meaning is that each man individually followed Joab.

In (7), ‘every precious stone’ that adorned the king of Tyre is enumerated in the remainder of the verse:

- (7) בְּעֶדֶן גֶּן־אֱלֹהִים הָיִיתָ כָּל־אֶבֶן יָקָרָה מִסַּכְתָּךְ אָדָם פִּטְוָה וַיְהִלֵּם תְּרֻשִׁישׁ
 שֹׁהַם וַיִּשְׁפֹּה סַפִּיר נִפְדָּ וּבִרְקָת וְזָהָב מְלֹאכֶת תַּפְיִד וְנִקְבִּידָ בָדָּ בַיּוֹם הַבְּרָאָךְ
 כּוֹנְנִנוּ:

‘You were in Eden, the garden of God. **Every precious stone** was your adornment: carnelian, topaz, and aquamarine; chrysolite, onyx, and jasper; lapis lazuli, malachite, and emerald; and gold beautifully wrought for you, mined for you, prepared on the day you were created’. (Ezek. 28.13)

Again, it is not possible to understand *kol* NP as a ‘free choice’ item—‘any precious stone was your adornment’—because the specific precious stones of the adornment are enumerated.

In (8a), mention is made of seven-hundred chosen warriors who were left-handed. The sentence that begins with *kol* describes a further characteristic of each one:

- (8a) מִכָּל הָעָם הַזֶּה שֶׁבַע מֵאוֹת אִישׁ בָּחֹר אֶטֶר יַד־יְמִינִי כָל־זֶה קָלַע בָּאַבֶּן אֶל־
 הַשִּׁיעָרָה וְלֹא יִחָטָא:

‘From all this army (lit. people), 700 chosen men were left-handed, **every one** could sling a stone at a hair and not miss.’ (Judg. 20.16)

The nominal item that *kol* precedes is the singular masculine demonstrative pronoun *ze*, which is the subject of a MS participle and a 3MS imperfect verb. Contrast the similar expression with *kol-ʿelle* in (8b) as the subject of a plural participle:

- (8b) וַיֵּצֵא בְנִימִן | לְקִרְאָתָם | מִן־הַגִּבְעָה בַּיּוֹם הַשֵּׁנִי וַיַּשְׁחִיתוּ בְּבִגְיִי יִשְׂרָאֵל עוֹד
שָׁמַנְתָּ עֶשְׂרֵי אֲלָף אִישׁ אֶרְצָה כָּל־אֵלֶּה שְׁלֹפֵי חֶרֶב:

‘But the Benjaminites came out from Gibeah against them on the second day and struck down 18,000 more of the Israelites, **all of these** wielding (PL) a sword.’ (Judg. 20.25)

In (8a), *kol* with the singular demonstrative and singular agreement is distributive, referring to the sharp-shooting ability of each of the seven-hundred left-handed warriors. In (8b), *kol* with the plural demonstrative and plural agreement is universal, referring to the fallen Israelites as a group.⁵ In neither (8a) nor (8b) is a free choice interpretation with ‘any’ possible.

In (9), pieces of meat are to be collected in a cauldron, specifically, every choice piece from the thigh and shoulder of the animal:

- (9) אָסַף נִתְחִיָּה אֵלֶיהָ כָּל־נֶתַח טוֹב יֶרֶךְ וְכֹתֵף מִבְּחֵר עֲצָמִים מִלֵּא:
‘Collect its pieces (of meat) in it [the cauldron]—**every good piece**, thigh and shoulder—fill (it) with choice cuts.’ (Ezek. 24.4)

Again, a free choice interpretation of *kol* is not possible.

⁵ The feminine singular demonstrative *zōt* is used in the same construction after *kol* when there is generic reference to events or circumstances; see, e.g., Gen. 41.39; Deut. 32.27; Judg. 6.13; 2 Chron. 21.18; 31.1; 35.20; Ps. 44.18; Mic. 1.5.

In (10) there are two instances of distributive *kol*:

- (10) אָבָה כָּל-סוֹס בְּתַמְחוֹן וְרִכְבּוֹ בְּשֹׁגְעוֹן וְעַל-בֵּית יְהוּדָה אֶפְקַח אֶת-עֵינַי וְכָל
סוֹס הָעַמִּים אָבָה בְּעוֹרוֹן:

‘I will strike **every horse** with panic and its rider with madness. But over the house of Judah, I will open my eyes. And **every horse of the peoples** I will strike with blindness.’
(Zech. 12.4)

The phrase with *kol* and the singular indefinite noun סוס is distributive in that each horse has its own rider. At the end of the verse, *kol* in the phrase וְכָל סוֹס הָעַמִּים ‘every horse of the peoples’ refers to the totality of the individual members, that is, each individual entity.

We conclude that *kol* with a singular, indefinite, count NP can be used to convey distributivity.

Second, Doron (2020, 9) argues that because *kol* with singular NP can be used as the subject of collective predicates, *kol* NP_{sing} refers to the entirety of the group and does not have a distributive meaning. She provides illustrations with three collective predicates: הִתְקַבֵּץ, נִקְהַל, and אָסַף. Her first example is (11a):

- (11a) וַיִּתְקַבְּצוּ אֵלָיו כָּל-אִישׁ מִצּוֹק וְכָל-אִישׁ אֲשֶׁר-לֹו נִשָּׂא וְכָל-אִישׁ מֵרֶגֶץ וַיְהִי
עֲלֵיהֶם לְשָׂר וַיְהִי עִמּוֹ כְּאַרְבַּע מֵאוֹת אִישׁ:

‘**Every man who was in straights and every man who was in debt and every man who was bitter of spirit** (they) joined themselves to him and he became leader over them. There were about 400 men with him.’ (1 Sam. 22.2) (Doron 2020, 9, example 16a)

The subject of the collective predicate consists of three conjoined phrases of *kol* with a singular, indefinite NP. The second phrase

(וְכָל-אִישׁ אֲשֶׁר-לֹו נִשָּׂא) further exhibits singular agreement within the relative clause that modifies it. We understand each of these conjoined phrases to indicate distributively the types of persons who joined themselves to David. Ezra 9.4 is similar in having *kol* with a singular participle to indicate the set of persons who gathered to Ezra (Doron's example 16c [2020, 9]).

By contrast, the same collective verbal predicate in the plural (וַיִּתְקַבְּצוּ) may have a plural subject consisting of *kol* and a plural definite NP as in (11b) (see also Judg. 9.47; Ezra 10.9):

- (11b) וַיִּתְקַבְּצוּ כָּל זִקְנֵי יִשְׂרָאֵל וַיָּבֹאוּ אֶל-שָׁמוּאֵל הַרְמָתָה:
 'All the elders of Israel gathered themselves together and came to Samuel at Ramah.' (1 Sam. 8.4)

The phrase with *kol* and a definite plural NP indicates the totality of the specific group that assembled (see also Gen. 29.8; Judg. 9.6; 2 Kgs 23.1).

A further contrast can be made with a collective verbal predicate in the plural and a subject consisting of *kol* and a definite singular NP:⁶

- (11c) וַיִּקְהָלוּ כָּל-עֵדַת בְּנֵי-יִשְׂרָאֵל שָׁלָה לַעֲלֹות עֲלֵיהֶם לָצֶבָא:
 'The whole congregation of the Israelites assembled at Shiloh to go up against them in war.' (Josh. 22.12)

The plural predicate conveys the nuance that the individual members of the collective are acting—in this case, the members

⁶ For an example that makes a sharp contrast with (10b) in using the collective verb וַיִּקְבְּצוּ with the collective singular subject כָּל-יִשְׂרָאֵל, see 1 Sam. 25.1.

of the congregation individually assemble together after hearing about the altar built in Transjordan.

A collective singular NP can also occur with the same collective lexical verb in the singular:

(11d) וַיִּקְהֵל כָּל־הָעָם אֶל־יִרְמְיָהוּ בְּבֵית יְהוָה:

‘All the people assembled to Jeremiah in the house of the LORD.’ (Jer. 26.9)

The singular predicate conveys the nuance that the people as a whole are acting as a collective to shield Jeremiah from the officials who want to kill him.

Examples of other singular definite nouns with a collective meaning that may be used as the subject of collective predicates include: כָּל־עֵדֻת בְּנֵי־יִשְׂרָאֵל ‘the congregation of the sons of Israel’ (Josh. 18.1; 22.12), כָּל־יִשְׂרָאֵל ‘all of Israel’ (Josh. 8.24; 1 Sam. 3.20; 4.5), כָּל־אִישׁ יִשְׂרָאֵל ‘every man of Israel’ (Judg. 20.11; 1 Kgs 8.2; 2 Chron. 5.3), כָּל־הָעָם ‘the people’ (Neh. 8.1).

We conclude that *kol* with a singular NP as the subject of a plural collective verb does not preclude distributivity. When *kol* precedes a singular, indefinite NP with a count noun, as in (11a) above, the usual meaning of *kol* as a distributive quantifier is present. When *kol* precedes a plural definite NP as the subject of a plural collective verb, as in (11b) above, *kol* indicates the totality of the individual members of the entity. When *kol* precedes a singular definite collective noun, it may function as the subject of a plural collective predicate, as in (11c), or of a singular collective predicate, as in (11d), with slight nuances of meaning. With a plural predicate, the individual members of the collective entity are in view; with a singular predicate, the collective entity as a

whole is in view. The alternation in BH between singular and plural predicates with *kol* NP subjects will be further examined in §2.3.

Third, Doron (2020, 9–10) argues that *kol* with singular NP may denote “the entirety of an individual: *the whole NP/all the NP*.” The two examples that she cites involve the singular indefinite nouns *lēb*/*lēbāb* ‘heart’, *neṣēš* ‘soul’, and *rōš* ‘head’. The first example involves the phrases *bə-kāl-lēb* and *bə-kāl-neṣēš*:

- (12) וְלִשְׁמֹר מִצְוֹתָיו וְאֶת־חֻקָּתָיו בְּכָל־לֵב וּבְכָל־נֶפֶשׁ
 ‘...to observe his commandments and his injunctions, and
 his statutes **with all (their) heart and with all (their) soul...**
 (2 Kgs 23.3) (Doron 2020, 9, example 17a)

In covenant contexts, the usual expressions employ the second person pronominal suffix on the nouns ‘heart’ and ‘soul’, either the singular suffixes (Deut. 6.5; 10.12; 11.13; 30.2, 6) or the plural pronouns (Josh. 22.5; 23.14; 1 Sam. 7.3; 12.20, 24). In all of these cases, the phrase *bə-kāl* NP seems to mean ‘with your whole heart’/‘with all your heart’ or ‘with your whole soul’/‘with all your soul’, etc. Outside covenantal contexts, the phrase *bə-kāl-lēb* occurs five times in which it clearly means ‘with the whole heart, wholeheartedly’ (see also Ps. 119.34, 58, 69, 145; Zeph. 3.14):⁷

- (13) אֲשֶׁר־יִצְרֶה יְדֹתָיו בְּכָל־לֵב יִדְרֹשׁוּהוּ:
 ‘Happy are those who observe his decrees; they turn to him
with a whole heart.’ (Ps. 119.2)

⁷ See also the expanded prepositional phrase בְּשִׂמְחַת כָּל־לֵבב ‘with wholehearted glee’ (Ezek. 36.5).

By contrast, without the preposition, the phrase *kāl lēb/lēbāb* is used distributively for ‘every heart’ (see also Isa. 13.7; Ezek. 21.12), just as *kāl-rōš* is used for ‘every head’:

- (14) עַל מָה תִּכּוּ עוֹד תּוֹסִיפוּ סָרָה כָּל־רֹאשׁ לְחָלִי וְכָל־לֵב דָּוִי:
 ‘Why should you (PL) be beaten further? Why do you (PL) continue to rebel? **Every head** is sick, **every heart** faints.’
 (Isa 1.5) (not ‘**the whole head** is sick, **the whole heart** faints’
 [Doron 2020, 9])

Mass nouns with *kol* do not indicate distributivity and must be translated ‘all’ (as noted in Naudé 2011, 412 fn. 5, 417–18; Doron 2020, 9–10). However, Doron (2020, 9 fn. 11) claims that “Naudé’s account ignores *kol* applied to NP_{-count-def} ...which Naudé claims does not exist (2011a, 418)...” She bases her claim on (15):

- (15) וְכָל־בְּסֵף וְזָהָב וְכָל־נְחֹשֶׁת וְכָל־קֶדֶשׁ הוּא לַיהוָה
 ‘**But all the silver and gold and vessels of bronze and iron** are consecrated to the LORD.’ (Josh. 6.19) (Doron 2020, 10, example 18)

Doron (2020, 9 fn. 12) claims further that “[t]he nouns gold and silver are mass nouns in BH, just as they are in Modern Hebrew and in English, since they do not pluralize, and, though singular, denote space-filling substance.” This claim is too strong. Although there are no attested cases of זָהָב in the plural in BH, בְּסֵף occurs in the plural as in (16), contra Doron’s claim:

- (16) וַיִּצְוֵה יוֹסֵף וַיִּמְלְאוּ אֶת־כְּלִיָּהֶם בָּרֶ וְלָהֶשִׁיב כֶּסֶף־יָהֶם אִישׁ אֶל־שָׁקוֹ
 ‘Then Joseph gave orders to have their containers filled with grain, and to return **their silver [pieces]** (PL)—each one’s to his sack’. (Gen. 42.25)⁸

When the noun כֶּסֶף is used to refer to silver pieces, which can be counted, it undergoes recategorisation from a mass noun to a count noun and thus occurs in the plural (see Corbett 2000, 81–87 for discussion and examples).

As claimed by Naudé (2011a, 417–18), a singular mass noun (זָהָב) occurs with the definite article to convey the nuance ‘the totality of the entity’ as in (17):

- (17) כָּל־הַזָּהָב הָעָשׂוּי לְמִלְאָכָה בְּכָל מְלָאכַת הַקֹּדֶשׁ וַיְהִי זָהָב הַתְּנוּפָה תִּשְׁעַ וּשְׁשָׁרִים כֶּכָּר וּשְׁבַע מֵאוֹת וּשְׁלֹשִׁים שָׁקֶל בְּשֶׁקֶל הַקֹּדֶשׁ:
 ‘**All the gold** that was used for the work, in all the work of the sanctuary—the elevation offering of gold—came to 29 talents and 730 shekels by the sanctuary weight.’ (Exod. 38.24)

The definite article plus the singular noun refers to a single body of gold (mass noun). When quantified with *kol*, it has a nuance similar to that of *kol* with a definite plural count noun.⁹ This usage differs from the usage in (15) of זָהָב (and כֶּסֶף) in the singular without the definite article, which refers to the booty of Jericho, which must be interpreted within the context in light of Achan’s answer in (18):

⁸ See also Gen 42.35.

⁹ See also כָּל־הַחֶלֶב (Exod. 7.20), which acts like a plural subject, כָּל־הַחֶלֶב (Exod. 29.13), and כָּל־הַבָּשָׂר (Isa. 40.6).

- (18) וַאֲרָא בַשְּׁלָל אֶדְרֶת שְׁנַעַר אֶחָת טוֹבָה וּמֵאֲתָיִם שְׁקָלִים כֶּסֶף וּלְשׁוֹן זָהָב אֶחָד
חֲמִשִּׁים שְׁקָלִים מִשְׁקָלוֹ

‘I saw among the booty a beautiful mantle from Shinar, and two hundred shekels of silver, and a bar of gold weighing fifty shekels’. (Josh. 7.21)

In light of (18) it seems that all kinds of countable artefacts manufactured from gold and silver formed, *inter alia*, part of the booty of Jericho. The phrase *כָּל כֶּסֶף וְזָהָב* in (15) must rather be translated as ‘all silver and gold [objects]’, since it does not refer to a single body of gold or silver, but to various objects of gold and silver that are all kinds of countable artefacts. The construction acts, then, like an indefinite plural count noun and is distributive.¹⁰

A case of *כֶּסֶף* without the definite article with only a free choice ‘any’ interpretation as last resort is presented in (19):¹¹

¹⁰ See also, *כָּל-חֵלֶב לַיהוָה* (Lev. 3.16), which refers to various kinds of fat, *כָּל-בָּשָׂר* (Gen. 6.12), which is a metaphorical use referring to people (= all people) and *כָּל-מַיִם* (Isa. 32.20), referring to various masses of water (= all waters).

¹¹ “Last resort” refers to “the principle that grammatical operations do not apply unless they have to as the only way of satisfying some grammatical requirement” (Radford 1997, 513). An example of last resort in English is “*do*-support”, the use of the auxiliary *do* in interrogative sentences when no other auxiliary is present to undergo inversion (see Radford 1997, 216–19). The free choice meaning of *kol* (‘any’) is unusual in BH and is used here as a last resort. For another example, see Ezra 7.16.

- (19) וַיֹּאמֶר יְהוֹאָשׁ אֶל־הַכֹּהֲנִים כָּל־כֶּסֶף הַקִּדְשִׁים אֲשֶׁר־יוֹבֵא בֵּית־יְהוָה כֶּסֶף
עוֹבֵר אִישׁ כֶּסֶף וּנְפֻשׁוֹת עִרְבּוּ כָּל־כֶּסֶף אֲשֶׁר יַעֲלֶה עַל לֵב־אִישׁ לְהָבִיא בֵּית
יְהוָה:

‘Jehoash said to the priests, “**All the silver of the sacred donations** which is brought into the House of the LORD (must be collected)—current money, money a man may pay as the money equivalent of persons, **any money** that a man may be minded to bring to the House of the LORD”’. (2 Kgs 12.5)

We have seen that *kol* with a singular, indefinite noun usually indicates distributivity. With a plural collective predicate, a distributive expression with *kol* and a singular indefinite noun highlights the collectively distributive nature of the action. When the singular indefinite noun is a mass noun, distributivity is precluded and the expression with *kol* indicates ‘all’. When the body part is *lēḥ/lēḥāḇ* ‘heart’, the expression with *bə-kāl-lēḥ* may refer to the entire heart of an individual or an aggregate of individuals, whereas the expression *kāl-lēḥ* may be used distributively of ‘every heart’ of a group of individuals. To conclude, the claims of Doron (2020, 9 fn. 11) for an alternative analysis and her criticism of Naudé’s (2011a) proposed analysis are falsified in the light of data presented in this section.

2.3. Verbal Agreement with *kol* NP

The third argument of Doron that we consider concerning the lack of distributivity with *kol* is that of verbal agreement:

If *kol* were distributive, we would expect *kol* NP_{sing} to strictly agree in the singular like *every* and unlike *all*

(which agrees either in the plural or the singular). Yet irrespective of the number marking of NP, verbal agreement is often plural, even for singular NP. (Doron 2020, 10)

Doron provides four contrastive examples. The first involves four terms for body parts, each introduced with *kol*:

- (20) וְנִמְסָה כָּל־לֵב וְרַפּוּ כָּל־יָדַיִם וְכָהֲתָה כָּל־רוּחַ וְכָל־בְּרָכִים תִּלְכְּנָה מַיִם
 ‘Every heart shall sink (SG) and every [pair of] hands (DU) hang slack (PL); every spirit shall grow faint (SG) and every [pair of] knees (DU) turns to water (PL).’ (Ezek. 21.12) (*not* ‘and all knees will be weak as water’ [Doron 2020, 10])

The singular NPs all have singular verbal agreement. The other two NPs are not plural, but rather dual. They therefore are distributive in the same way that the singular NPs are distributive; none of the instances of *kol* NP in this verse should be interpreted as *all*. The only difference is that it is the *pair* of hands and the *pair* of knees that are distributively quantified, alongside the heart and the spirit. The verbs are plural because dual subjects ordinarily take plural verbal agreement (JM 597d). The use of *kol* before a dual noun is infrequent in the Hebrew Bible; it is often used to rhetorically indicate the bodily effects experienced by individual persons in a group.¹²

Doron’s second and third examples contrast the use of *kol* with a singular or plural form of the noun יָד:

¹² Additional examples include: כָּל־יָדַיִם (Isa. 13.7; Jer. 48.37; Ezek. 7.17), כָּל־בְּרָכִים (Ezek. 7.17), and כָּל־מַתְנִים (Jer. 48.37; Ezek. 29.7; Amos 8.10; Nah. 2.11).

- (21a) כִּי־מָתוּ כָּל־הָאֲנָשִׁים הַמְּבַקְשִׁים אֶת־נַפְשְׁךָ:
 ‘...for **all the men** who were seeking your life are dead.’
 (Exod. 4.19)
- (21b) וַיֹּאמֶר אֲמֹנֹן הוֹצִיאוּ כָּל־אִישׁ מִמָּעֵלִי וַיֵּצְאוּ כָּל־אִישׁ מִמָּעֵלָיו:
 ‘Amnon said, “Make **every man** go out from me.” And they, **every man**, went out from him.’ (2 Sam. 13.9; see also Gen. 45.1) (*not* ‘so **everyone** left’ [Doron 2020, 10])

Doron understands both NPs to refer to plural ‘all the men’ or ‘everyone’. However, the use of singular or plural NP should rather be understood to convey either the totality of the individual members of the entity (with the singular indefinite NP) or the totality of the members of the group (with the plural definite NP).

Doron’s fourth example involves the singular definite NP *kāl-hā-ʿezrāh* ‘every citizen’ as the subject of a plural verb:

- (22a) כָּל־הָאֲזִרָה בְּיִשְׂרָאֵל יֵשְׁבוּ בַסֹּכֶת:
 ‘**Each and every citizen** in Israel will live (PL) in booths’.
 (Lev. 23.42)

Doron translates ‘All who are native Israelites shall dwell in booths’ (Doron 2020, 10, example 20b), arguing that the singular noun *ʿezrāh* is a collective noun and thus takes plural agreement. However, singular agreement with the same noun preceded by *kol* also occurs:

- (22b) כָּל־הָאֲזִרָה יַעֲשֶׂה־כִּכָּה אֶת־אֵלֶּה לְהַקְרִיב אִשָּׁה רִיח־נִיחֹחַ לַיהוָה:
 ‘**Every citizen** shall do (SG) thus with these (offerings) when presenting an offering by fire of pleasing odour to the LORD.’ (Num. 15.13)

Doron is correct that subject-verb agreement in BH is not ‘haphazard’ (Doron 2020, 10). Instead, it is well documented that

collective nouns may take singular or plural agreement, even in adjacent verses (e.g., עַם יִוֹדֵד in Judg. 9.36 versus עַם יִוֹדֵיִים in Judg. 9.37; see JM 518e). This means that variation in number agreement is one strategy in BH for conveying semantic-pragmatic nuance. Furthermore, there is a diachronic aspect in that later biblical books tend to use the plural rather than the singular (contrast הָעָם נָסוּ in 2 Sam. 23.11 with הָעָם נָסוּ in 1 Chron. 11.13). A careful analysis of each of her counterexamples reveals that number agreement with *kol* NP cannot be used as an argument against the distributivity of *kol*.

2.4. Floated *kol* and Quantificational Distributivity

Doron argues that floated *kol* (that is, *kol* with a pronominal suffix) is not quantificational, but rather indicates lexical distributivity. For example, in (23), Doron views floated *kol* as indicating lexically the distributivity of the preceding *kol* NP phrase:

- (23) וְכָל-צָרֶיךָ כָּלָם בְּשָׁבִי יֵלְכוּ
 ‘All your adversaries, **every one of them**, shall go into captivity.’ (Jer. 30.16; Doron’s translation)

We argue that because floated *kol* is a quantifier, it may convey distributive quantification or universal quantification, depending upon the syntactic characteristics of the NP that it modifies, just like non-floated *kol*.

First, floated *kol* involves a construction in which *kol* has ‘floated’ from its normal position before a NP to a location after the NP. Compare the non-floated *kol* in (24a) and the floated *kol* in (24b) (from Naudé 2011b, 121–22):

(24a) שְׁמְעוּ-נָא כָּל-עַמִּים

‘Hear, now, **all peoples!**’ (Lam. 1.18)

(24b) יוֹדוּךָ עַמִּים כָּלָם

‘Peoples will praise you, **all of them.**’ (Ps. 67.4; also Mic. 1.2)

The resumptive pronominal suffix on floated *kol* in (24b) refers to the NP עַמִּים ‘peoples’. In the same way that *kol* as a quantifier in (24a) is a universal quantifier before a plural noun (‘all peoples’), *kol* as a floated quantifier in (24b) is a universal quantifier (‘all of them’)—*kol* in (24b) cannot be interpreted as having a distributive meaning (‘each one of them’). The semantics of *kol* as indicating universal or distributive semantics when it floats are identical to its semantics when it occurs before the NP (Naudé 2011b, 135–36).

In (23) above, the translation must be ‘and all your adversaries, all of them, will go into captivity’—floated *kol* has universal meaning and not distributive meaning. Although it is cross-linguistically unusual for a floated *kol* phrase to be appositional to *kol* NP, it does occur in BH; floated *kol* “indicates a strengthening of the nuance of quantification” (Naudé 2011b, 133).

Second, many instances of floated *kol* in BH cannot possibly be interpreted as distributive:

(25) וְהָר סִינַי עָשָׂן כָּלּוֹ

‘Mount Sinai was smoking, **all of it.**’ (Exod. 19.18)

Because Mount Sinai is a single entity, it cannot be referred to distributively.¹³ Instead, with the quantifier *kol*, it can only mean ‘all of Mount Sinai’ or ‘the whole Mount Sinai’.

Similarly, many collective nouns (or proper names referring collectively to people-groups) are used with floated *kol*, which cannot be understood distributively:

- (26) עַל־כֵּן עַל־מוֹאָב אֵילִיל וְלִמוֹאָב כָּלָהּ אֶזְעַק
 ‘Therefore, for Moab I will howl, and for Moab, **all of it**, I will cry out.’ (Jer. 48.31)

However, instances of distributive floated *kol* are also found:

- (27) כִּי מִקְטָנָם וְעַד־גְּדֹלָם כָּלוּ בּוֹצֵעַ בָּצַע וּמִנְבִּיא וְעַד־כֹּהֵן כָּלוּ עָשָׂה שָׁקֶר
 ‘For from their smallest [person] to their greatest [person], **each one** is greedy for gain; and from prophet to priest, **each one** acts falsely’. (Jer. 6.13)

In future research, we will exhaustively present an analysis of floated *kol* as a quantifier with respect to universal and distributive quantification.

3.0. Conclusions

In this paper we have examined Doron’s recent arguments made against viewing *kol* as indicating distributivity in BH, which form part of her larger argument against *kol* as a quantifier in pre-modern Hebrew (Doron 2020). Drawing on our approach to language as a complex system (Miller-Naudé and Naudé 2020a) and

¹³ Additional examples include Zech 4.2; Job 34.13.

attention to the specific morpho-syntactic features of each instance of *kol* NP (e.g., definiteness, number, countability, nominal status, specificity, individuation, inclusivity; see especially Naudé 2011a), we have provided evidence that Doron's arguments against a distributive use of *kol* cannot be accepted.

In future research, we will examine Doron's other arguments concerning *kol* in BH and its historical development in pre-modern Hebrew. In particular, we will examine her views that the definite article is not a determiner in BH, *kol* as a 'free choice determiner', mass nouns and *kol*, 'floated *kol*' and its distributive and universal usages, and maximality and homogeneity of *kol* (with implications for negated *kol* NP).

References

- Corbett, Greville G. 2000. *Number*. Cambridge Textbooks in Linguistics. Cambridge: Cambridge University Press.
- Doron, Edit. 2020. 'From a Collective to a Free Choice Determiner in Biblical Hebrew'. In *Quantification and Scales in Change*, edited by Remus Gergel and Jonathan Watkins, 1–31. Berlin: Language Science Press.
- Francez, Itamar, and Katja Goldring. 2012. 'Quantifiers in Modern Hebrew'. In *Handbook of Quantifiers in Natural Language*, edited by Edward L. Keenan and Denis Paperno, 347–97. Studies in Linguistics and Philosophy 90. Dordrecht: Springer Science. DOI 10.1007/978-94-007-2681-9_7

- GKC = Kautzsch, Emil (ed.). 1910. *Gesenius' Hebrew Grammar*. Translated by Arthur E. Cowley. 2nd English edition. Oxford: Clarendon.
- Gil, David. 1995. 'Universal Quantifiers and Distributivity'. In *Quantification in Natural Languages*, edited by Emmon Bach, Eloise Jelinek, Angelika Kratzer, and Barbara H. Partee, 321–62. Dordrecht: Kluwer Academic Publishers.
- . 1996. 'Universal Quantification in Hebrew and Arabic'. In *Studies in Afroasiatic Grammar: Papers from the Second Conference on Afroasiatic Languages, Sophia Antipolis, 1994*, edited by Jacqueline Lecarme, Jean Lowenstamm, and Uri Shlonsky, 105–22. The Hague: Holland Academic Graphics.
- Haspelmath, Martin. 1995. 'Diachronic Sources of "all" and "every"'. In *Quantification in Natural Languages*, edited by Emmon Bach, Eloise Jelinek, Angelika Kratzer, and Barbara H. Partee, 363–82. Dordrecht: Kluwer.
- . 1997. *Indefinite Pronouns*. Oxford: Oxford University Press.
- JM = Joüon, Paul, and Takamitsu Muraoka. 2006. *A Grammar of Biblical Hebrew*. 2nd edition. Subsidia Biblica 27. Rome: Pontifical Biblical Institute.
- Miller-Naudé, Cynthia L., and Jacobus A. Naudé. 2020a. 'A Programmatic Proposal for the Study of Biblical Hebrew as a Language'. *Journal for Semitics* 29/2: 29 pages. <https://doi.org/10.25159/2663-6573/9103>
- . 2020b. 'Negative Polarity in כֹּל Constructions in Qumran Hebrew'. *Dead Sea Discoveries* 27: 351–71.

- . 2021. 'Syntactic Patterns of $\pi\tilde{\alpha}\varsigma$ as a Quantifier in New Testament Greek'. *HTS Theologiese Studies/Theological Studies* 77/1: 9 pages. <https://doi.org/10.4102/hts.v77i1.6922>
- Naudé, Jacobus A. 2011a. 'The Interpretation and Translation of the Biblical Hebrew Quantifier KOL'. *Journal for Semitics* 22: 408–21.
- . 2011b. 'Syntactic Patterns of Quantifier Float in Biblical Hebrew'. *Hebrew Studies* 52: 121–36.
- . Forthcoming. 'Syntactic Features of *kōl* as a Polarity Item in Negative Statements'. In *'May You Favor the Work of His Hands': Essays in Memory of Michael Patrick O'Connor*. Atlanta: Scholars Press.
- Naudé, Jacobus A., and Cynthia L. Miller-Naudé. 2015. 'Syntactic Features of כֹּל in Qumran Hebrew'. In *Hebrew of the Late Second Temple Period: Proceedings of a Sixth International Symposium on the Hebrew of the Dead Sea Scrolls and Ben Sira*, edited by Eibert Tigchelaar and Pierre van Hecke, 88–111. *Studies on the Texts of the Desert of Judah* 114. Leiden: Brill.
- . 2022a. 'Unity and Diversity in Qumran Hebrew: Evidence from Quantification'. In *Emerging Sectarianism in the Dead Sea Scrolls: Continuity, Separation, and Conflict*, edited by John J. Collins and Ananda Geyser-Fouché, 78–115. *Discoveries in the Judean Desert* 141. Leiden: Brill.
- . 2022b. 'Generative Syntax and Septuagint Greek: A Preliminary Analysis of the Quantifier $\pi\tilde{\alpha}\varsigma$ '. In *The Septuagint South of Alexandria*, edited by Johann Cook and Gideon R.

- Kotzé, 431–64. *Vetus Testamentum Supplements* 193. Leiden: Brill and Atlanta: Society of Biblical Literature.
- . 2023. ‘Generative Linguistics as a Theoretical Framework for the Explanation of Problematic Constructions in Biblical Hebrew’. In *Linguistic Theory and the Biblical Text*, edited by William A. Ross and Elizabeth Robar, 6–66. *Cambridge Semitic Languages and Cultures* 19. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/obp.0358.01>
- Naudé, Jacobus A., Cynthia L. Miller-Naudé, and Daniel J. Wilson. 2019. ‘Trajectories of Diachronic Change in Qumran Hebrew: Evidence from the Negative Existential in Post-Predicate Position’. In *Scribal Practice, Text and Canon in the Dead Sea Scrolls: Essays in Memory of Peter Flint*, edited by John Collins and Ananda Geyser-Fouché, 273–96. *Studies on the Texts of the Desert of Judah* 130. Leiden: Brill.
- . 2022. ‘The Negative Existential Cycle in Ancient Hebrew’. In *The Negative Existential Cycle*, edited by Ljuba Veselinova Arja Hamari, 113–35. *Research on Comparative Grammar* 2. Berlin: Language Science Press.
- Propp, William H. C. 2006. *Exodus 19–40: A New Translation with Introduction and Commentary*. Anchor Bible. New York: Doubleday.
- Radford, Andrew. 1997. *Syntactic Theory and the Structure of English: A Minimalist Approach*. *Cambridge Textbooks in Linguistics*. Cambridge: Cambridge University Press.

- Van der Merwe, Christo H. J., Jacobus A. Naudé, and Jan H. Kroeze. 2017. *A Biblical Hebrew Reference Grammar*. 2nd edition. London: Bloomsbury.
- Van Gelderen, Elly. 2011. *The Linguistic Cycle: Language Change and the Language Faculty*. Oxford: Oxford University Press.
- Waltke, Bruce K., and M. O'Connor. 1990. *An Introduction to Biblical Hebrew Syntax*. Winona Lake, IN: Eisenbrauns.

KOL AS A UNIVERSAL QUANTIFIER IN BIBLICAL HEBREW*

Adina Moshavi

The determiner כָּל, which occurs approximately 5400 times in the Hebrew Bible, is one of the most versatile grammatical items in Biblical Hebrew (BH), with at least five apparently distinct uses. With a singular noun whose meaning involves physical or temporal extension, it can mean ‘the whole’, as in (1a).

(1a) וְשֵׁם־הַנָּהָר הַשֵּׁנִי גִיחוֹן הוּא הַסּוֹבֵב אֶת כָּל־אֶרֶץ כּוּשׁ:

‘The name of the second river is the Gihon. It is the one that flows around the whole land of Cush’. (Gen. 2.13 NRSV); ‘entire’ (NIV)

* It is a privilege to contribute to this paper to the Festschrift in honour of Geoffrey Khan, whose towering intellectual achievements and dedication to collaborative scholarship have fundamentally transformed the many intersecting worlds of research in which he participates. A previous version of this paper was presented at the Annual Meeting of the Society of Biblical Literature in Denver, Colorado, on 12 November 2022. My thanks go to Elitzur Bar-Asher Siegal and Nora Boneh for helpful conversations on the subject of this paper. My thanks also go to the anonymous reviewers, whose comments on an earlier draft spurred me to deepen the theoretical basis of the paper and thereby substantially improve the analysis.

The other uses, illustrated in (1b)–(1e), fall under the rubric of *quantification*, a term denoting the semantic function of determiners such as English *some*, *all*, *any*, *most*, etc. (Naudé 2011):¹

- (1b) וַיְהִי כָּל־יְמֵי אָדָם אֲשֶׁר־חָיָה תִּשְׁעַת מֵאוֹת שָׁנָה וּשְׁלֹשִׁים שָׁנָה
 ‘Thus **all the days that Adam lived** were 930 years. (Gen. 5.5 *ESV*)
- (1c) וַיֵּצֵא מִן־הָאֲדָמָה כָּל־עֵץ נֹחַמֵּד לְמַרְאֶה וְטוֹב לְמֵאֱכָל
 And out of the ground the LORD God made to spring up
 ‘**every tree that is pleasant to the sight and good for food.**’
 (Gen. 2.9 *ESV*)
- (1d) לֹא־תַעֲשֶׂה כָּל־מְלָאכָה
 ‘You shall not do **any work.**’ (Exod. 20.10 *ESV*)
- (1e) וְכָל־אֲשֶׁר יִקְרָאֵלּוּ הָאָדָם בְּנֶפֶשׁ חַיָּה הִוא שְׁמוֹ
 ‘And **whatever the man called every living creature**, that
 was its name.’ (Gen. 2.19 *ESV*)

In its ‘all’ (1b) and ‘every’ (1c) uses כָּל expresses *universal* quantification, indicating that a property or relation holds for all items in a particular set or group. The difference between the meaning of כָּל in the two sentences above is generally characterised as the difference between *distributive* and *collective* quantification: (1b) expresses that the total number of days that Adam lived was 930 years, and (1c) expresses that God created every (kind of) tree.

¹ Additional papers by Naudé and Miller-Naudé on כָּל are cited in §2.5, below. For a general discussion of determiners that express quantification, see Payne and Huddleston (2002, 358–97). On quantifiers in Modern Hebrew, see Goldring and Francez (2012); Netzer (2013).

In its ‘any’ reading (1d) כָּל expresses *existential* quantification, indicating the existence of at least one entity belonging to a particular set or group. In this use, כָּל is a *negative polarity item*, a type of word which is grammatical only in non-affirmative sentences (Pullum and Huddleston 2002, 834–38).² In its ‘whatever’ use (1d) כָּל expresses *free choice*, which involves ignorance and/or indifference (Pullum and Huddleston 2002, 832). This use often occurs in modal (1d) or generic clauses, and is frequently characteristic of phrases that are modified by relative clauses, as in (1e).

The present paper is concerned with כָּל as a universal quantifier, a use which occurs in a broader range of syntactic and semantic clause types than the existential and free choice uses. A central question regarding universal כָּל is its distributivity/collectivity in different syntactic environments. Hebraists widely agree that the universal quantifier כָּל is distributive when it quantifies an indefinite singular noun (כָּל-יֶלֶד) and collective when it quantifies a definite plural noun (כָּל-הַיְלָדִים); they disagree on its meaning with a definite singular noun (כָּל-הַיֶּלֶד) or with an indefinite plural (כָּל-יְלָדִים). Since the Modern Hebrew descendant of כָּל, *kol*, is grammatical only in the first two constructions, the question of how to understand its uses in the latter two constructions takes

² On this use of כָּל in BH, see Naudé and Rendsburg (2013); Naudé (f.c.); on a somewhat similar use of *kol* in Modern Hebrew, see Glinert (1982; 2013). On the Modern Hebrew quantifier *kolšehu* ‘any’ and its semantic development from Rabbinic Hebrew to Modern Hebrew, see Bar-Asher Siegal (2022).

on added significance. Another question is whether there are differences between the meanings of BH לָ and Modern Hebrew *kol* in their common syntactic environments.

This article takes a fresh look at the meaning of universal לָ in Classical Biblical Hebrew (CBH) prose, drawing on modern linguistic research on universal quantifiers in English, Modern Hebrew, and other languages. I will argue that לָ is always distributive with singular indefinite nouns, but can be distributive or collective with plural definite nouns. Furthermore, I will argue that the two constructions which are ungrammatical in Modern Hebrew, the definite singular לָ phrase and the indefinite plural לָ phrase, are not broadly productive constructions in BH either, but are restricted to certain non-prototypical noun classes and/or mismatches between morphosyntactic and semantic definiteness.

The structure of the paper is as follows: §1.0 presents essential theoretical background on the concepts of collective and distributive universal quantification. §2.0 surveys and evaluates views on universal לָ in the literature on BH. Research methods and definitions are described in §3.0, and a corpus-based analysis of CBH prose is presented in §4.0. Conclusions are summarised in §5.0.

1.0. Theoretical Background

1.1. Distributivity and Collectivity

Distributivity and collectivity are generally defined as pertaining to the relation between the predicate of a sentence and an argument denoting a set or group of two or more entities (generally a

plural or coordinated noun phrase).³ A predicate is distributive if it applies to each member of the set denoted by the subject/object, and is collective if it applies only to the set as a whole. For example, the predicate *smile* is always distributive, since smiling is an activity that can be performed only by an individual (e.g., 2a). Additional predicates that are always distributive include, e.g., *sleep*, *walk*, and *sing*. In contrast, the predicate *met* is collective, because the act of meeting can only be performed by a group of two or more individuals, e.g., (2b). Additional predicates that are always collective include, e.g., *gather*, *meet*, and *be numerous*.

(2a) *The girls smiled.*

(2b) *The girls met in the park.*

Distributive and collective predicates can be distinguished by the distinct logical entailments of the sentences in which they occur. For example, (3a) entails both *Kim smiled* and *Sandy smiled*, while (3b) entails neither **Kim met in the park* nor **Sandy met in the park*.

(3a) *Kim and Sandy smiled.*

(3b) *Kim and Sandy met in the park.*

A predicate can be collective with respect to one argument and distributive with respect to another. For example, *kill* is always distributive with respect to the object, but may be distribu-

³ Relevant linguistic studies on distributivity and collectivity include, among others, Taub (1989); Winter (2002); Brisson (2003); Tonciulescu (2011); De Vries (2017); Champollion (2020); Glass (2021).

tive or collective in relation to the subject. Thus (4) has two readings: in one the boys each killed different snakes, and in the second reading they killed the snakes together.

(4) *The boys killed two snakes.*

Adding a distributive marker (e.g., *each*) or collective marker (e.g., *together*) can eliminate one of the readings. *The boys each killed two snakes* has only the distributive reading and *The boys killed two snakes together* has only the collective reading.

1.2. Distributive and Collective Universal Quantification

Universal quantifiers are classified as distributive or collective depending on the relation between the predicate and the quantified noun which serves as an argument: when the predicate is collective/distributive, the quantifier is likewise said to be collective/distributive. As already mentioned, the presence of distributive or collective markers can force a particular interpretation of ambiguous predicates.

English has two universal quantifiers, *every* and *all*. *Every* is considered to be a distributive quantifier, because it occurs with distributive predicates, e.g., (5a), and is incompatible with collective predicates, e.g., (5b).⁴ *Every* is only compatible with indefinite singular nouns. While this would appear to contradict the statement above that distributivity (and collectivity) apply to

⁴ The discussion here is limited to the use of universal quantifiers with prototypical count nouns, i.e., nouns which inflect for number and denote individuated entities.

nouns denoting a set of entities, *every* pragmatically implicates that the quantified noun belongs to a set with more than two members (Huddleston and Pullum 2002, 379).

(5a) *Every girl smiled.*

(5b) **Every girl met in the park.*

While *every* is exclusively distributive, *all* cannot be simply characterised as collective. *All* quantifies plural nouns, both indefinite and definite. While *all* is compatible with some collective predicates, e.g., (6a),⁵ it resembles *every* in its compatibility with distributive predicates, e.g., (6b). In fact, there is no semantic difference between (5a), with *every*, and the corresponding sentence with *all* in (6b).

(6a) *All the girls gathered in the park.*

(6b) *All the girls smiled.*

According to Huddleston and Pullum's (2002, 377), *all* usually has a distributive interpretation, but does not exclude a collective interpretation. Gil (1995, 324) maintains that *all* is unmarked with respect to distributivity and collectivity, but this is hard to reconcile with the fact that, for many speakers, *all* forces a distributive reading of sentences with ambiguous predicates, like (7) (Champollion 2020).⁶

(7) *All the students wrote an essay.*

⁵ Other collective predicates, such as *be numerous*, are incompatible with both quantifiers: **Every girl/*all the girls were numerous*.

⁶ For other speakers both readings are possible (Taub 1989, 2; Gil 1995, 322).

1.3. The Modern Hebrew Universal Quantifier *kol*

Modern Hebrew has only one universal quantifier, *kol* (the descendent of the BH quantifier).⁷ When it quantifies an indefinite singular count noun, *kol* is compatible only with distributive predicates, as seen by contrasting (8a) with the ungrammatical (8b) (Shlonsky 1991; Haspelmath 1995, 379; Tonciulescu 2011, 79; Francez and Goldring 2012, 380). In this use it is equivalent to English *every*.

(8a)	<i>kol yeled hiyex.</i>	‘Every child smiled.’
(8b)	* <i>kol yeled nifgaš ba-parq.</i>	‘*Every child met in the park.’

When it quantifies definite plural nouns, *kol* can occur with distributive (9a) or collective predicates (9b). Here, too, *kol* appears to be equivalent to *all*. *Kol*, however, cannot quantify indefinite plurals as in (9c), unlike *all*, which is grammatical in such sentences.

(9a)	<i>kol ha-yeladim hiyxu.</i>	‘All the children smiled.’
(9b)	<i>kol ha-yeladim nifgešu ba-parq.</i>	‘All the children met in the park.’
(9c)	* <i>kol yeladim nifgešu ba-parq.</i>	‘All children met in the park.’

⁷ The discussion here does not address other uses of *kol*, which shares the same range of meanings exemplified in (1a), (1d), and (1e), above.

2.0. Previous Studies of the Biblical Universal Quantifier כָּל

This section briefly surveys the treatment of universal כָּל in the existing literature on BH.

2.1. GKC

According to GKC (§127b–c) the interpretation of כָּל depends exclusively on the definiteness of the quantified noun: with a definite noun (e.g., כָּל־הָאָדָם) the meaning of כָּל is ‘*the entirety*, i.e., *all, the whole*’. What we would call the collective use of the quantifier is viewed by GKC as closely linked to the original use of כָּל as a noun meaning ‘whole’. With an indefinite noun, according to GKC, כָּל means ‘any’ (the negative polarity use, not relevant for our purposes) or “distributively ‘each, every’”, e.g., כָּל־יְמֵי ‘every day’ (Ps. 7.12).⁸

GKC introduces, if only implicitly, a distinction between syntactic and semantic definiteness: it is noted that the collective use may lack the article in poetry, as in (10). The implication is that כָּל־בְּמֹות is semantically definite and therefore כָּל־בְּמֹות (בְּ) is collective.

⁸ A similar view is expressed in JM (§139e–h). BDB (כָּל) does not distinguish clearly between collectivity and distributivity, stating, for example, that the singular is collective with or without the article, but glossing some of the adduced examples as ‘every’.

(10) וַיִּקְטְרוּ־שָׁם בְּכָל־בָּמוֹת

‘and there they made offerings on **all the high places**’ (2 Kgs 17.11 *ESV*); ‘**every high place**’ (*NIV*)

GKC grapples with reconciling the assertion that indefinite כל phrases are distributive with the fact that כל is also used of indefinite non-count nouns, as in (11). The explanation offered is that when כל is combined with “singular nouns used collectively” (i.e., in this case, aggregate nouns), the distributive meaning of כל is extended to indicate “totality”.⁹

(11) כִּי־הִשְׁחִית כָּל־בָּשָׂר אֶת־דִּרְכּוֹ עַל־הָאָרֶץ: ס

‘for **all flesh** had corrupted its ways upon the earth.’ (Gen. 6.12 *NRSV*)

2.2. Brockelmann

Brockelmann (1956, 71) presents a different view in a brief discussion which does not explicitly invoke the concepts of collectivity and distributivity. In contrast to GKC, he asserts that number, rather than definiteness, is the conditioning factor of the interpretation of כל: with plural nouns כל means ‘alle’ and with singular nouns it means ‘jeder’.

⁹ Such a semantic change would be highly unexpected: Haspelmath’s (1995) crosslinguistic study identifies multiple languages in which a word meaning ‘whole’ changes to a universal quantifier meaning ‘all’, and a few languages, including Hebrew, in which a quantifier meaning ‘all’ changes to mean ‘every’, but does not cite any in which a quantifier meaning ‘every’ changes to ‘all’.

2.3. Bekins

Bekins (2014, 97) asserts briefly that both definiteness and number must be taken into account to determine whether כָּל is collective or distributive: when it is combined with indefinite singular nouns it is distributive, and in all other cases (i.e., definite plurals, definite singulars, and indefinite plurals) it is collective, and should be glossed ‘all’.¹⁰

2.4. Naudé and Miller-Naudé

Naudé and Miller-Naudé (Miller 2010; Naudé 2011a; 2011b; f.c.; Naudé and Miller-Naudé 2015; Miller-Naudé and Naudé 2020) observe that the biblical universal quantifier כָּל appears to have a broader syntactic distribution than Modern Hebrew *kol*: like the modern quantifier, כָּל can quantify indefinite singular nouns and definite plural nouns, but it can also occur in two constructions that are not compatible with modern *kol*: definite singular count nouns (12a) and indefinite plurals (12b).

(12a) כָּל־הָאֲזִכָּרִי יַעֲשֶׂה־בָּכָה אֶת־אֵלֶּה לְהַקְרִיב אֹשֶׁה רֵיחַ־נִיחֹחַ לְיְהוָה:
 ‘**Every native Israelite** shall do these things in this way, in offering a food offering, with a pleasing aroma to the LORD.’
 (Num. 15.13 *ESV*)

(12b) וַיִּקְטְרוּ־שָׁם בְּכָל־בָּמֹת
 ‘and there they made offerings on **all the high places**’ (2 Kgs 17.11 *ESV*); ‘**every high place**’ (*NIV*)

¹⁰ Bekin’s distributive example (Josh. 11.14), which he glosses ‘any’, is actually an instance of the existential (negative polarity item) use of כָּל.

In Naudé and Miller-Naudé's view the meaning of כל is only partially encapsulated by the distributive/collective opposition; an additional property, *individualisation* (a term that they do not define) is also relevant.¹¹ The distributivity versus collectivity of כל depends on the definiteness of the quantified noun, while individualisation depends on its number.¹² Their claims are as follows (glosses are theirs):

1. With a definite plural noun (כָּל-הַיְלָדִים 'all the children'), כל is collective and non-individualising, meaning 'the totality of'.
2. With a definite singular noun (כָּל-הַיֶּלֶד 'all the children'), כל is collective and individualised, meaning 'the totality of the individual members of the group'.¹³

¹¹ In Naudé (2011) a different (undefined) term, *specificity*, is used as a synonym for individualisation.

¹² It can be objected that individualisation is not intuitively different from distributivity; indeed GKC §127b appears to use the two terms synonymously. See also *BHRG* (309), where the parameter of individualisation is omitted, and both singular and plural indefinites are given the same gloss, 'each and every'.

¹³ As an example of this category Naudé and Miller-Naudé cite כָּל-יֶחֱבֹן הַיְּלֹד הַיִּזְרָה תִּשְׁלֹכֶהוּ וְכָל-חֶבֶת תִּחְיֶה (Exod. 1.22). The כל phrases in this verse, however, are in modal clauses, and are modified by relative clauses (in the second phrase elliptically), resulting in ambiguity between a universal and a free-choice rendering: 'Every Hebrew boy that is born (or: any Hebrew boy that is born) you must throw into the Nile, but let every girl (or: any girl) [that is born] live.' (*NIV*, round and square brackets mine).

3. With an indefinite singular noun (כָּל-יֶלֶד 'every child'), כָּל is distributive and individualised.¹⁴
4. With an indefinite plural noun (כָּל-יְלָדִים 'each and every child'), כָּל is distributive and non-individualised.

2.4. Interim Discussion

Comparing the four above views, we see that there is agreement that כָּל is collective when it quantifies a definite plural noun (כָּל-הַיְלָדִים), and is distributive when it quantifies an indefinite singular noun (כָּל-יֶלֶד).

The meaning of כָּל with a definite singular noun (כָּל-הַיֶּלֶד) is debated: according to GKC, Bekins, and Naudé and Miller-Naudé, it is collective, whereas in Brockelmann's view, it is distributive. The meaning of כָּל with an indefinite plural (כָּל-יְלָדִים) is also debated: according to GKC and Naudé and Miller-Naudé, it is distributive, whereas according to Bekins, it is collective. Naudé and Miller-Naudé's introduction of the concept of individualisation does not resolve this debate, since what it means for a phrase to be both collective and individualised is not explained. Nor are how individualised and non-individualised distributivity differ; their paraphrases ('the totality of the individual members';

¹⁴ In keeping with the assertion that כָּל with an indefinite singular noun is always distributive, Naudé (2011, 418) denies that an indefinite mass noun can be quantified by כָּל. Doron (2020, 9) points out that this assertion is incorrect, citing כָּסֶף וְזָהָב | וְכֹל 'but all silver and gold' (Josh. 6.19 *ESV*).

‘every’ versus ‘each and every’) are not of much help in this regard.¹⁵

GKC and Naudé and Miller-Naudé appear to view distributivity and collectivity as inherent properties of the noun phrase, rather than as depending on the predicate. Although Bekins understands collectivity and distributivity as properties which “affect the semantics of the event structure,” he does not demonstrate that each type of כָּל phrase is restricted to a particular kind of event structure.

2.5. Doron

Doron’s (2020) analysis of כָּל is radically different from the views discussed above. In her view, biblical כָּל is not a quantifier, but rather a degree determiner, denoting the entirety of a group or mass entity (i.e., ‘the whole set’).¹⁶ Definiteness and number are irrelevant to its interpretation, which is invariable.¹⁷ Doron does not deny that many sentences with כָּל, such as וַיִּשְׁקֶה לְכָל-אֶחָיו ‘and

¹⁵ See also Muraoka (2020, 172–73) for a critique of Naudé and Miller-Naudé with respect to Qumran Hebrew.

¹⁶ In the post-biblical period, according to Doron, the word developed into a distributive determiner, which was nonetheless not a quantifier. Doron’s definition of quantifiers is unusual, excluding determiners that serve as the syntactic heads of construct phrases, such as Modern Hebrew *kol* ‘all’, *rov* ‘most’, *še’ar* ‘the rest of’, etc. (for details, see Doron 1992). For the standard view that all of these Modern Hebrew determiners are quantifiers, see Francez and Goldring (2012); Netzer (2013).

¹⁷ It should be noted that, in Doron’s view, the article הַ does not mark definiteness in BH, but is an emphatic marker.

he kissed all his brothers' (Gen. 45.15), have a distributive meaning which can be conveyed by the English gloss 'every'. Rather, she claims that the property of distributivity is not conveyed by כל, but by some other element in the sentence, either overt or covert. The element can be a predicate that is inherently distributive with regard to a particular argument, e.g., הרג 'kill', which is distributive with relation to the object. Other elements which can convey distributivity include, e.g., the distributive adverb איש 'each', as in (13a), and lexical reduplication, as in (13b).

(13a) וַיִּכְרְתוּ גַם-כָּל-הָעָם אִישׁ שׁוֹכֵה

'So **every one of the people** also cut down his bundle (lit. also **all the people** cut down **each** his bundle)' (Judg. 9.49 *ESV*)

(13b) אֵלֶיךָ לַמִּטָּה אֵלֶיךָ לַמִּטָּה לְכָל מִטּוֹת יִשְׂרָאֵל תִּשְׁלְחוּ לַעֲבָדָא:

'You shall send a thousand from **each of the tribes of Israel** to the war (lit. a thousand **for a tribe**, a thousand **for a tribe**, **from all the tribes of Israel**).' (Num. 31.4 *ESV*)

The sense in which כל is 'collective' for Doron differs fundamentally from the way universal quantifiers such as *all* are collective: while a universal quantifier is collective only when the predicate is collective, for Doron כל is 'collective', i.e., denoting the entire set, even when the predicate is distributive. This surprising claim rests on the unorthodox assertion that the biblical word is a degree determiner meaning 'entirety (of a group)', rather than a universal quantifier. Against this is the fact that כל does not fit the standard definition of a degree determiner, i.e., a determiner that inflects for grade (comparison), like *many/more/most*. Moreover, in the standard view, degree determiners are

considered to be a type of quantifier, expressing so-called *multal* quantification (Huddleston and Pullum 2002, 365, 393). Yet another difficult aspect of Doron's position is the attribution of the meaning 'entirety of a group' to כל phrases with singular nouns.

3.0 Research Methods and Definitions

3.1. Delineation of the Corpus and Excluded Clause Types

The data for this analysis is restricted to classical BH prose (Genesis–Kings), henceforth CBH. Poetry, which has a tendency to omit the definite article and often pluralises abstract nouns which are always singular elsewhere, deserves a separate study. כל in Transitional and Late Biblical Hebrew awaits a separate study as well.

Sentences in which כל is open to an interpretation other than the universal one have been excluded. Negative sentences and other negative polarity contexts (primarily interrogatives and conditionals) have been systematically excluded, since כל generally has an existential ('any') interpretation in these contexts. Singular כל phrases in modal sentences expressing permission or obligation, e.g., (14a)–(14b), or in habitual past sentences, e.g., (14c), have been systematically excluded as well. In these types of sentences, the universal ('every/all') and free choice ('any', whatever') interpretations frequently have the same truth conditions, making it difficult to rule out the free

choice reading (see Doron 2020).¹⁸ When a phrase is modified by a relative clause, the free-choice reading is often likely even in non-habitual past tense sentences (14d).

(14a) מִכָּל עֵץ-הַגָּן אָכַל תֹּאכֵל:

‘You may surely eat of **every tree of the garden**.’ (Gen. 2.16 *ESV*); ‘**any**’ (*NIV*)

(14b) וַעֲתָה הָרְגוּ כָל-זָכָר בָּטָף וְכָל-אִשָּׁה יָדַעַת אִישׁ לְמִשְׁכַּב זָכָר הָרִגּוּ:

‘Now therefore, kill **every (= any) male among the little ones**, and kill **every (= any) woman who has known man by lying with him**.’ (Num. 31.17 *ESV*)

(14c) וַרְאָה שָׂאוּל כָּל-אִישׁ גִּבּוֹר וְכָל-בֶּן-חַיִּל וַיֹּאסְפֶהוּ אֵלָיו: ס

‘And when Saul saw **any strong man**, or **any valiant man**, he attached him to himself.’ (1 Sam. 14.52 *ESV*)

(14d) וַיָּבֹאוּ כָל-אִישׁ אֲשֶׁר-נִשְׁאָז לְבּוֹ

‘And they came, **everyone whose (= whoever’s) heart stirred him**’ (Exod. 35.21 *ESV*)

Occurrences in which כל may have the meaning ‘whole’, rather than universal quantification, include definite nouns that denote entities with physical or temporal extension, e.g., כָּל-הָאָרֶץ

¹⁸ This is also true for comparative כל phrases with a singular group noun, e.g., וַיִּגְבֹּה מִכָּל-הָעָם מִשְׁכְּמוֹ וּמִמְעָלָה ‘he was taller than **any of the people** from his shoulders upward’ (1 Sam. 10.23 *ESV*); ‘**all the people**’ (*NJPS*), as well as comparative phrases with a noun that has a pseudo-group use (see §3.2, below), such as וַיִּחָכֵם מִכָּל-הָאָדָם ‘For he was wiser than **all other men**’ (1 Kgs. 5.11 *ESV*); ‘**anyone else**’ (*NIV*). Comparative phrases with plural nouns do not seem to be ambiguous in this way, even though they can be translated with *any of*, e.g., וַיִּשְׂרָאֵל אֶהָב אֶת-יוֹסֵף מִכָּל-בָּנָיו ‘Now Israel loved Joseph more than **all his children**’ (Gen. 37.3 *KJV*); ‘more than **any other of his sons**’ (*ESV*).

‘all the land/the whole land’ (Gen. 13.9), and definite group nouns, e.g., בְּלִיקְהָל הָזֶה ‘all this congregation/this whole congregation’ (Exod. 16.3). When nouns such as עִיר ‘city’ and אֶרֶץ ‘land, world’ are used metonymously to refer to the inhabitants of a region, they behave like group nouns and exhibit the same ambiguity, e.g., וְכָל־הָאָרֶץ ‘and all the world/the whole world’ (Gen. 41.57).¹⁹

Also excluded are occurrences in which כָּל appears without an overt quantified noun, e.g., (15a), or is “floated” after the noun with a suffixed resumptive pronoun, e.g., (15b) (Naudé 2011).²⁰

(15a) בִּירֶק יַעֲשֶׂב נָתַתִּי לָכֶם אֶת־כָּל:

‘And as I gave you the green plants, I give you **everything**.’

(Gen. 9.3 *ESV*)

(15b) וְהָר סִינַי עָשָׂן כָּלֹ

‘Now Mount Sinai was **all** in smoke’ (Exod. 19.18 *JPS*)

3.2. Linguistic Categories

The first two subsections below present definitions of morpho-syntactic definiteness and number, as well as semantic aspects of

¹⁹ When the phrase has a definite singular group noun and is governed by partitive בֵּין, כָּל is not ambiguous, e.g., מִכָּל הָעָם הָזֶה שִׁבְעַת מֵאוֹת אִישׁ, ‘Among **all these** were 700 chosen men who were left-handed’ (Judg. 20.16 *ESV*).

²⁰ The latter construction is rare in classical prose; in all of its occurrences the determiner has the meaning ‘whole’ rather than universal quantification.

these concepts. The last subsection presents definitions of distributivity and collectivity.

3.2.1. Definiteness

A noun is morphosyntactically definite if it has the article, is a personal or demonstrative pronoun or a proper name, or is in construct with a definite noun or noun phrase. Definite direct objects are often governed by the direct object marker ל . A direct object that is governed by ל is characterised here as morphosyntactically definite even if it lacks other indications of definiteness.

A noun is semantically definite if it refers to an identifiable and/or unique entity in the context of the discourse.²¹ While the most common way for an expression to be semantically definite is through anaphoric reference (i.e., referring to an entity evoked in the preceding textual context), expressions can also be considered definite when they are identifiable based on world knowledge, or are conventionally associated with an entity or a situation evoked in the text, as in ‘the waiter’ in a text describing a meal at a restaurant. Although morphosyntactic and semantic definiteness generally coincide, nouns are occasionally morphosyntactically indefinite, but semantically definite.

3.2.2. Number and Noun Class

Number is defined here as a morphosyntactic category. In the case of a prototypical count noun, the singular form is the one

²¹ For further discussion of semantic definiteness in BH, see Bekins (2013).

that is morphologically unmarked (i.e., does not have a plural morpheme) and triggers singular verbal and pronominal agreement when functioning as the subject or antecedent of an anaphor, respectively. Plural forms have plural morphemes and trigger plural agreement; they can be quantified by numerals. The singular and plural forms of prototypical nouns also differ semantically, in that the singular refers to a single entity and the plural refers to multiple entities.

Number in the case of non-prototypical count nouns does not fit these neat patterns. *Uninflectable plural nouns*, e.g., BH בָּקָר ‘cattle’, are morphologically unmarked, but trigger plural verbal agreement and can be quantified by high numerals (Huddleston and Pullum 2002, 345); semantically, they refer to multiple entities.

The *group noun*, e.g., BH קָהָל ‘congregation’, denotes an individuated entity that is composed of multiple entities; it inflects for number like prototypical nouns, but verb and pronominal agreement rules vary from language to language (Corbett 2000, 187–90).²² BH is among the languages that allow morphologically singular group nouns to trigger either singular or plural agreement (JM §150e), unlike Modern Hebrew, which treats them as singular. We classify such BH forms as having *compound*, rather than singular number. From the semantic perspective, sin-

²² I avoid the term *collective noun* sometimes applied to group nouns in order to avoid confusion with the concept of collectivity as discussed in this paper. Group nouns can be distributive or collective depending on the predicate of the sentence.

gular group nouns have both singular and plural aspects, designating a single entity that is comprised of multiple entities. Plural group nouns refer to multiple groups of entities.

The concept of compound number is also relevant to BH nouns whose morphologically singular forms have a *quasi-group* use that refers to multiple individuals, in addition to a prototypical use. These are mostly nouns referring to well-established categories of people, e.g., אִישׁ ‘a man/people’ in phrases such as אִישׁ יִשְׂרָאֵל ‘a man/the men of Israel’; נָפֶשׁ ‘a person/people’; זָכָר ‘male/males’ (JM §135). A singular quasi-group noun can trigger either singular or plural agreement, just like a group noun. In the plural, quasi-group nouns differ from group nouns in that they refer to a single group of individuals, e.g., אֲנָשֵׁי יְהוּדָה ‘the men of Judah’.

Number is inapplicable to non-count nouns, which constitute a separate class with several sub-types (Huddleston and Pullum 2002, 335–39). They are generally morphologically unmarked for number, are uninflectable, trigger singular agreement, and are not able to be quantified by numerals.²³ Three types occurring in the biblical corpus are *mass nouns*, which denote a substance rather than an entity, e.g., זָהָב ‘gold’; *uninflectable abstract nouns*, e.g., מְלָאכָה ‘work’, which occur only in

²³ An exception is the non-count מַיִם ‘water’, which is uninflectable like other non-count nouns, but is morphologically plural and triggers plural agreement.

the singular;²⁴ and *aggregate nouns*, which denote a collection of objects belonging to a functional category, e.g., רְכוּשׁ ‘goods’.

Non-count nouns differ from count nouns in their compatibility with universal quantification. For example, Modern Hebrew universal *kol* can quantify definite non-count nouns, e.g., **kol ha-sukar matoq* ‘all the sugar is sweet’,²⁵ even though it cannot quantify definite singular count nouns, e.g., **kol ha-yeled ĥiyex* ‘*all the child smiled’. Furthermore, *kol* cannot quantify indefinite non-count nouns, e.g., **kol sukar matoq* ‘*all sugar is sweet’, despite the fact that it can quantify indefinite count nouns, e.g., *kol yeled ĥiyex* ‘every child smiled’ (Francez and Goldring 2012, 392). In the analysis below we will examine whether there are differences between the biblical כָּל and modern *kol* in their compatibility with non-count nouns.

3.2.3. Distributivity and Collectivity

A universal כָּל phrase in a particular sentence in its context is classified as distributive if the predicate applies separately to each individual referred to by the noun phrase; otherwise, it is

²⁴ Some of these nouns occur in the plural in poetry or late texts; if their only occurrences in CBH is in the singular, they are assumed here to be uninflectable.

²⁵ The Hebrew sentence with the mass noun is ambiguous: it can be interpreted as a generic sentence describing a property of sugar, or a predication with respect to a particular quantity of sugar; in English, in contrast, the generic reading is available only when the quantified noun is indefinite, e.g., *all sugar is sweet*.

collective. Distributivity is confirmed by a translation test: when the predicate is distributive, כל can be appropriately rendered ‘every’, assuming the necessary adjustments of definiteness and number are made.

4.0. Analysis of the Data

4.1. Indefinite Singular כל phrases

There are relatively few indefinite singular כל phrases with prototypical count nouns in our corpus; illustrative examples follow.²⁶

- (16a) וַיֵּצֵאֵם יְהוָה אֱלֹהִים מִן־הָאֲדָמָה כָּל־עֵץ נָחֵמַד לְמִרְאָה וטוֹב לְמֶאֱכֹל
 ‘And out of the ground the LORD God made to spring up every tree that is pleasant to the sight and good for food’ (Gen. 2.9 *ESV*); cited above as (1c)²⁷
- (16b) כִּי־עָצָר עָצָר יְהוָה בָּעֵד כָּל־רָחִם לְבֵית אֲבִימֶלֶךְ
 ‘For the LORD had closed all the wombs of the house of Abimelech’ (Gen. 20.18 *ESV*); ‘every womb’ (*NJPS*)
- (16c) וְכָל־אִשָּׁה חֲכַמַּת־לֵב בִּידֶיהָ טָווּ
 ‘And every skillful woman spun with her hands’ (Exod. 35.25 *ESV*)

The indefinite singular כל phrases in the corpus, in the morphosyntactic sense of number defined above, are all distributive. While there are collective phrases with nouns that are unmarked

²⁶ The other occurrences are Gen. 7.14; 20.18; Exod. 35.22; Num. 8.16; 18.21; 31.51; Deut. 3.6; 1 Sam. 4.8; 2 Kgs 17.13.

²⁷ Additional indefinite singular occurrences referring to kinds are Gen. 7.14 and Exod. 35.22.

for plural inflection, these are all used in a pseudo-group sense, i.e., *נָפֶשׁ* ‘people’, e.g., (17a), *זָכָר* ‘males’, e.g., (17b), or *בְּכוֹר* ‘firstborn’, e.g., (17c).²⁸ Significantly, all the phrases are semantically definite, referring to already-mentioned entities, e.g., (17a) or entities that are inferable from known entities, e.g., (17b) and (17c). The semantic definiteness of the phrases is typically reflected in the use of syntactically definite renderings in the translations.

(17a) אֵלֶּה בְּנֵי רָחֵל אֲשֶׁר יָלַד לְיַעֲקֹב כָּל-נֶפֶשׁ אַרְבָּעָה עָשָׂר:

‘These are the sons of Rachel, which were born to Jacob: **all the souls** were fourteen.’ (Gen. 46.22 KJV) (≠ every soul)

(17b) פְּקֻדֵיהֶם בְּמִסְפָּר כָּל-זָכָר מִבֶּן-חֹדֶשׁ וּמַעֲלָה פְקֻדֵיהֶם שִׁבְעָת אֲלָפִים וַחֲמִשׁ
מֵאוֹת:

‘Their listing according to the number of **all the males** from a month old and upward was 7,500.’ (Num. 3.22 ESV) (≠ every male)

(17c) וַיְהִי כָל-בְּכוֹר זָכָר בְּמִסְפָּר שְׁמוֹת מִבֶּן-חֹדֶשׁ וּמַעֲלָה לְפְקֻדֵיהֶם שְׁנַיִם וְעֶשְׂרִים
אֲלֶף שְׁלֹשָׁה וּשְׁבַעִים וּמֵאוֹת: פ

‘And **all the firstborn males**, according to the number of names, from a month old and upward as listed were 22,273.’ (Num. 3.43 ESV) (≠ every firstborn male)

The above data indicate that Modern Hebrew and BH do not differ with respect to the distributivity/collectivity of singular indefinite כל phrases: both restrict such phrases to distributive

²⁸ The other occurrences with pseudo-group nouns are Gen. 46.22, 25, and 26; Exod. 1.5; Num. 3.12, 22, 28, 34, 39, 41, 43; 8.18; 26.62; 31.35.

meaning. The fact that כל phrases with semantically definite pseudo-group nouns are able to be collective is explainable on the basis of their syntactic and semantic resemblance to definite plural כל phrases, which, as discussed below, can be distributive or collective.

Notably, the CBH corpus also contains כל phrases with indefinite non-count nouns, as in the non-inflectable abstract noun מְלָאכָה ‘work’ in (18a)²⁹ and the aggregate noun בָּשָׂר ‘flesh’ (= living things) in (18b). This usage of כל differs from Modern Hebrew, where, as noted above, such phrases are ungrammatical.

(18a) וַיִּמְלֵא אֱתוֹ רוּחַ אֱלֹהִים בְּחָכְמָה בְּתַבּוּנָה וּבְדַעַת וּבְכָל-מְלָאכָה:
 ‘and he has filled him with the Spirit of God, with skill, with intelligence, with knowledge, and with **all craftsmanship**’
 (Exod. 35.31 *ESV*)

(18b) כִּי-הִשְׁחִית כָּל-בָּשָׂר אֶת-דִּרְכּוֹ עַל-הָאָרֶץ:
 ‘for **all flesh** had corrupted its ways upon the earth.’ (Gen. 6.12 *NRSV*); cited above as (11)

4.2. Definite Plural כל Phrases

Definite plural כל phrases are very common in the corpus; they frequently involve prototypical nouns, and can be distributive or collective. In all these respects CBH exhibits no differences from

²⁹ Additional indefinite uninflectable abstract nouns quantified by כל are טוב ‘goodness’ (Deut. 6.11); מְלָאכָה ‘handiwork’ (Exod. 35.31); עֲבָדָה ‘labour’ (Exod. 1.14); עֵת ‘time’ (e.g., Exod. 18.22).

Modern Hebrew. The following are representative examples with distributive meaning.³⁰

- (19a) וַתֵּצֵאֶן כָּל־הַנָּשִׁים אַחֲרֶיהָ
 ‘and **all the women** went out after her’ (Exod. 15.20 *ESV*)
 (= every woman)
- (19b) וַיִּקְמוּ כָל־בָּנָיו וְכָל־בָּנוֹתָיו לְנַחֲמוֹ
 ‘**All his sons** and **all his daughters** rose up to comfort him’
 (Gen. 37.35 *ESV*) (= every son... every daughter)
- (19c) וַיָּבֹאוּ כָל־נְשֵׂאֵי הָעֵדָה
 ‘And when **all the leaders of the congregation** came’ (Exod. 16.22 *ESV*) (= every leader)
- (19d) וַיִּנָּשֶׁק לְכָל־אָחָיו
 ‘And he kissed **all his brothers**’ (Gen. 45.15 *ESV*) (= every brother)

³⁰ Additional distributive examples include, e.g., Gen. 7.11; 17.23, 27; 35.4; 45.15; 50.7 (2x); Exod. 9.14; 34.30; 35.13, 16; 38.3, 30, 31; 39.37, 39; Num. 15.40; 16.10; 17.21; Deut. 2.34; Josh. 3.1; 11.4; Judg. 9.3 (2x), 46, 51, and many additional occurrences. Definite plural כל phrases governed by comparative מן are generally distributive, e.g., וַיִּשְׂרָאֵל אֶהָב אֶת־יוֹסֵף מִכָּל־בָּנָיו ‘Now Israel loved Joseph more than **all his children**’ (Gen. 37.3 *KJV*) presumably means that Israel loved Joseph more than each of his other sons, not that he loved him more than all of his other sons put together.

Illustrative collective examples are shown below.³¹

- (20a) כָּל־מִשְׁפַּחַת הַשּׁוּחַמִּי לְפָקְדֵיהֶם אַרְבַּעַה וְשָׁשִׁים אָלֶף וְאַרְבַּע מֵאוֹת: ס
 ‘All the clans of the Shuhamites, as they were listed, were 64,400.’ (Num. 26.42 *ESV*) (≠ every clan)
- (20b) כָּל־עָרֵי בְנֵי־אֶהֱרֹן הַכֹּהֲנִים שְׁלֹש־עֶשְׂרֵה עָרִים וּמִגְרָשֵׁיהֶן: ס
 ‘The cities of the descendants of Aaron, the priests, were in all thirteen cities with their pasturelands.’ (Josh. 21.19 *ESV*) (≠ every city)
- (20c) וּבָדָךְ בָּחַר יְהוָה לְהִיזֹת לוֹ לְעָם סְגֻלָּה מִכָּל הָעַמִּים
 ‘For the LORD your God has chosen him out of all your tribes’ (Deut. 18.5 *ESV*)

4.3 Definite Singular כָּל Phrases

This construction, which is ungrammatical in Modern Hebrew, is scarcely attested in CBH, contrary to initial impressions.³² While there are many definite כָּל phrases in the corpus that are singular

³¹ Additional collective occurrences serving as subjects include, e.g., Gen. 5.5, 8, 11, 14, 17, 20, 23, 27, 31; 9.29, Num. 1.45, 46; 2.9, 16, 24, 31 (and many similar occurrences in passages following); 26.43; 35.7; Josh. 10.6. Also collective is a כָּל phrase in Gen. 40.20 designating multiple beneficiaries. Partitive phrases like (21c) are collective as well, e.g., Exod. 19.5; Deut. 7.6; 12.5; 29.20; 1 Sam. 2.28; 2 Sam. 10.9; 1 Kgs 5.4, 14; 11.32; 14.21.

³² Many occurrences of כָּל phrases with definite singular nouns are ambiguous between the universal and free-choice interpretations (see discussion in §3.1, above), and are therefore excluded from the data. Of the eligible clauses that might have been included in this category, many are not actually morphosyntactically singular, as detailed below.

in the sense that they are unmarked for plural inflection, unambiguous cases of the morphosyntactic singular according to the definition presented above are vanishingly rare in this construction.³³ The only occurrence I have found is *אֶת-כָּל-עִיר* ‘every city’, in (21), which is definite because it is governed by the object marker.³⁴

- (21) וְנָלְכָד אֶת-כָּל-עִרֵינוּ בְּעֵת הַהוּא וְנַחֲרֵם *אֶת-כָּל-עִיר* מֵתָם וְהַנָּשִׁים וְהַטָּף
 ‘And we captured all his cities at that time and devoted to destruction *every city*, men, women, and children.’ (Deut. 2.34 *ESV*)³⁵

The other occurrences which might have been thought to provide evidence of this construction are not unambiguously singular in the morphosyntactic sense defined above. Many involve non-count nouns, to which the category of number is inapplicable. For example, there are several phrases with mass nouns such as *עָפָר* ‘dust’, e.g., (22a).³⁶ Many have uninflectable abstract

³³ While *כל* with a suffixed pronoun satisfies the conditions for this category, in all these occurrences the meaning is ‘whole’ rather than universal quantification (e.g., Exod. 25.36).

³⁴ The Targum translates *ית כל קרויא* ‘all the cities’. The Samaritan Pentateuch has *ערינו* ‘his cities’ instead of *עיר*. Deut. 2.34 can be compared to the similar Deut. 3.6, which has an indefinite phrase *כָּל-עִיר* ‘every city’, without the object marker.

³⁵ A reviewer suggests that *אֶת* here might be the comitative preposition ‘with’ rather than the object marker; in that case the *כל* phrase would be indefinite.

³⁶ Other mass nouns occurring in definite *כל* phrases include, e.g., *דָּם* ‘blood’ (Exod. 29.12); *זָהָב* ‘gold’ (e.g., Num. 7.86); *כֶּסֶף* ‘silver’ (e.g., Num. 7.85); *עָפָר* ‘dust’ (Exod. 8.13); *עֵשֶׂב* ‘grass’ (e.g., Exod. 10.15). As

nouns, such as מְלָאכָה ‘work’, e.g., (22b),³⁷ or aggregate nouns, such as רְכָשׁ ‘goods’, e.g., (22c).³⁸ A few occurrences involve uninflectable plural nouns, such as צֹאן ‘sheep’, e.g., (22d).³⁹ The last example is distributive.

noted above, definite singular mass nouns can be quantified in Modern Hebrew with *kol* as well, despite the fact that this construction is ungrammatical with count nouns.

³⁷ Other apparently uninflectable abstract nouns occurring in definite בָּל phrases include (not a comprehensive list; includes concrete applications of the abstract meaning): אֱמֶת ‘truth’ (Gen. 32.11); חֵכְמָה ‘wisdom’ (e.g., 1 Kgs. 10.4); חֲמֻדָּה ‘desire’ (1 Sam. 9.20); חֶפְצִי ‘delight’ (e.g., 1 Kgs 5.24); חֶשֶׁק ‘desire’ (1 Kgs 9.1); טוֹב ‘goodness’ (e.g., 2 Kgs 8.9); מְלָאכָה ‘work’ (e.g., 1 Kgs 7.14); מַעֲשֶׂה ‘deed, work’ (e.g., Deut. 2.7); נְבִלָה ‘disgraceful folly’ (Judg. 20.10); עֲבֹדָה ‘labour’ (e.g., Num. 3.26); עֲצָה ‘advice’ (e.g., 2 Sam. 16.23); תְּלָאָה ‘hardship’ (e.g., Exod. 18.8).

³⁸ Other aggregate nouns occurring in definite בָּל phrases include (not a comprehensive list): אֹכֶל ‘food’ (e.g., Gen. 14.11); זֶרַע ‘seed, offspring’ (e.g., Gen. 46.6); חֵיל ‘wealth’ (e.g., Num. 31.9); לֶחֶם ‘bread’ (Josh. 9.5); מִלְקוֹחַ ‘booty’ (Num. 31.11); פֵּרִי ‘fruit’ (e.g., Exod. 10.15); רֶכֶב ‘chariotry’ (e.g., Judg. 4.15); שָׁלַל ‘spoil, plunder’ (e.g., Num. 31.11). On nouns which may or may not belong in this category see fn. 39, below.

³⁹ Another uninflectable plural noun is בָּקָר ‘cattle’ (e.g., Num. 7.87). There is insufficient evidence to determine whether the following animal terms are aggregate nouns or uninflectable plural nouns: בְּהֵמָה ‘beasts’ (e.g., Gen. 8.1); חַיָּה ‘animals’ (e.g., Gen. 2.20); מִקְנֵה ‘cattle’ (e.g., Gen. 31.18); עוֹף ‘birds’ (e.g., Gen. 2.19); גְּרֵמֶשׂ ‘creeping things’ (e.g., Gen. 1.25). הָ ‘children’ (e.g., Gen. 34.29) does not fit neatly into either category, as it variously triggers singular or plural agreement (both occurring together in Num. 14.31).

- (22a) כָּל־עֹפֶר הָאָרֶץ הָיָה כְּנִים בְּכָל־אֶרֶץ מִצְרַיִם:
 ‘All the dust of the earth became gnats in all the land of Egypt. (Exod. 8.13 *ESV*)
- (22b) וַיֵּרָא מֹשֶׁה אֶת־כָּל־הַמְּלָאכָה
 ‘And Moses saw all the work’ (Exod. 39.43 *ESV*)
- (22c) וַיָּשָׁב אֶת כָּל־הָרֶכֶשׁ
 ‘Then he brought back all the possessions’ (Gen. 14.16 *ESV*)
- (22d) וַיֵּלְדוּ כָּל־הָעֶזְאָן נִקְדָּיִם
 ‘all the flock bore spotted’ (Gen. 31.8 *ESV*)

Another group of purportedly singular phrases involves nouns which have a pseudo-group use; the pseudo-group reading is variously certain or at least possible, depending on the context. For example, the plural verb in (23a) establishes that the singular subject, כָּל־אִישׁ יִשְׂרָאֵל, is used in its pseudo-group meaning and, therefore, has compound number. This example is distributive.⁴⁰ In (23b), the pseudo-group reading is forced by a collective predicate. In (23c) the singular verb creates ambiguity between the pseudo-group reading (‘all the men of Israel’) and the prototypical use (‘every man of Israel’); both readings are distributive.

- (23a) וַהֲגֵה כָּל־אִישׁ יִשְׂרָאֵל בָּאִים אֶל־הַמֶּלֶךְ
 ‘Then all the men of Israel came to the king’ (2 Sam. 19.42 *ESV*) (= every man of Israel)

⁴⁰ Other distributive occurrences with אִישׁ are Judg. 20.33; 1 Sam. 31.12; 2 Sam. 19.42. A distributive occurrence with בְּכֹר ‘firstborn’ is Num. 3.42.

(23b) כָּל-נַפְשׁ בָּנָיו וּבָנוֹתָיו שְׁלֹשִׁים וְשָׁלֹשׁ:

‘all the souls of his sons and his daughters were thirty and three.’ (Gen. 46.15 KJV)⁴¹ (≠ every soul)

(23c) וַיַּעַל כָּל-אִישׁ יִשְׂרָאֵל מֵאַחֲרֵי דָוִד

‘So every man of Israel went up’ (2 Sam. 20.2 KJV); ‘all the men of Israel’ (ESV)⁴²

The last group of purportedly singular phrases involves proper names of nations (24a)–(24b). Such names have compound number and are inherently definite. The first illustrative example is distributive and the second collective.

(24a) וַיְהוֹשֻׁעַ וְכָל-יִשְׂרָאֵל רָאוּ כִּי-לָכַד הָאֲרָב אֶת-הָעִיר

‘And when Joshua and all Israel saw that the ambush had captured the city’ (Josh. 8.21 ESV) (= every person in Israel)

(24b) וַיִּקַּח שָׁאוּל שְׁלֹשֶׁת אֲלָפִים אִישׁ בְּחֹרֶם מִכָּל-יִשְׂרָאֵל

‘Then Saul took three thousand chosen men out of all Israel’ (1 Sam. 24.3 ESV) (≠ every person in Israel)

The almost complete absence of definite כל phrases with morphosyntactically singular nouns in the corpus indicates that this construction is not productive in CBH, presenting no contrast

⁴¹ Other collective occurrences with definite singular נַפְשׁ are Gen. 46.27 and Exod. 1.5.

⁴² When the כל phrase is the subject of a singular verb (e.g., Judg. 7.24) or functions as object (e.g., Josh. 10.24), it is usually impossible to distinguish the quasi-group and prototypical readings. An additional ambiguous structure is the כל phrase which is a constituent in a coordinated subject in a sentence with a plural verb, e.g., סוס ‘horse/s’ (Exod. 14.23; Deut. 29.9) סוס has a quasi-group use in military contexts, often appearing in coordination with the aggregate noun רֶכֶב ‘chariots’).

with Modern Hebrew in this respect. The fact that definite pseudo-group nouns and names of nations can occur with לַל is most likely due to their compound, rather than truly singular number. As we have already seen, the definite plural לַל phrase is a highly productive construction. Like the latter, the definite compound-number לַל phrase can be either distributive or collective. It is worth remembering that while definite mass nouns can be quantified by לַל in CBH, this is true of modern *kol* as well.

4.4. Indefinite Plural לַל Phrases

This construction, ungrammatical in Modern Hebrew, is extremely rare in the CBH corpus. Only one occurrence involves a semantically indefinite noun phrase:⁴³

⁴³ While Rashi explains this to mean ‘instruments made out of wood’, modern scholars widely emend it to בכל עז ובשירים ‘with all (his) might’ or בכלי עז ‘with mighty instruments. The former emendation is based on v. 14 in the same chapter, the parallel to our verse in 1 Chron. 13.8, which has בְּכָל־עֵז וּבְשִׁירִים, and 4QSam^a, with essentially the same text as Chronicles. The latter emendation is based on the LXX. According to the first emendation, the לַל phrase involves a non-count abstract noun, and according to the second emendation, there is no לַל phrase.

- (25) וְדָוִד | וְכָל־בֵּית יִשְׂרָאֵל מְשַׁחֲקִים לִפְנֵי יְהוָה בְּכָל עֵצֵי בְרוֹשִׁים וּבִכְנֹרוֹת
וּבִנְבָלִים וּבַתְּפִילִּים וּבִמְנַנְעִים וּבַצִּלְצְלִים:

‘And David and all the house of Israel played before the LORD on **all manner of instruments made of fir wood**, even on harps, and on psalteries, and on timbrels, and on cornets, and on cymbals.’ (2 Sam. 6.5 KJV) (= on every kind of instrument)

The other seven definite plural כל phrases I am aware of appear to be semantically definite, and are typically translated with a definite noun phrase. Four occurrences refer to lists of entities appearing immediately earlier in the texts, as in כל־עָרִים ‘all (the) cities’ in (26a), which provides a sum of all the cities previously listed;⁴⁴ all four are collective. The occurrence in (26b) refers to multiple entities, בְּכָל־בָּמֹת ‘all (the) high places’ that have been repeatedly mentioned throughout the passage, most recently two verses earlier. This example is distributive.

- (26a) כָּל־עָרִים עֶשְׂרִים וְתִשְׁעַ וְחִצְרֵיהֶן: ט
‘**all the cities** are twenty and nine, with their villages’ (Josh. 15.32 KJV) (≠ every city)

- (26b) וַיִּקְטְרוּ־שָׁם בְּכָל־בָּמֹת
‘And there they made offerings on **all the high places**’ (2 Kgs 17.11 ESV); ‘at **every high place**’ (NIV)

The rarity of prototypically indefinite plural כל phrase indicates that it is not a productive construction in CBH. Since almost all of the few phrases with this structure are semantically definite, they are presumably a variation of the highly productive

⁴⁴ The others are Josh. 21.26, 39, both with עָרִים ‘the cities’, and Josh. 12.24, with מְלָכִים ‘the kings’.

definite plural construction, which, as seen above, can be distributive or collective.

5.0 Conclusions

This article has drawn new conclusions regarding the classification of לָּ in different syntactic constructions in CBH prose. These results are the product of the following research methods and procedures, which, taken together, distinguish the present study from existing literature on the subject:

1. Corpus-based analysis
2. Isolating universal לָּ from other uses of the determiner
3. Distinguishing between number in prototypical and non-prototypical count nouns
4. Distinguishing between morphosyntactic and semantic definiteness
5. Defining distributivity and collectivity based on the relation between the לָּ phrase and the meaning of the sentence in which it occurs

It has been demonstrated that biblical לָּ has the same meaning as modern *kol* in their common syntactic environments: לָּ is distributive with singular indefinite nouns, and can be distributive or collective with plural definite nouns. Obscuring the former rule is the common phenomenon of pseudo-group nouns that are semantically definite appearing in לָּ phrases. The fact that such phrases can be collective can be explained by their syntactic and semantic resemblance to definite plural לָּ phrases.

It has further been demonstrated that the two constructions that are ungrammatical in Modern Hebrew, i.e., the definite singular phrase and the indefinite plural phrase, are not productive constructions in CBH prose either. Almost all the definite singular לָ phrases in the corpus require or admit a pseudo-group use interpretation, or are names of nations; both types, therefore, resemble the plural לָ phrase from the syntactic and the semantic perspective. The few indefinite plural לָ phrases in the corpus are best understood as variations of definite plural לָ phrases, since they are nearly always semantically definite. Like the definite plural phrase, they, too, can be distributive or collective.

Finally, a difference between the biblical and modern universal quantifiers was identified, namely that only biblical לָ can be used with indefinite non-count nouns.

References

- Bar-Asher Siegal, Elitzur. 2022. 'Kolšehu: From Rabbinic Hebrew to Modern Hebrew'. *Leshonenu* 84: 110–43.
- BDB = 1979. *The New Brown-Driver-Briggs-Gesenius Hebrew-English Lexicon*. Peabody, MA: Hendrickson.
- Bekins, Peter. 2013. 'Non-prototypical Uses of the Definite Article in Biblical Hebrew'. *Journal of Semitic Studies* 58/2: 225–40.
- . 2014. *Transitivity and Object Marking in Biblical Hebrew: An Investigation of the Object Preposition 'et*. Winona Lake, IN: Eisenbrauns.

- BHRG* = van der Merwe, C. H. J., Jacobus A. Naudé, and Jan H. Kroeze. 2017. *A Biblical Hebrew Reference Grammar*. 2nd edition. London: Bloomsbury T and T Clark.
- Brisson, Christine. 2003. 'Plurals, *all*, and the Nonuniformity of Collective Predication'. *Linguistics and Philosophy* 26/2: 129–84.
- Brockelmann, Carl. 1956. *Hebraische Syntax*. Neukirchen: Moers.
- Champollion, Lucas. 2020. 'Distributivity, Collectivity and Cumulativity'. In *The Wiley Blackwell Companion to Semantics*, edited by Daniel Gutzmann et al. Wiley Online Library.
- Corbett, Greville G. 2000. *Number*. Cambridge Textbooks in Linguistics. Cambridge, UK: Cambridge University Press.
- De Vries, Hanna. 2017. 'Two Kinds of Distributivity'. *Natural Language Semantics* 25/2: 173–97.
- Doron, Edit. 1992. 'The Structure of the Noun Phrase'. In *Hebrew Computational Linguistics: Papers Presented at Seminars Held in 1988, 1989, 1990*, edited by Uzi Ornan, Edit Doron, and Gideon Arieli, 116–21. Israel: Ministry of Science and Technology. [Hebrew]
- . 2020. 'From a Collective to a Free Choice Determiner in Biblical Hebrew'. In *Quantification and Scales in Change*, edited by Remus Gergel and Jonathan Watkins, 1–31. Berlin: Language Science Press.
- Francez, Itamar, and Katja Goldring. 2012. 'Quantifiers in Modern Hebrew'. In *Handbook of Quantifiers in Natural Language*, edited by Edward Keenan and Denis Paperno, 347–97. Dordrecht: Springer.

- Gil, David. 1995. 'Universal Quantifiers and Distributivity'. In *Quantification in Natural Languages*, edited by Emmon W. Bach, 321–62. Dordrecht: Springer and Kluwer.
- Glass, Lelia. 2021. 'The Lexical and Formal Semantics of Distributivity'. *Glossa: A Journal of General linguistics* 6/1: 1–28. <https://doi.org/10.5334/gjgl.1137>
- GKC = *Gesenius' Hebrew Grammar*. 1910. Edited by Emil Kautzsch. 2nd edition. Translated by Arthur E. Cowley. Oxford: Clarendon.
- Glinert, Lewis. 1982. 'Negative and Non-Assertive in Contemporary Hebrew'. *Bulletin of the School of Oriental and African Studies* 45: 434–70.
- . 2013. Negation: Modern Hebrew'. In *Encyclopedia of Hebrew Language and Linguistics*, edited by Geoffrey Khan, et al. http://dx.doi.org/10.1163/2212-4241_euhl_EHLL.COM.00000318
- Haspelmath, Martin. 1995. 'Diachronic Sources of "all" and "every"'. In *Quantification in Natural Languages*, edited by Emmon W. Bach, 363–82. Dordrecht: Springer and Kluwer.
- JM = Joüon, Paul, and Takamitsu Muraoka. 2009. *A Grammar of Biblical Hebrew*, 2nd edition. Subsidia Biblica 27. Rome: Pontifical Biblical Institute Press.
- Miller, Cynthia L. 2010. 'Definiteness and the Vocative in Biblical Hebrew'. *Journal of Northwest Semitic Languages* 36/1: 43–64.
- Miller-Naudé, Cynthia L., and Jacobus Naudé. 2020. 'Negative Polarity in כֹּל Constructions in Qumran Hebrew'. *Dead Sea Discoveries* 27: 351–71.

- Muraoka, Takamitsu. 2020. *A Syntax of Qumran Hebrew*. Leuven: Peeters.
- Naudé, Jacobus A. 2011a. 'The Interpretation and Translation of the Biblical Hebrew Quantifier *KOL*'. *Journal for Semitics* 20/2: 408–21.
- . 2011b. 'Syntactic Patterns of Quantifier Float in Biblical Hebrew'. *Hebrew Studies* 52: 121–36.
- . Forthcoming. 'Syntactic Features of *kol* as a Polarity Item in Negative Statements'. In *May You Favor the Work of His Hands: Essays in Memory of Michael Patrick O'Connor*, edited by Peter T. Daniels et al. Catholic Biblical Quarterly Monograph Series. Washington, D.C.: Catholic Biblical Association.
- Naudé, Jacobus, and Cynthia L. Miller-Naudé. 2015. 'Syntactic Features of כֹּל in Qumran Hebrew'. In *Hebrew of the Late Second Temple Period: Proceedings of a Sixth International Symposium on the Hebrew of the Dead Sea Scrolls and Ben Sira—International Symposium on the Hebrew of the Dead Sea Scrolls and Ben Sira*, edited by Eibert J. C. Tigchelaar and Pierre van Hecke, 88–111. Studies on the Texts of the Desert of Judah 114. Leiden: Brill.
- Naudé, Jacobus A., and Gary A. Rendsburg. 2013. 'Negation: Pre-Modern Hebrew'. In *Encyclopedia of Hebrew Language and Linguistics*, edited by Geoffrey Khan et al. http://dx.doi.org/10.1163/22124241_ehll_EHLL_COM_000008

- Netzer, Yael. 2013. 'Quantifier'. In *Encyclopedia of Hebrew Language and Linguistics*, edited by Geoffrey Khan et al. http://dx.doi.org/10.1163/2212-4241_ehll_EHLL.COM_00000208
- Payne, John, and Rodney Huddleston. 2002. 'Nouns and Nouns Phrases'. In *The Cambridge Grammar of the English Language*, edited by Rodney Huddleston and Geoffrey K. Pullum, 326–523. Cambridge: Cambridge University Press.
- Pullum, Geoffrey K., and Rodney Huddleston. 2002. 'Negation', In *The Cambridge Grammar of the English Language*, edited by Rodney Huddleston and Geoffrey K. Pullum, 785–849. Cambridge: Cambridge University Press.
- Shlonsky, Ur. 1991. 'Quantifiers as Functional Heads: A Study of Quantifier Float in Hebrew'. *Lingua* 84/2–3: 159–80.
- Taub, Alison. 1989. 'Collective Predicates, Aktionsarten and All'. *University of Massachusetts Occasional Papers in Linguistics* 15: *Papers on Quantification*, Article 16: 1–33.
- Tonciulescu, Keren C., 2011. 'Licensing Conditions for Indefinite Pronouns in Modern Hebrew'. PhD dissertation, University of Ottawa.
- Winter, Yoad. 2002. 'Atoms and Sets: A Characterization of Semantic Number'. *Linguistic Inquiry* 33/3: 493–505.

A MORE POLITE SUGGESTION: THE LENGTHENED IMPERATIVE IN BIBLICAL HEBREW*

Ethan Jones

The imperative in Biblical Hebrew (BH) knows a short (קִים) and lengthened form (קִימָה). The function of the latter has been elusive and at times uninteresting to Hebraists. As Kaufman (1991, 198) observes, the long imperative is “generally ignored or at best left unexplained in most grammars.” To his point, Waltke and O’Connor (1990, §34.4) consider the two imperatives as tautological: “No differentiation *is possible* between the regular and long (קִי-) forms of the imperative, since they occur in similar contexts” (emphasis mine). On the other hand, Fassberg (1999, 7) finds the lengthened imperative “a salient feature of biblical Hebrew grammar.”

In the variegated landscape of scholarly proposals, this essay puts forth a claim that the lengthened imperative is marked

* It is a privilege to present this essay in honour of Geoffrey Khan. Geoffrey’s hospitality, kindness, generosity, and command of ancient as well as modern grammar made my year as a Visiting Scholar at FAMES (Cambridge) full of joy. Thanks also to Aaron Hornkohl, reviewers, and attendants at the Linguistics and Biblical Hebrew section (SBL 2021), who responded to earlier versions of this paper. Any error is mine alone.

for politeness. While not entirely novel in its conclusion, the present study breaks new ground by way of linguistic politeness. This linguistic background allows the study to avoid mutual exclusions that have appeared in previous research. In other words, this essay is able to appreciate, to some degree, claims of directionality (Fassberg 1999) and euphony (JM §§48d, 114m), all while keeping in mind the possibility of pragmatic and semantic shifts in later stages of Hebrew (cf. Notarius 2021).

In what follows, I introduce the most significant proposals for the function of the lengthened imperative in BH. In doing so, I highlight the merits and challenges of the arguments (§1.0). From there, the field of historical linguistic politeness is presented (2.0). Special attention is given to the work of Kim Ridealgh on ancient Egyptian politeness. Once done, I offer my own description of the lengthened imperative according to a taxonomy of linguistic politeness (§3.0).

1.0. Review of Literature

1.1. Redundancy and Style

We begin with claims that call into question the purpose of this essay. As noted, Waltke and O'Connor (1990) consider the two forms as tautological. In addition, Tsevat (1955) is ambivalent about any distinction between the short and long imperative. The evidence these scholars usher forth is so-called similar contexts.

First a word on this line of argumentation. *Prima facie*, a claim based on similar contexts does not stand up to scrutiny. For instance, any number of features can appear in similar 'contexts'

(whatever such a word might mean) and still manifest some distinction in pragmatics or semantics. Thus, Tsevat's confident conclusion and the like are to my mind suspect.¹

Second, the textual evidence merits our attention.

- (1) שְׁמַע יִשְׂרָאֵל יְהוָה אֱלֹהֵינוּ יְהוָה אֶחָד: 'Hear, O Israel: The LORD is our God, the LORD alone.' (Deut. 6.4)²
- (2) שְׁמַע אֱלֹהִים רִנָּתִי הִקְשִׁיבָה תַּפְלְתִּי: 'Hear my cry, O God; listen to my prayer.' (Ps. 61.2)

It would seem unlikely that the use of the long forms in (2) is indiscriminate.³ Nevertheless, Waltke and O'Connor (1990, §34.4) find the second imperative in (2), הִקְשִׁיבָה, to have a "fixed imperative form." For the first (שְׁמַע), euphony may be a reasonable factor in this context. But there is still more to see in this text. The following verses, (3–4), are filled with reciprocity between the psalmist and God as well as the explicit praise of the addressee, all of which are typical of a *positive politeness* strategy (cf. 2.1).

A fairly convoluted position is held by JM (§48d). In one way, theirs is close to that of the tautologists above. They write

¹ Tsevat's bravado (1955, 111) is plainly seen in his remark that, had one simply noted what he did, then it "would have saved many an author from seeking special meanings in the [long] imperative... where none exist..." (cf. GKC §48k).

² All translations are NRSV, unless otherwise noted.

³ Example (2) has explicit reference to the speaker, which is lacking in (1), i.e., (2) is more personal than (1)—interpretable as a function of directionality and/or politeness.

that the second person imperative with paragogic *heh* “has, in general, *no appreciably different nuance* from the usual form” (emphasis mine). Confusingly, they find the paragogic *heh* as “emphatic in origin” (however ambiguous ‘emphatic’ might be). Despite no particular nuance in meaning, they conclude that the lengthened form does carry an “honorific” sense when one is addressing God, prophet, and priest. In response, I think it quite unlikely that the grammatical form has no distinct meaning except when addressing the deity or other religious authorities, somehow being a vestige of the so-called ‘emphatic’ use. In any case, linguistic politeness may be able to categorise this ‘honorific’ sense better.

Beyond the above conclusions, there are two substantial proposals that merit discussion. The first is that the lengthened imperative marks directionality toward the speaker (§1.2). The second is that the form highlights politeness (§1.3). We turn now to the case of directionality.

1.2. Directionality

Fassberg (1999) makes an argument that has immediate appeal. He claims the long imperative signals that the action is directed *toward the speaker*, whereas the short imperative is aimed elsewhere. Fassberg’s contention finds corroboration with previous claims, such as the use of הָבֵה, קוּמָה, and לָכָה as exhortations in which cooperation of and by the speaker is intended (Mann 1954).⁴

⁴ See also the similar, though independent, study of Shulman (1996), as well as her later research (1999; 2001).

Some representative examples of Fassberg's taxonomy (1999, 10) are:

- (3) שְׁמֶרָה נַפְשִׁי וְהַצִּילֵנִי אֶל־אֲבוֹשׁ כִּי־חָסִיתִי בָּךְ:
'O **guard my life**, and deliver me; do not let me be put to shame, for I take refuge in you.' (Ps. 25.20)
- (4) וַיֹּאמְרוּ הִבָּהּ | נִבְנֶה־לָּנוּ עִיר
'Then they said, "**Come, let us build ourselves** a city, and a tower with its top in the heavens, and let us make a name for ourselves; otherwise we shall be scattered abroad upon the face of the whole earth."' (Gen. 11.4a)
- (5) הָאֵירָה פָּנֶיךָ עַל־עַבְדְּךָ
'Let your face **shine upon your servant**.' (Ps. 31.17)

The evidence of directionality includes the first-person pronominal suffixes (3), verbs inflected in the first person (4), and third-person expressions of deference 'your *servant*' (5). Fassberg (1999, 11) finds that the directionality is contextual in some instances (e.g., Gen. 32.30). Beyond that, he identifies an "indirect relation" to the speaker. Thus, there is no expected concrete movement towards the speaker, but rather some type of relief (e.g., Ps. 9.20–21).

At this point, Fassberg (1999, 11–12) must reckon with the fact that these benefactive petitions are often directed to God. What is more, these social dynamics and literary contexts (typically Psalms) have been interpreted as polite requests to the deity. Fassberg (1999, 12), however, dismisses the polite interpre-

In her view, these data refute the direction or benefit of the speaker as a marked feature of the lengthened imperative (2014, 71). Thus, per Fassberg's argument, the two forms would have to be mere stylistic variations, at least as far Dallaire reads the data.

In addition, Dallaire (2014, 71) intends to dismiss the directionality argument by claiming that "Commands are generally given with the interest of the speaker of mind." This, at the most basic level, is correct. It in no way disproves Fassberg's argument for directionality (1999, 12), however.

Fassberg, like JM, recognises the abundance of lengthened imperatives in Psalms. As mentioned, he entertains the idea of politeness, but is not persuaded. For one, the form occurs in various social directions. Dallaire (2014, 71) counters this by claiming politeness need not only or always be speech from a subordinate to a superior. Her retort is correct, if only anecdotal.⁸

1.3. Politeness

The next view we consider is marked politeness. This interpretation has received support by Stephen Kaufman (1991).⁹ More recently, however, Kaufman's view on the origin and function of

⁸ Dallaire (2014, 71) states "Superior can also address subordinates with respect," and observes how in English a parent commands a child, both with urgency and with politeness. Noteworthy, however, is the added didactic factor in parent-child interaction, whereby the parent tries to teach the child proper social conventions. This is arguably different from biblical cases in which a superior commands an inferior using the lengthened imperative.

⁹ So, for example, the passing comment in JM (§48.d) on the form being in some cases "honorific."

The emotional dispositions expressed in the passages where the long imperative appears with ṣṭ are quite similar to those found in contexts where the regular imperative appears with ṣṭ . But, since the particle ṣṭ expresses respect or politeness and the long imperative is marked for polite commands, we assume that the combination of the two elements includes a level of modality superior to that found in contexts where only one of the two features is present. The more numerous the modal elements, the higher the level of modality. (Dallaire 2014, 73)

Dallaire is forced to admit the similarity in contexts. One way to maintain her position of politeness is, therefore, to argue on the level of *degree*.

Last and perhaps most confusingly, Dallaire's taxonomy of function for the long imperative + ṣṭ includes such nuances as urgency (Num. 22.6), non-urgent request (2 Kgs 5.22), politeness (Gen. 32.30), and manipulative petition (Gen. 38.16). It is fair to say that one could find without much difficulty these nuances occurring with the regular imperative.¹⁰ Moreover, the fact that both ṣṭ and the lengthened imperative are considered separately as markers of politeness leaves the sub-category of 'politeness' (Gen. 32.30) dubious, at best.¹¹ On the whole, this view, while being persuasive at times, suffers more substantively from the

¹⁰ Shulman (2001), for example, understands the overall sense of the imperative to be urgency, as opposed to other forms, such as *weqatal*.

¹¹ Dallaire (2017, 161) repeats these exemplars, asserting "The long imperative with ṣṭ no doubt increases the level of markedness or mitigation of the command."

lack of definition and linguistic rigour. What follows is a suggestion that attempts to overcome such infelicities.

2.0. Politeness in Scholarship

Every day is filled with politeness. Often, we intuitively sense when someone is polite or rude. In scholarship, however, definitions of politeness are “surprisingly elusive” (Ridealgh 2019, 56; cf. Grainger 2011, 167). Despite the lack of precision, the quest has yet to quell; politeness is a flourishing field of study (Nodoushan 2019, 109).

Before pressing too far into the subject, I need to be quite clear that ‘politeness’ does not denote customs and manners, *per se*. Rather, the topic at hand is the pragmatic research of linguistic politeness. To our benefit, this realm of politeness has been observed and analysed in detail, both in modern and ancient languages.¹²

In the last decade, politeness research has made its way into biblical studies in earnest (Pilch 2014). This is overall a positive sign. The scope, however, is typically restricted to narratives within the Hebrew Bible (Bridge 2011; 2016; 2019; Di Giulio 2007). This has left biblical poetry, especially Psalms, unattended. This lacuna provides opportunity for linguistic politeness study of the long imperative, especially given scholars’ tendency to see the frequent form in Psalms as purely stylistic.

Below, I provide an overview of the complex world of politeness research and the precedents in historical politeness study

¹² Cf. the special issue of *Journal of Politeness Research* 12 (2016, 149–294).

that serve as catalysts. This essay utilises numerous areas within politeness studies. I begin with the most basic.

2.1. Linguistic Politeness

Brown and Levinson's ground-breaking work on linguistic politeness appeared in 1987 (see also Brown and Levinson 1978, 56–311). They developed a taxonomy of politeness that hinges on the concept of 'face'. At the most basic level, there is 'positive' face and 'negative' face. These terms are not necessarily common-sensical, however. The former, 'positive' face, emphasises the common ground between speaker and addressee. Here lies the desire for connection. 'Negative' face, on the other hand, concerns the speaker not imposing on the addressee (Mills and Grainger 2015, 5). This entails a certain level of autonomy.

Face-work is essential, Brown and Levinson observe, across the world's languages. Since their work, these concepts have become highly productive in crosslinguistic research. True, scholars have challenged, tweaked, and nuanced nearly every aspect of Brown and Levinson's programme (Fraser 2005; Werkhofer 2005; Mills 2011; Kádár, Parvaresh, and Reiter 2021). Yet, their work on 'face' still remains a critical and mainstream avenue for research (Mills and Grainger 2015, 4).

2.2. Face-work

In this essay, I observe the general contours of 'face' as outlined by Brown and Levinson. Specifically, I will survey the text and label positive and negative politeness strategies used by speakers.

For positive politeness strategy, a speaker may, for example, exaggerate for interest or sympathy, seek agreement, use in-group markers, give reasons and/or gifts, and assert reciprocity (Brown and Levinson 1987; Bridge 2019). A negative politeness strategy could entail questioning or hedging, showing deference, apologising, and minimising any ‘face-threatening’ actions (Brown and Levinson 1987; Bridge 2019).

2.3. Discernment

Beyond face-work, this essay includes discussion of additional linguistic politeness foci that have benefitted the study of ancient languages (Dickey 2016, 197; Ridealgh and Junker 2019, 65; Ridealgh 2021a, 127). One such focus is ‘discernment’. Discernment in pragmatics is linguistic behaviour that “is socially and situationally appropriate and quasi mandatory and which closely reflects the social relationship between speaker and addressee, as well as the social and linguistic context within which the exchange takes place” (Ridealgh and Junker 2019, 56). A possible implication, for example, is that honorifics do not speak to face-wants of the addressee (so Brown and Levinson), but merely acknowledge the difference between speaker and addressee, particularly their power or authority.

In analysing ancient Hebrew, we will be mindful of the distinction in power between the psalmist, for example, and the addressee (God). What is more, we will be keen to observe how the language of the speaker might be mandatory in some way. In doing so, we would do well to recognise that the addressee is in fact

a deity and understood by the speaker as not simply another human. This reality, that is, speaking of/to a deity, rarely appears in politeness studies (Ridealgh 2021b, 61).¹³

Adopting the best of Brown and Levinson's theory, Ridealgh (2021b, 67) demonstrates the interconnection of face-work and discernment in the stark status differential between deity and speaker. Unlike the Egyptian literature cited by Ridealgh, however, the Hebrew Bible has a number of cases where the subordinate speaker criticises the deity. Thus, while we can find analogy to her programme, we must keep in front of mind the fact that ancient Egyptian hierarchy is not the same as that in ancient Hebrew (cf. Pss 13; 89).

2.4. Linguistic Ritual

Making use of multiple linguistic approaches, Ridealgh (2021b, 68) incorporates 'linguistic ritual' in her analysis. Linguistic ritual is a "recurrent action" that "re-enacts ideologies or ethos of relational network" (Terkourafi and Kádár 2017, 172). Relevant here is in-group ritual. This ritual, contra convention, includes a specific group in a social interaction and generates a response (Ridealgh 2021b, 70). Moreover, and to our interest, linguistic ritual can incite "intense emotions and affect" (Terkourafi and Kádár 2017, 172). Beyond this, it promotes close social connections.

One notable absence in traditional face-work study that sensitivity to linguistic ritual helps correct is the consideration of

¹³ Yet, as a leading expert in historical linguistic politeness, Ridealgh has paved the way for the exploration of divine and human communication in the Hebrew Bible.

face-enhancing activities. These acts are rightly seen as significant in the ancient world writ large (Ridealgh 2021b, 65). These include actions such as statements of offerings and uttering a divine name. In this inclusion, Ridealgh (2021b, 63) emphasises the communication within the historical data, rather than the “mechanisms of religion itself.”

3.0. The Lengthened Imperative and Linguistic Politeness

Here we take note of how the long imperative assists in the maintenance or saving of face by way of positive and negative politeness strategies.

3.1. Lengthened Imperative with נָּ and -לִי

The lengthened imperative appears frequently with נָּ and -לִי + first-person suffix.¹⁴

- (6) וְעַתָּה שָׂא-נָּא כֶּלֶיךָ תְּלִיךָ וְקִשְׁתְּךָ וְצֵא הַשָּׂדֶה וְצוּדָה לִי צֵיד (ק'; ב': צידה):
 ‘Now then, take your weapons, your quiver and your bow,
 and go out to the field, **and hunt** game for me.’ (Gen. 27.3)

The particle נָּ occurs early in (6). The benefactive לִי follows the long imperative וְצוּדָה . It is within reason that this imperative is lengthened to attain euphony with the *ketiv* object צידה .¹⁵ However, the use of נָּ and the context of desperation demonstrate face-work via *positive politeness*.

¹⁴ Gen. 25.31; 27.7, 19, 21; 38:16; Num. 22.17; 23.27; Judg. 16.10; 1 Sam. 9.18; 10.15; 25.8; 30.7; 2 Kgs 4.22; 5.22; 8.4; Jer. 38.25; Jon. 1.8.

¹⁵ Equally, this could fit well with the directional / benefactive view.

- (7) ותאמר דלילה אל-שמעון הנגידה-נא לי במה כחך גדול
 ‘So Delilah said to Samson, “**Please tell** me what makes your strength so great.” (Judg. 16.6a)

Here in close proximity, we find the long imperative, נא, and the benefactive לי. To be sure, הנגיד frequently has -ל to denote the addressee (e.g., Deut. 4.13; 5.5; 1 Kgs 1.20; Isa. 41.22). This could comport with Fassberg’s (1999) taxonomy, but the presence of נא and the clear attempt to persuade suggest the lengthened imperative, if directional, also marks politeness (cf. Jer. 38.25; Jon. 1.8).

- (8) אנא אדני תהי נא אונך-קשבת אל-תפלת עבדך ואל-תפלת עבדיך החפצים
 ליראה את-שמך והצליתה-נא לעבדך היום ותגהו לרחמים לפני האיש הזה
 ‘O Lord, let your ear be attentive to the prayer of your servant, and to the prayer of your servants who delight in revering your name. **Give success** to your servant today, and grant him mercy in the sight of this man!’” (Neh. 1.11a–b)¹⁶

The frequent use of נא, notes of deference (עבדך), and the clear and urgent need press beyond any directional explanation. The context and use of the long imperative suggest *positive and negative politeness*.¹⁷

¹⁶ While this is an example of Late Biblical Hebrew, it is unclear (to me) at this point if there is any diachronic development in the function of the long imperative and/or נא.

¹⁷ This, of course, takes נא as having a mitigating/deferential function. And while this may be the majority/traditional view in scholarship and in Talmudic interpretation, it is not the only view: נא is taken by some scholars to be a marker of logical consequence, ‘then, thus, so then, in

3.2. Lengthened Imperative with אָנֹכִי

Only occasionally does the long imperative appear with אָנֹכִי, but without a directional.¹⁸ However, the direction or benefit is typically presumed by way of common ground between the speaker and addressee.

- (9) אָנֹכִי יְהוָה הוֹשִׁיעָה אֶנָּה אָנֹכִי יְהוָה הַצִּלֵּיתָהּ אֶנָּה :
 ‘Save us, we beseech you, O LORD! O LORD, we beseech you,
 give us success!’ (Ps. 118.25)

The psalm as a whole and the particular opening and closing of the A and B lines of v. 25 do more than just hint that the long imperative connotes something more than euphony or directionality. The stacking of אָנֹכִי, אָנֹכִי, and the long imperative presents strong evidence for *positive politeness*.¹⁹ Here is an overlap in my research and Fassberg’s (1999) so-called indirect relation.

that case’ (Lambdin 1971, 170–71; Waltke and O’Connor 1990, §37.4a; Fassberg 1994, 70–71), which is how it is translated in some of the Targums and the LXX. In other words, my analysis above is plausible, but not definitive.

¹⁸ Judg. 19.11; Job 17.3; 33.1; Ecc. 2.1.

¹⁹ Goldingay (2008, 362) illustrates the politeness strategy nicely without recourse to ‘please’: “Oh now, Yhwh, do deliver; oh now, Yhwh, do give success”.

This, to be sure, is not to equivocate the semantics of אָנֹכִי and אָנֹכִי, but to suggest that they are used, as here, to draw sympathy, express urgency, and stress dependency on the addressee, all of which are ways of maintaining, as well as not infringing upon, the face of the addressee (positive politeness). Such linguistic deployment is for the sake of securing the desired response from the addressee, in this case, God. Waltke and O’Connor (1990, 40.2.5a–c), drawing on Lambdin, find אָנֹכִי to be very

3.3. Lengthened Imperative without אָנָּה

The most frequently occurring pattern is the lengthened imperative without אָנָּה.²⁰ This seems to be the best proving ground for whether the imperative itself can mark politeness.²¹ Indeed, it is here that linguistic politeness plays a significant role in interpreting the contextual features.

- (10) תִּנֵּה אֶת־נַשִּׁי וְאֶת־יְלָדֵי אֲשֶׁר עֲבַדְתִּי אִתְּךָ בְּהֵן וְאֶלְכָה בִּי אֶתָּה יְדַעְתָּ אֶת־
עֲבַדְתִּי אֲשֶׁר עֲבַדְתִּיךָ:

“Give me my wives and my children for whom I have served you, and let me go; for you know very well the service I have given you.” (Gen. 30.26)

similar to אָנָּה in having to do with a logical consequence. Notably, they mention אָנָּה in their discussion of “*cries or impolite utterances*,” as well as exclamations that are “*polite*,” though they do not consider the particles at hand to mark politeness.

²⁰ Gen. 27.4; 29.15; 30.28; 37.13; 42.37; 43.8; Exod. 32.10; Num. 10.29, 35; 11.13, 16; 22.6, 11; 23.7; Deut. 26.15; Josh. 10.6; 14.12; 15.19; Judg. 4.18; 11.6, 13; 14.12; 16.26; 17.10; 1 Sam. 8.15; 9.26; 14.6; 16.11; 17.44; 20.11; 22.23; 23.27; 24.22; 30.15; 2 Sam. 3.12, 14; 1 Kgs 13.7; 15.19; 21.6; 2 Kgs 14.8; Isa. 44.22; Jer. 49.11; Hos. 14.2; Joel 2.17; Pss. 4.7; 5.2; 6.5; 7.7; 9.20; 12.2; 17.1, 13; 20.10; 21.14; 22.20; 25.20; 28.9; 31.17; 35.23; 38.23; 39.13; 40.14; 41.5; 44.27; 50.7; 54.4; 55.2; 56.9; 57.12; 59.5; 60.7; 61.12; 68.29; 69.19; 70.6; 74.3; 78.1; 82.8; 84.9; 86.2, 6, 16; 90.13; 102.2; 108.6; 116.4; 119.149; 120.2; 140.7; 141.1; 142.7; Job 33.5; 34.16; Prov. 1.11; 4.20; 5.1; 23.26; Ruth 4.4; Songs 1.7; 7.12; Lam. 1.11; 2.20; 3.59, 63; Neh. 5.19; 6.7, 14; 13.14, 22, 29, 31; 1 Chron. 21.22, 29.18.

²¹ This occurs with and without לֹ.

While the imperative תֵּלֵךְ may for a moment lend to the directionality taxonomy, it needs to be clear that the lexeme (נָתַן) typically takes -לָ (e.g., Exod. 5.7, 10; 13.5, 11; 17.2; Num. 11.13, 18, 21; 21.16).²² One observes several features here pertinent to linguistic politeness: the reason for giving (תֵּלֵךְ) is so that he may go (וְאָלַכָה); common ground is made explicit within the כִּי clause (אֵתָּה יִדְעָתָּ); reciprocity in relationship (עֲבַדְתִּי אֶתְּךָ בְּהֵן). These are all features of a *positive politeness* strategy.

(11) הֵמָּה בָּאוּ בְּאֶרֶץ צֹף וְשָׂאוּל אָמַר לְנַעֲרוֹ אֲשֶׁר-עִמּוֹ לָכֵה וְנִשׁוּבָה פְּנֵי-יְחִידֶל
אָבִי מִדְּאֵתָנֹת וְדָאֵג לָנוּ:

‘When they came to the land of Zuph, Saul said to the boy who was with him, “Let us turn back, or my father will stop worrying about the donkeys and worry about us.”’ (1 Sam. 9.5)

One might want to dismiss (11) as politeness because Saul is speaking to his servant (so Fassberg 1999). Yet the general awareness of superiors speaking politely to subordinates has already been noted (Dallaire 2014). Notably, the translation above forgoes לָכֵה ‘come’ (e.g., *ESV*; *KJV*).²³

To my interest, Saul uses a hypothetical that hinges on sympathy: פְּנֵי-יְחִידֶל אָבִי מִדְּאֵתָנֹת וְדָאֵג לָנוּ. This is a mixture of *negative* and *positive politeness*.

²² This includes לָ + first-person suffix. See, for example, Isa. 50.4; Exod. 22.28, 29. In imperative (short, second person form): Gen. 14.21; 2 Chon. 1.10; plural imperative: Gen. 23.4; Exod. 17.2; 1 Sam. 17.10.

²³ Nonetheless, my argument does not concern translation, but the pragmatic force of persuasion and face-work.

- (12) וַיִּדְבֹר אַחָאָב אֶל־נָבוֹת | לֵאמֹר | **תֵּן־לִי** אֶת־כַּרְמְךָ יְהוֹיָדָה לְגַן־יֵרֶק כִּי הוּא קְרוֹב אֶצְלִי בֵּיתִי וְאַתָּנָה לְךָ תַּחְתָּיו כָּרֶם טוֹב מִמֶּנּוּ אִם טוֹב בְּעֵינֶיךָ אֶתָּנָה־לְךָ כֶּסֶף מְחִיר זֶה:

‘And Ahab said to Naboth, “**Give me** your vineyard, so that I may have it for a vegetable garden, because it is near my house; I will give you a better vineyard for it; or, if it seems good to you, I will give you its value in money.”’ (1 Kgs 21.2)

Ahab is far from a commendable character in the book of Kings. Nevertheless, his speech includes a long imperative (תֵּן) and numerous features of linguistic politeness. The latter include: the purpose of the giving (יְהוֹיָדָה לְגַן־יֵרֶק); the reason for request/demand (כִּי הוּא קְרוֹב אֶצְלִי בֵּיתִי); reciprocity (וְאַתָּנָה לְךָ תַּחְתָּיו); conditionality (אִם טוֹב בְּעֵינֶיךָ). Specifically, these are all *positive politeness* features that maintain face.

- (13) **קוּמָה** יְהוָה | הוֹשִׁיעֵנִי אֱלֹהֵי כִּי־הִכִּיתָ אֶת־כָּל־אֹיְבֵי לִחֵי שָׁנֵי רָשָׁעִים שִׁבְרָתָ: **‘Rise up,** O LORD! Deliver me, O my God! For you strike all my enemies on the cheek; you break the teeth of the wicked.’ (Ps. 3.8)

The psalmist waits till v. 8 to make an explicit plea. Before that, the psalm is filled with common ground, markers of relationship (אֲנִי שָׁכַבְתִּי וְאִישָׁנָה הִקְצוּתִי כִּי יְהוָה יִסְמְכֵנִי v. 6), and expressions of trust (e.g., וְאַתָּה יְהוָה מִגֵּן בְּעַדִּי v. 4), all of which contribute to *positive politeness*. Following the plea initiated by the long imperative, the psalmist gives a reason in which common ground of past relation is once again laid out: כִּי־הִכִּיתָ אֶת־כָּל־אֹיְבֵי. Thus, even when the direct plea is made in v. 8, it is immediately followed by *positive politeness*.

- (14) הַבִּיטָה עֵינַי יְהוָה אֱלֹהֵי הָאֶרֶץ עֵינַי פֶּן־אֵישׁן הַמָּוֶת: **‘Consider** and answer me, O LORD my God! **Give light to** my eyes, or I will sleep the sleep of death.’ (Ps. 13.4)

The second imperative “answer me” secures the fact that the psalmist is the implied object of הַבִּיטָה. That might move toward the directionality argument of Fassberg (1999). As above, however, the context for linguistic politeness puts forward a different explanation of the long imperative. For example, the A line concludes not only with the divine name (יְהוָה), which could be considered a polite use or could simply be part of linguistic ritual (§§2.2–2.4), but also with ‘my God’ (אֱלֹהֵי). The designation of relationship is quite conducive to face-work. Moreover, the B line, which contains a second-long imperative (הָאֶרֶץ), heightens the intensity by concluding with a hypothetical that highlights the worst possible outcome: פֶּן־אֵישׁן הַמָּוֶת.²⁴ Such is typical for garnering sympathy from the addressee. Significantly, the addressee in this case is understood by the psalmist to be one who can resolve the dire situation.

- (15) וַיֹּאמֶר סוּרָה שָׁבָה־כֹּה פֶלְנִי אֶלְמָנִי וַיֵּסֶר וַיֵּשֶׁב: **‘So Boaz said, “Come** over, friend; **sit down** here.” And he went over and sat down.’ (Ruth 4.1b)

As before, we might be persuaded that the first long imperative (סוּרָה) is for directionality. Linguistic politeness is, nevertheless, a more felicitous explanation. It is plain that Boaz wants

²⁴ Kraus (1993, 215) notes here the “imperatives are ultimate extreme cries for help.... The petitioner... now prays for God’s sympathy and attention”.

to convince להגיד.²⁵ Given that, the use of the long imperative seems to be more than purely directional. Put positively, the use of the lengthened imperative seems part of the rhetorical purpose of the speech: soft and congenial directives that maintain, if not enhance, one's 'face'.

3.4. Directionality and Difficult Cases

There are examples that give the politeness interpretation difficulty. Some fit the directionality taxonomy because of לִי, or appear (almost) exclusively in long form, or perhaps do not seem to co-occur with any politeness strategy (cf. Gen. 47.31).

For instance, the imperative הִבֵּה balks at a politeness rendering.²⁶ Nevertheless, several occurrences have a stated reason (Gen. 29.21; 1 Sam. 14.41; Ps. 60.13), or are followed by אֲנִי (Gen. 38.16) or פֶּן 'lest' (Exod. 1.10), all of which can serve a *positive politeness* strategy. Perhaps the strongest example of politeness

²⁵ Eskenazi and Fryer-Kensy (2011, 71) seem to have it right that these imperatives are an "invitation" and find it possible to translate the speech as "Would you come over and sit down?" The situation is, of course, complicated. Boaz is informing the closer relative of his obligation, but does not actually want the relative to perform the obligation. There are competing factors here. Nonetheless, maintaining one's face as opposed to giving purely directional directives still is a means to that end.

²⁶ Cf. לִי (JM §48.d), yet, the long form is notably followed by cohortatives (Gen. 31.44; Num. 6.2, 7; 1 Sam. 9.5; 14.1, 6; 17.44; 2 Kgs 14.8; Prov. 1.11), also a preceding question (Gen. 37.13), with אֲנִי (Num. 22.6; Eccl. 2.1; cf. Jenni 2012), and, most especially, a hedging hypothetical (Num. 22.11).

with הָבָה is (16), as an attempt at culling sympathy in the latter two clauses (cf. Gen. 30.1).

(16) וַיִּתֶּם הַכֶּסֶף מֵאֶרֶץ מִצְרַיִם וּמֵאֶרֶץ כְּנָעַן וַיָּבֵאוּ כָּל-מִצְרַיִם אֶל-יֹסֵף לְאֹמֶר
הָבָה-לָּנוּ לֶחֶם וְלָמָּה נָמוּת נֶגְדְךָ כִּי אֲפִס כֶּסֶף:

‘When the money from the land of Egypt and from the land of Canaan was spent, all the Egyptians came to Joseph, and said, “Give us food! Why should we die before your eyes? For our money is gone.”’ (Gen. 47.15)

Others, such as עוֹרָה (Ps. 7.7; 44.24; 57.9; 59.5; 108.3), may be euphonic (JM §48.d) or “fixed” (Waltke and O’Connor 1990, §34.4). Those conclusions, however, do not completely satisfy occurrences that are, yes, in poetry (cf. Tsevat 1955), but more importantly filled with sympathy, social markers, and vows (Ps. 57.6–11).

4.0. Conclusion

This essay has argued that the long imperative is indeed a salient part of BH grammar (so Fassberg 1999). What is more, it has on a number of occasions found agreement with observations of directionality and euphony. Nevertheless, the contribution of the form is to mark politeness. Taking the form as part of a politeness strategy allows the fine observations of Fassberg on the concrete and metaphorical direction to stand. Thus, this essay has done without the claim for mutual exclusivity: politeness *or* directionality. Furthermore, it has left the question of the historical origin of the form open. The essay refrained from arguing for the use of politeness by degrees (so Dallaire), which is debated amongst

scholars researching politeness, but rather contended for the utilisation of multiple linguistic features for a politeness strategy—the long imperative being only one.

Politeness is by no means simple. The present study has not sought a narrow or ad hoc definition of politeness. An appeal to the translation of ‘please’ and its near synonyms has not been made. Rather, on the basis of current and ongoing research on linguistic politeness, we have noted the contextual features of face-work throughout the Hebrew Bible.

References

- Bridge, Edward. 2011. ‘Self-Abasement as an Expression of Thanks in the Hebrew’. *Biblica* 92: 255–73.
- . 2016. ‘An Audacious Request: Abraham’s Dialogue with God in Genesis 18’. *Journal for the Study of the Old Testament* 40: 281–96.
- . 2019. ‘Polite Rhetoric: Judah’s Plea to Joseph in Genesis 44.18–34’. *Journal for the Study of the Old Testament* 43: 571–87.
- Brown, Penelope, and Stephen Levinson. 1978. ‘Universals in Language Usage: Politeness Phenomena’. In *Questions and Politeness: Strategies in Social Interaction*, edited by E. N. Goody, 56–311. Cambridge: Cambridge University Press.
- . 1987. *Politeness: Some Universals in Language Usage*. Cambridge: Cambridge University Press.
- Cook, John A. 2012. *Time and the Biblical Hebrew Verb: The Expression of Tense, Aspect, and Modality in Biblical Hebrew*. Linguistic Studies in Ancient West Semitic 7. Winona Lake, IN: Eisenbrauns.

- Goldingay, John. 2008. *Psalms: 90–150*. Baker Commentary on the Old Testament Wisdom and Psalms 3; Baker Commentary on the Old Testament. Grand Rapids, MI: Baker Academic.
- Grainger, Karen. 2011. “First Order” and “Second Order” Politeness: Institutional and Intercultural Contexts’. In *Discursive Approaches to Politeness*, edited by Linguistic Politeness Research Group, 167–88. Berlin: De Gruyter Mouton.
- Hatav, Galia. 2018. *The Semantics-Pragmatics Interface of the Biblical Hebrew Verb Forms*. Journal of Semitic Studies Supplement 42. Oxford: Oxford University Press.
- Jenni, Ernst. 2012. ‘Erwägungen zur Etymologie der althebräischen Modalpartikel *nā*’. In *Studies zur Sprachwelt des Alten Testaments III*, edited by Hanna Jenni, Hans-Peter Mathys, and Samuel Sarasin, 121–30. Stuttgart: Kohlhammer.
- JM = Joüon, Paul, and Takamitsu Muraoka. 2006. *A Grammar of Biblical Hebrew*. 2nd edition. Subsidia Biblica 27. Rome: Pontifical Biblical Institute.
- Kádár, Dániel, Vahid Parvaresh, and Rosina Reiter. 2021. ‘Alternative Approaches to Politeness and Impoliteness: An Introduction’. *Journal of Politeness Research* 17: 1–8.
- Kaufman, Stephen A. 1991. ‘An Emphatic Plea for Please’. *Maarav* 7: 195–98.
- Kraus, Hans-Joachim. 1993. *Psalms 1–59*. A Continental Commentary. Translated by Hilton Oswald. Minneapolis, MN: Fortress.
- Lambert, Mayer. 1946. *Traité de grammaire hébraïque*. Paris: Presses universitaires de France.

- Mann, Y. 1954. 'On the Use of Verbs of Exhortation'. *Leshonenu* 19: 3–12. [Hebrew]
- Mills, Sara. 2011. 'Discursive Approaches to Politeness and Impoliteness'. In *Discursive Approaches to Politeness*, edited by Linguistic Politeness Research Group, 19–56. Berlin: De Gruyter Mouton.
- Mills, Sara, and Karen Grainger. 2015. *Directness and Indirectness across Cultures*. London: Palgrave Macmillan.
- Nodoushan, Mohammad Ali Salmani, 2019. 'Clearing the Mist: The Border between Linguistic Politeness and Social Etiquette.' *International Journal of Language Studies* 13: 109–20.
- Notarius, Tania. 2021. 'The Imperative-hortative Paradigm in Biblical Hebrew in Typological and Diachronic View'. *Brill's Journal of Afroasiatic Languages and Linguistics* 13: 75–100.
- Pilch, John. 2014. 'Insults and Face Work in the Bible'. *HTS Theological Studies* 70:1–8.
- Ridealgh, Kim. 2021a. "'Without You I Am an Orphan": Exploring Emotion and Interpersonal Pragmatics in the Late Ramesside Letters'. In *The Expression of Emotions in Ancient Egypt and Mesopotamia*, edited by Shih-Wei Hsu and Jaume Raduà, 126–43. Leiden: Brill.
- . 2021b. 'Talking to God: Conceptualizing an Alternative Politeness Approach for the Human/Divine Relationship'. *Journal of Politeness Research* 17: 61–78.
- . 2016. 'Polite like an Egyptian? Case Studies of the Politeness in the Late Ramesside Letters'. *Journal of Politeness Research* 12: 245–66.

- Ridealgh, Kim, and Andreas Junker. 2019. 'Late Egyptian, Old English and the Re-Evaluation of Discernment Politeness in Remote Cultures'. *Journal of Pragmatics* 144: 56–66.
- Shulman, Ahouva. 1996. 'The Use of Modal Verb Forms in Biblical Hebrew Prose'. PhD dissertation, University of Toronto.
- . 1999. 'The Particle סֵךְ in Biblical Hebrew Prose'. *Hebrew Studies* 40: 57–82.
- . 2001. 'Imperative and Second Person Indicative Forms in Biblical Hebrew Prose'. *Hebrew Studies* 42: 271–87.
- Terkourafi, Marina, and Dániel Kádár. 2017. 'Convention and Ritual (Im)politeness'. In *The Palgrave Handbook of Linguistic (Im)politeness*, edited by Michael Haugh and Dániel Kádár, 171–95. London: Palgrave Macmillan.
- Tsevat, Matitياهو. 1955. *A Study of the Language of the Biblical Psalms*. Journal of Biblical Literature Monograph Series 9. Philadelphia: Society of Biblical Literature.
- Waltke, Bruce K., and Michael Patrick O'Connor. 1990. *An Introduction to Biblical Hebrew Syntax*. Winona Lake, IN: Eisenbrauns.
- Werkhofer, Konrad. 2005. 'Traditional and Modern Views: The Social Constitution and the Power of Politeness'. In *Politeness in Language: Studies in its History, Theory and Practice*, edited by K. Ehlich, S. Ide, R. Watts, 155–99. Berlin: De Gruyter Mouton.

LEXIS-CODING ORTHOGRAPHY IN 4QISA^M (4Q66)*

Noam Mizrahi

Five fragments were assigned to 4QIsa^m (or 4Q66), dated on palaeographic grounds to the first half of the first century BCE (Skehan and Ulrich 1997, 131–32 and pl. XXII; cf. Lange 2009, 173–274). However, fragments 1–3, which preserve words from six lines (containing Isa. 60.20–61.1), differ in terms of size, colour, shape, and, perhaps, scribal hand, from fragments 4–5, which contain the ends of five lines (covering Isa. 61.3–6). It remains uncertain, therefore, whether the two groups of fragments indeed belong together (as proposed by Eugene Ulrich) or rather represent two different manuscripts (as originally surmised by Patrick Skehan).

The present study focuses on fragments 4–5. They witness two variant readings vis-à-vis the MT in vv. 3 and 5 (lns 2 and 4,

* This paper stems from the research project ‘Revealing the Sealed Document: Revisiting the Qumran Isaiah Scrolls’, generously supported by the Israel Science Foundation (ISF 1000/20). The present paper greatly benefitted from the critique and feedback of my research group, which includes Dr Asaf Gayer, Dr Adi Amsterdam, Dr Nevo Shimon Vaknin, Beatriz Riestra, Chananya Rothner, and Avital Cohen. I am also grateful to the Israel Antiquities Authority and, especially, to Dr Joe Uziel and his team of the Dead Sea Scrolls Unit, for fruitful cooperation.

respectively), and this paper is concerned with the first variant, which entails a scribal correction:

top margin

- 1 [נקם לאלהינו לנחם כל אבלים ³ לשום לאבלי ציון] לַתֵּת לֵהֶם פֶּאֶר תַּחַת אֶפֶר
- 2 [שמן ששון תחת אבל מעטה תהלה תחת רוח כהה וק] רָא לֵהֶם אֵלֵי הַצֹּדֵק
- 3 [מטע יהוה להתפאר ⁴ ובנו חרבות עולם שממות ראשני] יְקוֹמְמוּ וְחִדְּשׁוּ עָרֵי
- 4 [חרב שממות דור ודור ⁵ ועמדו זרים ורעו צאנ..ם ובני] זָכַר אֲכַרְיָהֻם
- 5 [וכרמי..ם ⁶ ואתם כהני יהוה תקראו משרתי אלהינו י] אֲמַל לְ[כֶם חַי] לַ

Figures 1 and 2: 4Q66, fragments 4–5: Courtesy of the Israel Antiquities Authority



Figure 1
PAM 43.014
Photograph: Najib Anton Albina
(July 1959)




Figure 2
IAA B-362297 (digitally enhanced)
Photograph: Shai Halevi
(June 2012)

At first glance, the added *yod* in אֵלֵי הַצֹּדֵק (ln. 2) seems a relatively small, even insignificant, detail. It is usually construed as

a mere orthographic correction.¹ All the more so, since the scribal hand of the corrector is usually identified as that of the original scribe (Skehan and Ulrich 1997, 131; cf. Lange 2009, 273).

Nonetheless, if one seriously reflects on the question of *why* this variant occurs *where* it does, then even this tiny detail, when contextualised text-critically, may be interpretable as a manifestation of broader late Second Temple exegetical concern regarding interpretation of the phrase אֵלֵי הַצֶּדֶק in Isa. 61.3. This exegetical debate also has implications for Biblical Hebrew (BH) lexicography, as it reveals an ancient debate about the very existence of a rare lexeme.

Isa. 61.3 is a particularly attractive passage for Second Temple scholars, of course, because Isa. 61.1–3 have a well-documented reception history as a messianic proof-text in the Qumran scrolls, especially 4Q521 and 11Q13 (see especially Sanders 1975; Collins 1997; for 11Q13, see Miller 1969; Achenbach 2015), and the New Testament, especially Luke 4 (see, e.g., Flusser 1960; Neirynck 1997; Rosik and Onwukeme 2002). Previous discussions of the reception of v. 3, however, are generally limited to its first part (v. 3a).² A study of ancient interpretations

¹ Such an assessment would explain why this reading was left out of Parry's (2020) comprehensive discussion of the textual variants witnessed by the Isaiah scrolls. Morrow (1973, 161) records the variant, but does not discuss it.

² Tellingly, even the comprehensive work of Metzenthin (2010) excludes a discussion of Isa. 61.3b, though the passage Isa. 61.1ff. is referred to several times. Similarly, none of the passages pertinent to the case under investigation are discussed by Koenig (1982) or Pulikottil (2001), who previously explored exegetical trends in 1QIsa^a.

of v. 3b, which contains the phrase אֵילִי הַצֶּדֶק, thus fills a lacuna in our existing knowledge.

1.0. Orthography and Linguistic Marking

Scrutiny of this case should be framed by a preliminary, theoretical consideration of orthography.³

The alphabetic writing system of both ancient and Modern Hebrew is quite exceptional among the world’s written languages, in permitting the coexistence of a relatively broad spectrum of orthographic representations of speech segments. A random example from Qumran Hebrew is furnished by the feminine singular demonstrative זאת ‘this’, the rounded middle vowel of which is spelled in 1QIsa^a in at least three different ways in addition to the MT’s זאת—זאות, זוואת, זזות—with subsequent corrections that yield even more spellings, e.g., זזיות:

MT	1QIsa ^a
Isa. 5.25 בָּכַל-זֹאת לֹא-יִשָּׁב אָפוֹ	5.13–14 בכול זואת לוא שב אפו
Isa. 9.16 בָּכַל-זֹאת לֹא-יִשָּׁב אָפוֹ	9.7 בכול זואת לוא שב אפו
Isa. 14.26 הָעֵצָה הַיְעוּצָה עַל-כִּלְהֶאָרֶץ זֹאת	12.28–29 הָעֵצָה הַיְעוּצָה עַל כול הָאָרֶץ זואת
	זזות הַיֵּד הַנְּטִיָּה עַל כול הַגּוֹאִים

In the above cases, the orthographic variation occurs in the same recurring formula or within one and the same context, so diverse

³ Barr (1989) remains indispensable for any theoretical exploration of BH orthography. Significantly, Khan (2018) demonstrates that the common, unidirectional perception of orthography as mere representation of speech is too simplistic, as orthoepy results in attempts at the phonetic realisation of orthographic and other notational peculiarities. For the notion of “orthographic knowledge” and its complex interaction with psycholinguistic factors, see Berninger (1994; 1995).

functional values are unlikely to underlie the different spellings. Experience shows, however, that, in time, competing spellings of this sort can become functionally differentiated. Illustrations for this phenomenon may be adduced from Modern Hebrew.

An example of sociolinguistic values attached to competing spellings is furnished by the stylistic coding expressed by one's preferred orthography. Generally speaking, defective spellings, e.g., שלש *ša'loš* 'three', of segolate nouns of the type of פעל *po'al* 'verb', and of words traditionally written with *ḥaṭef qamets*, like צהרים *ṣohor'ayim* 'noon', are associated with old-fashioned, archaic, or even archaistic style, because they represent an orthographic standard established on the basis of BH, which was enforced throughout the Israeli educational system until the early 1980s. By contrast, *plene* spellings, e.g., שלוש, פועל, צוהוריים, are considered to represent a 'younger' and more up-to-date style. Tellingly, despite recent approval and even promotion by the Academy of the Hebrew Language,⁴ older literati tend to view some of the more modern conventions with contempt as vulgar spellings.

Another example, this time of distinct linguistic values attached to competing spellings, is supplied by the Hebrew word for '(Jewish) priest'. In contemporary, written Israeli Hebrew, the *plene* spelling כוהן is automatically decoded by native speakers as

⁴ See <https://hebrew-academy.org.il/topic/hahlatot/missingvocalizationspelling/> (Rule II: The /o/ Vowel), and the accompanying press release at <https://hebrew-academy.org.il/2017/06/17/כללי-הכתיב-המלא-הכללים-החדשים-סיוון/>, highlighting frequent words whose prescribed spelling was reformed.

marking the common noun and accordingly pronounced with ultimate stress: [ko'hen]. By contrast, the default decoding of the defective spelling כהן is as the proper noun (i.e., surname) 'Cohen', which is accordingly pronounced with penultimate stress: ['kohen]. The orthographic variants, encoding a distinction in grammatical category, are given to different phonetic realisations.

A final example illustrates that orthographic variants may be used for distinguishing between contrasting lexemes. Modern Hebrew inherited two words that were originally pronounced differently: מִלָּה *mil'la* 'word' and מִלְּה *mi'l'la* 'circumcision'. Due to the loss of both vocalic length and consonantal gemination in Israeli Hebrew, however, their pronunciation merged into [mi'la]. Nonetheless, one can discern a strong tendency among authors to retain the defective spelling for 'word', while maintaining the *plene* spelling for 'circumcision', in order to distinguish orthographically between the two lexemes—a tendency that is now eroding due to the equally strong tendency among younger generations to prefer *plene* orthography across the board.⁵

To be sure, I do not argue that such cultural constructs should be retrojected, wholesale, onto ancient Hebrew texts. Moreover, orthographic fluctuation is amply recorded in both the Dead Sea Scrolls and medieval codices of the Hebrew Bible.⁶

⁵ The differentiated spellings of *plene* אישה (= אִשָּׁה) 'her man (i.e., husband)' and defective אשה (= אִשָּׁה < אִשָּׁה) 'woman', both realised in Modern Hebrew as [iʃa], are undergoing a comparable process.

⁶ Examples pertinent to the word under investigation can be culled from both corpora. Qimron (2018, 66–67) records cases of the *plene* spelling

What I insist on, rather, is that we be aware that competing spellings could have, at least in some cases, signalled differentiated linguistic or sociolinguistic values for ancient readers and scribes. It would be wrong, therefore, to dismiss them out of hand.

The methodological problem that remains is how, in the absence of ancient Hebrew native speakers or literati, to distinguish between variants that are purely orthographic, on the one hand, and those that are functionally differentiated, on the other. In the case of the biblical scrolls from Qumran, however, one may have recourse to an external control, namely, the ancient versions. The very necessity of translating the Bible into other languages carries with it the potential for revealing such functional linguistic differences, and comparative analysis of the various translations into Greek, Latin, Syriac, and Jewish Aramaic enables one to discern at least some cases in which seemingly orthographic variants might have been perceived by ancient readers as marking linguistically distinct values, especially in the realm of lexis. Put differently, if the Hebrew textual witnesses vary with

of 'gods' (e.g., *וּמִי בְּנֵי הָאֱלִים* 4Q381 15.6), contrary to the MT's consistent preference for the defective spelling of this word (e.g., *בְּבָנֵי אֱלִים* MT Ps. 89.7). He also notes examples of the other direction: cases of defective spelling of 'rams' (*אֵלִים*), especially in 11QT^a), whereas the MT shows a clear preference for representing its first vowel with a *yod* (67 occurrences of *אֵלִים* versus only two of *אֵלִים*). Similarly, the critical editions of Kennicott (1776–1780) and Ginsburg (1908–1913) testify to many orthographic variants in medieval codices with respect to these words, though most of the collated manuscripts are relatively late and otherwise deviate very often from the received orthography underlying the Masoretic notes of the early authorities.

respect to the orthographic representation of a certain word, but all the versions essentially agree on its translation, then the variation may very well be purely orthographic. But if the versions reflect different lexical identifications, or widely disparate understandings of the word, then it is legitimate to explore the possibility that orthographic variation entailed linguistic differentiation.

Another group of potential cases of linguistically functional orthographic variants can be identified in the case of intentional corrections of orthographic variants. Why would a corrector intervene in an existing written text, adding or deleting a vowel letter, if it makes no difference to interpreting the word in question? Theoretically, the scribe may have corrected an error in copying his *Vorlage*, or possibly tried to clarify an original form that was difficult to read or interpret for any number of potential reasons. More specifically, such scribal interventions make sense if the corrected form was thought to be functionally different from the original one, even if this function is not immediately apparent to modern readers. In other words, orthographic corrections might be a means of interpretive explication, thereby injecting what I call 'micro-exegesis' into the textual fabric of a transmitted work.

If a given case satisfies both criteria, namely, exhibiting an explicit correction by a Hebrew scribe, while also corresponding to divergent renderings in the ancient versions, then the consideration of its orthography as a means of marking a linguistically functional distinction becomes plausible.

2.0. Common Interpretation

It is against this background that I propose that the superlinear *yod* in י'א partially disambiguates the lexical identity of a word given to various interpretations. The exegetical crux with which the scribe was wrestling can be clarified with the help of the ancient versions.

Isa. 61.1–4 describes how the currently miserable state of the Judaeen returnees will take a turn for the better; in the future, those who are now “the mourners of Zion” (אֲבֵלֵי צִיּוֹן) will be given a new designation: אֵילֵי הַצֶּדֶק.⁷ Modern scholarship, relying on medieval lexicography and exegesis, usually interprets this phrase like the *NRSV*: “the oaks of righteousness.”⁸ This line of interpretation assumes that the unattested, singular form *^ʾayl or *^ʾēl is the masculine counterpart of the feminine אֵלָה 'ēl' כ' ‘terebinth tree’.⁹

⁷ On thematic and syntactic grounds, vv. 1–4 can be subdivided into an introduction (v. 1a), a list of infinitival clauses (vv. 1b–3a), the new designation (v. 3b), and the restoration of the towns (v. 4). This division can also be supported by colometrical analysis (de Vries 2013), even without adhering to all its strictures. The compositional interaction of these sections with each other, with various passages of Deutero- and Trito-Isaiah, and with additional passages, especially of the Restoration Period, is a complicated matter that cannot be addressed here. See, e.g., Gregory (2007); Stromberg (2009).

⁸ See, in addition to the commentaries and lexica, Gignilliat (2011).

⁹ In the Hebrew Bible, the terebinth is sometimes associated with sacred or ritual sites (e.g., Gen. 35.4; Judg. 6.11, 19; 1 Kgs 13.14; Ezek. 6.13; Hos. 4.13; 1 Chron. 10.12; notably, Josh. 24.26 testifies to the geminated biform אֵלָה). A few other occurrences, however, demonstrate that

An augmented form of the masculine noun apparently underlies אֵלֹן *ʿēlōn* ‘oak’, employed in place names or designations of sacred sites.¹⁰

3.0. The Versions

This interpretation of the masculine plural אֵלִים (י)א, or construct אֵלִים (י)א, has been applied to a few other BH passages.¹¹ Intriguingly,

it was also typical of the local Palestinian flora (2 Sam. 18.9, 10, 14; Isa. 1.30; 6.13).

¹⁰ The geminated biform אֵלֹן *ʿallōn*, sometimes mentioned in juxtaposition to אֵלֶךְ (Isa. 6.13; Hos. 4.13), functions as a common name, designating oaks or terebinth trees (Gen. 35.8; Isa. 2.13; 44.14; Ezek. 27.6; Amos 2.9; Zech. 11.2). Historically, it appears that Hebrew אֵלֹן *ʿēlōn* is cognate of Aramaic אֵלֶן *ʿiln* ‘tree’, both being derived from Proto-Northwest Semitic **iylān*. While the specific sense of ‘oak’ (i.e., a particular kind of tree) was preserved in Hebrew, as demonstrated by the fact that the same sense is witnessed by other Semitic languages (see Ugaritic *aln* and Akkadian *allānu*, from Old Akkadian on), in Aramaic it underwent semantic extension to the broader sense of ‘tree’.

¹¹ For instance, both the BDB and *HALOT* assign the meaning of ‘tree’ in Isa. 1.29; 57.5; 61.3; Ezek. 31.14, as well as in the place name אֵלֶךְ (Gen. 14.6) (BDB 18a, s.v. אֵלֶךְ; *HALOT* 40a, s.v. אֵלֶךְ*). For our present concern, it is immaterial whether the passages discussed above are—from a literary point of view—independent or intertextually related (as suggested by, e.g., Jüngling 1993, esp. 214–16).

however, the ancient versions very rarely agree with this interpretation, preferring instead a different understanding of the word.¹² This is best exemplified by Isa. 57.5:

(1) Isa. 57.5

- MT הנחמים בַּאֱלִים תַּחַת כָּל-עֵץ רֵעֵן
‘You that burn with lust among the **oaks**, under every green tree’
- 1QIsa^a הנחמים בַּאֱלִים תַּחַת כּוֹל עֵץ רֵעֵן
LXX οἱ παρακαλοῦντες ἐπὶ τὰ εἰδωλα ὑπὸ δένδρα δασέα
‘You are the ones who call on their **idols** under thick trees’
- Vulg *qui consolamini in diis subter omne lignum frondosum*
‘Who seek your comfort in **idols** under every green tree...?’
- Pesh וְהַנְחָמִים בַּאֱלִים תַּחַת כָּל עֵץ רֵעֵן
‘Who are comforted by idols, beneath every forest tree’
- TJ דְּפָלְחִין לְעֵשָׁוִתָא תַּחַת כָּל אֵילָן עֲבוֹרָא
‘who serve **idols** under every leafy tree’

Clearly, all the versions take the word in question as the plural of אֱלֹהִים ‘god’ (as explicitly translated by the Vulgate), even if most of them interpret this term as actually referring to false gods or ‘idols’ (so the Septuagint, Peshiṭta, and Targum Jonathan).¹³ This is due primarily to the context, which employs the formulaic

¹² The English translations are taken from the *NRSV* (MT), *NETS* (LXX), Douay-Rheims-Challoner (Vulgate), Greenberg and Walter (2012; Peshiṭta), Stenning (1949; Targum Jonathan; cf. Chilton 1987).

¹³ This translational equivalent is not self-evident. It is not employed by the versions even in passages that clearly attest אֱלֹהִים in the sense of ‘idol’ (e.g., Isa. 44.10, 15, 17). In the Septuagint, for instance, εἰδωλον translates אֱלֹהִים only in the passages discussed above, even though εἰδωλον is used for translating the related terms אֱלֹהִים and אֱלִילִים.

phrase “under every green tree,” commonly denoting an illicit locus of idolatrous worship in Deuteronomistic phraseology.¹⁴

Arguably, not only the context, but also the defective spelling—which is the rule in the case of the plural form of אֱלֹ in the sense ‘god, divine being, angel’¹⁵—has facilitated this understanding of the word אֱלִים in a passage that most modern lexica take to mean ‘terebinth trees’.¹⁶

If so, one may begin to understand why a Second Temple scribe would consider it essential to distinguish orthographically between the defective and *plene* spellings of אֱלִי/אֱלִי הַצֶּדֶק in Isa. 61.3.¹⁷ If the head noun is read as the plural of אֱלֹ ‘god’, then the entire phrase could be taken as a pluralised form of the divine epithet אֱלֹהֵי צֶדֶק (Ps. 4.2), implying that the prophet boldly en-

¹⁴ Deut. 12.2; 1 Kgs 14.23; 2 Kgs 16.4 || 2 Chron. 28.4; 17.10; Jer. 2.20; 3.6, 13; 17.2; Ezek. 6.13.

¹⁵ In Qumran Hebrew, the term אֱלִים (also spelled אֱלִיִּים) can refer to angelic beings, as is evident from its antithetic parallelism with אֲנָשִׁים ‘people, humans’ (e.g., 1QM 1.10–11; 4Q511 10.11). Similarly, אֱלֹ is translated once in the Septuagint as ἄγγελος (Job 20.15).

¹⁶ Note that in this particular case, the orthography of the word is safeguarded in the Aleppo Codex by a Masoretic note that compares it to the homographic בָּאֱלִים in Exod. 15.11. Accordingly, Ginsburg (1911, 79) records no manuscript exhibiting *plene* orthography. By contrast, Kennicott (1780, 73) records many *plene* spellings, but this only testifies to the inferior quality of his sources, from a Masoretic point of view.

¹⁷ As far as I am aware, the only scholar who previously entertained this line of thinking—albeit hesitantly, and with no recourse to 4Q66, which was as yet unpublished—is Sanders (1975, 84–85 [= 2019, 51]).

dows the Judaeen returnees with qualities and titles that are elsewhere reserved exclusively for God. Whether or not the passage makes such a theological assertion is an exegetical matter that merits scribal explication, especially in light of the messianic matrix in which the entire passage of Isa. 61.1–4 was interpreted in the late Second Temple Period.

In Isa. 1.29, the versions treat the word אֱלִים(י) similarly to how they do in Isa. 57.5:

(2) Isa. 1.29

- MT כִּי יִבְשׁוּ מַאֲלִים אֲשֶׁר חֲמַדְתָּם
 ‘For you shall be ashamed of the **oaks** in which you delighted’
- 1QIsa^a כִּי אֵל יִבְשׁוּ אֲשֶׁר חֲמַדְתָּם
 LXX διότι αἰσχυνθήσονται ἐπὶ τοῖς εἰδώλοις αὐτῶν, ἃ αὐτοὶ ἠβούλοντο
 ‘For they shall be ashamed because of **their idols**, which they themselves wanted’
- Vulg *confundentur enim ab **idolis** quibus sacrificaverunt*
 ‘For they shall be confounded for the **idols**, to which they have sacrificed’
- Pesh כִּלְלָהּ וְנִבְשְׁתָּהּ מִן הָאֱלִים אֲשֶׁר חָשְׁתָּהּ
 ‘For they will be ashamed of the **idols** that they coveted’
- TJ אֲרֵי תִבְהִיתוֹן מֵאֵלֵינוּ טְעוֹתָא דְחַמִּידָתוֹן
 ‘For ye shall be ashamed of the **trees of the idols** which ye have desired’

In this case, too, the ancient translators apparently took the word as the plural of ‘god’, interpreting it as a reference to ‘idols’ in accordance with the context. It is no coincidence, then, that while

the MT exhibits *plene* spelling (אֱלִילִים),¹⁸ 1QIsa^a uncharacteristically features here defective spelling (אִלִּים).¹⁹ It stands to reason that 1QIsa^a's form is no mere matter of alternative orthography; rather, the defective spelling is meant to convey a particular lexical identification of the word in question, interpreting it in line with the other versions.

Intriguingly, the orthographic disagreement between the MT and 1QIsa^a is matched by a translational debate within the Greek tradition. While the Septuagint translates “over their **idols**” (ἐπὶ τοῖς εἰδώλοις αὐτῶν), two later revisions offer alternative renditions. Symmachus translates אֱלִילִים as ἀπὸ τῶν **δρυμῶν** ‘from the **forests**’. This translation is matched by the double rendition offered by Targum Jonathan: מֵאִלְנֵי טְעוּתָא ‘from **the trees of idols**’. These two are the earliest witnesses to the interpretation of the

¹⁸ In the Aleppo Codex, however, this word is not safeguarded by a Masoretic note. Kennicott (1780, 3) and Ginsburg (1911b, 7) record some orthographic fluctuation.

¹⁹ Admittedly, Kutscher (1974, 152–53) highlights inconsistency in the use of *yod* as a *mater lectionis* in 1QIsa^a, but his discussion includes spellings of different vowels (both *i* and *e*) of all sorts of historical origins (including historical diphthongs). As a matter of fact, 1QIsa^a testifies to only one word in which **ay* > *ē* is spelled defectively, namely, the plural forms of ‘egg’: בָּצִים (9.29) || MT בָּצִים (10.14), בָּצִי... מִבְצִיהֶמָּה (48.15–16, and so also 1QIsa^b 25.21–22) || MT מִבְצִיהֶמָּה... בָּצִי (Isa. 59.5). Cf. MT הַבָּצִים (Deut. 22.6) versus בָּצִים (4QpaleoDuet^r [4Q45] 27–29.6; *DJD* 9, 143 and pl. XXXV); 11QT^a 65.3. The widespread defective spelling might suggest a variant vocalisation of the word (e.g., *bāšim* rather than *bēšim* from SG *bēšā* < **bayšā*; see Bauer and Leander 1922, 202, §171).

term אֲלִי (י) as ‘trees’ and the only ones among the ancient versions. More important for our concerns is Aquila, who translates ἀπὸ [τῶν] ἰσχυρῶν ‘from the **mighty ones**’.

This term can be compared to the Greek version of 2 Kgs (4 Kgdms) 24.15, in which it renders the phrase אֲלִי הָאָרֶץ ‘the chiefs (or noblemen) of the land’:

- (3) 2 Kgs (4 Kgdms) 24.15
- MT וְאֵת אֲוִלֵי (אֲלִי) הָאָרֶץ הוֹלִיךְ גּוֹלָה מִירוּשָׁלַם בָּבֶלָה
 ‘and **the elite of the land**, he took into captivity from Jerusalem to Babylon’
- LXX αἱ τοὺς ἰσχυροὺς τῆς γῆς ἀπήγαγεν ἀποικεσίαν ἐξ Ἱερουσαλὴμ εἰς Βαβυλῶνα
 ‘And **the strong men of the land** he led away as a colony from Ierousalem to Babylon’
- Vulg et **iudices terrae** duxit in captivitatem de Hierusalem in Babylonem
 ‘and the **judges of the land** he carried into captivity, from Jerusalem, into Babylon’
- Pesh וְאֵת אֲוִלֵי הָאָרֶץ הוֹלִיךְ גּוֹלָה מִירוּשָׁלַם בָּבֶלָה
 ‘and **the noblemen of the land**: he took them into exile, from Jerusalem, to Babylon’
- TJ וְיֵת רַבְרָבֵי אֶרֶץ אוֹבִיל בְּגִלוּתָא מִירוּשָׁלַם לְבָבֶל
 ‘and **the chiefs of the land** he took away in exile from Jerusalem to Babylon’

Historically, the social term אֲלִי הָאָרֶץ appears to be semantically derived from אֵיל in the sense of ‘ram’, just as the social term אֲלוֹי originally denoted ‘bull’, but subsequently shifted to the sense of ‘chief’ (e.g., Gen. 36.15–19; Zech. 12.5–6)—semantic changes that betray the socio-economic background of the ancient, seminomadic Israelite society, in which social status and symbolic capital depended on one’s possession of herds of sheep

and cattle. At any rate, the term **אֵלֵי הָאָרֶץ** is correctly understood by all the versions as denoting the high officials of the Judahite kingdom.

The phrase recurs in another passage, Ezek. 17.13, and is similarly translated:

(4) Ezek. 17.13

MT וְאֵת **אֵלֵי הָאָרֶץ** לָקַח

‘He had taken away **the chief men of the land**’

LXX καὶ τοὺς ἡγουμένους τῆς γῆς λήμψεται

‘And he shall take **the chief men of the land**’

Vulg *sed et fortes terrae tollet*

‘Yea, and he shall take away the **mighty men of the land**’

Pesh מִבְּיָדוֹ (לְעֹלְמָה) נִשְׁחָטוּ

‘He carried off **the rulers of the land**’

TJ וְיָתִיב רַבְרָבֵי אֶרֶץ דְּבָר

The nobles of the land he carried off (Levey)

The only difference between this and the previous passage is that the Greek and Latin versions switched their lexical preferences: this time, the Septuagint employs a political term (ἡγούμενος), whereas the Vulgate selects an adjective meaning ‘mighty one’ (*fortis*).

Noteworthy for our concerns is the fact that in both occurrences of **אֵלֵי הָאָרֶץ**, the governing noun is spelled *plene* (in 2 Kgs 24.15 there is an inter-Masoretic interchange between *waw* and *yod*).²⁰ This fact suggests that Aquila’s *Vorlage* in Isa. 1.29 was similar to the MT, and not to 1QIsa^a.

²⁰ No defective spellings are recorded by Ginsburg for 2 Kgs 24.15 (1911a, 427) and Ezek. 17.13 (1911b, 250). Kennicott, however, records the defective spelling **אֵלֵי** for Ezek. 17.13 (1780, 194).

Equipped with this evidence, we are now in a position to return to our passage, Isa. 61.3:

(5) Isa. 61.3

- MT וְקָרָא לָהֶם אֵילֵי הַצִּדִּיק מִטֵּעַ יְהוָה לְהַתְפָּאֵר:
‘They will be called **oaks of righteousness**, the planting of the LORD, to display his glory’
- 1QIsa^a וקראו להמה אילי הצדק מטע יהוה להתפאר
4QIsa^m [וק] רָא להם אֵילֵי הַצִּדִּיק [מטע יהוה להתפאר]
LXX καὶ ἀκηθῶσονται γενεαὶ δικαιοσύνης, φύτευμα κυρίου εἰς δόξαν.
‘They will be called **generations of righteousness**, a plant of the Lord for glory’
- Vulg et vocabuntur in ea **fortes iustitiae** plantatio Domini ad glorificandum
‘and they shall be called in it the **mighty ones of justice**, the planting of the Lord to glorify him’
- Pesh ܘܕܡܝܐ ܕܒܪܐܝܐ ܕܕܝܢܐ ܕܡܝܢ ܥܝܢܐ ܕܡܝܢܐ ܕܡܝܢܐ.
‘They will be called “**The rams of righteousness**,” the Lord’s praiseworthy plant’
- TJ וְיִקְרֹון לָהֶון רַבְרַבֵּי קִשְׁטָא עַמִּיה דְּיוֹי לְאַשְׁתַּבָּח
‘and they shall call them **princes of righteousness**, the people of the Lord, that he may be glorified’

As we have seen, the two other occurrences of the word that medieval and modern lexica and commentaries take as ‘trees’ were almost uniformly interpreted by the versions as false ‘gods’, in accordance with their context. In this case, however, the versions present anything but uniformity, probably because the phrase אֵילֵי הַצִּדִּיק is patently applied to humans, namely, the prophet’s addressees.

First, the fact that 1QIsa^a exhibits the *plene* spelling, just as the MT does,²¹ is likely related to the Vulgate and Targum Jonathan's preference for taking the phrase אֵילֵי הַצֶּדֶק in (5) in much the same way they understand אֵילֵי הָאֲרָץ in (3)–(4), i.e., as referring to the political elite.²² Next, the Peshitta translates ܐܝܠܝܗܐ, also presupposing the *plene* spelling, but interpreting it literally, as 'rams', rather than figuratively, as 'chiefs'. Finally, the Septuagint anomalously translates "generations of righteousness" (γενεαὶ δικαιοσύνης).²³

The two Greek components of this phrase recur in Isaiah in only one other place, Isa. 51.8, in which God speaks in the first person: ἡ δὲ δικαιοσύνη μου εἰς τὸν αἰῶνα ἔσται, τὸ δὲ σωτήριόν μου εἰς γενεὰς γενεῶν 'but my righteousness will be forever, and my salvation for generations of generations', which is an apt translation

²¹ The word is not safeguarded by a Masoretic note in the Aleppo Codex. According to Ginsburg (1911b, 85), most manuscripts and editions of the MT employ the *plene* spelling; the defective spelling is recorded in only very few late sources (cf. Kennicott 1780, 79).

²² Interestingly, in his commentary on Isaiah, Jerome supplies a transcription of the Hebrew word, *ele*, commenting that "each syllable is lengthened" (Scheck 2015, 787; for the Latin original, *vel iuxta Hebraicum ele, per extensam utramque syllabam*, see Adriaen 1963, 708). This comment explicitly refers only to the pronunciation of the word as [ʔe:le:], but does it also imply that both vowels were spelled *plene* (i.e., אֵילֵי) in Jerome's *Vorlage*, as in the MT and 1QIsa^a?

²³ Ottley (1904–1906, 2:369) comments that γενεαὶ is "To explain 'oaks,' here as 'an emblem of the life of the righteous' (Skinner)," but this is very forced. Penner (2020, 629) does not comment on the perplexing Greek phrase.

of an MT-like Hebrew text: וְצִדְקָתִי לְעוֹלָם תִּהְיֶה וְיִשׁוּעָתִי לְדוֹר דּוֹרִים ‘but my deliverance (lit. my righteousness) will be forever, and my salvation to all generations’. This verbal similarity suggests that the translator’s point is theological, implying that the prophet’s words in Isa. 61.3 (“They will be called generations of righteousness, a plant of the Lord for glory”) echo God’s soteriological promise in Isa. 51.8. The divine righteousness, in other words, will be revealed as being realised in the destiny of his people; the title by which the people will be known among the nations reflects God’s essence as a righteous saviour.²⁴

One cannot help wondering whether this complicated doctrinal construction is meant to cope with a theologically perplexing assertion that the translator may have found in his *Vorlage*. Is it possible that it indirectly reflects a phrase such as אֱלֹהֵי הַצִּדְקָה, as recorded in the original reading of 4Q66? Such a phrase would literally mean ‘gods of righteousness’, which is theologically challenging not only because of the plural form, but also due to its application to flesh-and-blood Judaeans. Is it possible that the Greek rendition is an attempt to accommodate what the translator perceived as a baffling application of a divine epithet to the people of Yehud? If so, the Septuagint suggests how the presence

²⁴ For alternative explanations, see Baer (2001, 195–96, followed by Spans 2012, 55); Kagan (2018, 21–23, this section was omitted from the published version of his MA thesis). In the latter’s view, the Greek rendition reflects a correct interpretation of the Hebrew phrase in the sense of ‘rightful heirs’, equating אֱלֹהֵי הַצִּדְקָה with צִמְח צִדְקָה (Jer. 23.5), and taking the *nomen regens* as a reference to offspring (lit. ‘plant, tree’), while the *nomen rectum* refers to their right of inheritance.

or absence of even a single *yod* can play a pivotal role in the exegetical reception of the passage. Since the Greek translator's *Vorlage* is not directly accessible, this proposal is regrettably bound to remain hypothetical.

4.0. Conclusion

Regardless of the interpretation of the Greek version, which remains something of a mystery, there is sufficient evidence for the claim that by adding *yod*, the corrector of 4Q66 (possibly identical with the original scribe) was attempting to prevent his readers from construing the word יְהוֹי as 'gods' or 'divine beings', pushing them to whatever other sense this term could have in its present context.²⁵ Underlying this correction, then, is the idea that the entire theological meaning of a scriptural passage might hinge on the scribal care for a single *yod*. It is thus our scholarly duty not to neglect even this seemingly slight textual variant, as it has the potential to reveal the underlying linguistic motivations and ideological concerns of ancient scribal traditions.

Such a notion should come as no surprise to scholars of Second Temple Judaism and nascent Christianity, since another manifestation of it, albeit in a different context and with greater emphasis on the Law rather than to the Prophets, is found in Jesus's famous words in the Sermon on the Mount: "Do not think

²⁵ Unfortunately, the *plene* spelling remains intrinsically ambiguous, so that one cannot be certain which particular homonym was preferred by the scribe: 'rams', 'chiefs', or 'trees', as all these meanings could be assigned to the spelling יְהוֹי , and are, indeed, recorded in the versions surveyed above.

that I have come to abolish the Law or the Prophets; I have come not to abolish but to fulfil. For truly I say to you: till heaven and earth pass away, not even *one iota or one stroke of a letter* (ἰῶτα ἓν, ἢ μία κεφαλαία) will pass from the Law until all is accomplished” (Matt. 5.17–20).²⁶

References

- Achenback, Reinhard. 2015. ‘11QMelki-Zedek und der Repräsentant Zions in Jesaja 61’. In *Jesus, Paulus und die Texte von Qumran*, edited by Jörg Frey, Enno Edzard Popkes, and Sophie Tätweiler, 383–92. Tübingen: Mohr Siebeck.
- Adriaen, Marc. 1963. *S. Hieronymi presbyteri opera, pars I: Opera exegetica, 2A: Commentarium in Esaiam, libri XII–XVIII*. Corpus Christianorum: Series Latina 73A. Turnholt: Brepols.
- Baer, David A. 2001. *When We All Go Home: Translation and Theology in LXX Isaiah 56–66*. Journal for the Study of the Old Testament Supplement 318. Sheffield: Sheffield Academic Press.
- Barr, James. 1989. *The Variable Spellings of the Hebrew Bible*. The Schweich Lectures of the British Academy 1986. Oxford: Oxford University Press.
- Bauer, Hans, and Pontus Leander. 1922. *Historische Grammatik der Hebräischen Sprache des Alten Testament*. Halle: Max Niemeyer.

²⁶ For the Hebrew terms יוד and קוץ underlying the Greek phrase, see Kister (2021).

- Berninger, Virginia Wise (ed.). 1994. *The Varieties of Orthographic Knowledge I: Theoretical and Developmental Issues*. Neuropsychology and Cognition 8. Dordrecht: Springer.
- . 1995. *The Varieties of Orthographic Knowledge II: Relationships to Phonology, Reading, and Writing*. Neuropsychology and Cognition 11. Dordrecht: Springer.
- Chilton, Bruce D. 1987. *The Isaiah Targum: Introduction, Translation, Apparatus and Notes*. The Aramaic Bible 11. Wilmington, DE: Michael Glazier.
- Collins, John J. 1997. 'A Herald of Good Tidings: Isaiah 61:1–3 and its Actualization in the Dead Sea Scrolls'. In *The Quest for Context and Meaning: Studies in Biblical Intertextuality in Honor of James A. Sanders*, edited by Craig A. Evans and Shemaryahu Talmon, 225–40. Biblical Interpretation Series 28. Leiden: Brill.
- De Vries, Pieter. 2013. 'Structural Analysis of Isaiah 61 with a Special Focus on Verses 1–3'. *Old Testament Essays* 26/2: 298–314.
- Flusser, David. 1960. 'Blessed are the poor in spirit...'. *Israel Exploration Journal* 10: 1–13 (reprinted in David Flusser, *Judaism and the Origins of Christianity*, 103–14. Jerusalem: Magnes Press, 1988).
- Gignilliat, Mark. 2011. 'Oaks of Righteousness for His Glory: Horticulture and Renewal in Isaiah 61,1–4'. *Zeitschrift für die Alttestamentliche Wissenschaft* 123/3: 391–405.
- Ginsburg, Christian David. 1911a. *Prophetæ priores*. London: Bible Society.
- . 1911b. *Prophetæ posteriores*. London: Bible Society.

- Greenberg, Gillian, Donald M. Walter (trans.), George A. Kiraz, and Joseph Bali (eds). 2012. *The Syriac Peshitta Bible with English Translation: Isaiah*. Antioch Bible. Piscataway, NJ: Gorgias.
- Gregory, Bradley C. 2007. 'The Postexilic Exile in Third Isaiah: Isaiah 61:1–3 in Light of Second Temple Hermeneutics'. *Journal of Biblical Literature* 126/3: 475–96.
- Jüngling, Hans-Winfried. 1993. 'Die Eichen der Gerechtigkeit: "Protojesajanisches" in Jes 61'. In *Biblische Theologie und gesellschaftlicher Wandel für Norbert Lohfink*, edited by Georg Braulik et al., 199–219. Freiburg: Herder.
- Kagan, Itai. 2018. 'The Evolution of the Idiom "True Plant" in Second Temple Literature: Inheritance, Election and Righteousness'. MA Thesis, The Hebrew University of Jerusalem (published in revised form as "'A Rightful Plant Forever": The Evolution of a Phrase in Second Temple Literature', *Meghillot* 15 [2020–2021]: 203–47). [Hebrew]
- Kennicott, Benjamin. 1776–1780. *Vetus Testamentum Hebraicum cum variis lectionibus*. 2 vols. Oxford: Clarendon.
- Khan, Geoffrey. 2018. 'Orthoepy in the Tiberian Reading Tradition of the Hebrew Bible and Its Historical Roots in the Second Temple Period'. *Vetus Testamentum* 68/3: 378–401.
- Kister, Menahem. 2021. 'Jots and Tittles: Literary Units, Sayings, and Expressions in Rabbinic Literature and the Gospels'. *Eretz Israel* 34 (*Ada Yardeni Volume*): 147–55. [Hebrew]
- Koenig, Jean. 1982. *L'herméneutique analogique du judaïsme antique d'après les témoins textuels d'Isaïe*. *Vetus Testamentum Supplement* 33. Leiden: Brill.

- Lange, Armin. 2009. *Handbuch der Textfunde vom Toten Meer 1: Die Handschriften biblischer Bücher von Qumran und den anderen Fundorten*. Tübingen: Mohr Siebeck.
- Metzenthin, Christian. 2009. *Jesaja-Auslegung in Qumran*. Abhandlungen zur Theologie des Alten und Neuen Testaments 98. Zurich: Theologischer Verlag.
- Miller, Merrill P. 1969. 'The Function of Isa 61:1–2 in 11Q Melchizedek'. *Journal of Biblical Literature* 88/4: 467–69.
- Morrow, Francis J. 1973. 'The Text of Isaiah at Qumran'. PhD dissertation, Catholic University of America.
- Neirynck, Frans. 1997. 'Q 6,20b–21; 7,22 and Isaiah 61'. In *The Scriptures in the Gospels*, edited by Christopher M. Tuckett, 27–64. Bibliotheca Ephemeridum Theologicarum Lovaniensium 131. Leuven: Leuven University Press and Peeters.
- Ottley, Richard R. 1904–1906. *The Book of Isaiah According to the Septuagint (Codex Alexandrinus)*. 2 vols. London: Clay and Sons and Cambridge University Press.
- Parry, Donald W. 2020. *Exploring the Isaiah Scrolls and Their Textual Variants*. Supplements to the Textual History of the Bible 3. Leiden: Brill.
- Penner, Ken M. 2000. *Isaiah*. Septuagint Commentary Series. Leiden: Brill.
- Pulikottil, Paulson. 2001. *Transmission of Biblical Texts in Qumran: The Case of the Large Isaiah Scroll 1QIsa^a*. Journal for the Study of the Pseudepigrapha Supplement Series 34. Sheffield: Sheffield Academic Press.
- Qimron, Elisha. 2018. *A Grammar of the Hebrew of the Dead Sea Scrolls*. Jerusalem: Yad Ben-Zvi.

- Rosik, Mariusz, and Victor Onwukeme. 2002. 'Function of Isa 61,1–2 and 58,6 in Luke's Programmatic Passage (Lk 4,16–30)'. *Polish Journal of Biblical Research* 2/1: 67–82.
- Sanders, James A. 1975. 'From Is 61 to Luke 4'. In *Christianity, Judaism and Other Greco-Roman Cults: Studies for Morton Smith at Sixty*, 4 vols., edited by Jacob Neusner, 1:75–106. *Studies in Judaism in Late Antiquity* 12. Leiden: Brill (reprinted in James A. Sanders, *Scripture in Its Historical Contexts II: Exegesis, Hermeneutics, and Theology*, 47–71. Tübingen: Mohr Siebeck, 2019).
- Scheck, Thomas P. 2015. *St. Jerome: Commentary on Isaiah, Including St. Jerome's Translation of Origen's Homilies 1–9 on Isaiah*. New York and Mahwah, NJ: The Newman Press.
- Skehan, Patrick W. 1978. 'Qumrân: IV. Littérature: A. Textes bibliques'. *Supplément au Dictionnaire de la Bible* 9/51: 805–22.
- Skehan, Patrick W., and Eugene Ulrich. 1997. 'Isaiah'. In *Qumran Cave 4, X: The Prophets*, 7–143, pls I–XXIII. *Discoveries in the Judaean Desert* 15. Oxford: Clarendon.
- Spans, Andrea. 2012. 'Eine prophetische Gruppe in Zion und ein priesterlicher Übersetzer in der Diaspora: Zur Deutung der Sprecheridentität in Jes 61 MT und Jes 61 LXX'. *Biblische Notizen* 152: 35–66.
- Stenning, John F. 1949. *The Targum of Isaiah*. Oxford: Clarendon.
- Stromberg, Jacob. 2009. 'An Inner-Isaianic Reading of Isaiah 61:1–3'. In *Interpreting Isaiah: Issues and Approaches*, edited by David G. Firth and Hugh G. M. Williamson, 261–72. Nottingham: Apollos and Downers Grove, IL: InterVarsity Press.

THE VOCABULARY OF THE SAMARITAN PENTATEUCH: A GENERAL OVERVIEW

Moshe Florentin

The uniqueness of the Samaritans and the difference between them and their Jewish neighbours is evident in every field: history, beliefs and customs, material culture, literature and language. My friend, Prof. Geoffrey Kahn, has mastered a great number of Semitic languages, eastern and western, northern and southern. In our conversations, he has also shown great interest in the languages that have been used by the Samaritans: Hebrew, Aramaic, and Arabic. In this article dedicated to him, I seek to present a general picture of Samaritan vocabulary as it is reflected in the Samaritan version of the Pentateuch (SP).¹

The subject requires a preliminary discussion of the uniqueness of SP, which was recognised already in ancient times. The modern investigation of SP began in 1815, with the seminal study of Wilhelm Gesenius. The discovery of the Dead Sea Scrolls has taught us that SP was based on one of the versions used in Eretz

* I am grateful to my friend and colleague, Prof. Steve Fassberg, from the Hebrew University of Jerusalem. He read the first draft of this paper and significantly contributed to its content and language style.

¹ Tov (2012) is a reliable source from which the English reader can draw general information as well as some specifics about the character of SP.

Israel around the beginning of the Christian Era. This version was edited by members of the Samaritan community and adapted to their beliefs and language. Their efforts culminated in two layers of SP, both of which serve as a basis for examining SP vocabulary.

The first layer is reflected in the written text of SP. It is known from hundreds of Samaritan manuscripts, whose earliest copies date to the twelfth and thirteenth centuries CE.² Contrary to the Masoretic Text (MT), SP never crystallised into a *textus receptus*, a text uniform in all its details. Even if the Samaritans attribute a status of sanctity to the manuscript they designate the ‘Book of Abisha’ (Castro 1959), its spelling (on the vowel system, see below) is considered no more ‘correct’ than that of other manuscripts.

Indeed, Samaritan manuscripts differ greatly in their spelling. If we compare SP to MT, we may say that the different spellings of Samaritan words constitute ‘allo-variants’. Note, for example, *וְלוֹ יִקְרֶהֶת עַמִּים* ‘And to Him shall be the obedience of peoples’ (Gen. 49.10) in MT as opposed to SP *וְלוֹ יִקְרֶהֶתוּ (יִקְחֶתוּ) עַמִּים* ‘and to him peoples shall gather’:³ [יִקְרֶהֶתוּ] and [יִקְחֶתוּ] are ‘allo-variants’ of */יִקְרֶהֶתוּ/*, which is different from the MT variant */יִקְרֶהֶת/*. In the same way, one may say that each of the Samaritan manuscripts is an ‘allo-version’ of the Samaritan version.

² A short review of the major manuscripts of SP can be found in the preface to the edition by Schorch (2013, xxi–xxii).

³ Our translation (Florentin-Tal 2025) is based on the Samaritan interpretation reflected in the Samaritan Targum (ST) *יִתְכַנְשֹׁן* and the Arabic translation *يُتَمَع*.

The second layer is the vocalisation. Here the difference between the transmission of SP and the transmission of MT is more acute. Unlike their Jewish neighbours, the Samaritans did not develop an elaborate and complete system of vowel signs. In Samaritan manuscripts one finds sporadic signs for marking vowels, but the use of these marks is limited in scope and not uniform (Ben-Ḥayyim 2000, §0.6). In other words, a language study based solely on these signs does not present a complete picture of SP and Samaritan Hebrew (SH). On the other hand, the Samaritans have a precise and faithful reading tradition of their Torah. It is customary to assume that the foundations of this tradition, though not in all its details as they are heard today, go back to the end of the Second Temple Period.

Thus, whoever wants to know SP, and in our case its vocabulary, must have recourse to one of the editions of SP⁴ together with the fourth volume of *The Literary and Oral Tradition of Hebrew and Aramaic amongst the Samaritans* (Ben-Ḥayyim 1977), in which Z. Ben-Ḥayyim presented readers with a complete transcription of the Samaritan pronunciation of the Torah and a concordance.

⁴ Critical editions include those of von Gall (1918) and Schorch (2018). Tal and Florentin (2010) is a parallel edition of SP versus MT. The Samaritan manuscript on which the latter edition is based can also be found with the English translation in Florentin and Tal's new edition (2025).

1.0. Non-lexical Differences

The nature of the vocabulary of SP should be examined in the light of the general uniqueness of SP. There are three types of differences between SP and MT: (a) textual; (b) grammatical; (c) orthographic, i.e., involving the use of *matres lectionis*. Since spelling differences, such as הצפור ‘the bird’ (MT) versus הצפור (SP, Lev. 14.7) are not relevant to an examination of the lexicon, we will look for potential differences in vocabulary as they are related to text and grammar.

The order of the text at all levels is one of the most prominent features of SP, at the level of both verse and discourse. Thus, for example, in MT it is written: וַיֹּאמֶר קַיִן אֶל-הָבֶל אָחִיו וַיְהִי בְהִיוֹתָם: בַּשָּׂדֶה ‘Cain said to Abel his brother, and when they were in the field’ (Gen. 4.8), while SP presents a smoother text: וַיֹּאמֶר קַיִן אֶל-הָבֶל אָחִיו נֵלְכָה הַשָּׂדֶה וַיְהִי בְהִיוֹתָם בַּשָּׂדֶה “Cain said to Abel his brother, “Let us go to the field,” and when they were in the field”. Although the words נלכה and השדה do not occur in the MT verse, it is worth noting that these two words are found elsewhere in both versions. Thus, this essential difference does not reflect any lexical innovation. In Gen. 29.3 MT relates וַיִּגְלְלוּ וְגִלְלוּ כָל-הָעֶדְרִים וַיִּגְלְלוּ וַיִּגְלְלוּ וַיִּגְלְלוּ ‘And all the flocks would be gathered there, and they would roll the stone from the well’s mouth’. SP knows that the subject of the verb וַיִּגְלְלוּ ‘and they would roll’ is not the herds, but their shepherds. It removes ambiguity by replacing MT הָעֶדְרִים ‘the herds’ with הָרְעִים ‘the shepherds’, resulting in ‘and all the shepherds would gather there’. Yet רעים (רועה SG) is not a neologism in SP, as it appears in several other places in the Torah.

SP often reflects a different approach to the events narrated in the text. For example, in the MT version of Jacob's blessing for his sons Simeon and Levi are severely condemned, 'Cursed (אָרוֹר) be their anger' (Gen. 49.7). Conversely, in SP Jacob praises the two brothers, using the word אָדִיר 'exalted'. In this case, too, however, there is no lexical innovation, for both אָדִיר and אָרוֹר occur elsewhere in the two versions.

Particularly notable, though not numerous in number, are cases that reflect religious differences between Jews and Samaritans regarding the place God chose לִשְׁכֵּן שְׁמוֹ שָׁם 'to put His name there' (Deut 12.11; 14.23; 16.6; 26.2). The Jews believe it is Jerusalem, which had not yet been chosen when the children of Israel entered the land of Canaan, whereas for the Samaritans it is Mount Gerizim. Thus, in MT it is written 'in the place which he will choose (יִבְחֶר)', while in SP בָּחַר 'he has chosen' occurs (Deut. 12.5, etc.). Yet, again, there is no difference in vocabulary here, since imperfect יִבְחֶר is attested in SP elsewhere (e.g., Num. 16.5) and MT attests perfect בָּחַר (e.g., Deut. 7.6).

In Deut. 27.4, according to MT, the children of Israel are commanded to build a stone altar 'on Mount Ebal' (בְּהָרֵי עֵיבָל); SP reads 'on Mount Gerizim' (בְּהַר גְּרִיזִים). Here, too, no lexical difference separates the two versions, since Mount Ebal appears in SP elsewhere, as does Mount Gerizim (written as separate words, הָרִי גְרִיזִים) in MT.

Nor do harmonising additions in SP create lexical differences between SP and MT, since they are pericopes that have

been added from other parts of the Pentateuch common to both SP and MT.⁵

This rather general overview teaches us that the multiple differences between the versions of the two traditions do not necessarily lead to differences in vocabulary.

In what respect, then, is Samaritan vocabulary different from MT vocabulary? It lies in the realms of *phonology* and *morphology*, and, to a great extent, in the *interpretation* given to the words over the generations by the Samaritan community. Scarcely does one find completely *different* words (verbs, common and proper nouns) in SP. Below we will begin with minor differences in vocabulary and move on to major ones.

2.0. Phonetic Differences Expected according to Samaritan Hebrew Phonology

This type of difference is exemplified by the Tiberian word אֱלֹהִים ‘God’, pronounced by the Samaritans *ēluwwəm*. Four sound shifts are attested in this word: (a) the vowel *u* is assimilated to *o* before *ww*; (b) the consonant *w* is the geminated reflex of an intervocalic glottal stop; (c) the vowel *a*, unrelated to the Tiberian *shewa*, is the expected reflex of the vowels *i* and *e* in a closed post-tonic syllable; (d) as is true in the vast majority of words in SH, stress

⁵ An exception is the independent addition in עברה שכח ועברה כי עשה זאת בזבח שכח ועברה ‘for whoever does so is like one who sacrifices while abandoning (God’s commandments), and it is a transgression against the God of Yāqob’ (SP Num. 27.19a). Yet, even this highly important addition includes no lexical innovation.

falls on the penultimate, rather than ultimate (see, respectively, Ben-Ḥayyim 2000, §§1.1.8; 1.2.5; 1.4.6; 1.5.3.1).

Such is the case with many words in SP: they differ from their Tiberian counterparts only in terms of pronunciation according to predictable sound shifts.

3.0. Phonetic Differences Resulting from Sporadic Changes

The Canaanite shift, secondary gemination, and the various realisations of the *shewa* are linguistic phenomena whose character and distribution in SH differ from those in Tiberian Hebrew (TH). Usually we are unable, however, to predict their appearance. Let us briefly demonstrate these phenomena.

The Tiberian personal pronoun אֲנִי is pronounced by the Samaritans *ānāki*.⁶ This is one of the cases in which—contrary to TH—the Canaanite shift does not occur in SH. As elsewhere, so too here, we do not know the reason for the lack of the shift. It would not have been surprising if the form of this pronoun had been **ānūki*, whose vowel *ū* reflects the vowel *o*, as in TH.

The noun אֲדֹן ‘lord, master’ has three forms in SH—one in the locution אֲדֹן הָאֲדֹנִים *ādon ā:dūnām* ‘Lord of lords’, which demonstrates the Canaanite shift like the Tiberian form. The second is the equivalent of the Tiberian divine epithet אֲדֹנָי ‘Lord’, realised in SH as *ādāni*, i.e., without the Canaanite shift. The third parallels Tiberian title employed with human referents אֲדֹנִי ‘my

⁶ The plosive pronunciation of the /k/ is expected (Ben-Ḥayyim 2000, §1.1.5).

lord', SH *ādanni*. The gemination of *n* in the latter form is secondary and thus unexpected. It should be noted that, though this phenomenon is of a purely phonetic nature, in this case it reflects one of the most significant characteristics of the vocabulary of SH, i.e., semantic differentiation. This matter is discussed in greater detail in §5.0 below.

4.0. Non-semantic Morphological Differences

Morphological differences between SH and TH are numerous and occur in all grammatical categories of the language. Many verbs that in TH belong to the *qal* stem are attested in SH in the geminated *pi^cel* stem with no difference in meaning (Ben-Ḥayyim 2000, §2.15.5). Thus, the root ש"ח appears in SH only in the *pi^cel*, e.g., MT שָׁחַחְתָּ (Gen. 38.23) but SP *šallātti*. The Tiberian personal pronoun אַתְּ 'you' (FSG) is realised in the SP as *atti*, while Tiberian אַתְּ 'you' (MPL) is paralleled by Samaritan *attimma*. Differences of this kind, consistent or sporadic, are numerous.

In SH, secondary roots were also formed whose meanings do not usually differ from the meanings of the original roots in TH (cf., however, יפת, below, §8.0). Thus, for example, in contrast to the MT internal passive form of *qal* יִתֵּן 'will be given' from the root ית"ן, the Samaritans read *yētān*, a perfect form of the passive of *qal* from the secondary root ית"ן.⁷ The Samaritan verb parallel to Tiberian *nif'al* of נִמַּל מו"ל is passive *qal* of נִמַּל *nēmāl*.⁸ In

⁷ According to Ben-Ḥayyim (2000, §2.15.5), the form *yētān* preserves the ancient root ית"ן.

⁸ In late Samaritan sources, a feminine proper noun נְמִילָה *nēmīlā* literally 'circumcised', i.e., 'pure', is widely attested (see Florentin 2005, 294).

conclusion, all these phonetic and morphological differences relate only to form. They are not differences in meaning.

5.0. Morphological Differences for Semantic Differentiation⁹

Here, too, we deal with neither words unattested in TH nor new meanings of existing words, but rather different morphologies, which are exploited for purposes of semantic differentiation. In other words, a word that in TH has two functions or meanings is divided in SH into two forms, each with a distinct meaning.

Some of these distinctions are grammatical. In the verbal system, they are used to establish an aspectual difference between a non-habitual action and one that is habitual, e.g., in *qal* the *qotel* pattern is used to express habitual action, whereas *qatil* expresses non-habitual action: הנחל היוֹרֵד מִן הָהָר ‘the brook that descended from the mountain’ (*ayyūrād*, Deut. 26.21) versus מַלְאֲכֵי אֱלֹהִים עֹלִים וְיֹרְדִים ‘the angels of God were ascending and descending’ (*wyārēdam*, Gen. 28.12).

More interesting semantically are similar meanings but differences in use, e.g., as opposed to TH בְּכוֹר ‘firstborn’, SH distinguishes between a generic firstborn, realised as *bākor*, and the firstborn for a sacrifice, *bikkor* (Deut. 15.19). The basic meaning of the MT בָּכָה ‘weep’ is expressed by the *qal*, e.g., *yēbēku* (Num. 13.11), but when ‘mourn’ is intended, the *piʿel* is used, e.g., *yēbakku* (Lev. 10.6). MT מוֹעֵד ‘meeting’ is pronounced in SP as

⁹ For a detailed discussion see Florentin (1996, 217–41).

muwwəd (Exod. 27.21), but when indicating ‘time’ it is realised as *muwwad* (Exod. 9.5).

A special case is the verb תאכל, for which SH has a special form when denoting ‘peeling off the skin’, a meaning unattested in TH exegesis. The derivations of אכל in the sense of ‘eat’ are expressed by *qal* verbs, e.g., אָכַל *ākāl*, תאכל *tā’ūkāl*. However, when the Samaritans interpret it as ‘peeling off the skin’, they pronounce it *tākkāl*, e.g., נפש אשר תאכל נבלה ‘And every soul who skins that which dies’ (Lev. 17.15). As for the meaning, it should be noted that some manuscripts of the Samaritan Targum (ST) render תאכל with the verb אכל and others with the verb גרף, i.e., they are not unequivocal as to the meaning of the word תאכל in the verse. Thus, it is possible that the distinction is not in meaning, but rather in use, i.e., ‘eating’ is simply expressed by the *qal* whereas ‘eating a carcass’ by the *pi’el*.

SP also distinguishes between proper and common nouns, which in MT share the same form. The proper noun *Jamin* יָמִין is pronounced *yāmān* (Gen. 46.8), while the common noun יָמִין ‘right’ is realised as *yammān*. More complex is the semantics of the word לָבָן, which is pronounced *lābān* (Gen. 30.35) when signifying ‘white’, is *lābān* (Gen. 24.29) when referring to Laban (לָבָן) Rebecca’s father, and is pronounced *libbān* (Deut. 1.1) when designating the toponym Laban (לָבָן).

6.0. Samaritan Contemporisation of Rare and Archaic Words

If the generally accepted assessment of SH is correct, then it is, on the whole, a linguistically modernised version of a more ancient language type. The modernisation is reflected mainly in the simplification of the language and the bringing of its forms closer to the language used in the Second Temple Period. Thus, we see in SP the almost complete absence of grammatical and archaic forms that do not correspond to the language of the period, e.g., instead of *וְחַיֵּיתוֹ-אֶרֶץ* ‘the beast of the earth’ (Gen. 1.24), SP reads *wayyāt āraṣ*, instead of *וּבְחֵתָנָה* ‘in its place’ (Gen. 2.21) SP has *tattiyya*, and instead of *לְדַעַתָּה* ‘to know’ (Exod. 2.4) SP has updated *al dāt*.

As part of this trend, obscure lexical forms, which probably seemed corrupt to the editors of the text, were also reworked. Thus, instead of *סוּתָה* ‘his vesture’ (Gen. 49.11 *ketiv*), SP has *kassūtu* in the same sense; instead of the rare and obscure *תִּרְיִד* ‘you grow restless’ (Gen. 27.40), SP shows *tādār* ‘you shall become powerful’; instead of *וּמִתָּן* ‘and a gift’ (Gen. 34.12) SP reads *wmāttāna* with the same meaning; instead of *וְהִעָרָה* ‘she emptied’ (Gen. 24.20) SP has *wtūrād* ‘she let it down’; instead of *הִצָּו* ‘contended’ (Num. 26.9) there is *uwwā’ēdu* ‘gathered’; and instead of *רִבְּבָקָךְ* ‘your strength’ (Deut. 33.25), *rābbak* ‘your greatness’. While TH has three words signifying ‘dread’—*חֵת*, *חֵתָה*, *חֵתָת*—only *חֵת* is attested in SP, e.g., TH *וְחֵתְכֶם* ‘your dread’ (Gen. 9.2) versus SP *wātātkimma*; in MT, the noun *חֵתָה* is found only outside the Torah (Job 6.21).

Even so, none of these changes gave rise to new words in SP. At most, we have in this version new morphological forms of existing words, but very rarely new derivations, such as MT's contextually difficult substantive פָּחוּז 'unstable' (Gen. 49.4), which was replaced with the verb פָּחוּזת *fā'izta* 'you have been unstable'.

7.0. Proper Nouns

This group of nouns reflects, to a significant extent, the character of the lexical differences between the two traditions. SP morphology differs greatly from its MT counterpart. Sometimes the differences are between vowels, as in עֹבָל 'Obal' (Gen. 10.28) versus עִיבָל *ibāl* in SP. Sometimes the proper nouns differ consonantly due to (1) sound shift, e.g., בְּנִימִין 'Benjamin' versus בְּנִימִים *binyāmām*, or (2) graphic confusion, e.g., דֹּדָנִים 'Dodanim' versus רֹדְנִים *rūdānām* (Gen. 10.4), צִדְדָּה 'toward Zedad' versus צִרְדָּה *ṣāridda* (Num. 34.8), וְשִׁמְאֵבֶר 'and Shemeber' versus וְשִׁמְאָבֶד *wšam'abbād* (Gen. 14.2).

In some cases, the proper nouns differ in MT and SP in a particular verse, e.g., the oft-cited difference בְּהָרַ עִיבָל 'on Mount Ebal' in MT versus בְּהָרֵי גֵרִיזִים *bārgārīzām* 'on Mount Gerizim (written as a single word)' (Deut. 27.4), or בְּשִׁמְתָּה 'Basemath (Esau's wife)' versus מַחֲלַת *mā'elāt* (Gen. 36.3; cf. MT מַחֲלַת 'Mahalath [daughter of Ishmael]' Gen. 28.9). However, all these proper nouns also appear elsewhere in SP and MT. The difference in these cases is, therefore, only in the distribution of the words.

Sometimes a proper noun is interpreted as a common noun, such as וְכַלְנֵה 'and Calneh' (Gen. 10.10), which the Samaritans

read *wkallinna* ‘and all of them’, i.e., the noun כל + 3FPL pronominal suffix. In this case, too, SP exhibits no lexical innovation.

8.0. Morphological Differences with Specialised Lexical Meanings

There are not many such words and they are similar in form to their MT parallels. Representative examples are

- (a) The verb יִפֹּת (short imperfect of פת"י) in the verse יִפֹּת אֱלֹהִים לְיִפֹּת ‘May God enlarge Japheth’ (Gen. 9.27) is pronounced by the Samaritans *yefat* (see above, §4.0). A secondary root יפ"ת was created, whose meaning ‘beautiful’ is reflected in the translations into Aramaic יפה (in MS A of the ST) and Arabic (يحسن). But it must be stressed that, while the form of the Samaritan verb is unambiguous, its interpretation by the Samaritans is not uniform, since another manuscript of ST has יִפְתִּי, as in MT.
- (b) Instead of MT וַיֵּרֶק אֶת־חֲנִיכָיו ‘he led forth/mustered(?) / armed(?) his trained men’ (Gen. 14.14), the Samaritans read וידק *wyiddāq*, a verb derived from דק"ק, a variant of דו"ק ‘see’, probably related to Akkadian *deku* ‘mobilise troops’. If one follows ST זיאן (which is also attested in Targum Neofiti to MT [!]), one may interpret וידק as ‘equipped’.
- (c) The interrogative הלוּא is pronounced by the Samaritans *ā'lū* (usually written הלוא). Unlike MT, it does not include the negating particle לא, pronounced by the Samaritans *lā* (and always written without *mater waw*). In SH, it is rather an interjection probably related to the presentative

particle אֲלוּ in Biblical Aramaic, which was realised variously elsewhere in Aramaic: אַרִי, אַרוֹם, אַרִי, הֶלוּ, and in Mishnaic Hebrew (MH) as הִרִי. For this reason, while almost all English translations of MT render הֶלוּא ‘is it not?’, in our translation of SP (Florentin and Tal 2025), we prefer to render אֲלוּ as the interjection ‘behold’.

- (d) A clear case of a lexical difference involves the enigmatic TH word מְכַרְתֵּיהֶם (Gen. 49.5) versus SP מכרתיהם *makrēṭīyyimma*. In MT, the word has been given some thirty interpretations (Florentin 2001, 189–202). Regardless of its obscure etymology in MT, it differs from the Samaritan *makrət*, which is derived from כִּרַּת (for its meaning see below, §9.0).

9.0. Samaritan Exegesis

The meaning of מכרתיהם *makrēṭīyyimma* in SP—‘their swords’ or ‘their alliance’—brings us to the focal point of difference between the Samaritan lexicon and that of MT, i.e., interpretation and exegesis. Indeed, in most cases SP does not reflect a different vocabulary, but different ways of interpreting the text. Since the Samaritan exegesis of SP, like that of MT, is not uniform, one often finds that a particular Samaritan interpretation differs from the accepted interpretation of the MT, but that a second way of interpretation corresponds to the accepted interpretation in MT. In many cases the Samaritan interpretation contradicts the version that emerges from the reading tradition.

- (a) The noun צרה ‘distress’ is spelled in Samaritan manuscripts both צרה and צרעה (!). In the verse על כן באה אלינו

כל הצרה הזאת ‘Therefore all this trouble comes to us’ (Gen. 42.21), it is pronounced by the Samaritans *āṣṣ'ra*. In fact, this reading fits the pronunciation of the noun צרעה ‘hornet’ (the noun צרה ‘trouble’ is pronounced *ṣārrā*). Thus, in contrast to MT הצרה, SP *āṣṣ'ra* ‘hornet’—with its two written ‘allo-variants’ הצרה and הצרעה—is the version before us. However, the Samaritan translations into Aramaic (ציקתה, עקתה) and Arabic (الضيقه) show that translators interpreted this word as ‘distress’, rather than ‘hornet’. Is *āṣṣ'ra* a late tradition, which substituted the alleged original *āṣārrā*? Whatever the case may be, here, too, the issue is not a difference in lexical inventory, but rather in lexical distribution in the text.

- (b) The noun שָׁפִיפֹן ‘viper’ (Gen. 49.17) is pronounced by the Samaritans *šāfāfon* (and spelled accordingly שפפון). This is ostensibly just a morphological difference, and indeed there is no hint in SP that the text presents a different word with a different meaning. However, ST renders it as מִבְּמָן ‘hidden’, i.e., שפפון was perceived as an adjective derived from the root שפ"ף ‘bent’, which is not attested in BH.

Should a Samaritan dictionary include the different interpretations offered by the Samaritan sources for each and every word? The biblical lexicons of MT do not present all the interpretations of a given word and neither should a SH dictionary of the Pentateuch.

Indeed, the field of Samaritan studies awaits a comprehensive study of the Samaritan interpretation of the Torah in all its

details no less than a Samaritan dictionary or a detailed monograph that presents the uniqueness of the Samaritan lexicon of the Torah.

References

- Ben-Ḥayyim, Ze'ev. 1977. *The Literary and Oral Tradition of Hebrew and Aramaic amongst the Samaritans*, vol. 4. Jerusalem: Bialik Institute. [Hebrew]
- . 2000. *A Grammar of Samaritan Hebrew*. Jerusalem: The Hebrew University Magnes Press and Winona Lake, IN: Eisenbrauns.
- Castro, Pérez F. 1959. *El Séfer Abiša*. Madrid: C.S.I.C.
- Florentin, Moshe. 1996. 'Studies in the Morphology of Samaritan Hebrew'. *Leshonenu* 59: 217–41.
- . 2001a. 'כלי חמס מכרתייהם' and the Samaritan Version of the Pentateuch'. *Leshonenu* 63: 189–202.
- . 2001b. *Late Samaritan Hebrew: A Linguistic Analysis of its Different Types*. Leiden: Brill.
- Florentin, Moshe, and Abraham Tal. 2025. *The Samaritan Pentateuch: An English Translation with a Parallel Annotated Hebrew Text*. Cambridge Semitic Languages and Cultures 30. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers.
<https://doi.org/10.11647/OBP.0415>
- Gesenius, Wilhelm. 1815. *De Pentateuchi samaritani origine, indole et auctoritate, commentatio philologico-critica*. Halle: Renger.

- Schorch, Stefan. 2013. *A Critical Editio Maior of the Samaritan Pentateuch: State of Research, Principles, and Problems*. Hebrew Bible and Ancient Israel 2. Berlin: De Gruyter.
- Tal, Abraham, and Moshe Florentin. 2010. *The Pentateuch: The Samaritan Version and the Masoretic Version*. Tel-Aviv: The Haim Rubin Tel-Aviv University Press.
- Tov, Emanuel. 2012. *Textual Criticism of the Hebrew Bible*. Minneapolis, MN: Fortress Press.
- von Gall, August F. 1918. *Der hebräische Pentateuch der Samaritaner*. Giessen: Töpelmann.

SOME CASES OF GRAMMATICALISATION IN MISHNAIC HEBREW AND THEIR DIACHRONIC IMPLICATIONS

Edward Cook

The transition from Old to Middle Hebrew was a watershed, catalysed by new historical and societal factors that gave greater impetus to an Aramaic substratum and irrevocably and permanently changed the Hebrew language (Cook 2017; 2021). The differences between Old (Biblical and Qumranic) Hebrew and Middle (Mishnaic) Hebrew are so stark that they make the variations between stages and dialects of Old Hebrew seem minor in comparison. Nevertheless, an appreciation of the effect of Aramaic interference should not lead us to discount the amount of continuity between the Old and Middle stages of Hebrew. An examination of some instances of grammaticalisation in Mishnaic Hebrew (MH) casts light on the nature of this continuity.

This essay is offered with admiration and affection to Geoffrey Khan, with warm memories of his visit to Washington to deliver the inaugural Henri Hyvernât Lecture at the Catholic University of America in 2012 and of his kind hospitality during our visit to Cambridge in 2016.

1.0. The Conjunction הוֹאִיל - 'because, since'

The particle הוֹאִיל, invariably followed by the conjunction -וְ, is self-evidently a grammaticalisation of the Biblical Hebrew (BH) verb הוֹאִיל (*hif'il* of a putative root יא"ל that occurs in no other stem). In the Bible, הוֹאִיל appears 18 times, sometimes with an infinitive complement (Gen. 18.27, 31; Exod. 2.21; Josh. 17.12; Judg. 1.27, 35; 17.11; 1 Sam. 12.22; 1 Chron. 17.27), but also as a co-verb, as the first verb in a paired sequence, connected syntactically or asyndetically (Deut. 1.5; Josh. 7.7; Judg. 19.6; 2 Sam. 7.29; 2 Kgs 5.23; 6.3; Hos. 5.11; Job 6.9, 28). In both constructions it functions as an auxiliary to the verbal form that follows it and never appears on its own.

Contextually, some such gloss as 'desire, resolve, consent (to do something)' yields a good sense in all of the occurrences; semantically, it expresses the act of will that generates the action signified by the verbal form that follows, e.g., **וְהוֹאִיל** הָלֹךְ לְשֹׁבֵת אֶת- 'the Levite **resolved/decided** to live with the man' (Judg. 17.11); **הוֹאִיל** הָלֵךְ אַחֲרֵי-צִו 'he **was determined** to go after vanity' (Hos. 5.11); **הוֹאִיל** מֹשֶׁה בְּאֵר אֶת-הַתּוֹרָה הַזֹּאת לֵאמֹר 'Moses **undertook** to expound this instruction' (Deut. 1.5). In the imperative, it means little more than 'please': **הוֹאִלְ** וּבֵרַךְ אֶת-בֵּית עַבְדְּךָ: 'now, **be pleased** and bless the house of your servant' (2 Sam. 7.29); **הוֹאִלְ** גַּם וְלֵין 'please spend the night' (Judg. 19.6).

הוֹאִיל was used, like its complements, only with personal (human or divine) subjects. With finite complements, it agreed in number, gender, and tense. In these respects, it functioned like a full-fledged verb; but it had lost some of its autonomy in that it

always had to be linked with another verbal form and could not be used by itself.

In the Mishna and other Tannaitic sources,¹ we find the invariant form הוֹאִיל followed by -י in the meaning ‘because, since’, used at the head of a clause, e.g., הוֹאִיל וְנִשְׁחַט שְׁלֹא עַל פִּי מוֹמָקָה אֲסוּר וְלָמָּה מְזַכְּרִין אֶת דְּבָרֵי יַחֲיד בֵּין הַמְּרֻבֵּין הוֹאִיל וְאֵין הַלָּכָה אֶלָּא כְּדִבְרֵי הַמְּרֻבֵּין ‘since it was slaughtered not by the command of an expert, it is prohibited’ (m. Bek. 4.3); וְלָמָּה מְזַכְּרִין אֶת דְּבָרֵי יַחֲיד בֵּין הַמְּרֻבֵּין הוֹאִיל וְאֵין הַלָּכָה אֶלָּא כְּדִבְרֵי הַמְּרֻבֵּין ‘why do they mention the opinion of an individual among the majority, since the *halakha* follows the opinion of the majority?’ (m. Eduy. 1.5); מָה אֶכְפֹּת לָךְ הוֹאִיל וְאֵנִי נֹתֵן לָךְ חֲבוּרָךְ ‘what is it to you, since I am giving you your rental?’ (m. Bab. Mes. 9.4); הוֹאִיל וְאָמְרָה תוֹרָה תֵּן תְּפִלִּין בְּרֹאשׁ ‘since the Torah said, Put tefillin on the head, put tefillin on the hand (as well)’ (*Mekhilta*, Lauterbach 2004 [1933], I:102).

The clause headed by הוֹאִיל may be either verbal or verbless (i.e., copular); if verbal, the verb must be in the past or the present (participial) tense. The meaning ‘since’ is never temporal, but always introduces a reason or motivation for a particular conclusion or remark.

In the centuries between the biblical and the tannaitic examples, הוֹאִיל evidently lost its ability to inflect as a verb, as well as its independent meaning, and was converted wholly into a causal conjunction—in short, it underwent grammaticalisation. This was clearly seen by Wilhelm Bacher over a century ago:

¹ The Mishnaic citations are taken from the transcription of the Kaufmann MS as contained in the Mishna module of Accordance Bible Software (MISH-T, Accordance 12.3.7).

Das nur zur Einführung des Hauptverbuns dienende und an sich keinen eigentlichen Inhalt darbietende Verbum verlor durch den Gebrauch seine Bedeutung und seine Betonung; es erstarrte gleichsam and wurde zur Partikel: das Verbum wurde zur Conjunction und der begründende Hauptsatz zu einem Nebensatze des Grundes. (Bacher 1905, 38)

That grammaticalisation happened is clear, but the process is less clear. We are forced to infer almost all of the intermediate steps between BH הוֹאִיל and MH הוֹאִיל־ן. The BH occurrences show the incipient loss of autonomy due to auxiliation, and the MH usage shows the complete change of category from verb to clausal subordinator.

Bacher suggested that a sentence, such as הוֹאִיל וְאָמַר הַכָּתוּב ‘the scripture desired to say’, was used as an exegetical justification for a ruling. This eventually led to a reinterpretation of הוֹאִיל as ‘since the scripture said’, which in turn led to the release of הוֹאִיל from its verbal origins and its consequent transformation into a pure particle—bringing with it into its new role the residual, and now meaningless הוֹאִיל־ן, as an invariable accompaniment. He placed the evolution of the form completely within an exegetical context and, by implication, within the rabbinic period (Bacher 1905, 51–52).

This would imply that lexical הוֹאִיל in the meaning ‘want, wish, consent’ was known in the rabbinic period. However, there is some evidence that later generations had forgotten the meaning of lexical הוֹאִיל before the rabbinic period (the time of the *Tanna'im*). The major ancient translations (LXX, Vulgate, Targum) frequently translate it as ‘begin’, and the Tannaitic midrash

Sifre (2nd century CE) says explicitly (with regard to Deut. 1.5) *הואיל אין הואלה אלא התחלה* ‘*he uayil* means to *begin*’. The earliest attestation of this is in the Septuagint; in eleven of the eighteen occurrences of *הואיל*, the Greek translates it as ‘begin’; in the other seven, it either does not translate it or translates *ad sensum* (never using a word meaning ‘desire/wish’). The targumic evidence is also important, since the targums (unlike the Vulgate) are less likely to have been influenced by the LXX. (The gloss ‘begin’ has left some traces in modern lexicography,² but is not considered primary.) In short, it was a traditional guess to render *הואיל* as ‘begin’, but there are no clear Hebrew attestations of the word in that meaning, and it seems that lexical *הואיל* had fallen out of use by post-biblical times.³ Its grammaticalisation must have taken place long before the rabbinic period.

Therefore, *הואיל*’s ‘off-stage’ evolution into a particle most probably took place within the biblical era, although the particular idioms and implicatures which motivated this change are now irretrievable. (Possibly the change followed a semantic line from *be willing, consent* > *grant, admit* > *granted, admittedly* > *given that, since*.) By the late centuries BCE, the meaning of the

² Gesenius’s first edition (1815) lists *anfangen* as one sense, but this survives only as *sich an etw[as] machen, etw[a] in Angriff nehmen* (i.e., to address oneself to a task) in Gesenius-Buhl (1905), citing Deut. 1.5, and the recent volume by Dietrich and Arnet follows suit (2003, 200). BDB and the *Dictionary of Classical Hebrew* do not include ‘to begin’ among the senses.

³ The Peshiṭta does translate with words meaning ‘wish, desire’ (Exod. 2.21; Josh. 17.12; Judg. 1.35; 19.6; 1 Sam. 12.22; 2 Kgs 6.3; Hos. 5.11; Job 6.9, 28). These are most likely accurate *ad sensum* guesses.

lexical etymon הוֹאִיל had been forgotten, but the conjunctive combination הוֹאִיל-ן survived in the vernacular dialect that, transformed by Aramaic interference, eventually became MH.

It is apparent that contact with Aramaic did not cause the grammaticalisation of הוֹאִיל, for Aramaic does not have any conjunctions that are formally or functionally similar to it. Nor have any Aramaic verbs of the same semantic range undergone a similar process of grammaticalisation. This is a process that is explicable completely in terms of internal Hebrew development.

2.0. The Conjunction כְּדִי ‘in order to, in order that’

The conjunction כְּדִי is transparently a combination of the preposition כִּי and the lexical word דִּי ‘(sufficient) amount’, in construct דִּי. In BH, the substantive is used in a number of ways both with and without prepositions. In construct with another noun, it means ‘enough X for’ something, e.g., **דִּי** מִחֶסֶדְךָ **דִּי** תַּעֲבִידְךָ **דִּי** ‘you shall lend him **enough** (money) for his need’ (Deut. 15.8); **דִּי** בָּעֵר וְחִיתוֹ **דִּי** אֵין **דִּי** עוֹלָה **דִּי** ‘Lebanon is not **enough** (wood) for fuel, and its beasts not **enough** (meat) for a burnt offering’ (Isa. 40.16); **דִּי** חֵלֶב עֲזִים לְלֶחֶם **דִּי** | **דִּי** ‘(There is) **enough** goats’ milk for your food’ (Prov. 27.27). The preposition כִּי can be added to דִּי without apparent difference in meaning: **דִּי** גְּאֻלָּתוֹ **דִּי** **כִּי** ‘**enough** (money) for his redemption’ (Lev. 25.26).

Words like דִּי meaning ‘enough’ express scalar quantification, so that some item or quality necessary for enabling a partic-

ular situation has reached the critical enabling point on an implicit scale.⁴ Besides the enabling item and enabled situation, the syntactic expression of the quantification in BH may include the possessor of the item, or agents otherwise involved in the situation, e.g., דָּבַשׁ מֵצֵאתָ אֲכַל דִּיָּךְ ‘If you have found honey, eat **enough** (honey) **for yourself**’ (Prov. 25.16). Here the enabler is honey, the enabled situation is, tacitly, the satisfaction of hunger, and the possessor of the honey is encoded in the pronominal suffix.

In MH, כָּדִי also has the meaning of ‘enough’: כָּדִי תְרוּמַת מַעֲשֵׂר וְחֻלָּה ‘**enough** [item] for the offering of tithe and bread’ (m. Dem. 2.4)—enabled situation as the complement; כָּדִי חֻלָּה מֵעִיסָה ‘**enough hallah** from the dough’ (m. Ḥal. 4.6), with the item as the complement. This usage matches the biblical usage.

כָּדִי is also used with an infinitive verbal complement, e.g., לְנַעֲנִיעַ בּוֹ כָּשֵׁר לְיָדָיו שְׁלֹשָׁה טַפָּחִים כָּדִי ‘a *lulav* three hand-breadths, **enough** (length) to shake with it, is valid’ (m. Sukk. 3.1). The verbal complement may also take the form of -שׁ plus the imperfect: וּבְגָדוֹל כָּדִי שִׁיאָחֲזוּ שְׁנַיִם בְּיָדוֹ אֶחָת ‘In size, **enough that** one may hold two (*etrogs*) in one hand’ (m. Sukk. 3.7).

Since the concept ‘enough’ already entails a situation that comes about as the result of some enabler, the word כָּדִי eventually comes to mark that situation as the goal of some other action, without any implied quantification of an enabler. Consider the following instance: מִבְּחוּץ כָּדִי שִׁיְהוּ הַמִּצְרִים רוֹאִין וּמִיַּעֲהֵם מִתְּחַתְּכִין [referring to whether the Passover blood should be displayed inside

⁴ This analysis is indebted to the description and terminology used by FrameNet (<https://framenet.icsi.berkeley.edu/fndrupal/luIndex>), s.v. *Sufficiency*.

the house or outside] ‘Outside, כְּדִי ש- the Egyptians will see and their bowels will be upset’ (*Mekhilta*, Lauterbach 2004 [1933], I:59). Here there is no suggestion that the amount of blood is at issue. It is not whether the blood is ‘enough’, but where it is to be located. If it is outside, then the Egyptians will be able to see it and will be afraid. The enabling situation is polar (inside versus outside), not scalar, as in the ‘enough’ scenario, and this shows that the meaning ‘enough’ can recede from כְּדִי and it can be used as a simple marker of purpose, i.e., it has undergone grammaticalisation.

This is particularly clear with negative purpose clauses, as in the following: פִּיאָה אֵין קוּצְרִין אוֹתָהּ בַּמַּגְלוֹת וְאֵין עוֹקְרִין אוֹתָהּ בְּקַרְדּוּמוֹת: ‘כְּדִי שְׁלֹא יָבוּ אִישׁ אֶת רֵעֵהוּ’ (As for) *pe’a*: they do not harvest it with sickles or uproot it with spades, **so that one may not** strike another (with the tool)’ (m. *Pe’a* 4.4). Since the ‘enough’ schema requires an enabled situation, a ‘disabled’ situation, so to speak, is excluded by definition; if כְּדִי is used simply to introduce a purpose clause, then the clause can be negated. This is the clearest expression of the extension of כְּדִי into its new function.

Thus far all is clear, and there is no indication that any move in this semantic evolution is indebted to outside influence, such as from Aramaic. However, there is a similar construction in Aramaic, where the word for ‘enough, sufficiency’ is *missat* or *messat*. Like כְּדִי, *missat* is a noun in construct that became frozen and indeclinable.

In Syriac, the word came to serve as a conjunction to introduce purpose clauses: **ܟܕܝܢܐ** ‘**so that** he should have a little comfort from Hagar’ (Aphrem on Gen.

73.9); ܠܗܝܠܟܝܢ ܠܥܝܢܐ ܠܥܡܡܝܬܐ ܠܐ ܡܨܬܐܝܬܐ ‘so that the ranks of the priesthood should not be levelled’ (Theodore bar Koni 129.20) (exemplification from Sokoloff 2009, 796), and elsewhere.

Although these examples from literary Syriac come from a time after the development of MH, it is unlikely that they have been influenced by it; most of the Hebrew influence on Syriac comes in the form of religious terms borrowed from BH. But is it possible that the influence could have gone in the other direction?

The evidence for Aramaic usage is chronologically vast, but, for the earlier dialects, very sparse from the perspective of corpus linguistics. Whenever a new discovery of an early Aramaic text is made, later dialects have to be drawn on for purposes of lexical and grammatical comparison. That this is so often effectively testifies to a rather high degree of homogeneity in the history of Aramaic, perhaps due to the long influence of Imperial Aramaic on its literary expression and to the probable existence of an Aramaic dialect continuum across the Near East that began in the first millennium BCE and lasted until almost the end of the first millennium CE. For this reason, it is justified to draw on all the Aramaic dialects (before the modern period) to reconstruct the Levantine dialect(s) that served as a substratum during the development of MH in the late Second Temple Period.

This has to be done with caution, however, and the later rabbinic Jewish dialects that were in close contact with MH sources should probably be considered as ineligible for this purpose, especially if the relevant *comparanda* are limited to these dialects alone. They might have been influenced by Hebrew. But

Syriac presents a different picture; since it is unlikely to have been influenced by MH, any similarities between the two must be due to parallel development or prior Aramaic influence on MH.

Therefore, the use of *messat* to introduce purpose clauses in Syriac might testify to a broader Aramaic use which formed part of the Aramaic substratum of MH. I am inclined to doubt this, however. The path of development in MH of כְּדִי is fully documented and presents no sudden leaps, gaps, or oddities that might betray outside influence. The same is true, indeed, of Syriac *messat*, which suggests that this is a case of parallel development. The functional expansion of כְּדִי is fully explicable in terms of continuous development within Hebrew, beginning from the attested usages in the biblical dialect.⁵

3.0. The Particle בְּשִׁבִּיל ‘for the sake of, in order that, so that’

בְּשִׁבִּיל is a grammaticalised form of the noun שֶׁבִּיל ‘road, path’, plus the preposition בְּ-. The noun itself occurs twice in the Hebrew Bible (Jer. 18.15; Ps. 77.20), and a few times in Hebrew Ben Sira (5.9) and the Qumran literature (4Q184 1.9; 4Q266 2 ii 3; 4Q275 1.1). It is noticeably more common in Aramaic sources and may be an Aramaic loan in Old Hebrew.

⁵ The form בְּכִדִּי seems to have developed later to mark the meaning ‘enough’. It is rare in Tannaitic sources (e.g., t. Kil. 2.12).

In Tannaitic literature, the noun also appears (m. Pe'a 2.1; m. Bava Mets. 2.3; etc.), but is vastly more frequent in its grammaticalised form with *-בְּ*, as a beneficiary preposition *בְּשָׂבִיל* 'for, on behalf of' or as a conjunction *בְּשָׂבִיל שֶׁ-* 'in order to', introducing purpose clauses. The grammaticalised form does not appear in Aramaic.

Since words for 'road, path' are not known to grammaticalise directly into purpose clause particles, some intervening change likely occurred that, in turn, led to the purpose grammaticalisation. This intervening process was probably the use of 'road, path' as a marker of the allative.

Allative morphemes—i.e., those that mark "spatial goals, directions, or destinations" (Rice and Kabata 2007, 452)—are often associated with grammaticalised forms of motion verbs (Heine and Kuteva 2002, 160), but there is no reason why 'path' nouns may not lend themselves equally well for use as allatives. In fact, the prototypical 'path' noun in Old Hebrew, i.e., *דֶּרֶךְ*, is already used allatively in the Hebrew Bible, with the meaning 'toward': *וְהִתְפַּלְּלוּ אֶל־יְהוָה דֶּרֶךְ אֲשֶׁר בָּחַרְתָּ בָּהּ וְהַבַּיִת אֲשֶׁר־בָּנִיתִי לְשִׁמְךָ* 'they pray to the LORD **toward** the city that you have chosen and the house that I have built for your name' (1 Kgs 8.44 NRSV). This example is particularly telling, since the verb with which the noun occurs, i.e., 'pray', is not a motion verb, demonstrating that the original nominal meaning of the lexeme was neutralised in this context.

However, this usage of *דֶּרֶךְ* does not further grammaticalise towards becoming a marker of purpose clauses. Although it is reasonable to suppose that nominal *שָׂבִיל*, joined to *-בְּ*, similarly

became an allative marker (*on the way to* > *toward*) and then developed into a purpose clause marker (*toward* > *in order to*, cf. Heine and Kuteva 2002, 39), the process is not documented.

The primary explicit marker of purpose clauses in BH is לְמַעַן, used in much the same way as MH בְּשֵׁבִיל; it is not used in MH, except in biblical quotations. It must have been confined to the literary register in the Second Temple Period, and was evidently not present in the hypothetical vernacular Old Hebrew that formed one of the ingredients of MH

However, the particle בְּשֵׁל, a calque of Aramaic בְּדִיל, is used in some Late Biblical Hebrew texts (Jonah and Qohelet), as well as in 4QMMT. In Tannaitic Hebrew, בְּשֵׁל disappears and is replaced by בְּשֵׁבִיל. A few examples will suffice to show how they are used in the same way: **בְּשֵׁל שֶׁא** 'so that the pure might sprinkle on the impure' (4Q394 3–7 i 19), compared to **בְּשֵׁבִיל שֶׁתִּהְיֶה מְנוֹטֶפֶת** 'so that it shall keep dripping' (m. Shab. 2.4); **בְּשֵׁל שֶׁתִּשְׂמַח** 'so that you might rejoice' (4Q398 14–17 ii 6), compared to **בְּשֵׁבִיל שֶׁיִּכָּנֵס הַדָּם לְתוֹכָהּ** 'so that the blood might flow into it' (m. Hul. 2.9); as prepositions, cp. **בְּשֵׁלִי הַסַּעַר הַגָּדוֹל הַזֶּה** 'because of me is this great storm' (Jon. 1.12) and **בְּשֵׁבִילִי נִבְרָא הָעוֹלָם** 'because of me was the world created' (m. Sanh. 4.5).

בְּשֵׁל, as noted, is a calque on Aramaic בְּדִיל. בְּשֵׁבִיל, on the other hand, is not a calque on any Aramaic form, i.e., there is no equivalent Aramaic grammaticalisation which it might have sought to duplicate. Formally, at least, it is purely Hebrew. However, as noted, it functions in the same way as בְּדִיל and בְּשֵׁל, respectively, an Aramaic conjunction/preposition and its Hebrew

calque. In addition to this functional similarity, a rough phonological similarity exists. Yet, the question remains: why did *בְּשֵׁל* fall out of use to be replaced, as it seems, by *בְּשָׁבִיל*?

To answer this question, we begin by noting that the sequence *שֵׁל+בְּ* does exist in Tannaitic Hebrew, specifically as a combination of two separate morphemes, as in the following examples: *כָּל יוֹם הָיָה חוֹתָה בְּשֵׁל כֶּסֶף וּמַעֲרָה בְּתוֹךְ שֵׁל זָהָב* ‘every day he used to scoop out *with (a pan) of* silver and empty it into (a pan) of gold’ (m. Yoma 4.4); *בְּרֹאשׁ הַשָּׁנָה תּוֹקְעִין בְּשֵׁל זָכָרִים, וּבַיּוֹבֵל בְּשֵׁל* ‘at the New Year they blow *with (horns) of* rams, and on the Jubilee *with (horns) of* wild goats’ (m. Rosh ha-Shanah 3.5). The meaning of *בְּשֵׁל* here is just the meaning of the two morphemes that compose it, *בְּ* ‘in, with’ and *שֵׁל* ‘of’. By contrast, the older particle *בְּשֵׁל* is monomorphemic with a non-compositional meaning. As a result, the sequence *בְּשֵׁל* could be ambiguous between a bimorphemic ‘with (the one) of’ and a monomorphemic reading ‘because of’.

Thus, the functions of *שֵׁל* developed in such a way that it led to ambiguous readings between the monomorphemic preposition *בְּשֵׁל* ‘for the sake of, in order that, so that’ and bimorphemic *שֵׁל+בְּ*. Although in most cases context would have prevented serious confusion, it is possible that *בְּשָׁבִיל* became favoured as an unambiguous alternative to monomorphemic *בְּשֵׁל*. The latest attestation of (conjunctive) *בִּשְׁל* is in Mur. 46.7, a letter from Yonatan b. Maḥanaim to Yose b. Galgula around 133 CE: *בִּשְׁל שִׁיבוּ לוֹ* ‘*so that* it would come to him’ (*DJD* 2, 165). The earliest attestation of *בְּשָׁבִיל*, in a fragmentary context, is in Mur. 47.4, a frag-

mentary letter from the same period (*DJD* 2, 167). After this period, monomorphemic בָּשָׁל is no longer used and בִּשְׁבִיל takes its place.

4.0. The Conjunction כִּי־ן ‘as soon as, when’

The hollow root כו"ן is used to form the adjective כִּי־ן ‘straight, right, honest’, which has been grammaticalised as a temporal conjunction ‘as, since, as soon as’. The word is likely of Aramaic origin, since Hebrew does not natively form words from hollow roots with consonantal *waw*. In fact, as an adjective, the word appears almost exclusively in Aramaic, in Targums Onkelos and Jonathan: אֱלֹהֵא דְכִי־נָא אִוְרַחִיה *‘God, whose way is right’* (TJ 2 Sam. 22.31); כָּל דְּמַהֲלִיד בְּזָכוּ וּמַמְלִיל כִּי־נָא *‘all who walk in innocence and speak right words’* (TJ Isa. 33.15); וְרַגְלֵיהֶן רַגְלִין כִּי־נָא *‘their legs were straight legs’* (TJ Ezek. 1.7); לֹא נָפִיק דִּינָא כִּי־ן *‘the law does not go forth rightly’* (TJ Hab. 1.4).

כִּי־ן is attested only once in Tannaitic Hebrew as a deadjectival adverb. But its appearance as a subordinating conjunction is impossible to understand without assuming a prior history as an adjective or adverb: אֶחָד יוֹרֵד לְאַמַּת הַשְּׁחִי וְאֶחָד פּוֹתֵחַ כִּי־ן *‘(as for the two keys,) one goes down (into the lock) as far as the armpit, and the other opens (the door) at that exact moment’* (m. Tamid 3.6). (Another adverbial occurrence is in post-Tannaitic Hebrew: כִּי־ן *‘it is possible to make it [a Syrian cake] in a mould, and it would shape it right away’* [b. Pesah. 37a].)

In MH, the word *בִּיּוֹן* is used preceding the complementiser *-שׁ* to introduce temporal clauses, ‘when, as soon as’. The following examples are typical. It may be temporal and marked for simultaneity: *בִּיּוֹן שֶׁהִיא נוֹתֶנֶת אֶת הַמִּים מִגְבֶּהֶת חֻלְתָּהּ* ‘as soon as she puts the water in, she removes her dough offering’ (m. Ḥal. 3.1); *בִּיּוֹן שֶׁכָּפַר בּוֹ חַיִּיב* ‘the moment he has denied him, he is liable’ (m. Shevu. 5.1); *בִּיּוֹן שֶׁהִשְׁלִים מָת* ‘just as he fulfilled (his vow), he died’ (m. Nazir 1.7); or it may be temporal, without the implication of simultaneity: *בִּיּוֹן שֶׁנִּתְמַרְחַ הַגּוֹרֵן לֹא יֵאָכֵל עַד שִׁיעֶשֶׂר* ‘when the threshing floor is clear, he may not eat until he tithes’ (t. Ma‘as. 1.6); *בִּיּוֹן שֶׁעֲמָדוֹ שְׁבִטִים לִים זֶה אֹמֵר אֵין אֲנִי יוֹרֵד תַּחֲלָה לִים זֶה אֹמֵר אֵין אֲנִי יוֹרֵד תַּחֲלָה לִים* ‘when the tribes stood at the sea, one would say, I am not going in first to the sea, and the other would say, I am not going in first to the sea’ (Mekhilta, Lauterbach 2004 [1933], I:155, apparatus). In post-Tannaitic Hebrew, it may be causal: *בִּיּוֹן שֶׁלֹּא שָׁמְעוּ גִּלּוֹ* ‘because they did not obey, they went into exile’ (Lamentations Rabba⁶).

The use of *בִּיּוֹן* as a subordinator is most readily understood as an extension of its use as an adverb in the sense ‘just then, right away, at that moment’, itself an extension of the adjectival ‘true, right, proper’. Partial parallels for the use of words meaning ‘right, true, proper’ to indicate temporal simultaneity can be found in European languages, such as English *just* ADJ ‘right, proper’ > *just* ADV ‘exactly’ (derived from French *juste*) > *just as* (adverbial modifier of conjunction). The extension to causal conjunction does not take place in English.

⁶ Text according to <https://web.archive.org/web/20120801081906/http://www.tsel.org/torah/midrashraba/eicha.html>.

Although the adjective itself is a borrowing from Aramaic, it is not clear that the extension to temporal subordinator was also borrowed from Aramaic. The extension does occur in later Jewish Aramaic, as in the Palestinian Targums: **כיון** דנפקו תריהון **when** the two of them went out in the field' (TN Gen. 4.8); **כיון** די אשכחו כתיב בגוזה לא תהוון קטולין לא קבילו יתה; **when** [or perhaps **because**] they (the Edomites) found written in it (the Torah) "Don't be killers," they did not receive it' (TN Deut. 33.2). It is also used in Babylonian Aramaic (examples taken from Sokoloff 2002, 574–75): **כיון** דעתירי מפנקי ולא עבדי עבידתא: **since** the rich are pampered and do no work' (b. Shab. 54a); **כיון** דאגבהיה: **as soon as** he lifted it up, he fulfilled his obligation' (b. Pesah. 7b).

How should we assess these Aramaic occurrences? Since the original adjective is itself Aramaic, it is possible that the grammaticalisation occurred in Aramaic, and then entered Hebrew. However, all the Hebrew attestations of the grammaticalised form are uniformly earlier than the Aramaic ones, and there are no Aramaic attestations from non-Jewish dialects. This is consistent with a hypothesis of Jewish Aramaic borrowing from Hebrew, rather than Aramaic interference in Hebrew.

5.0. Conclusions

The examples of **הואיל** and **כדי** suggest that one of the ingredients of MH was a vernacular whose history was continuous with Old Hebrew as documented, as a literary register, in Classical Biblical Hebrew. This implies that the origin of MH does not lie in a dialect separate from BH (against the view of, e.g., Koller 2017, 152–

55). The case of *בְּשִׁבִּיל* suggests later ‘off-stage’ developments for MH, although not, in this case, with any apparent antecedents in the classical language. The same is true for *בְּיִין*, a clear Aramaism, at least in its lexical form, but whose grammaticalisation appears to be solely an internal Hebrew development. Therefore, although contact with Aramaic in the late post-exilic period played an important and determinative role in the development of Hebrew, a complete account must infer the existence of undocumented Hebrew varieties, which continued to evolve before, during, and after the transition to Middle (Mishnaic) Hebrew.

References

- Bacher, Wilhelm. 1905. *Die exegetische Terminologie der jüdischen Traditionsliteratur*. Leipzig: Hinrichs.
- Cook, Edward. 2017. ‘Language Contact and the Genesis of Mishnaic Hebrew’. *The Edward Ullendorff Lectures in Semitic Philology* 1. Cambridge: Faculty of Asian and Middle Eastern Studies, University of Cambridge.
- . 2021. ‘Aramaic Influence on Mishnaic Hebrew: Borrowing or Interference?’ In *Hebrew Texts and Language of the Second Temple Period: Proceedings of an Eighth Symposium on the Hebrew of the Dead Sea Scrolls and Ben Sira*, edited by Steven Fassberg, 25–36. *Studies on the Texts of the Desert of Judah* 134. Leiden: Brill.
- Dietrich, Walter and Samuel Arnet (eds). 2003. *Konzise und aktualisierte Ausgabe des Hebräischen und Aramäischen Lexikons zum Alten Testament*. Leiden: Brill.

- DJD 2* = Benoit, Pierre, Józef T. Milik, and Roland deVaux (eds). 1961. *Les Grottes de Murabba'āt*. Discoveries in the Judaean Desert 2. Oxford: Clarendon.
- Heine, Bernd, and Tania Kuteva. 2002. *World Lexicon of Grammaticalization*. Cambridge: Cambridge University Press.
- Koller, Aaron. 2017. 'The Social and Geographic Origins of Mishnaic Hebrew'. In *Studies in Mishnaic Hebrew and Related Fields: Proceedings of the Yale Symposium on Mishnaic Hebrew, May 2014*, edited by Elitzur A. Bar-Asher Siegal and Aaron J. Koller, 149–73. Jerusalem: Magnes Press.
- Lauterbach, Jacob Z. 2004 (1933). *Mekhilta de-Rabbi Ishmael*. Philadelphia: Jewish Publication Society.
- Rice, Sally A., and Kaori Kabata. 2007. 'Crosslinguistic Grammaticalization Patterns of the Allative'. *Linguistic Typology* 11: 451–514.
- Sokoloff, Michael. 2002. *A Dictionary of Jewish Babylonian Aramaic of the Talmudic and Geonic Periods*. Ramat-Gan: Bar-Ilan University Press.
- . 2009. *A Syriac Lexicon*. Winona Lake, IN: Eisenbrauns/Penn State University Press and Piscataway, NJ: Gorgias Press.

RABBINIC HEBREW *KYD* ~ ‘*KYD*: INSIGHTS FROM PALESTINIAN ARABIC*

Mila Neishtadt

MS Kaufmann of the Mishna includes two main transmissions: that of the text’s scribe and that of its vocaliser. The MS also includes numerous corrections by more than one hand (Bar-Asher 2009–2022, I:212–13). For example, in one case we read:

* This article was presented as a poster at the conference ‘Biblical and Rabbinic Hebrew: New Perspectives in Philology and Linguistics’ on July 8, 2019, at the University of Cambridge. An expanded lecture was given at the conference titled ‘The Heart Yearned for Jerusalem: Gustaf Dalman’s Holy Land Research and Its Reception’ at the University of Greifswald on June 30, 2022. I am indebted to Prof. Simon Hopkins, Dr Etan Ayalon, Dr Hillel Gershuni, and Dr Doron Ya‘akov, who read various versions of this paper. Several useful comments and corrections were suggested by an anonymous reviewer. This article is much richer thanks to their vast knowledge and detailed feedback; any errors are mine alone.

This project has received funding from the European Union’s Horizon 2020 research and innovation programme under the Marie Skłodowska-Curie grant agreement No. 101027323.

- (1) המוכר את בית הבד מכר את הים ואת הממלל ואת הבתולות אבל לא מכר את הכיד(ון) ולא את הגלגל ולא את הקורא
 'If a man sold an olive-press he has sold also the vat, the grindstone, and the posts, but he has not sold the pressing boards, the wheel, or the beam'. (m. Bava Batra 4.5 [MS Kaufmann p. 283/fol. 145v], trans. Danby 1933, 371)

The word הכיד(ון) *hkyd()*[*wn*] is especially notable in terms of history of transmission. The ending of הכיד *hkyd* in MS Kaufmann was deliberately deleted. The ink at the end of the original word was scraped and corrected with two thinner letters—ון *wn*—in a slightly lighter colour of ink. This type of correction, the shape of the letters, and the colour of the ink are all typical of the manuscript's vocaliser, who, using various methods, occasionally corrected the text (Mastey 2018, 80–81).¹ The current version reads הכיד(ון) *hkyd()*[*wn*] and is vocalised הכידון *hak-kīdōn* (see Figure 1 below).

Figure 1: m. Bava Batra 4.5, MS Kaufmann A50, p. 283/fol. 145v²



¹ A similar correction made by the vocaliser is discussed in detail in Mastey (2014, 84).

² Courtesy of the Library and Information Centre of the Hungarian Academy of Sciences.

The meaning of the word כִּידֹן *kīdōn* ‘javelin, short sword, scimitar’ (HALOT 472) does not fit naturally among the various olive press terms mentioned in this passage. Moreover, a comparison of the corresponding orthographic words in other Rabbinic MSS reveals numerous variants.

In this article, I seek to identify the original version(s) and meaning of הַכִּידֹן *hak-kīdōn* (m. Bava Batra 4.5, MS Kaufmann), to explain the multiple MSS variants, and to suggest possible etymological directions.

1.0. Rabbinic Hebrew MSS Variants of *hak-kīdōn* in m. Bava Batra 4.5 (MS Kaufmann)

1.1. M. Bava Batra 4.5/b. Bava Batra 67b

Numerous variations of the word in question are attested in Rabbinic Hebrew (RH) MSS:

Table 1: m. Bava Batra 4.5 MSS

MS Kaufmann A50	הַכִּידֹן (וּן) <i>hak-kīd(ō)[ōn]</i>
MS Parma, De Rossi 138	הַכִּירִים <i>h-kyrym</i>
MS Cambridge Add.470.1	הַכִּיִּים (י) <i>h-ʿ(y)bydym</i>
MS Saint-Petersburg Yevr. III B 202	הַכִּיִּים <i>hak-kīḏīm</i>
MS Cambridge T-S NS 329.603	הַכִּיִּים <i>h-kydym</i>

Table 2: b. Bava Batra 67b MSS

MS	Mishna	Talmud
MS Hamburg 165	העבדים <i>h-bdym</i>	עבידים <i>bydym</i> העבדים <i>h-bydym</i>
MS Florence II.1.8–9	העבירין <i>h-kyryn</i>	עבירין <i>byryn</i> העבירין <i>h-kyryn</i>
vol. I, fol. 198 ³	העבירין <i>h-kyryn</i>	—
MS Vatican ebr. 115.[b]	העבירין <i>h-byryn</i>	עבירין <i>kyryn</i> העבורין <i>h-bwryn</i>
MS Munich 95	'העמודי <i>h-mwdy</i> '	'עמודי <i>mwdy</i> ' 'העמודי <i>h-mwdy</i> '
MS Oxford 369 (Cat. Neubauer)	הע?ב/ב?ירים <i>h-?k/b?yrym</i> 'העמודי <i>h-mwdy</i> ' ⁴	עבירים <i>kyrym</i> העמודים <i>h-mwdym</i>
MS Paris Suppl. Heb. 1337	העבירין <i>h-kyryn</i>	עבירין <i>kyryn</i> העבירין <i>h-kyryn</i>
MS Frankfurt Carmeliter 4	'העבירי <i>h-byry</i> '	—
MS Escorial Gl-3	העמודים <i>h-mwdym</i>	עמודין <i>mwdyn</i> העמודים <i>h-mwdym</i>
Editio princeps (Pesaro 1509–1516)	עבירים <i>byrym</i>	סידים <i>sydym</i> העבירים <i>h-byrym</i>

Based on this presentation, we already note that all the variants end with a plural suffix, *-ym* ~ *-yn*, or a shortened *-y*' version thereof. It is, therefore, fair to assume that the original word in MS Kaufmann was in all probability a plural form,⁵ ending with the plural suffix *-ym* or *-yn*. The first option, *-ym*, seems a better fit, based on several considerations: (1) all the

³ An erroneous double copying of the relevant page (vol. II, fol. 57) is found in vol. I, fol. 198 (Sussmann 2012, I:61).

⁴ The version 'העמודי *h-mwdy*' appears as an addition: מכר את העבירים ולא העמודי.

⁵ The plural form is also evident in b. Bava Batra 67b, where the word in question is explained by the plural form כבשי *kbšy* 'presses' (see §2.0 below).

other m. Bava Batra 4.5 MSS have the plural ending *-ym*; (2) the plural suffix *-ym* is statistically more frequent than the plural suffix *-yn* in nouns in MS Kaufmann;⁶ (3) the scraped area is larger than the space required by a final *nun* ; (4) had the plural ending been *-yn*, then instead of scraping away the word's ending, the vocaliser could have effortlessly extended the foot of the *yod* in the plural ending ין- into יי-; (5) examining the ink shades on the other side of the vellum also supports the hypothesis of an original plural *-ym* suffix.⁷ All these considerations suggest הכידים *h-kydym* as the most probable original variant of the corrected הכידון *hak-kīdōn* in m. Bava Batra 4.5, MS Kaufmann. This reconstructed version is suggested in the critical editions of the Mishna (Historical Dictionary Project 2019, 170; Heijmans f.c.) and in Bar-Asher (2015, I:116). We shall return to these variants in the analysis in §1.3 below.

1.2. M. Kelim 12.8/t. Kelim Bava Batra 7.12

1.2.1. M. Kelim 12.8

The abovementioned reconstructed הכידים *h-kydym* in m. Bava Batra 4.5 is reminiscent of m. Kelim 12.8 (MS Kaufmann):

⁶ For further details, see Naeh (1993, 384–88) and Mor (f.c.). Detailed statistics are available for MS Kaufmann order Zera'im: the distribution of the plural suffixes in nouns is 83.3 percent *-ym* versus 16.7 percent *-yn* (Ya'akov 2005, 52).

⁷ For the application of this technique to the MS Kaufmann vocaliser's corrections, see Mastey (2014, 85–95).

- (2) האולר [ו]הקולמוס והמטולטל(ו)ת והמשקלות והכידים והכנ והכנה טמאין
‘The penknife, pen, plummet, weights, pressing-plates, measuring-rod, and measuring tables are susceptible to un-
cleanness.’ (m. Kelim 12.8, trans. Danby 1933, 622)

In m. Kelim 12.8 (MS Kaufmann) we find והכידים *wə-hak-kīdīm*, without any corrections made by the vocaliser. There the word comes after והמשקלות *wə-ham-mišqālōt* ‘and the weights’ which, for its part, is preceded by והמטולטל(ו)ת *wə-ham-məṭultəlet* ‘the plummet’. The attestation in other MSS of m. Kelim 12.8 can be summarised as follows:

Table 3: Other textual witnesses to m. Kelim 12.8

MS Kaufmann A50	והכידים <i>wə-hak-kīdīm</i>
MS Parma, De Rossi 497	והכידין <i>wə-hak-kīdīn</i>
MS Parma, De Rossi 138	והכידים <i>wə-hak-kīdīm</i>
MS Cambridge Add.470.1	והכירון <i>w-h-kyrwn</i>
MS Cambridge T-S E1.125	הכירים <i>h-kyrym</i>
MS Cambridge T-S E2.90	והכידין <i>w-h-kydyn</i>

1.2.2. T. Kelim Bava Batra 7.12

Tractate Kelim lacks a counterpart reference in both the Babylonian and Palestinian Talmudim, but has a counterpart in the Tosefta, t. Kelim Bava Batra 7.12 (MS Vienna Cod. Hebrew 20):

- (3) האולד והקולמוסין והמטלטלות והמשקלות והעתידין והכנ והכנה של
זכוכית טהורין
‘Glass penknife, pens, plummets, weights, ?, measuring-rod, and measuring table are pure.’ (t. Kelim Bava Batra 7.12, trans. Neusner 1977–1986 VI:80, adapted)

Here we find several differences compared to the Mishnaic text. The relevant one is that instead of MS Kaufmann *wə-hak-kīdīm*, we find the entirely different plural form *w-h-tydyn* in both MS Vienna Cod. Hebrew 20 and *editio princeps* Venice, 1521.

In his *Tosefet Rishonim*, Lieberman cited the Tosefta version of ha-Rash, the twelfth–thirteenth-century Rabbi Samson ben Abraham of Sens: האולר והקולמוס והמטולטלת והמשקלות והעכידים והכן. והכנה של זוכית טהורין. Ha-Rash explained the version *w-h-tydyn* as a variant of the Mishnaic *w-h-kydym*, the two words denoting the same thing. Lieberman also cited *w-h-wbrwt*, an alternative version of *w-h-tydyn* in t. Kelim Bava Batra 7.12, which appeared in the printed editions of *Sefer ha-Keritut* by Rabbi Samson of Chinon (twelfth–thirteenth century). Lieberman noted that the Tosefta variant *w-h-tydyn* is unreliable and the correct version was likely *w-h-kydym*, as suggested by ha-Rash, or alternatively עכירים *kyrym* or עבירים *byrym*, the latter being close to the *w-h-wbrwt* version of Rabbi Samson of Chinon (Lieberman 1937–1939, III: 95, 598).

1.3. Analysis of MSS Textual Variants

Thus far I have mentioned over a dozen variants of the word in question. Occasionally more than one variant appears within the same MS. Some further variants are found in other sources, e.g., *h-kdym* הכדים, *bwdym* עבודים, and *b-ydym* בידים (Epstein 1921–1924, I:27, fns 9–11).

All the variants can be primarily divided into two groups: variants with and without an initial ‘*ayin*. This primary division does not seem to be arbitrary. With only two exceptions,⁸ the variants with an initial ‘*ayin* are typical of the Babylonian Talmud and the Tosefta MSS, whereas the variants without an initial ‘*ayin* are typical of Mishnaic MSS.

Each of the two primary groups can be divided according to frequent alternations between two pairs of letters: כ/ב and ר/ד. Three additional variants have a different letter instead of the first pair: *mem* in עמוד ‘*mwd*, *tav* in עתיד ‘*tyd*, and *samekh* in סיד *syd*. These data can be summarised as follows:

Table 4: Categorisation of variants

	No Initial ‘ <i>ayin</i>		Initial ‘ <i>ayin</i>	
	Second ד	Second ר	Second ד	Second ר
First כ	כיד	כיר	עכיד	עכיר
	כיד() [ן]	כירון		
	כד			
First ב	ביד	סיד	עביד	עביר
			עבד	עובר
			ע(י)ביד	
			עבוד	עבור
			עמוד	
			עתיד	

⁸ See m. Bava Batra 4.5 MS Cambridge Add.470.1 ה(י)בידים *h-(y)bydym* and the Babylonian Talmud *editio princeps* (Pesaro 1509–1516), in which one of the versions in b. Bava Batra 67b is סידים *sydym*.

2.0. Traditional and Modern Exegesis

Despite the great variation, the Babylonian Talmud explains the m. Bava Batra 4.5 (MS Kaufmann) הכִּידֹן *hak-kīdōn* as כבשי *kbšy* ‘presses’, an interpretation which might be appropriate in an oil-pressing context yet does not explicitly indicate what these ‘presses’ were.

Epstein’s (1921–1924, I:27) *Der Gaonäische Kommentar zur Ordnung Teharoth*, an early commentary on order Ṭoharot, already makes a connection between m. Kelim 12.8 and b. Bava Batra 67b: והכירין כדא’ בבאבי אחרן מאי עבירין כבשי ואי’ דא’ כידין: *w-h-kyryn*, as in another version in another chapter [Bava Batra 67b]: “What is ‘byryn?’ ‘Presses’, and some say *kydyn*.”

Later commentaries are more detailed, and various meanings have been suggested. *The Mainz Commentary* (eleventh–twelfth centuries), an early Ashkenazi commentary formerly attributed to Rabbenu Gershom, explains b. Bava Batra 67b as follows: עבירין כיבשי אותן קצצים [קצעין] של בקעת שנותנים על הקרשים בין הקרשים ובין הקורה כשעוצרין הקורה *‘kyryn*: presses, those cut chips of slivers of wood that are put on the boards, between the boards and the beam when the beam is pressed’ (Leitner 1998, 153–54).

Two other meanings are suggested in *Sefer he-‘Arukh* by Nathan ben Yehi’el of Rome (eleventh century):

- (a) s.v. עכירים ~ עבירין *kyrym* ~ *kyryn*: כבשי והם גלגלי ‘and one interpretation is “presses” and they are big rounded stones pierced in the middle, used for the crushing and pressing of olives’ (Kohut 1878–1892, VI:199); (b) s.v. כבשי *kbšy*: כירין כבשי הם *‘kyryn*: presses, they are beams for olive pressing’ (Kohut 1878–1892, IV:191).

A similar meaning—‘pressing boards’—is found in multiple later sources. It appears as one of the explanations in a later twelfth-century commentary on tractate Bava Batra by the Maghrebi Rabbi Zecharia ben Yehuda Aġmātī:

עבִידִים כִּיבִשִּׁי וְהוּא כִּמוֹ לֹחִים וְעֵצִים שְׁנוֹתָנִין אוֹתָן עַל הַקּוֹפּוֹת שֶׁל זֵתִים
וְגַם עַל [הַחֲרָצָנִים שֶׁל] עֲנָבִים הַדְּרוּכִים כְּדֵי שֶׁתֵּרֵד עֲלֵיהֶם הַקּוֹרָה וְכוּבֶשֶׁת
אוֹתָם וּמוֹצִיָּאָה כָּל [מֶה] שֶׁבְּתוֹכָם

‘*kydym* means presses, and this is like boards and logs that are placed on the baskets of olives and on [the pips of] trodden grapes so that the beam descends upon them, presses them, and extracts everything out of them’ (Leveen 1961, 240).

The thirteenth-century Rabbi Meir ben Todros Ha-Levi Abulafia (Spain) offers a similar explanation for עבִידִין *bydyn* (Shulman 1989–1993, II:468).

In Maimonides’s commentary on the Mishna (m. Bava Batra 4.5), according to his autograph (MS Oxford, Pococke 295, fol. 27v), we find הַכִּדִּין *hak-kīdīn*, which is spelled with a *yod* after *kaf* later in the commentary:

וּכְיָדִין אֵלֶּתְקֵלָאֵת אֵלֶּתִי תַתְקֵל בָּהָא אֵלֶּאוּעִיָּה אֵלֶּתִי פִּיהָ אֵלֶּזִּיתוֹן
וְעֲלִיָּהָ תַתְעֵלֶק אֵלֶּחֶגֶר אֵלֶּפּוֹקָאֲנִיָּה

‘and *kīdīn*: the weights with which the vessels with olives are weighed and on which the upper stone is fixed’ (Qafih 1963–1969, Neziqin, 116).

In *Mishne Tora* (Hilkhot Mekhira 25.8), which relates to b. Bava Batra 67b, Maimonides explained it as follows: הַכוֹבֶשֶׂת שֶׁמִּכְבֶּשֶׁת שֶׁבִּן הַזֵּיתִים ‘the presses for pressing olives’ (Shailat 2004–2021, XII:73). The same word is interpreted entirely differently in the

context of m. Kelim 12.8: ⁹ ובידים דהוק מן חדיד ירכו בהא אלזיתון פי 'and *kydym* are iron poles by which the olives are pressed in the olive production facilities' (Qafih 1963–1969, Ṭeharot 1, 127). The same explanation appears in *Mishne Tora* (Hilkhot Kelim 9.16): ¹⁰ והבידיים שלברזל שחובטין בהן הזיתים 'and the iron *kydyym* for beating the olives' (Shailat 2004–2021, X:227). It seems that Maimonides essentially suggested different meanings: in b. Bava Batra 67b he understood the word as 'weights' or 'presses', whereas in m. Kelim 12.8 he interpreted the word as 'iron poles'. It is only the second meaning that appears in *al-Murshid al-Kāfī*, a lexicon on Maimonides' *Mishne Tora* by Tanḥum ha-Yerushalmi (thirteenth century), s.v. *kyd*: וקיל אן כידין 'And it is said that *kydyn* are iron bars or hammers with which olives are crushed' (Shy 2005, 252).

The Maghrebi Rabbi Zecharia ben Yehuda Aḡmātī offers another explanation, along with the above-mentioned 'pressing boards': עבידין *mwdyn* and according to another version 'kydyn were the screws (למגאזל *al-magāzil*) of the press that lift up the big weight-stone' (Leveen 1961, 240).

⁹ According to another MS: והבורים *w-h-kwrym* (Qafih 1963–1969, Ṭeharot 1, 127).

¹⁰ The form והבידיים *w-h-kydyym* with a dual plural suffix is based on the British Library, MS Or. 2421, fol. 134v. According to other editions: והכיריים *w-h-kyryym* (Warsaw-Vilna ed. reprinted in Shailat's edition: Shailat 2004–2021, 187), והכירים *w-h-kyrym* (Frankel 1993, 250), and והבידים *w-h-kydym* (Qafih 1993, 298).

In modern research, the word in question is mentioned in the nineteenth-century dictionary by Jacob Levy, who considered *kyrym* כִּירִים or *kyryn* כִּירִין to be a shortened version of the singular form **kyr* עֵבִיר. He mentioned some of the other variants and understood the word to refer to ‘big round stones’ that were rolled back and forth on the pressing boards of the press with the aim of pressing the olives beneath (Levy 1876–1889, II:324). Marcus Jastrow listed the variant *ākīrīm* עֵבִירִים or *ākīrīn* עֵבִירִין as “stirrers, implement connected with the wine or oil press for stirring up the pulp, loadstones (?), screws (?)” (Jastrow 1903, II:1078).

Alexander Kohut, who edited *Sefer he-Arukh* by Nathan ben Yehi'el, addressed the numerous versions of the word and, after mentioning the version *h-mwdyn* העמודין, at the end expressed his own opinion by adding *ואולי נכון הוא* ‘and perhaps this is correct’ (Kohut 1878–1892, IV:191, fn. 2).

In his *Talmudische Archäologie*, Samuel Krauss (1910–1913, II:599–600, fn. 536) followed one of the traditional interpretations and suggested the word denoted round pressing boards made of solid wood that were placed over the mass of the crushed olives or grapes, so that pressure could spread evenly over the surface. He considered *byrym* עֵבִירִים to be the correct variant, possibly connected to the Hebrew *hif'il* verb *העביר* ‘pass (tr.)’ (Krauss 1910–1913, II:223). He nonetheless remarked on the other variants as well (II:599–600, fn. 536). Krauss understood the variant *mwdym* עמודים ~ *mwdyn* עמודין as ‘two posts holding the olive mass together’ (II:223). In his view, *mwdym* עמודים may once have appeared in the Mishna alongside *byrym* עֵבִירִים; however, since the word *mwdym* עמודים ‘pillars’ was intelligible and

hence received no comment in the Talmud, it was eventually dropped from the Mishnaic text (II:599–600, fn. 536).

In his research on oil production in the Holy Land in the Tannaitic period, Felix Goldmann (1907, 20 fn. 2, 22, fn. 1) mentioned that both the etymology and the correct reading of the relevant word in m. Bava Batra 4.5 were unclear. In his view, the m. Kelim 12.8 connection does not clarify the matter, since many variants prevail there as well. Goldmann (1907, 22) disagreed with Jastrow's 'screw' interpretation and suggested that עכיר *'kyr* was one of the large press weight-stones fixed at the end of the press's beam.

From an archaeological point of view, Goldmann's suggestion was adopted by Rafael Frankel, who identified the press mentioned in m. Bava Batra 4.5 as the complex lever-and-weights press (see Figure 3, below). Frankel added an important semantic consideration based on m. Kelim 12.8. There the word in question appears after two smaller types of weights (MS Kaufmann): והמטולטל (ו)ת *wə-ham-məṭulṭeṭ* 'a plummet' (small sized) and והמשקלות *wə-ham-mišqālōt* 'and the weights' (medium sized). The 'press weight-stone' fits perfectly as the largest of the weights, arranged in ascending order by size. Frankel used the variant עכיר *'kyr* in his 1986 study, yet later he preferred עכיד *'kyd*, without providing any considerations to support either variant (Frankel 1986, 58–59; 1996, 212; 1999, 189–90).


3.0. The Material Culture of Traditional Olive Presses

Pressing is one of the stages in traditional olive oil production. The word [יז]()הכיד *h-kyd()*[wn] in m. Bava Batra 4.5 (MS Kaufmann) appears in what is clearly a context of olive press terminology, in which the קוֹרָא *qōrā* [*sic*, otherwise קורה] ‘beam’ is mentioned.

Several types of presses are known from both Palestinian ethnographic studies and archaeological findings. Gustaf Dalman (1928–1942, IV:201–55) described the traditional pre-industrial olive oil production in the Holy Land at the beginning of the twentieth century in detail. Rafael Frankel (1999, 159–61 and Map 41 there; 2009, 1–18) has presented an accessible illustrated summary.


One of the types of presses is the lever-press. This type of press has a beam that is anchored at one end and acts as a lever. Force exerted on the free end of the beam brings pressure to bear on the crushed olives, which are placed below the beam in flat baskets (Frankel 2009, 4). The oldest subtype of lever-press is the simple lever-and-weights press, which was used in Iron Age Southern Levant. Force was applied by means of weights hung on the beam, as we can see in Figure 2 (facing page).

Figure 2: Simple lever-and-screw weights olive press, used in Tel Baṭaṣh (biblical Timna) during the Iron Age (Frankel 1994, 39)




In later periods, the lever-and-weights press became larger and more complex, as seen in Figure 3, a reconstruction of the complex lever-and-weights press at Khirbet Zibdī in the Galilee (Frankel 1994, 44). It is this type of press that Frankel connects to the press mentioned in m. Bava Batra 4.5, with *kyr* being the name for a weight-stone (Frankel 1986, 58–59).

Figure 3: Parts of a press in m. Bava Batra 4.5, according to Frankel (1986, 59)



Pre-industrial lever-and-weights presses were still in use in Palestine in the first quarter of the twentieth century, as we see in Figure 4 (see also: Dalman 1928–1942, IV:214–15).

Figure 4: Dalman's (1928–1942, IV: Bilderanhang 56) sketch of a lever-and-weights press equipped with a winch, in al-Ṭāfile, Transjordan



A chronologically later subtype of lever-press, typical of the Byzantine period onwards, is the lever-and-screw press. Similar pre-industrial presses were used in Palestine, as we see in Figure 5 (facing page), which shows two different olive oil production processes. In the background of the picture, we observe a crushing installation: a horizontal, circular crushing basin and a vertical crushing wheel pulled by a working animal walking in circles. In the foreground of the photograph, we see a lever-and-screw olive press.


The screw weight-stone is buried in a pit and cannot be seen in the photo. The screw measures about four metres in height. The screw weight-stone is fitted to the bottom of the screw with the help of a wooden 'collar' (Dalman 1928–1942, IV:218–9; Frankel 1994, 50–61).

Figure 5: Lever-and-screw olive press operating in Bēt Sāḥūr, 1934–1939 (image: the American Colony, Jerusalem, G. Eric and Edith Matson Photograph Collection, accessed 26 December 2024, <https://www.loc.gov/pictures/item/2019694385>)



A reconstructed model of the lever-and-screw olive press exhibited at MUSA, the Eretz Israel Museum in Tel-Aviv (Figure 6, overleaf) allows a closer look at this traditional oil industry implement. The model is made of original parts from the Galilee (the weight-stone of the lever-and-screw press) and Samaria (the screw and the nut plank), with the ‘collar’ added according to the parts of a press found *in situ* in ‘Ayn Ḥawḍ, an Arab village at the foot of Mount Carmel. Figures 7a and 7b (overleaf) show close-up photographs of the screw weight-stone.

Figure 6: Reconstruction of a lever-and-screw olive press, MUSA, the Eretz Israel Museum, Tel-Aviv (image: Dr Etan Ayalon)



Figures 7a and 7b: Close-up photos of the screw weight-stone in MUSA, the Eretz Israel Museum, Tel-Aviv (images: Dr Etan Ayalon)



Evidence of lever-and-screw presses in common use dates only to the Byzantine period, more than one hundred years after the final redaction of the Mishna (Frankel 2009, 5–6). It is therefore unlikely that the passage in question (m. Bava Batra 4.5) refers to a lever-and-screw press. Additionally, a major component of this press, the לולב *lūlāḇ* ‘screw’, goes unmentioned there. For these reasons, archaeologists have identified the press in m.

Bava Batra 4.5 as the complex lever-and-weights type of press illustrated in Figure 3 previously (Frankel 1986, 58–59).

4.0. Dalman's Attestation of Palestinian Arabic Oil Press Terminology and Identification of *m*. Bava Batra 4.5 *h-kyd()*[*wn*] (MS Kaufmann)

The common term for the screw weight-stone (see Figures 7a and 7b above) in a lever-and-screw olive press in Palestinian Arabic is *lakkīd* (Dalman 1928–1942, IV:217ff). The probable connection between the Palestinian Arabic *lakkīd* and *h-kyd()*[*wn*] in MS Kaufmann and its numerous variants in other MSS was mentioned by Gustaf Dalman, who listed the variant עֲבִיר *ʿāḳīr* ‘Gewicht der Ölpresse’ in his dictionary (Dalman 1922, 312), but later on considered it uncertain. Dalman owned a facsimile edition of MS Kaufmann, on which the correction can be clearly seen,¹¹ but he apparently did not notice it and thus suspected that [הכידן] *h-kyd()*[*wn*] was likely a corruption of the original הכידן *h-kydyn*, hesitantly noting: “Wenn *kīdīn* die richtige Leseart ist, könnte man allenfalls *lakkīd*, die Arabische Bezeichnung des Pressgewichts zum Vergleiche heranziehen (‘If *kīdīn* is the correct reading, then *lakkīd*, the Arabic term for the press weight, might possibly be drawn upon for comparison’)” (Dalman 1928–1942, IV:233).

I was unable to find any attestation of *lakkīd* in other Arabic dialects or in Classical Arabic. It also seems to be absent from

¹¹ This information became available to me after visiting Dalman's personal library at the Gustaf Dalman Institute in Greifswald.

other written attestations of Palestinian Arabic oil industry terminology. The *l* in *lakkid* may be reconstructed as deriving from the Arabic definite article *al-* in a process of reanalysis and back-formation (see the details in §5.0 below). Given the original הכידים *h-kydym* (in MS Kaufmann and other MSS) in the context of olive press parts, a substrate relationship between Mishnaic כיד *kīd* and Palestinian Arabic *lakkid* seems convincing.

The Palestinian realia term *lakkid* confirms כ and ד as the correct consonants of this obscure RH word and provides a reliable identification of singular כיד *kyd* as the press weight-stone. Given כ and ד as the original consonants, it seems that the correct variant with an initial ‘ayin is עכידים *‘kydym* ~ עכידין *‘kydyn*, the plural form of עכיד *‘kyd*. This variant is attested in Aḡmātī’s commentary (see §2.0 above).

The variants containing ב and ר instead of the original כ and ד, respectively, are scribal corruptions caused by the resemblance of these respective pairs of letters.¹² Some of the erroneous variants resulted from the replacement of a rare, incomprehensible word with a known, common alternative based on the similarity of letter shape, e.g., העבדים *h-‘bdym* ‘the slaves’ (MS Hamburg 165), which does not fit the context of the sentence in which it appears, or the more compelling variant העמודים *h-‘mwdym* ‘the pillars’ (MS Munich 95, MS Oxford 369, and MS Escorial Gl-3). Samuel Krauss’s suggestion, that עמודים *‘mwdym* may once have appeared in the Mishna and was later dropped (see §2.0 above),

¹² For cases of possible ד and ר interchange in Hebrew and Late Jewish Aramaic due to phonemic proximity and blurring of /d/ and /r/, see Howard (2022).

seems radical. A more plausible explanation is that the MSS that have the plural forms of עמוד *mwd* ‘pillar’ in b. Bava Batra 67b are examples of a later scribal corruption caused by the resemblance of the sequence כי (or the corrupted בי) to the letter מ *mem*. Alternatively, *kaf* alone, particularly if vocalised with a *dagesh*, כּ, also resembles a *mem*. The same tendency may explain the less syntactically successful variant with *tav*, namely והעתידין *w-h-ʿtydyn* ‘and are about to’ in t. Kelim Bava Batra 7.12 (MS Vienna Cod. Hebrew 20).

Gustaf Dalman attested Palestinian Arabic *lakkid* only in the context of the lever-and-screw type of press—a press that dates to a period later than that of the final redaction of the Mishna (early third century CE). Moreover, the form כידים *kydym* is mentioned in the plural in the Mishna, which makes it difficult to identify the Mishnaic plural כידים *kydym* as a single weight-stone in the lever-and-screw press. However, these problems are easily resolvable. The plural form might refer to the plural weights in the earlier, complex lever-and-weights type of press, as suggested above (Frankel 1994, 41). The semantics of this word may well have ‘progressed’ with the development of the oil press, continuing to denote the press weight-stone in the later, more advanced lever-and-screw press.

5.0. Linguistic Analysis and Etymological Leads

The Palestinian Arabic substrate word *lakkid* offers more than just confirmation that the original pair of consonants were כ and ד and identification of the meaning of RH כיד *kyd* ~ עכיד *ʿkyd*. A diachronic linguistic analysis of this word may also explain the

Babylonian MSS variants with an initial *ʿayin* and their connection to Mishnaic variants without that letter.

As mentioned above, the *l* in the Palestinian Arabic *lakkīd* likely derives from the Arabic definite article *al-* in a process of reanalysis and back-formation. This process is attested in other Aramaisms in Syro-Palestinian colloquial Arabic, originally beginning with an initial Aramaic *ʾa-*, for example:

**attūn* > **al-ʾattūn* > *lattūn* ‘limekiln’

**āḫūt* > **al-ʾāḫūt* > *lāḫūt* ‘scraper fitted at the non-pointed end of the goad’

Hence, possibly:

**akkīd* > **al-ʾakkīd* > *lakkīd*

Given the morphology of Arabic *lakkīd*, a similar process cannot be fluently explained without the reconstructed stage **akkīd* with an initial glottal stop, a version that has not survived in any of the existing Hebrew MSS witnesses. A follow-up question would be: how can this reconstruction be reconciled with the two established original versions כִּיד *kyd* and עִיד *ʿkyd*?¹³

There are two possible ways of explaining the reconstructed initial glottal stop in **akkīd*.

5.1. *kid* > **akkid* ~ *ʿakkid*

The first possibility is that the reconstructed **akkid* has an initial non-radical *ʾalef* before a consonant followed by a vowel (prothetic *ʾalef*). Similar instances of a prothetic *ʾalef* are found in

¹³ Hereafter transcribed *kid* and *ʿakkid*, respectively.

Biblical Hebrew, such as הַאֲבַתִּיחִים *hā-ʾāḇattīhīm* 'melons' (Num. 11.5), אֲבַעְבֹּת/אֲבַעְבֻּת *ʾāḇaʿbūʾōt* 'blisters, ulcers' (Exod. 9.9–10), as well as in the biblical doublet with and without 'alef: בְּאִזְקִים *bā-ʾziqqīm* (Jer. 40.1) ~ הַאֲזִקִּים *hā-ʾziqqīm* (Jer. 40.4) and בְּזִקִּים *bə-ziqqīm* 'fetters, manacles' (e.g., Ps. 149.8) (Bauer and Leander 1922, §61-Oe; JM §17a, §88La). Among similar prosthetic 'alef doublets in RH are גִּיס *gīs* ~ אֲגִיס *ʾāgīs* 'brother-in-law' (Bar-Asher 2015, I:131; Sharvit 2016, 361–62) and גּוּדָל *guddāl* ~ אֲגּוּדָל *ʾāguddāl* 'thumb' (Bar-Asher 2015, II:1074–75; Sharvit 2016, 361).

David Talshir (1992, 285–86) suggested that the original role of this type of 'alef was morphological: to expand short monosyllabic words into longer, trilateral ones. This suggestion seems to fit the present case quite well, although it clearly does not work in case of longer words, such as הַאֲבַתִּיחִים *hā-ʾāḇattīhīm* 'melons' or אֲבַעְבֹּת/אֲבַעְבֻּת *ʾāḇaʿbūʾōt* 'blisters, ulcers'.

The word עכיד *'akkid* with 'ayin, likely the correct version of the Babylonian Talmud, may then reflect an 'alef ~ 'ayin alternation **'akkid* ~ *'akkid*. Such alternations are not rare in RH, regardless of the consonant's position in the word, e.g., אֲנִישֵׁי פִשְׁתָּן *ʾānīšē pištān* ~ אֲנִישֵׁי פִשְׁתָּן *ʾānīšē pištān* 'flax fibers', רַעִי *reʿi* ~ רֵאִי *reʿi* 'animal faeces', מַרְדֵּה *mardē* ~ מַרְדֵּעַ *mardēa* 'goat' (Henshke 2011, 185–87; Bar-Asher 2015, I:625–26, 737; Sharvit 2016, 35–36, 73, 100–01). The difficulty with this explanation is that there are no known examples of 'alef ~ 'ayin alternation in the case of a prosthetic 'alef.

5.2. *‘akkid* ~ **’akkid* > *kid*

Prima facie, the second explanation is linguistically simpler. We can consider the possibility of development in the opposite direction, i.e., view the form עכיד *‘akkid* with initial *‘ayin* as the original form. The version **’akkid* with an initial glottal stop can then be seen as yet another example of guttural weakening, a frequent phenomenon in both Rabbinic (Sharvit 2016, 20–22) and Samaritan Hebrew (Ben-Ḥayyim 2000, 38–43), as well as in the local Western Late Aramaic dialects (for Galilean Aramaic see: Kutscher 1976, 67–96; for Christian Aramaic see: Bar-Asher 1977, 367–420; for Samaritan Aramaic see: Tal 2013, 27). The shorter version כיד *kid* found in the Mishnaic MSS is then explicable as a shortened version of the reconstructed intermediary **’akkid* due to loss of an initial glottal stop—a process opposite to that of the addition of a prosthetic *’alef* to monosyllabic words (Talshir 1992, 286).

Jacob Levy (1876–1889, II:324) long ago suggested that the relationship between the two variants is one of contraction, i.e., *‘akkid* > *kid*, according to the correct variant. The reconstructed stage **’akkid* would allow us to explain this shortening more convincingly, although similar cases in RH are mostly attested in proper names, e.g., אבא *’abba* ~ בא *ba*, אליעזר *eli’ezer* ~ ליעזר *li’ezer* (Sharvit 2016, 370–1). An example of a common noun is אָוֶז *’āwāz* ~ וז *waz* ‘sort of domestic bird’ (Bar-Asher 2015, 792).

The main difficulty with this explanation relates to chronology—namely, the different language versions of the Mishna. These divide roughly into the Palestinian branch, evident in the MSS of the Mishna itself, and the Babylonian branch, evident in

the Mishna as cited in MSS of the Babylonian Talmud. These two branches differ in many ways: in spelling, pronunciation, morphology, syntax, and vocabulary, as well as differences in the text (Bar-Asher 2009–2022, I:76–108). If we consider the form עכיד *ʿakkid* with an initial *ʿayin* the original form, then this would be one of the cases in which it is the Babylonian tradition that preserves the original Palestinian form of RH. This is not a far-fetched scenario, as has been previously discussed (Bar-Asher 2009–2022, I:100–06; Brody 2015, 3–4) and should thus be taken into consideration. A more chronologically problematic aspect would be that, according to this analysis, the late shorter form כיד *kid*, which represents the Palestinian linguistic version of the Mishna, chronologically precedes the intermediate reconstructed stage **ʿakkid*, which was most probably the common local (Aramaic?) form of the word by the time of the Arab conquests of the seventh century CE.

Each of the two abovementioned linguistic analyses has different implications for the etymology of עכיד *ʿakkid* ~ כיד *kid*. The first analysis, according to which כיד *kid* is the original word, may bring us to the Hebrew root כ"ד in BH כִּיד *kīd* (Job 21.20), which, according to the context, is semantically related to destruction. Another possibly related word is כִּידֹן *kīdōn* 'javelin, short sword' (HALOT, 472). It is conceivable that these words denoting 'destruction' and 'fighting' are connected to 'pressing', similar to the meanings of the Hebrew root כב"ש 'conquer' ~ 'press'.

A less morphologically probable etymology would be כד"ד, with the expected forms singular כִּד *kēd* and plural כִּדִּים *kiddīm*, which do not correlate with the vocalised MSS. However, several

alternations in this pattern do exist, e.g., זֵיר ~ זֵיר 'thin cane of vegetables and grain' (Bar-Asher 2015, I:127, 34). Moreover, several RH words deriving from geminate roots appear in this pattern, such as טִף *tif* 'drop'. Nonetheless, the attestation of this root in Hebrew suggests no clear answers: the word כַּד *kaḏ* 'bulbous vessel' does not seem to fit semantically. The adjective כַּד *kaḏ*, which appears in RH (b. Avoda Zara 40a; b. Ḥullin 64a) to describe the flat side of an egg as opposed to the pointed one, does not seem to be related either.

The roots כ"ד or כ"י in other Semitic languages seem to be a much better semantic fit. In Classical Arabic the verb *kadda* is attested in the meaning 'plied, pressed hard; trod ground (with hoofs)'; *'arḏ kadīd* 'ground trodden with the hoofs of horses or the like'. The noun *kadd* is 'a mortar in which things are pounded or bruised' (Lane 1863–1893, VII:2594–95). This meaning in Classical Arabic has been connected to *kyd* 'to tread, to trample, to walk' in Ethiopian languages (Leslau 1987, 872; Kogan 2015, 461). Nevertheless, these meanings are unattested in Hebrew and Aramaic.

The second analysis, suggesting that עכיד *'akkid* is the original form, would imply that the word is derived from עכ"ד. Both Hebrew and Aramaic lack this root, making it even less probable that this is the right etymological direction. The root עכ"ד is attested in Arabic in various meanings, such as *'akada ʾilā* 'he had recourse, betook himself, or repaired, to him for refuge, or protection', *'akad* 'a middle of a thing', and *'akadat-* 'the root of the tongue' (Lane 1863–1893, V:2119). These meanings do not seem

to suit the relevant context, which makes it hard to suggest any etymology for the עִיד 'akkid variant.

Overall, the first analysis of *kid* > *'akkid ~ 'akkid seems to be preferable, albeit not without its problems. The exact etymology of this peculiar RH word still requires a more comprehensive solution.

6.0. Conclusion

I have suggested that the original version of MS Kaufmann vocalised הַכִּידֹן *hak-kidōn* (m. Bava Batra 4.5) is ה־כִּידִים *h-kydym*, denoting 'press weight-stones'. I have argued that the RH כִּיד *kyd* (*kid*) ~ עִיד 'kyd ('akkid) is most likely a predecessor of the Palestinian colloquial Arabic substrate word *lakkid* 'screw weight-stone'. The *l* in the Palestinian Arabic *lakkid* derives from the Arabic definite article *al-*, as part of a process of reanalysis and back-formation, suggesting an intermediate (Aramaic?) stage with an initial glottal stop: *'akkid. This stage correlates with the Babylonian Talmud original singular form עִיד 'kyd ('akkid), with an initial 'ayin. I have explained this pair of forms as one of numerous examples of 'alef-'ayin alternation in RH. I have suggested that the short form כִּיד *kyd* (*kid*) in Mishnaic MSS is possibly a monosyllabic variant extended by addition of prosthetic 'alef, which in turn alternated with 'ayin (according to Babylonian Talmud MSS): *kid* > *'akkid ~ 'akkid. Finally, I have suggested several etymological directions, of which כִּיד ~ כִּיד"ד seems to be the most suitable, possibly correlating with Semitic cognates meaning 'press hard, tread, trample, walk over'.

References

- Bar-Asher, Moshe. 1977. 'Palestinian Syriac Studies: Source-texts, Traditions and Grammatical Problems'. PhD dissertation, The Hebrew University of Jerusalem. [Hebrew]
- . 2009–2022. *Studies in Mishnaic Hebrew*. 4 vols. Jerusalem: The Bialik Institute. [Hebrew]
- . 2015. *A Morphology of Mishnaic Hebrew: Introductions and Noun Morphology*. 2 vols. Jerusalem: Mosad Bialik. [Hebrew]
- Bauer, Hans, and Pontus Leander. 1922. *Historische Grammatik der Hebraischen Sprache des Alten Testaments: I: Einleitung, Schriftlehre, Laut- und Formenlehre*. Halle: Max Niemayer.
- Ben-Hayyim, Ze'ev. 2000. *A Grammar of Samaritan Hebrew: Based on the Recitation of the Law in Comparison with the Tiberian and Other Jewish Traditions: A Revised Edition in English with Assistance of Abraham Tal*. Jerusalem and Winona Lake, IN: Magnes Press and Eisenbrauns.
- Brody, Robert. 2015. *Mishnah and Tosefta Ketubbot: Text, Exegesis and Redaction*. Jerusalem: Magnes Press. [Hebrew]
- Dalman, Gustaf. 1922. *Aramäisch-neuhebräisches Handwörterbuch zu Targum, Talmud und Midrasch*. 2nd edition. Frankfurt am Main: J. Kauffmann.
- . 1928–1942. *Arbeit und Sitte in Palästina*. 7 vols. Gütersloh: C. Bertelsmann.
- Danby, Herbert. 1933. *The Mishnah: Translated from the Hebrew with Introduction and Brief Explanatory Notes*. Oxford: Oxford University Press.
- Epstein, J. N. 1921–1924. *Der Gaonäische Kommentar zur Ordnung Teharoth*. 2 vols. Berlin: Itzkowski. (Reprint edited by E. Z.

- Melamed. Jerusalem: Magnes Press and Tel-Aviv: Dvir, 1982). [Hebrew]
- Frankel, Rafael. 1986. *Bet ha-Bad ha-Qadum*. Tel-Aviv: Muze'on ʿErets Yiśraʿel, Sifriyat ʾAdam va-ʿAmalo.
- . 1994. 'Ancient Oil Mills and Presses in the Land of Israel'. In *History and Technology of Olive Oil in the Holy Land*, edited by Rafael Frankel, Shmuel Avitsur, and Etan Ayalon, 19–89. Arlington: Oléarius and Tel-Aviv: Eretz Israel Museum.
- . 1996. 'Oil Presses in Western Galilee and Judaea: A Comparison'. In *Olive Oil in Antiquity: Israel and Neighbouring Countries from the Neolithic to the Early Arab Period*, edited by David Eitam, and Michael Heltzer, 197–218. Padua: Sargon.
- . 1999. *Wine and Oil Production in Antiquity in Israel and Other Mediterranean Countries*. Sheffield: Sheffield Academic Press.
- . 2009. 'Introduction'. In *Oil and Wine Presses in Israel from the Hellenistic, Roman and Byzantine Periods*, edited by Etan Ayalon, Rafael Frankel, and Amos Kloner, 1–18. Oxford: Archaeopress.
- Frankel, Shabse (ed.). 1993. *Mishneh Torah by Moses Maimonides: Book of Taharah*. Jerusalem: Congregation Bnei Yosef. [Hebrew]
- Goldmann, Felix. 1907. 'Der Ölbau in Palästina in der tannaitischen Zeit'. *Monatsschrift für Geschichte und Wissenschaft des Judentums* 51/1–2: 17–40; 51/3–4: 129–41.

- HALOT* = Koehler, Ludwig, Walter Baumgartner, Mervyn E. J. Richardson, and Johann Jakob Stamm. 1994–2000. *The Hebrew and Aramaic Lexicon of the Old Testament*. 5 vols. Leiden: Brill.
- Heijmans, Shai (ed.). Forthcoming. *The Mishnah According to Codex Kaufmann*. Cambridge: Cambridge University Press.
- Henshke, Yehudit. 2011. ‘Gutturals in MS Cambridge of the Mishnah: A Historical-linguistic Study of Rabbinic Hebrew Traditions’. *Hebrew Studies* 52: 171–200.
- Historical Dictionary Project. 2019. *The Mishnah: Kaufmann Manuscript A50. Vol. 2: Nashim–Nezikin*. Jerusalem: The Academy of the Hebrew Language. [Hebrew]
- Howard, Jonathan. 2022. ‘Phonetic Variance of /d/ and /r/ in Hebrew in Late Antiquity’. *Journal of Semitic Studies* 67/2: 395–415.
- Jastrow, Marcus. 1903. *A Dictionary of the Targumim, the Talmud Babli, and Yerushalmi, and the Midrashic Literature*. 2 vols. London: Luzac.
- JM = Joüon, Paul, and Takamitsu Muraoka. 2011. *A Grammar of Biblical Hebrew*. 2nd edition, 3rd reprint with corrections. Rome: Gregorian & Biblical Press.
- Kogan, Leonid. 2015. *Genealogical Classification of Semitic: The Lexical Isoglosses*. Boston and Berlin: De Gruyter.
- Kohut, Alexander (ed.). 1878–1892. *Aruch completum: Sive lexicon vocabula et res, quae in libris Targumicis, Talmudicis et Midrashicis: Continentur, explicans auctore Nathane filio Jechielis*. 8 vols. Vienna: Georg Brog.

- Krauss, Samuel. 1910–1913. *Talmudische Archäologie*. 3 vols. Leipzig: G. Fock.
- Kutscher, Edward Yechezkel. 1976. *Studies in Galilean Aramaic: Translated from the Hebrew Original and Annotated with Additional Notes from the Author's Handcopy by Michael Sokoloff*. Ramat-Gan: Bar-Ilan University.
- Lane, Edward William. 1863–1893. *An Arabic-English Lexicon*. 8 vols. London: Williams and Norgate.
- Leitner, Tzvi (ed.). 1998. *Perush Rabenu Gershom ha-Shalem ʿal Masekhet Bava Batra ʿal pi Ktav Yad ʿAtiq she-be-ʾOqsford*. Jerusalem: n.p.
- Leslau, Wolf. 1987. *Comparative Dictionary of Geʿez (Classical Ethiopic): Geʿez-English, English-Geʿez, with an Index of the Semitic Roots*. Wiesbaden: Harrassowitz.
- Leveen, Jacob. 1961. *A Digest of Commentaries on the Tractates Bābhā Ḳammā Bābhā M^ʿṣīʾā and Bābhā Bhāth^ʿrā of the Babylonian Talmud: Compiled by Zachariah Ben Judah Aghmāti—Reproduced in Facsimile from the Unique Manuscript in the British Museum Or. 10013*. London: The Trustees of the British Museum.
- Levy, Jacob. 1876–1889. *Neuhebräisches und chaldäisches Wörterbuch über die Talmudim und Midraschim*. 4 vols. Leipzig: F. A. Brockhaus.
- Lieberman, Saul. 1937–1939. *Tosefet Rishonim*. 4 vols. Jerusalem: Bamberger and Wahrman.

- Mastey, Emmanuel. 2014. 'Reconstructing Linguistic Forms in MS Kaufmann of the Mishnah: Deleted Text, Its Significance, and Methods of Restoration'. *Leshonenu* 76/1–2: 79–105. [Hebrew]
- . 2018. "And They Shall Beat Their Swords into... Scrapers": Two Case Studies in the Vocabulary of Jewish Palestinian Aramaic'. *Journal of Semitic Studies* 63/2: 353–80.
- Mor, Uri. Forthcoming. 'An Old Issue Revisited: -m/-n Interchanges'. *Language Studies* 21. [Hebrew]
- Naeh, Shlomo. 1993. 'Shte Sugyot Nedoshot bi-Lshon Ḥaza"l'. In *Mehqerei Talmud II: Talmudic Studies Dedicated to the Memory of Professor Eliezer Shimshon Rosenthal*, edited by Moshe Bar-Asher, and David Rosenthal, 364–92. Jerusalem: Magnes Press. [Hebrew]
- Neusner, Jacob. 1977–1986. *The Tosefta: Translated from the Hebrew*. 6 vols [6th vol. in co-authorship with Richard S. Sarason]. New York: Ktav Publishing House.
- Qafih, Yosef (ed.). 1963–1969. *Mishna: Im Perush Rabenu Moshe ben Maimon*. 7 vols. Jerusalem: Mossad Harav Kook.
- (ed.). 1993. *Sefer Mishne Torah*. Vol. 16: Sefer Ṭohora. Jerusalem: Mekhon Mishnat ha-Rambam.
- Shailat, Isaac (ed.). 2004–2021. *Rambam Meduyaq*. 14 vols. Ma'ale Adumim: Ma'alilot.
- Sharvit, Shimon. 2016. *A Phonology of Mishnaic Hebrew: Analyzed Materials*. Jerusalem: The Academy of the Hebrew Language. [Hebrew]

- Shulman, Aryeh (ed.). 1989–1993. *Yad Rama 'al Masekhet Bava Batra le-Rabenu Me'ir ha-Levi 'Abul'afya*. 3 vols. Jerusalem: n.p.
- Shy, Hadassa. 2005. *Al-Muršid al-Kāfi: The Lexicon of Tanḥūm ben Yosef Hayerushalmi to Mishné Tora of Maimonides, with a Translation from Judaeo-Arabic into Hebrew and References*. Jerusalem: The Israel Academy of Sciences and Humanities. [Hebrew]
- Sussmann, Yaacov. 2012. *Thesaurus of Talmudic Manuscripts*. 3 vols. Jerusalem: Yad Izhak Ben-Zvi. [Hebrew]
- Tal, Abraham. 2013. *Samaritan Aramaic*. Münster: Ugarit-Verlag.
- Talshir, David. 1992. 'Prosthetic Aleph'. *Leshonenu* 56/3: 285–86. [Hebrew]
- Ya'akov, Doron. 2005. 'The Plural Suffixes in Mishnaic Hebrew According to "Seder Zera'im" in the Kaufmann Manuscript'. MA thesis, The Hebrew University of Jerusalem. [Hebrew]

THE REALISATION OF *šere* IN CONTEMPORARY HEBREW: MONOPHTHONGAL OR DIPHTHONGAL?*

Yehudit Henshke

It has long been recognised that the pronunciation of the Tiberian vowel sign *šere* and the distinction (or lack thereof) between it and *segol* is a distinguishing phonological feature of the Ashkenazic and Sephardic Hebrew reading traditions.¹ If from the thirteenth century on, Ashkenazic Jews realised *šere* as a diphthong in a number of variations—[ay], [ɛj], [ej]—and *segol* as [e] (Katz 1993, 55), Sephardic Jews realised *šere* as a monophthong [e] and made no distinction between it and *segol* (Henshke 2013, 537).²

* I thank my devoted research assistant, Eliyahu Gedalyovich, who has been part of the study of *šere* from its inception, and Dr Or Katz, advisor on statistics. Special thanks to Dr Evan Gary Cohen, who generously and willingly answered my questions. I also thank the peer reviewers for their insightful comments.

¹ For convenience, I utilise the graphic designations *šere* and *segol*.

² This phonological distinction is reflected in *halakha* and Jewish customs. Thus, for example, the question of the pronunciation of the segolate-paroxytone noun זכר in Parashat Zakhōr (Deut. 25.17–19), recited

With the revival of spoken Hebrew in the land of Israel came general adoption of the Sephardic realisation of the vowels by Ashkenazim, who refrained, for various reasons, from realisation of diphthongs (Va'ad ha-Lashon ha-'Ivrit be-'Erets Yiśrael 1928, 28; Téné 1996, 223; Harshav 2008, 183). This was by no means a straightforward process: in 1904, David Yellin recommended that a distinction be made not only between *şere* and *segol*, but also between the two types of *şere*—long and short (Yellin 1905)—even though the latter distinction is unknown in any pronunciation tradition. Although Yellin did not again raise this latter proposal, he did not retract his proposed distinction between *şere* and *segol* (Yellin 1937, 78–79; Ben-Hayyim 1992, 249–50, fn. 14).

The 1913 Language Committee decision in favour of the use of the Sephardic accent (Va'ad ha-Lashon ha-'Ivrit be-'Erets-Yiśrael 1928, 24–49) endorsed the elimination of the distinction both between Tiberian *qameş* and *pataḥ* and between *şere* and *segol*. Nonetheless, in actuality, realisation of vowels displayed no uniformity. Studies from the early 1950s show that a fair number of speakers of General Israeli Hebrew (GIH)—specifically

on the Sabbath before Purim, troubled Ashkenazic halakhists. Is it vocalised with *şere* ['zejxer]/['zajxer], or with *segol* ['zexer]? In the absence of a definitive decision, the word is read twice in Ashkenazic synagogues (*Mishnah Berurah* 682.18). Among Sephardim this question did not arise, as both *şere* and *segol* are realised as a simple monophthong ['zexer].

those of Ashkenazic extraction—continued to preserve the diphthongal realisation of *şere* as [ej] (Weiman 1950, 6), even if not regularly or consistently (Blanc 1964, 137–38; Ornan 1973, 156). The diphthongal realisation is still heard at present (<https://hebrew-academy.org.il/2011/05/01/הגייית-הצירי-המלא>).

A completely different phonological picture of GIH emerges from the Hebrew of native Israelis with roots in Islamic countries, presently termed *Mizraḥim*. In the 1980s Yaakov Bentolila noted the conspicuous presence of the monophthong among southern rural youth in his study's target population (Bentolila 1984, 129–37). Elhanan Peleg's study of urban youth in the Tel-Aviv region showed a reduction in the status of the diphthong among Ashkenazim, but identified the monophthongal realisation of *şere* [e] as an outstanding feature of Mizraḥi speech (Peleg 1989; 1992).

The question of the realisation of *şere* in GIH again arose in the late-twentieth and early-twenty-first centuries. These studies found that short *şere* (written without etymological *yod*) is generally pronounced as a monophthong [e] similar to *sego*, but that long *şere* written with *matres lectionis* (especially *yod*) can be realised in GIH as the diphthong [ej] (Rosenhouse 1990; Matras and Schiff 2005, 160–61; Neuman 2013).

At present, in the 2020s, with respect to Mizraḥi Hebrew the monophthongal pronunciation has been preserved and still serves as a definitive marker of its distinctiveness. This distinctiveness serves not only as a basis for sociolinguistic discussion, but also for biting satire.

This article's broad, updated sociolinguistic description of the pronunciation of *šere* confirms the perpetuation of the monophthongal picture in Mizraḥi Hebrew as compared to current GIH. Furthermore, I propose here that the rare diphthongs attested in Mizraḥi Hebrew are either based on pronunciation traditions or determined by their linguistic environment. In actuality, the 'diphthongs' found at the end of words are not 'true' diphthongs, but rather an attempt to arrive at so-called consistency in Modern Hebrew pronunciation in this context.

1.0. Research Methodology

I addressed this socio-phonological question in the context of a comprehensive study of twenty-first-century Mizraḥi Hebrew.³ Due to limitations of space, only the main findings are presented here. The data for the study derive from the 'Other Hebrew Corpus', a broad, recorded, and transcribed database of conversations between native Israelis of Mizraḥi origin that contains 1,248,538 tokens. These conversations reflect natural speech and do not contain selections read aloud or responses to preset questionnaires. Drawn from a varied population, the speakers belong to a range of ages (pupils to adults), genders, professions, education, religiosity, specific ethnic backgrounds, places of residence, proximity to Mizraḥi centres, and knowledge of spoken Jewish languages. In general, the aim of this corpus was to create a representative portrait of the native Israeli population in the periphery, primarily the Mizraḥi population.

³ With support of ISF grant 287/19.

In order to test its realisation in Mizrahi Hebrew, we examined some 9,500 realisations of *šere* as found in conversations including 86 speakers. Segments of 250 words were sampled from the different parts of each conversation, for a total of 750 words per conversation. Unlike other studies, the focus was not on orthography or historical vocalisation (short or long *šere*); I sought rather to integrate phonetic, phonological, morphological, and syntactic aspects with the social and demographic variables of the participants in the corpus.

2.0. Phonetics

From the start, the elusive nature of the *šere* posed a problem. Because the study was grounded in natural, mostly rapid, fluent conversations, vowels and diphthongs could be condensed. Indeed, the realisation of historical *šere* in our corpus is not uniform. Nonetheless, we can point to three main realisations: the [e] vowel, an [e] vowel with a very short approximant palatal consonant at its end [e^j], and a clear diphthong [ej]. Analysis with the Praat software showed the second realisation to be closer to the diphthong than to the short vowel [e]. In essence, we found a continuum of realisations.⁴

⁴ In order to broaden and sharpen identification of the diphthong in contemporary spoken Hebrew today, I am undertaking a new field study that focuses on comparative lexical examination of the *šere* vowel among Israelis, both Ashkenazic and Sephardic. In this context, using a preset list of words, we compare the distribution, length, and acoustic quality of the diphthong in the two groups.

Statistical analysis of the three types of *şere* in the sample according to One Way ANOVA showed significant, even dramatic, differences in the use of the simple vowel by speakers: $F(2,158) = 1745.21^{***}$.⁵

As seen above, notwithstanding the strong social and demographic variety among Mizrahi speakers, the [e] vowel predominates, and the two diphthongal realisations are less frequent. Moreover, there is no significant difference in the frequency of use of the long and short diphthongs.

Table 1: Means (M) and Standard Deviation (SD) for average frequency of the use of *şere*⁶

<i>şere</i> realisation	M	SD
vowel [e]	112.08	23.39
diphthong [ej]	1.22	1.54
short diphthong [ej]	1.54	2.05

We also used statistical tests (t-test, One Way ANOVA, and Spearman and Pearson correlations) to determine links between sociodemographic variables: gender (male and female), age (young to old), generation in Israel (first, second, third), education (elementary, high school, academic), religiosity (secular, traditional, observant), knowledge of Judaeo-Arabic (none, little,

⁵ One Way ANOVA (F) tests whether there is a significant difference between the use of the three types of *şere* and its realisation in each type. The higher the F value, the greater its significance, eliminating chance.

⁶ Means: the average frequency of the use of *şere* for each type; SD (standard deviation): the variability between speakers in the frequency of the use of *şere*.

medium, fluent) as independent variables, with realisation of *šere* as the dependent variable. The results showed a definitively negative link between fluency in Judaeo-Arabic and use of the diphthong. Although the realisation [e] dominates, speakers fluent in Arabic exhibited even less frequent use of the diphthong.

Table 2: Spearman rank correlation coefficient between fluency in Judaeo-Arabic and realisation of *šere*⁷

Variants	[ej]	[e ^j]	[e]
Fluency	-.268*	-.202	-.044
*p < .05			

This is an important finding that reiterates the link between Mizraḥi traditions and realisation of *šere*. It also indicates the influence of another factor on the monophthongal realisation of *šere* among Mizraḥi speakers: Judaeo-Arabic. Not only is the diphthong [ej] not pronounced in the Hebrew reading traditions in Islamic countries, Judaeo-Arabic as well does not recognise this diphthong (Harrell 1962, 14). This statistical finding therefore posits Judaeo-Arabic as another possible factor behind the monophthongal realisation of *šere* in Mizraḥi Hebrew, alongside their communal reading traditions (of Hebrew).

⁷ Spearman rank correlation tests the association between two variables. For example, the more fluent a speaker is in Arabic, the less frequent his use of the diphthong. The correlation is between -1.0 and $+1.0$. If closer to 0, the correlation is weak. If closer to -1.0 or $+1.0$, the correlation is stronger. A positive correlation means that if one variable is higher, the second variable is also higher. Conversely, negative correlation means that if one variable is higher, the second variable is lessened.

3.0. Phonology

By way of examining its phonological realisations, I present the categories in which *šere* was realised in our sample. I would like to stress from the start that, unlike the abovementioned studies, we found no link between *plene* spelling or penultimate stress and diphthongal realisations among our speakers.

3.1. Open Syllables

3.1.1. Initial Syllable

The [e] vowel is with one exception articulated in word-initial open syllables, whether stressed or unstressed, where the vowel's origins lie in the historical short *šere* (121 words in different inflections):

- General words such as: אדע 'I will know', אלה 'these', בסדר 'okay', עצים 'trees'
- Personal names: אהוד 'Ehud', אליהו 'Eliyahu' אתי 'Eti'

Only for one instance of historical short *šere*, the numeral תשע 'nine', did we find some realisation of the diphthong alongside the monophthong:⁸ [ej] 2x; [eⁱ] 3x; [e] 11x.

A similar phenomenon is attested for words with etymological *yod*, i.e., historical long *šere* (twenty words): for example, איפה 'where?', ביצה 'egg', בינוני 'intermediate, participle', עיניים 'eyes', שניהם 'both of them, the two of them', תימניה 'Yemenite (FS)', and also for words with proparoxytone stress, e.g., איזשהו

⁸ I also mention אלו for which a single diphthongal realisation [ej] was documented as opposed to [e] seven times.

‘some (X)’. Of the above instances, alongside the realisation [e], diphthongal realisation was found for only two words:

- איזה ‘which’: 4x as the diphthong [ej], 1x as a weak diphthong [eⁱ], as opposed to 263x with the monophthong [e]
- ביניהם ‘between them, among them’: 2x as a diphthong (once as [ej] and once as [eⁱ]), as opposed to 22x with the monophthong [e]

With respect to historical long *şere*, three proper nouns—a town and football team, another town, and a military campaign—displayed mixed realisation alongside exclusively diphthongal realisation:

- ביתר ‘Betar’: 2x with a weak diphthong [eⁱ] and 5x with the monophthong [e]
- חיפה ‘Haifa’: 2x with the diphthong [ej] and 1x with [e]
- איתן (צוק) ‘(Tzuk) Eitan’: 1x with the diphthong [ej] and 1x with weak [eⁱ]

3.1.2. Middle of Word

In open syllables in the middle of a word (penultimate syllable) (91 words), historical long *şere* was pronounced with the monophthong [e], for example, השתניתי ‘I changed’, אלינו ‘to us’, בעיניך ‘in your eyes’, יפיפיה ‘very beautiful’, לידינו ‘next to us’, תפילתנו ‘our prayer’. This was also the case for originally short *şere*, such as אמנו ‘our mother’, אצלנו ‘at ours’, בהמה ‘domesticated animal, beast’, מטחנה ‘food grinder’, רוממה ‘Romema (neighbourhood)’.

3.1.3. Final Syllables

The vowel [e] dominates in open syllables at the end of words (80 words; 83.3 percent), but here we find greater use of the diphthong. This group includes words that end in *heh* and primarily in 'alef, such as, הרבה 'many, much, a lot', הא 'the letter *heh*', הנה 'look!, here!', מבטא 'pronounces/-ing, expresses/-ing (MS)', מוצא 'finds/-ing (MS)', פא 'the letter *peh*', קורא 'calls/-ing, reads/-ing (MS)', רופא 'doctor'.

Note, however, that a significant portion of these words (47) appear in construct forms (mainly in the middle, but also at the end of an utterance), such as בתי- 'houses of', דברי- 'words of', לימודי- 'studies of', משחקי- 'games of', פרקי- 'chapters of', שני- 'two (M)', שתי- 'two (F)'. Only for sixteen forms (which comprise 17.5 percent of the words with this status), most of which are in plural construct state, with the minority the names of the letters *heh* and *peh*, was the diphthong attested.

3.2. Closed Syllables

3.2.1. Single-syllable Words

The same was true for single-syllable words (28 words), regardless of whether the source of the *şere* preserved etymological *yod* (long *şere*) or historical [i]. For example:

- Historical long *şere*: איך 'how?' (and איכשהו 'somehow'), אין '(there is/are) not', בין 'between, among', בית- 'house of', ליל 'eve, evening (of)', עין 'eye of', ריש '(the letter) *resh*', שתיים-עשרה 'twelve'

- Short *ṣere*: אש 'fire', בן 'son', כן 'yes, thus', לב 'heart', מם '(the letter) mem', שש 'six', תן 'give! (MS)'.

3.2.2. Final Syllable

In 485 words that ended with closed syllables, *ṣere* was consistently pronounced [e]. This group also includes words with historical long *ṣere* preserving etymological *yod*, e.g., נבוּיָה 'is (being) burned, disappointed, hurt (FS)', נִרְאִית 'appears, seems (FS)', and proper names, such as יִשְׂרָאֵל 'Israel', יְהִי'ֵל 'Yehi'el', יֶרְדֵּן 'Jordan', עֲדִי'ֵל 'Adi'el', and שְׁמוּאֵל 'Samuel'. This realisation is naturally frequent in names and verbs with no special features that end with *ṣere*, the majority of occurrences.

Only two realisations of the diphthong were found, both in words that end with furtive *pataḥ*. My conclusion was that in closed syllables, Mizraḥi speakers consistently realise *ṣere* as a monophthong [e].

To summarise up to this point: in Mizraḥi Hebrew *ṣere* is almost always realised with the vowel [e], irrespective of its historical source, spelling, stress, or placement in a sentence. Nor is its realisation dependent on education, gender, religiosity, occupation, place of residence, or the speakers' distant ethnic origins.

We now return to the irregularities in the predominantly monophthongal picture described above. Despite their limited number and lack of statistical significance, the cases of realisation of the diphthong shed light on the phonology of spoken Hebrew and on its relationship with classical Hebrew traditions. Below I present all the words for which diphthongal realisations are attested.

4.0. Lexicon

4.1. Loanwords

As expected, the outstanding group in which we find realisation of *šere* as a diphthong is that of loanwords, which are alien to the Hebrew pronunciation and grammatical systems. The preservation of the diphthong in these environments can be attributed to preservation of the form of the original word, especially given the close acquaintance of contemporary Israeli natives with English. Nonetheless, there are instances in which the pronunciation of the words is adjusted to the speakers’ phonological system, which lacks the diphthong [ej]. The following table lists the words in which the diphthong was attested.

Table 3: Loanwords

	[ej]	[e ^j]	[e]
אוקיי	20	2	7
פייסבוק	7	0	2
מייל	1	1	1
דיג'יי	2	0	0
פלייליסט	1	0	0

First place is occupied by the word אוקיי ‘okay’, which is a longstanding word in Hebrew; although it has twenty occurrences with a diphthong, there are seven monophthongal occurrences. It is followed by the relatively new word פייסבוק ‘Facebook’, which came into use at a time when English became more widespread in Israel; here we have seven diphthongal realisations as opposed to two monophthongal ones. The word מייל ‘email’, on the other hand, is realised with all three pronunciations. דיג'יי

‘deejay’, פליי ‘play (button)’, and פלייליסט ‘playlist’ occurred more rarely and were realised with the diphthong.

4.2. Fixed Context

A second group consists of words that appear in fixed contexts. Its members include place and personal names, along with frozen expressions in which *şere* can also be realised as a diphthong. Note that, as mentioned earlier, in all of these instances, *şere* appears in an open syllable in the middle or at the end of the word. Thus, the איתן (צוק) ‘(Tzuk) Eitan (campaign)’ was pronounced with the diphthong in the media and, like that of חיפה ‘Haifa’, its pronunciation became fixed.

Here I also include the letters הַה ‘*heh*’ and פַּה ‘*peh*’ and the numeral תשע ‘nine’, which belong to school language and whose pronunciation adheres to that acquired there.⁹ For the first two words, the diphthongal realisation dominates (87.5 percent): הַה was realised as [hej] three times and as [heʲ] once; פַּה was realised as [pej] twice, as [peʲ] once, and as [pe] once. However, the realisations of תשע attest the widespread realisation of the simple vowel [e] (68.75 percent), found eleven times, as opposed to [eʲ] three times, and [ej] twice. There is a higher realisation of the monophthong (80 percent) in the Aramaic expressions ‘etc.’, וכולי

⁹ The first teachers and educators in the 1950s and 1960s, as well as master teachers in the following decades, had Ashkenazic backgrounds and were speakers of GIH. Their influence on the periphery was substantial and continues to be discernible to the present in the educational sphere.

with [e] six times and [ej] once, and מילא 'oh well, so what, such is life', with [e] twice, [ej] once.

This trend toward diphthongal realisation of words in fixed contexts and in personal names is also attested in GIH. The diphthong is consistently realised in the place names חיפה 'Haifa' and גיא בן הינום 'Valley of Ben Hinnom', in the Aramaic expression וכולי 'etc.' (Rosenhouse 1990, 130), and in the words הא 'heh', פא 'peh', and תשע 'nine' (Neuman 2013, 247–48). Thus, the preservation of the diphthongal pronunciation in proper nouns and fixed contexts in GIH has penetrated Mizrahi Hebrew.

5.0. Phonology: Furtive *pataḥ*

An unexceptional group, but one with historic roots, encompasses the words that end with a glide due to furtive *pataḥ*, previously mentioned in the discussion of word-final closed syllables. Our sample corpus contains 32 words ending in a glide before one of the guttural consonants (*het*, *ayin*, *heh*). Most were pronounced [e] followed by [a], such as ריח ['reḥ] 'scent' written *plene*, and בורח 'flees/-ing (MS)', גובה 'gets/-ting taller (MS)', יודע 'knows (MS)', שומע 'hears/-ing (MS)', תוקע 'thrusts/-ing, sticks-/ing (MS)'. Only in two instances did we hear an approximant palatal consonant *yod* before the glide: תופח [to'fejaḥ] 'swollen', אורח [o'rejaḥ] 'guest'. The latter two realisations were produced by non-native Israelis, from Iraq and from Morocco, whose mother tongue was Judaeo-Arabic. This phenomenon of a break in the continuity of vowels (furtive *pataḥ*) before gutturals at the end of a word is not new, nor is it unique to Contemporary He-

brew; rather, it is attested in Mishnaic manuscripts. Thus, for example, תוקיע 'blow/-ing (the shofar) (MS)' (m. Rosh Hash. 4.5) in MS Kaufmann of the Mishna; מְקַדֵּיחַ 'drill' (m. 'Ohal. 13.1) in MS Parma B. The *yod* is clearly vocalised in both manuscripts (Bar-Asher 2009, I:138–39).

This realisation was also common in the reading traditions of different communities, sometimes with gemination:

- יודע [jo'dejaʕ] 'knows (MS)' (m. Beša 3.2, Aleppo) (K. Katz 1981, 51)
- מניח [man'nijəħ] 'sets/-ting (MS)' (m. Pe'a 5.6, Baghdad) (Morag 1977)
- שומע [šo'mejjaʕ] 'hears/-ing (MS)' (m. Ber. 2.5, Jerba) (Ktzia Katz 1977, 87; Maman 1984, 89–90)
- קורע [ko'rejaʕ] 'tears/-ing (MS)' (m. Shab. 13.2, Tetouan) (Maman 1984, 89–90)

Because the realisations אורח and תופח were attested only in the speech of first-generation immigrants, it seems likely that they should be attributed to the ethnic traditions with which they were familiar, and not to the influence of GIH, whose roots are Ashkenazic.

6.0. Morphology and Syntax

Apart from the phonological categories considered to this point, in which the diphthongal realisation is on the lexical plane, a fairly prominent phenomenon emerged in our corpus: the diphthongal realisation of *şere* in word-final open syllables, in construct state plurals, and in function words and quantifiers.

6.1. Plural Construct State

In GIH, in the plural construct state, *šere* is usually realised diphthongally, as in ערי ‘cities of’, מפרצי ‘gulfs of, bays of’ (Rosenhouse 1990, 130); here we find a strong distinction in Mizraḥi Hebrew. First, I present the occurrences for which the diphthong was attested, as mentioned above:

Table 4: Diphthongal Realisations in Plural Construct State

	nomen rectum	[ej]	[eʲ]
1	ילידי- ‘natives of’	2	0
2	קשיי יום ‘difficulties of the day’	1	0
3	שני- ‘two (M)’	1	0
4	טעמי מקרא ‘biblical accents’	1	2
5	קשרי מסחר ‘commercial connections’	1	0
6	גריסי חיטה ‘wheat grits’	1	0
7	כינויי גנאי ‘derogatory name’; כינויי חיבה ‘pet name’	0	2
8	מטעמי המימונה ‘because of the Mimouna (feast)’	1	0
9	סוגי- ‘types of’	1	0
10	פלפולי שפה ‘casuistry’	1	0
11	ריקודי (ה)בטן ‘belly dances’	3	0
12	שירי- ‘songs of’	2	0

Above I noted that the majority of the forms in the plural construct state in our sample were realised with a simple vowel and only a minority with a diphthong. Moreover, this lack of realisation has no discernible lexical motivation. The same words are realised at times with a diphthong, at others without. Thus, the numeral שני- (no. 3) was generally realised with [e]. Further reducing the diphthongal realisation are those construct-state forms in which the *nomen regens* begins with approximant palatal *yod*, such as ילידי ישראל ‘native Israelis’, קשיי יום ‘difficulties of the day’, and שני ילדים ‘two children’ (nos 1–3), or with the sonorant

consonant *mem*, such as ילידי מרוקו ‘native Moroccans’, קשרי מסחר ‘commercial connections’, טעמי מקרא ‘biblical accents’ (nos 1, 4–5). In these phrases, it is difficult to use Praat to distinguish the diphthong, as the *nomen rectum* could end with a simple vowel and the *yod* or the *mem* at the beginning of the next word create a mistaken impression of diphthongal realisation.

6.2. Function Words and Quantifiers

Another group of words with *şere* in word-final open syllables that have received scant attention in the scholarship are function words and quantifiers that end with the letter *yod*. Here, too, the diphthongal realisations in our sample are few as compared to the monophthongal ones; nonetheless, they are found more frequently in the plural construct state. Below I provide the data for realisation of the diphthong. I have excluded the word הרבה ‘many, much a lot’, which occurs 211 times in the corpus—210 with [e] and once with [ej]—because of the single appearance of the diphthongal pronunciation among the Mizrahi speakers taking part in the sample.

Table 5: Function words, adverbs, and quantifiers

	Function words, adverbs, and quantifiers	[ej]	[e ^j]	[e]	Total occurrences
1	די ‘rather, quite’	6	3	2	11
2	כדי ‘in order’	6	9	21	36
3	אחרי ‘after, behind’	4	5	51	60
4	לפני ‘before, in front of’	3	7	50	60
5	הרי ‘indeed, therefore’	1	2	12	15
6	לגבי ‘concerning’	0	1	5	6
7	לידי ‘to’	0	1	3	4

The two leading words in this category are די (no. 1), mentioned in Rosenhouse's (1990, 130) study of GIH, and כדי (no. 2), which was not mentioned. For די most of the occurrences in our sample were diphthongal, and the minority monophthongal; but for the remaining words the monophthongal realisation dominated. Nonetheless, the diphthongal realisations are not exclusive; thus, for example, אחרי or לפני (nos 3–4), which are realised monophthongally 50–51 times, have 9–10 diphthongal realisations.

To sum up to this point, the majority of the diphthongal realisations of *šere* in Mizraḥi Hebrew occur in word-final open syllables, in the middle or at end of an utterance.

This raises the question of why the diphthongal realisations appear in Mizraḥi Hebrew at the end of words in particular. As described above, in word-initial and word-medial open syllables the diphthong is virtually non-existent in our sample. But in GIH the situation differs: *šere* with etymological *yod* is almost always realised diphthongally; for example, איזה 'which? (MS)', איפה 'where?', בינוני 'intermediate, participle', ביצה 'egg', זיתים 'olives', מידע 'information', מיטב 'best', and צידה 'provisions', among others (Rosenhouse 1990, 130; Neuman 2013; <https://hebrew-academy.org.il/2011/05/01/הגייית-הצירי-המלא/>). In Mizraḥi Hebrew, on the other hand, the diphthong is scarcely realised, with the exception of the aforementioned words איזה 'which? (MS)' and ביניהם 'between them, among them'.

What, then, accounts for the divergence from Mizraḥi consistency in open syllables at the end, but not in the middle, of words? One scholar ascribes it to a phonemic distinction between

singular and plural construct forms, such as קנה מידה ‘scale’ and קני מידה ‘scales’ (Laufer 2008, 211). Others cite the influence of *plene* spelling (Rosenhouse 1990; Neuman 2013), even though our sample showed no link between orthography and the diphthongal realisations as seen from the realisation of *ṣere* in the middle of the word, such as איפה [‘efo] ‘where?’, ביצה [be’tsa] ‘egg’, and בעיניך [be’e’neχa] ‘in your (MS) eyes’, among others. The same is true of the different explanations applied to the diphthongal realisation of the letters *heh* *הא* and *peh* *פא* (Neuman 2013, 148); after all, the letters *bet* *בית* and *resh* *ריש* have identical lexical and sociolinguistic status, but are not pronounced diphthongally.

I seek, however, not a local, but rather a more comprehensive explanation for this phenomenon, as exemplified in word-final open syllables. It appears that a phonological explanation is called for. The initial syllable of words displays stability (Steriade 1994); this accounts for the preservation of the monophthongal realisation of *ṣere* by Mizraḥi Hebrew speakers at the beginning of words such as ביצה [be’tsa] ‘egg’ and עינים [‘e’naim] ‘eyes’, and in most occurrences of איזה [‘eze] ‘which?’, declined בין ‘between, among’, e.g., ביניהם [bene’hem] ‘between them, among them’, and תשע [‘teša] ‘nine’. But the case for the final syllable differs.

The realisation [ej] in Mizraḥi Hebrew occurs particularly in final open syllables. This perhaps represents a tendency to close open syllables at the end of words, especially in frequent, short words. The majority of words in Contemporary Hebrew end with closed syllables: more than 63.1 percent of words end with a closed syllable (CVC) compared to less than 29.7 percent with

open syllables (CV) (Asherov and Bat El 2019). Perhaps the relatively low number of final open syllables invites Mizraḥi speakers to arrive at so-called consistency in the system and to close the syllable with the semivowel [j].¹⁰

If my proposed explanation is tenable, it leads to another important phonological insight connected with the Israeli-Mizraḥi sociolect. This pertains to the question of the nature of the diphthongal *šere* in this sociolect: is it perceived by its speakers as a single phonological unit—a diphthong—or is it perhaps a combination of the [e] vowel and the closely related semi-vowel [j]? I contend, as proposed above, that Mizraḥi Hebrew speakers tend to close final open syllables in specific categories: thus, this is not a diphthongal ‘Ashkenazi’ realisation, but rather the closing of an open final syllable with [j].¹¹

7.0. Conclusion

Mizraḥi Hebrew speakers do not realise *šere* as a diphthong. The realisation of the [e] vowel + a close palatal consonant [j] is attested in their speech in words borrowed from foreign languages, in frozen expressions ‘borrowed’ from GIH, and at the

¹⁰ I am not aware of instances where final open syllables are closed with other vowels. I assume that the inclination to close final syllables in this context may be facilitated by the variant realisation in GIH. Nevertheless, this phenomenon warrants more extensive research.

¹¹ The proposal that GIH does not possess the diphthong [ej] was raised by Laufer (2008, 211) and by Asherov and Bat El (2019, 87) based on different considerations.

end of words. I propose that the realisation [ej] be regarded as a strategy for closing a final open syllable.

When I embarked on my examination of *şere* in Mizraḥi Hebrew, I assumed that the pronunciation of *şere* in Mizraḥi speech would not represent a consistent tradition like that among the first-generation immigrants to Israel, who acquired their communal Hebrew traditions in the Diaspora. I expected to find a spectrum between two poles among second- and third-generation Mizraḥi Hebrew speakers: unique Mizraḥi features as opposed to GIH features. But a different picture emerged. With regard to *şere*, Mizraḥi Hebrew tends to preserve its underlying tradition. As opposed to the rapid decline of emphatic consonants (*qof*, *tet*, *şadi*) and distancing from the guttural consonants (*‘ayin*, *het*), the realisation of *şere* was largely preserved.

Perhaps this can be attributed to the blurred borders—official standard and so-called sociolinguistic standard—of this phonological vocalic difference. On the one hand, the official decision by the Language Committee has not been changed by its successor, the Academy of the Hebrew Language (see §1.0, above). It calls for realisation of *şere* as the monophthong [e], a realisation that is in line with the Hebrew reading traditions of Jews from Islamic countries and their descendants in Israel. On the other hand, in actuality, significant enclaves in which *şere* is realised diphthongally still remain in spoken Hebrew and have become a sociolinguistic criterion. In addition, quite a number of speakers maintain that this is the proper way to speak. This lack

of clarity seems to underlie the retention of the traditional Mizrahi *šere* and the difficulty in automatically imitating and adopting the GIH realisations.

References

- Asherov, Daniel, and Bat-El Outi. 2019. 'Syllable Structure and Complex Onsets in Modern Hebrew'. *Journal of Afroasiatic Languages and Linguistics* 11: 69–95.
- Bar-Asher, Moshe. 2009. *Studies in Mishnaic Hebrew*. 2 vols. Jerusalem: Bialik Institute. [Hebrew]
- Ben-Hayyim, Ze'ev. 1992. *The Struggle for a Language*. Jerusalem: Academy of the Hebrew Language. [Hebrew]
- Bentolila, Yaakov. 1984. 'The Sociophonology of Hebrew as Spoken in a Rural Settlement of Moroccan Jews in the Negev'. PhD dissertation, The Hebrew University of Jerusalem. [Hebrew]
- Blanc, Haim. 1964. 'Israeli Hebrew Texts'. In *Studies in Egyptology and Linguistics: In Honour of H. J. Polotsky*, edited by H. B. Rosen, 123–52. Jerusalem: Israel Exploration Society.
- Harrell, Richard S. 1962. *A Short Reference Grammar of Moroccan Arabic*. Washington, D.C.: Georgetown University Press.
- Harshav, Benjamin. 2008. *Language in Time of Revolution: The Modern Jewish Revolution and the Renaissance of the Hebrew Language*. Jerusalem: Carmel. [Hebrew]
- Henshke, Yehudit. 2013. 'Sepharadi Pronunciation Traditions of Hebrew'. In *Encyclopedia of Hebrew Language and Linguistics*, edited by G. Khan et al., 3:536–42. Leiden: Brill.

- Katz, Dovid. 1993. 'The Phonology of Ashkenazic'. In *Hebrew in Ashkenaz: A Language in Exile*, edited by Glinert Lewis, 46–87. New York and Oxford: Oxford University Press.
- Katz, Ktzia. 1977. *The Hebrew Language Tradition of the Community of Djerba (Tunisia): The Phonology and the Morphology of the Verb*. 'Edah Ve-Lashon 2. Jerusalem: Hebrew University Language Traditions Project. [Hebrew]
- . 1981. *The Hebrew Language Tradition of the Aleppo Community: The Phonology*. 'Edah ve-Lashon 7. Jerusalem: Hebrew University Language Traditions Project. [Hebrew]
- Laufer, Asher. 2008. *Chapters in Phonetics and in Phonetic Transcription*. Jerusalem: Magnes Press. [Hebrew]
- Maman, Aharon. 1984. 'The Reading Tradition of the Jews of Tetouan: Phonology of Biblical and Mishnaic Hebrew'. *Massorot* 1: 51–120. [Hebrew]
- Matras, Yaron, and Leora Schiff. 2005. 'Spoken Israeli Hebrew Revised: Structures and Variation'. *Studia Semitica: Journal of Semitic Studies Supplement* 16: 145–91.
- Morag, Shelomo. 1977. *The Hebrew Language Tradition of the Baghdadi Community: The Phonology*. 'Edah ve-Lashon 1. Jerusalem: Hebrew University Language Traditions Project. [Hebrew]
- Neuman, Yishai. 2013. 'Moşa'ah shel ha-Du Tnu'a ey ba-'Ivrit Bat-Zmanenu ve-ha-Gormim ha-Matnim et Tefuşatah'. *Hebrew: A Living Language* 6: 237–60.
- Ornan, Uzi. 1973. 'Mivta'o shel ha-Şere'. In *Readings in Phonology*, 154–56. Jerusalem: The Hebrew University of Jerusalem. [Hebrew]

- Peleg, Elhanan. 1989. 'Sociolinguistic Variation and the Diffusion of Change in the Language of Israeli Adolescents'. PhD dissertation, The Hebrew University of Jerusalem. [Hebrew]
- . 1992. 'Pishute Du ha-Tnu'a [ei] ba-ʿIvrit ha-Yiśraelit: Hishtaqfutam shel Tahalikhim Ḥevratiyim be-Tahalikh Shinui Fonologi'. *Hebrew: A Living Language* 1: 141–52.
- Rosenhouse, Judith. 1990. 'Issues in Hebrew Phonetics: The Articulation of ḥ/x and Şere'. In *Proceedings of the Tenth World Congress of Jewish Studies*. Division D, I: 125–35. Jerusalem: World Union of Jewish Studies. [Hebrew]
- Steriade, Donca. 1994. 'Positional Neutralization and the Expression of Contrast'. Unpublished manuscript, University of California, Los Angeles.
- Téné, David. 1996. 'Shalosh He'arot 'al Hakhvanat ha-Lashon ha-ʿIvrit'. In *Evolution and Renewal: Trends in the Development of the Hebrew Language: Lectures Commemorating the 100th Anniversary of the Hebrew Language Council*, 212–44. Jerusalem: Israel Academy of Sciences and Humanities.
- Vaʿad ha-Lashon ha-ʿIvrit be-ʾEreṣ Yiśrael. 1928. *Zikhronot Vaʿad ha-Lashon A–C*. Jerusalem: The Academy of the Hebrew Language.
- Weiman, Ralph W. 1950. *Native and Foreign Elements in a Language: A Study in General Linguistics Applied to Modern Hebrew*. Philadelphia: Russell Press.
- Yellin, David. 1905. *Ha-Mivṭa ve-ha-Ktiv be-ʿIvrit*. Jerusalem: Luncz.
- . 1937. 'Le-Mivṭa ha-ʾOtiyot ve-ha-Tnu'ot be-ʿIvrit'. *Leshonenu* 8: 73–80.

THE BIBLE AND MODERN HEBREW

Yaron Peleg

The Hebrew Bible has played a major role in the formation of modern Jewish culture, particularly modern Hebrew literature, and was instrumental for promoting the early visions of the Jewish Enlightenment or *Haskala*. But while the ideas of *Haskala* were spread among Jewish readers in the Hebrew of the Bible, no one expected those readers to pick up Hebrew and start using it every day. It was only after the rise of Zionism that Hebrew sprang to spoken life and became a vernacular again. The Hebrew Bible was central for both developments—for articulating a proto-national Jewishness and for reviving spoken Hebrew—and this short essay looks at some of the different roles it played in this history and the changing influence it had on the perception of the Hebrew language as part of it—from a cultural conceit during the *Haskala* to a cultural imperative under Zionism.

Because much of this history is known, I note only briefly the instrumental use of Biblical Hebrew (BH) by many *maskilim*, especially those who were reluctant to use Yiddish, the language of their diaspora and subjugation, and who hoped that BH would remind Jews and non-Jews of the majesty of ancient Israel and the grace of its old language (Seidman 1997). When Hebrew writers referred to the biblical kingdoms of Judah and Israel, it was

not in service of a political programme for the restoration of Jewish independence. Not yet. That would come later with Zionism. BH was a sentimental device that gave Jews a greater sense of worth.

In 1853, Abraham Mapu (1808–1867) captured these sentiments in his runaway bestselling historical novel, *The Love of Zion* (אהבת ציון), a love story set in biblical times and written in BH throughout. Now, historical novels are always about the present, not the past, and so the love story and the political context in which it is set provide important clues to the novel's agenda. The pastoral romance teaches about personal fulfilment through love; the religious reforms of king Josiah resonate with the reformatory programme of the *Haskala*. Mapu worked on the novel for nearly twenty years and used a literary technique called *shibuts* in Hebrew, which roughly translates as 'mosaic'. He collected words, phrases, and names from the Hebrew Bible and rearranged them to create an entirely new text, a secular work of art that used a sacred language.

Because Mapu limited himself strictly to the language of the Hebrew Bible and cherry-picked dramatic elements from well-known stories, readers of the novel get an uncanny impression that they are reading the Holy Book. Here is the opening to the novel, which draws on the book of Job, on the book of Kings, on patriarchal stories, and on the story of the prophet Samuel:

איש היה בירושלים בימי אָחָז מלך יהודה ושמו יוֹרָם בן אֶבְיָעוֹר, אלוֹף
ביהודה ושר אלף, ויהי לוֹ שדות וכרמים בכרמל ובשרון ועדרי צאן ובקר
בבית לחם יהודה; ויהי לוֹ כסף וזהב, היכלי שן וכל שכיות החמדה, ושתי
נשים היו לוֹ, שם האחת חַגִּית בת עִירָא, ושם השנית נַעֲמָה. ויאהב יורם
את נעמה מאד, כי יפת תואר היא. ותקנא בה חגית צרתה ותכעיסנה, כי
לחגית היו שני בנים ולנעמה לא היה ולד.

In the days of Ahaz, king of Judah, there was a man in Jerusalem named Yoram ben Aviezer, a chieftain in Judah and captain of a thousand. He had fields and vineyards in Carmel and Sharon as well as sheep and cattle in Bethlehem of Judah. He also had silver and gold, ivory palaces, and lovely crafts. And he had two wives, one named Hagit daughter of Ira, the other named Na'ama. Yoram loved Na'ama very much, for she was beautiful. Hagit, her rival, was envious of her and tormented her, for she had two sons and Na'ama had no child.

Table 1. Biblical references in *The Love of Zion* (non-biblical material in brackets)

איש היה בירושלים 'There was a man (in Jerusalem)' (Job 1.1)
 בימי אֶחָז מֶלֶךְ יְהוּדָה 'in the days of Ahaz king of Judah' (Isa. 7.1)
 וּשְׁמוֹ יוֹרָם '(and his name was) Yoram' (2 Sam. 10.8)
 בֶּן אֲבִיעֶזֶר '(son of) Aviezer' (Josh. 17.2)
 אֲלוֹף בִּיהוּדָה 'chieftain (in Judah)' (Gen. 36.15)
 וְשָׂר אֶלֶף 'and a captain of a thousand' (1 Sam. 18.13)
 וְהָיָה לוֹ 'And he had' (Gen. 12.17)
 שָׂדֵה וְעֵצִים 'fields and vineyards' (1 Sam. 22.7)
 בְּכַרְמֶל 'in Carmel' (Josh. 18.26)
 וּבְשָׂרוֹן 'and in Sharon' (1 Chron. 27.29)
 וְעֵדְרֵי צֹאן וּבָקָר '(and flocks of) sheep and cattle' (Gen. 12.16)
 בְּבֵית לֶחֶם יְהוּדָה 'in Bethlehem of Judah' (Judg. 17.7)
 וְהָיָה לוֹ כֶּסֶף וְזָהָב '(and he had) silver and gold' (Gen. 24.35)
 הַיָּבֵלִי שֵׁן 'ivory palaces' (Ps. 45.9)
 שְׂכִיּוֹת הַחֲמֹדָה 'lovely crafts' (Isa. 2.16)
 וּשְׁתֵּי נָשִׁים הָיוּ לוֹ 'And he had two wives' (1 Sam. 1.2)
 שֵׁם הָאֶחָת 'The name of the one (was)' (Gen. 4.19)
 חָגִית 'Hagit' (1 Sam. 3.4)
 בַּת עִירָא '(daughter of) Ira' (2 Sam. 20.26)
 וּשְׁם הַשֵּׁנִית '(and the name of the other (was))' (Gen. 4.19)
 נַעֲמָה 'Na'ama' (Gen. 4.22)
 וַיֹּאהֲב יוֹרָם אֶת נַעֲמָה מְאֹד 'And Yoram (greatly) loved (Na'ama)' (Gen. 29.18)
 כִּי יָפֶת תּוֹאֵר הִיא '(for she was) beautiful' (Gen. 29.17)
 וַחֲגִית הָיָה עֹנֵה לָּהּ 'And (Hagit) was envious of' (Gen. 30.1)
 צֶרְתָּהּ 'her rival' (1 Sam. 1.6)
 וַתְּכַעֲסֶנָּה 'and tormented her' (1 Sam. 1.7)
 כִּי לְחָגִית הָיוּ שְׁנֵי בָנִים וּלְנַעֲמָה לֹא הָיָה וָלֶד 'for (Hagit had) two sons while (Na'ama) had no child. (Gen. 11.30)

A few decades later, in response to the limited emancipation the *Haskala* offered, Hebrew writers began giving their Hebrew a more political turn, as in Mordechai Zeev Feierberg's novella, *Whither?* (לָאֵן?), which ends with this vision: "I do believe," says the protagonist, "that if the Jewish people truly have a purpose, [they should live up to it] by going to the East," to the Land of Israel, "not as an enemy of the East, but as its loving brother." It will not be easy, he warns his listeners, but there is no doubt it shall come about. "I see it, though not now, I behold it, yet it is not near," he quotes the prophet Balaam (Num. 24.17), and ends his own prophecy with the call, "To the East! To the East! (מִזְרָחָה *mizraḥa*)." Feierberg (1874–1899) wrote those words at about the same time Zionism appeared on the world stage. It was not a coincidence, except that Feierberg and other Hebrew writers focused on culture, not on diplomacy, and hoped that language would bring those changes about. They were sorely disappointed. Most Jews were occupied with the ordinary stuff of an increasingly secular life and had little time or use for Hebrew. Many emigrated overseas in search of a better life, and those who remained in Europe still believed in integration. Hebrew became increasingly useless for both groups.

Zionism was a game-changer and it turned the fate of Hebrew around. If the *maskilim* were the first to imagine Hebrew in a secular context, Zionists gave that context a political meaning. With the establishment of the *Yishuv*, the modern Jewish community in Palestine in the first half of the twentieth century, Hebrew almost immediately became its transcendent expression. From that moment on, the Modern Hebrew library that had been

written outside of Palestine throughout the previous century became the linguistic and imaginative soil on which the Hebrew of the *Yishuv* grew and developed.

But although the Bible continued to be a source of inspiration during the heady days of the *Yishuv*, the focus of its Zionist readers shifted from its language to the Book's narrative content. If the *maskilim* had relied on the ancient register of Hebrew to invoke the glories of their past, Zionists hoped to create an equally glorious future. It was a momentous change that transformed the Hebrew language from an agent of change during the Jewish Enlightenment to something in line with the more usual way we think of language, as an expression of culture.¹ Put another way, if the Hebrew of the *Haskala* had been a conduit between Jewish tradition and Jewish modernity, Hebrew in the *Yishuv* became a more organic part of life. And if the Bible had always informed it, it was now more the content of the book than its language—the stories it told, the heroes it described, and the places it mentioned, rather than the Hebrew in which they were told (Shapira 2006).

It was a logical shift. Jerusalem, Bethlehem, Mount Carmel, and the Plain of Sharon were but metaphors for Mapu in *The Love of Zion*, memories of an ancient pedigree. This is why the kind of Hebrew he used was so important. The language itself was the message. But when Hebrew spilled from book to street in Palestine, it lost its ancient grandeur and became the “staff of life,” as Bialik once wrote (‘Revelment and Concealment in Language’).

¹ The philosophical question of language as reflecting or creating reality bears on this point, of course.

The men and women of the Yishuv, the ‘New Hebrews’, as they called themselves, were interested in the Jewish political craftsmanship of their biblical ancestors—especially the work of men and women of war, generals like Joab and courageous women like Jael. They were looking for actual role models, not allegories. “The Bible,” wrote educator Ben-Tzion Mossinsohn in 1920, “needs to provide our children with a complete picture of our nation’s life in its own land and raise in the hearts of little Hebrews a passion for life and for renewing our national history” (in Shahar 2021, 51). Moreover, he added, when studying the historical (*sic*) parts of the Bible, a geographic map of the Land of Israel should be displayed in class, for it would bring the stories to life and help link people and land in the minds of pupils (Shahar 2021, 53).

Biblical geography was immensely popular in the *Yishuv*. Zionists went on hikes to places like Anathoth, Tekoa, the Judean Desert, and Mount Ephraim. They also gave the pastime a name, ידיעת הארץ, which roughly translates as ‘Know Your Land’. Treks to biblical sites, real or imagined, became integral to Zionist education, extracurricular musts that functioned as an act of husbandry. Traversing the land on foot with Bible in hand acquainted New Hebrews with their *Altneuland*, encouraging them to trace their ancient past on it and take mental possession of it.

Since the Land of Israel is full of the relics of its rich past, moving through its space becomes a movement through history. Every village, every mountain, every fortress and river remind students of their people’s awesome past, of which they heard their teachers tell them. (Shahar 2021, 211)

The vogue of biblical archaeology from the 1950s onward was a more scientific expression of this trend (Finkelstein and Mazar 2007). Archaeologists like Yigael Yadin, who dedicated his academic career to verifying ancient Jewish history, dug up the breadth and width of Israel in search of hard evidence for the nation's roots. And if he was not always successful, it did not diminish his celebrity status, which underscored the cultural importance of the Bible for the young and officially secular Jewish state. Again, the Bible was not used as a dictionary for Israel's Hebrew vernacular. It was seen more as an historical deed to the country, a document that proved Jewish belonging to the land and ownership of it. On 27 November 1957, a short notice on page 2 of the daily *Haboker*, announced that "The remains of a very ancient city from the time of the Patriarchs, probably dating to the 18th century BCE, were found under an ancient Canaanite city in Hazor, which was destroyed by Joshua during the conquest of the Land." The note leaves no doubt as to the historical veracity of either the Patriarchs or Joshua.

With the passage of time and the development of Israel, the need to prove its political legitimacy and its ties to the land diminished as well. The success and prosperity of the state spoke for themselves, without the need to use the Bible as justification. It was especially so regarding military matters, which, in hindsight, seem like a self-fulfilling prophecy. As my Bible teacher once told us—it was in the 1970s—the succession of Israel's military victories in 1948, 1956, 1967, and 1973 were "biblical" in nature, so unlikely and miraculous, she said, that they could easily have fit into the books of Judges, Samuel, or Kings.

And when realpolitik replaced cultural politics, the relevance of the Bible and its Hebrew shifted once again, this time from history and politics to a more personal reading of the book's wisdom, as in this poem by Natan Zach (1930–2020):

<i>Man's days are like grass.</i>	אָנוֹשׁ כְּחֶצִיר יָמָיו.
<i>His days are like grass.</i>	יָמָיו כְּחֶצִיר.
<i>The days of man are like grass</i>	יָמֵי אָנוֹשׁ כְּחֶצִיר
<i>his days.</i>	יָמָיו.
<i>Do not fear.</i>	אַל תִּירָא.
<i>Man is to wretchedness born</i>	אָדָם לְעַמָּל יוֹלָד
<i>born to wretchedness.</i>	יוֹלָד לְעַמָּל.
<i>Man is born to wretchedness</i>	אָדָם יוֹלָד לְעַמָּל
<i>born.</i>	יוֹלָד.
<i>Do not fear.</i>	אַל תִּירָא.
<i>As sparks fly upward.</i>	וּבְנֵי רֶשֶׁף יִגְבִּיהוּ עוֹף.
<i>Upward sparks fly.</i>	יִגְבִּיהוּ בְנֵי רֶשֶׁף.
<i>As sparks fly upward</i>	וּבְנֵי רֶשֶׁף יִגְבִּיהוּ עוֹף
<i>fly upward.</i>	יִגְבִּיהוּ.
<i>Do not fear.</i>	אַל תִּירָא.

Quoting from Psalms and from Job, Zach bypasses the original piety of the teachings and reads their wisdom more personally in the spirit of 1960s western counterculture. Beginning each stanza with an original quote from the Bible, the lines that follow break up the quotes, change the word order, and repeat them in ways that deconstruct their original meaning. As a result, the brevity and wretchedness of existence become simple facts of life, well-known and unhallowed. Moreover, the fourth lines of the first

and second stanzas each contain one word only, יָמָיו 'his days' and יוֹלָד '(he) is born', respectively, emphasising the centrality of man over God. The single word יִגְבִּיהוּ '(they) will fly upward', in the fourth line of the last stanza, stresses that centrality by speaking of the heights or distances humans can attain even in their short lifespan, by their own effort. Finally, the common biblical phrase אַל תִּירָא 'fear not' that ends each stanza is used here not as a biblical promise of God's protection and reward to the faithful, but as a simple encouragement to believe in oneself.

Zach is just one example of the widespread poetic use of the Bible in Modern Hebrew literature (Shaked 2005). Meir Shalev is another writer who gave biblical stories a clever contemporary twist in his works. It made him very popular at the turn of the last millennium, although time is slowly changing that dynamic, too. Most of Shalev's readers were relatively old Israelis, who had grown up in the middle of the twentieth century, during the heyday of Israeli biblicism. Their children find the Bible less appealing, and their grandchildren read it with increasing difficulty.

There are some exceptions to this, like national religious Israelis, or settlers, who read the mythological geography of the ancient Land of Israel quite literally. But otherwise, the Bible in Israel has been overshadowed, like poetry and literature more generally, by social media and by the Internet; and this is not unique to Israel, of course. The change has also influenced the relevance of the Bible, certainly for secular Israelis. But in yet another reversal, it has made the Hebrew of the Book important once again, this time as a timeless linguistic standard and another

manifestation of the Zionist yearning for normalcy. The Bible today functions like a Hebrew Shakespeare, or more aptly, like a Hebrew Qur'ān, a standard against which language is constantly measured. The Hebrew Bible does not shape the spoken language of Israel anymore, except as a hallowed model, a measure of eloquence that continues to enrich the language and keeps it connected to its ancient roots.

References

- Brenner, Michael, Vicky Caron, and Uri K. Kaufman. 2003. *Jewish Emancipation Reconsidered: The French and German Models*. Schriftenreihe wissenschaftlicher Abhandlungen des Leo Baeck Instituts 66. Tübingen: Mohr Siebeck.
- Finkelstein, Israel, and Amihai Mazar. 2007. *The Quest for the Historical Israel*. Atlanta: Society of Biblical Literature.
- Mapu, Abraham. 1853. *The Love of Zion*. Vilnius: R. Josef Reuben.
- Seidman, Naomi. 1997. *A Marriage Made in Heaven: The Sexual Politics of Hebrew and Yiddish*. Berkeley: University of California Press.
- Shahar, David. 2021. *Myths and Education: Ethos, Mythos and National Narratives in Hebrew Education in Palestine 1882–1918*. Tel-Aviv: Ressling.
- Shaked, Malka. 2005. *The Bible in Modern Hebrew Poetry*. Tel-Aviv: Miskal. [Hebrew title: *La-Nestsah 'Anagenkha: Ha-Miqra ba-Shira ha-Ivrit ha-Ḥadasha*]
- Shapira, Anita. 2006. *The Bible and Israeli Identity*. Jerusalem: Magnes, The Hebrew University Press. [Hebrew title: *Ha-Tanakh ve-ha-Zehut ha-Yisre'elit*]

B. COMPARATIVE SEMITICS AND THE SEMITIC LANGUAGES

ALPHABETICAL ORDER AND ALPHABETICAL THINKING IN THE EAST AND WEST: FROM ANTIQUITY TO THE MIDDLE AGES*

Aaron J. Koller

The history of an idea as simple as alphabetical order can be mad-deningly difficult to write. The burden of the present paper is not to write that history, but to contribute towards its historiography. Eurocentric discussions of the history of alphabetisation have seen a blank slate in the millennium between Antiquity and the Western Europe of the thirteenth century. This silence is the result of ignoring relevant developments in the eastern Mediterranean and Near East, and later, as the Islamic world, including North Africa and Muslim Spain.¹

* It is an honour to dedicate this article to Prof. Geoffrey Khan, whose own work ranges across language and centuries in a way that reminds me like few others of my own shortcomings and limitations. Still, I hope that he accepts this modest contribution to a trivial historical problem with his typical grace and generosity. I am indebted to Joshua Dachman for comments and suggestions that improved this paper.

¹ This is the impression given by Daly (1967), who may be partially excused on the grounds that his is explicitly not a full history. However, he writes, “the refinement of alphabetic order may well be considered

The idea that alphabetical order was unused during the first millennium is *prima facie* unlikely. The conceptual prerequisites for alphabetisation are simple, and were present already in Antiquity, and even earlier. Assuming the use of an alphabet, there first needs to be an *order* to the alphabet, and second, users of the alphabet have to think of the alphabet metalinguistically—not only as a graphic method of conveying sounds, but as something that can stand outside of language, as well.² There is ample evidence from the ancient world that both of these conditions were met.

as something of a lost art” between the second century and the eleventh (72). Daly’s work misled others even more egregiously; a particularly ill-informed victim is Flanders (2020), who writes that “Aristotle, who had been dead for more than a millennium, was ultimately to do more for alphabetical order than any living person in the Middle Ages” (42). One earlier reviewer of Daly’s book also missed the need for a more expansive picture: “His work must needs (*sic*) be supplemented by the findings of specialists in several other fields: English, Germanics, Romance languages, Slavic, Celtic, to mention a few” (Kuhn 1972, 300–1). Missing from this list are the fields that deal with anything to the south or east of Christian Europe.

² Americans of a certain age may recall a Sesame Street skit that focuses on this ambiguity. When Big Bird sees a sign that says ABCDEFGHIJKL-MNOPRSTUVWXYZ, he reads it phonetically, /æbkədəfɡi:dʒekəlmi-nɒpkwɜrstu:vwiksɪz/, not realising that these graphemes were intended metalinguistically. Susan explains: “That’s not a word... this is the alphabet!” (see <https://www.youtube.com/watch?v=qTvhKZHAP8U>).

1.0. Alphabetical Order

Evidence for alphabetical order—indeed, two different alphabetical orders—comes from abecedaries³ in Israel, Ugarit, and South Arabia, for instance, and from alphabetic acrostics in biblical and later literature.⁴ Indirect evidence for the *'alef–bet–gimel* order arrives from borrowed alphabets. Both the Ugaritians and the Greeks added letters to the alphabet when they borrowed it; the location of these additional signs at the end of the alphabets indicates that the order of the first 27 letters was inherited from elsewhere (for the Greek data, see Jeffery 1961). There are also Iron Age practices such as the *'atbaš* cipher, which pairs the first letter of the alphabet with the last letter, the second with the penultimate, and so on (perhaps already in the twelfth-century BCE Izbet Šartah ostrakon, Demsky 1977, 19–20). Significantly,

³ For discussions, see Berlin (1985); Freedman (1986); First (2014). See also the discussions of Hallo (1996, 35–41; 2004); and especially the structure discerned by Demsky (2015). Furthermore, cuneiform lists of the alphabetic letters, from the second and first millennia BCE, show the familiar *'alef–bet–gimel* order (Cross and Lambdin 1960; Geller 1997–2000; Cross and Huehnergard 2003). The second alphabetical order, which begins *heh–lamed–het–mem*, is attested in the second millennium in abecedaries from Beth Shemesh and Ugarit, and, partially, from an even earlier ostrakon from Thebes (Haring 2015); in the first millennium, it is the standard order of the alphabet in southern Arabia (Irvine and Beeston 1988; the variation found in Central and Northern Arabia discussed by Macdonald 1986 will be put aside as secondary), and Egypt (see below), and continues into the Christian era in Ethiopia (Honeyman 1952).

⁴ For biblical and Qumran acrostics, see below.

the same tactic seems to be utilised in Jeremiah's writing of שֶׁשַׁח 'Sheshach' for בָּבֶל 'Babylon' (Jer. 25.26; 51.41) and לֵב קָמַי 'Leb-kamai' (lit. 'heart of my adversaries') for כַּשְׁדִּים 'Chaldeans' (Jer. 51.1) (Steiner 1996). The importance for our discussion is that this presupposes a known order for the alphabet, so that 'letters 1, 2, 3' and the corresponding 'letters 22, 21, 20' are culturally meaningful terms.⁵

2.0. Metalinguistic Thought

Evidence that alphabet users thought of the letters metalinguistically, not just as signs of sounds, is also ready to hand. Letters are used to mark bricks (Millard *apud* Curtis, Collon, and Green 1989; Millard 2009; Bloch 2018) and ivories (Millard 1962, 49–51), and later, baskets in the Jerusalem Temple: "In three baskets of three *se'ahs* they make the donations of the chamber, and on them was written 'alef, bet, gimel. Rabbi Ishmael says, 'Greek was written on them: *alpha, bita, gamma*'" (m. Sheḳalim 3.2).

Another possible indication of metalinguistic letter use, which also provides evidence for alphabet order, is the numerical calculation known later as *gematria*, in which each letter has a numerical value (for the term, Sambursky 1976). This may have roots in cuneiform literature (Lieberman 1987, 174–76),⁶

⁵ Related to this are the suggestions that the verb לָמַד 'learn' (Prov. 22.25) derives from the name of the first letter of the alphabet (Coogan 1990) and that *elementum* derives from the sequence *l–m–n*, i.e., the beginning of the second half of the alphabet (Coogan 1974).

⁶ It is not clear what order cuneiform signs would be in. One text often mentioned in this regard is Sargon II's claim, "I made the measure of its

and it is not implausible that *gematria* was in use already in biblical Israel, for example, in counting words in poems (Knohl 2012; for other examples of ‘alphabetical thinking’ in Deut. 32, see Skehan 1951) or in the connection between the figure 318 (the number of retainers Abraham brought with him to war according to Gen. 14.14), and the name of Araham’s servant, Eliezer (mentioned only once, in the difficult Gen. 15.2; discussion in Gevirtz 1969).

There are certainly instances of *gematria* in Jewish and Christian literature of the Roman era. In 3 Baruch, the number 360 has been plausibly interpreted as the *gematria* of the Greek word *drakon* written in Hebrew (דרקון), and the number 666 in Rev. 13.18 is said to be the *gematria* of “Caesar Nero” (נרון קסר) written the same way (Bohak 1990). Also in the New Testament, Matthew structures the genealogy of Jesus around the number 14, the *gematria* of דוד ‘David’ – who is fourteenth from Abraham; John’s reference to the catch of 153 fish (21:11) may be the *gematria* of עגלים, a place mentioned in Ezekiel 47; the number 153 is also utilised in 4Q252 for the number of days that Noah’s flood waters were on the earth (Brooke 1998; cf. Kiley 2008).

wall 16,283 cubits, (corresponding to) my name (*nibīt šumīya*).” It sounds like Sargon’s name has some numerical significance, but as Frahm (2005) points out, no one has yet figured out what this might be, and Frahm says that his attempts to work with the number-syllabary texts published by Pearce were unsuccessful. Indeed, Pearce (1996) collects the evidence for associating cuneiform signs with numerals, but can discern no logic in the associations, suggesting that they are arbitrary. Cf. the insightful discussions of Mullaney (2017) and Tsu (2022, 127–68) on comparable challenges in modern Chinese.

An obvious metalinguistic use of the alphabet in biblical times is the common practice of organising texts, particularly poems, into alphabet acrostics (comparative discussions in Soll 1988; Brug 1990): Nah. 1.2–8 (Arnold 1901); Pss 9–10; 25; 34; 37 (Maloney 2005); Pss 111; 112; 119; 145 (Meyney 2015); Prov. 31:10–31; Lam. 1–4 (Assis 2007); Ben Sira 51:13–30; Ps. 155 (preserved in Syriac and in the Dead Sea Scrolls Psalms Scroll); a Qumran composition labelled the ‘Apostrophe to Zion’ (in that same Psalms Scroll); and one additional text found in that scroll (Eshel and Strugnell 2000). As the last examples indicate, this practice survived into post-biblical times, as well (Marcus 1947).

Finally in this section we should cite Jesus’s saying “‘I am the Alpha and the Omega,’ says the Lord God” (Rev. 1.8; 21.6; 22.13). The theological claim seems to be based on “I am the first and I am the last” (Isa. 44.6).⁷ The use of the first and last Greek letters to incarnate, so to speak, the abstract concepts ‘first’ and ‘last’ is a dramatic metalinguistic use of the alphabet.

3.0. Textual Order

The final element needed to produce the use of alphabetical order is the desirability of textual order. A non-literate society would have no concept of such order, and a town with only three books

⁷ The rabbinic ‘response’ to Jesus’s claim is found in Bereshit Rabbah 88.2 (and parallels), where, commenting on the claim that חותמו של הקדוש ברוך הוא אמת ‘the seal of the Holy One, blessed be He, is *’emet* (‘truth’),’ Resh Lakish says, “*’alef* from the beginning of the letters, *mem* in the middle, and *taw* from the end, to fulfill ‘I am the first and I am the last’ [Isa. 44.6]” (see Weiss 2014, 124 fn. 141).

would have no need for one. On the other end of the spectrum, the use of alphabetisation is declining in the twenty-first century, as computing changes the realities of information technology. With dictionaries and library catalogues online, alphabetical order has disappeared from realms in which it used to be dominant.

These two realms—books and lists—are the natural homes of alphabetical order. The organisation of books must go back thousands of years, but as Mesopotamian archival practices are not entirely known, we do not know how the twenty-thousand tablets in Zimri-Lim's palace in Syria from 1800 BCE were organised. It presumably involved division by date and genre (political historical, diplomatic, legal, and domestic records are represented; Sasson 1972), and the use of dockets to label texts (Fales 1986; Abrahams and Coulon 2008; Dalley 2009; Hagen 2011; Hamidović 2014; for the earliest Mesopotamian evidence of archival organisation, see Molina 2016). There was a somewhat comparable structure in lists of Sumerian proverbs, which were grouped by the first sign of the proverb—all the NIG 'thing' proverbs, then all the URU 'city' proverbs, followed by the SA 'heart' proverbs, and so on (Gordon 1954). Both Mesopotamian and Egyptian wordlists, however, had no external order; they are loosely grouped only by word type—all the words for wooden objects, for instance, and then all plants; within the categories, there is no obvious order at all. In Mesopotamia, there are also no 'sequence acrostics', where texts are organised according to sign order.⁸

⁸ There are 'message acrostics', in which the initial signs of the lines spell out the name of the author, or a deity, or something else. For this

The archival practices in the library of Alexandria are somewhat better known to us. The library's histories, poems, philosophical works, books on science, on rhetoric, on politics, translated from many languages, defied simple classification (Daly 1967; Canfora 1990; Casson 2001; Olesen-Bagneux 2014), and so it is not surprising that alphabetical order was pressed into use. According to Daly (1967, 25–56),

it is a reasonable and attractive hypothesis that the [alphabetic] principle was first put to effective use by the scholars of Alexandria in response to the problems they faced as a result of the accumulation under their supervision of such an unprecedented mountain of literature and information.⁹

Lists, too, appear in alphabetical order first in Ptolemaic Egypt (Connor 2018). In surveying the papyri remains, Schironi (2009, 30–36) found nine papyri from the third century BCE to the third century CE that show this order—not a high number, to

distinction and the Mesopotamian data, see Brug (1990, 293–96). In Egypt there are acrostics organised in sequence, but the sequence shows that they did not have an order of the signs: each stanza begins with a homonym of a numeral, in ascending order.

⁹ One alleged early example of alphabetisation is the tradition that Aristotle's studies of 158 constitutions, of which his *Politeiai* was the first, were in alphabetical order. Keaney (1969) argues that this tradition was an invention of later Alexandrian scholars, accustomed as they were to alphabetical order, as does Daly (1967, 16–17); see also Rhodes (1993, 1 fn. 2). (Flanders 2020, 14, misunderstands what is known of Aristotle's works.)

ibe sure, but enough to show that the practice was in use throughout Antiquity. In the late second century, the scribe Menches, in the Egyptian village of Kerkeosiris in the Fayyum, around 135 miles south of Alexandria, made a list of three groups of tenants on crown lands; the three groups are separated by paragraph markers, and within each group, the list is alphabetised by the first letter (Verhoogt 1998, 118). Forty miles further to the south, cartonnage recovered from mummies at El Hibeh included an alphabetical lexicon of many Homeric words (Parsons 2011, 147). On the other hand, many tax rolls, census documents, and lists of soldiers remained untouched by alphabetical order during subsequent centuries.

Numerous other lists from Ptolemaic Egypt show Demotic lists structured in alphabetical order, as well. Although Demotic is not actually an alphabet, these lists have adapted the *idea* of alphabetical order, and grafted it onto the *h-l-h-m* order, as written in Demotic script (the <r> stands in for /l/, which did not exist in Egyptian); the known examples include P. Carlsberg 7 (Iversen 1958, 7–8), P. Saqqara 27 (Smith and Tait 1983, 198–213), O. Deir el-Medina 4-2 (Devauchelle 2014), and P. Berlin 8278 (Gaudard 2012).

As a number of scholars have pointed out (Iversen 1958; Devauchelle 2014, 63–65), Plutarch in the first–second centuries CE wrote that the Egyptian alphabet begins with an ibis, “dedicated to Mercury [i.e., Thoth]” (*Quaes. Conv.* 9.3.2), although Plutarch adds, “But it is not fit, in my opinion, to place an animal that makes no noise at the head of the letters.” Until recently it was not clear what Plutarch could have in mind, since (1) the

Egyptians were not known to have had an alphabet and (2) the alphabet does not begin with *hb* ‘ibis’. The pattern of texts pieced together in recent decades, however, confirms that Plutarch had good information in this case. He clearly had in mind the *h-l-h-m* order, and within Egypt there had developed a folk etymology for this order that suggested that the alphabet began with *h* because of the sacred ibis.¹⁰

Up in the Levant, an ostracon believed to be from Herodion shows a list of names that may simply be an elaborate abecedar. It begins with the letters in order (אבגדהוזחטיכלמנס/ עפצקרשת) and then moves to a list of names: אוריה בניה גמריה / דליה הודיה וני זכריה (Puech 1980). The names were clearly generated for organisational purposes. Remarkably, fragments of what appears to be the same list were found at Masada, as well, suggesting that this was a common way of memorising the alphabet or of practicing writing (Goff 2017, 87).

While documentary evidence is vanishingly rare from sites outside of Egypt and Israel, alphabetical order has also been detected within literary texts, suggesting that it may have played a larger role than the documentary evidence reveals. For example, Virgil gives us a list of Italian heroes in the Aeneid: “Aventinus, Catillus, Coras, Caeculus, Messapus, Clausus, Halaesus, Oebalus,

¹⁰ Note, too, that the fifteenth-century BCE ostracon from Thebes (above fn. 3) has no ibis symbol as the initial letter. Compare, too, the suggestion that the alphabetical order that begins with *’alef* ‘bull’ does so because of the Canaanite bull god El or the equation of El with Hathor (Morenz 2019).

Ufens, Umbro, and Virbius.” A. M. Cook wrote more than a century ago that “there is a method of arrangement, which I, or perhaps one of my pupils (I forget now), detected some time ago... The order is obviously alphabetical” (Cook 1919, 103–4).¹¹ In the late first century BCE, into the first century CE, the freedman Verrius Flaccus wrote an alphabetically arranged encyclopaedia of Roman scholarship, of which only fragments remain.¹² Similarly, a solitary plausible example has been identified in the Mishna, where a list of structurally similar statements seems to be organised alphabetically.¹³

¹¹ Given the tenacity with which scholars tend to arrogate credit for themselves, it seems certain that this insight properly belongs to Cook’s student, whose name unfortunately remains lost to history. As for the problem of Messapus, Cook simply emends the text and moves *Messapus* to the end, but O’Hara (1989) notes that *Messapus* is in fact a reflex of, or allusion to, *Cycnus*.

¹² See Nettleship (1880, 257–58); I am grateful to Dr Matthew Robinson (p.c.) for pointing me to Flaccus.

¹³ Louis Ginzberg *apud* Cohen (1935, 158), finds a partial alphabetical list of questions beginning with מנין ‘whence’ in m. Shabbat 9 (even more partially paralleled in t. Shabbat 9). Ginzberg notes that the final *samekh* stands in for *sin* (although *resh* is still missing) and adds, “The missing letters can be supplied from other sources.”

אמר רבי עקיבה:

מניין לספינה שהיא טהורה?....

מניין לערונה שהיא שישה על שישה טפחים....

מניין לפולטת שכבת זרע....

מניין שמרחיצין....

מניין שקושרין....

מניין לסיכה....

4.0. Medieval Europe and the Middle East

While Western Europe until the High Middle Ages may not have had need for sophisticated organisational tactics, the same was not true in the east. Flanders (2020, 95–96) argues that it was the increasing number of books in thirteenth-century monasteries and universities which made organisation necessary and invited the renaissance of alphabetisation. In this century, collections in western Europe did in fact grow: Paris University, said to have the largest collection, had something approaching 2000 volumes. At the same time, “five libraries in Baghdad alone numbered between 200,000 and 1,000,000 volumes each, including multiple copies of standard works to ensure many readers’ simultaneous access” (Gruendler 2021, 2). The need for organisation was therefore significantly greater, and significantly earlier, in Baghdad than in Paris.

Furthermore, Christians in Western Europe tell us that they spent much less time thinking about the alphabet than the Jews in their midst did. Agobard of Lyon, writing in the early ninth century, wrote that the Jews believe that the letters of the alphabet are primordial, and that prior to the creation of the world the letters fulfilled many tasks, for which they deserve to ‘preside’ in this world (for text and discussion, see Bonfil 1986). Since Agobard clearly did not believe this, it suggests that alphabetic thinking was foreign to Carolingian Christians at a time when Western European Jews took it for granted.

Indeed, there is remarkably no metalinguistic treatment of the alphabet among the Church Fathers (Ketterer 2005, 257, cited with additional discussion by Weiss 2014, 44–45). Perhaps

this was because they recognised the secondary or even tertiary (i.e., borrowed) nature of the letters they used. Already in the second century, Irenaeus of Lyon wrote,

It is only recently (as they say, ‘yesterday or the day before’) that the Greeks received an alphabet of sixteen letters from Cadmus; with the passage of time they discovered the aspirated consonants and the double consonants. Finally, Palamedes added the long vowels.

Responding then to the claim that the letters conveyed truth, Irenaeus says, “Therefore before all that took place among the Greeks Truth did not exist” (*Against Heresies* 1.15; Grant 1997, 61). As Rubin (1998) showed, Greek and Latin church fathers typically understood that Hebrew was the primordial language. Since their alphabets were in any case not the script of God, it is not surprising that Greek and Latin writers spent less time on the significance of the letters of their script. In the east, though, the situation was different: Syriac church fathers argued that the world was created in Syriac.

Off in the east, the tradition of using the alphabet for many types of non-linguistic purposes was alive and well. This means looking primarily at Hebrew and Syriac in the middle of the first millennium, and at Arabic and Hebrew in the latter part of the millennium and into the second millennium. When alphabetisation reappears in western Europe around the year 1200, then, it involves the *rediscovery* of the heritage of the Semitic world.

The alphabet was intensively studied and contemplated in the east. Space constraints preclude even a survey; suffice it to note that the Samaritans, especially as seen in *Tibât Mârqe* (Tal 2019; see also Weiss 2005), Jews (in rabbinic literature and other

works such as *Sefer Yeṣirah*; Weiss 2014; 2017), Syriac Christians (Weiss 2011; 2012; 2017, 55–75), Mandaeans (Drower 1960, 17–20), Byzantine Greeks, and Copts all thought about the alphabet in similar and connected ways (Paz and Weiss 2015). All of this suggests that the traditions of metalinguistic thinking about the alphabet were alive and well from Antiquity through the Middle Ages in the entire alphabetic world—except Western Europe.

Not only was alphabetical thinking present, but alphabetical order was used in the Semitic and eastern worlds throughout the first millennium CE. Although we have no direct evidence for libraries or lists, there is ample evidence of other kinds. Alphabetical acrostics are found in Jewish liturgical poetry of the Byzantine era from mystical circles, such as Hekhalot texts, e.g., אל אדון על כל המעשים (Bar-Ilan 1987, 16–19, 115); rabbinic liturgy, e.g., the *musaf* prayer for *shabbat* (a complete reverse acrostic: תכנת שבת, רצית קרבנותיה. צוית פרושיה עם סדורי נסכיה. מענגיה לעולם כבוד ינחלו. טועמיה חיים זכו, וגם האוהבים דבריה גדולה בחרו. ...אז מסיני...); poets such as Yannai and Yose b. Yose; and Aramaic poems, e.g., אזל משה (Yahalom 1978; Sokoloff and Yahalom 1999, 92–96; Sysling 2006).¹⁴

Syriac literary tradition is full of examples of alphabetically-arranged poetry. According to a later writer, the third-century Aphrahat “wrote two books, and many poems alphabetically arranged” (Mar Abd Yeshua, late thirteenth century, cited in

¹⁴ There are also midrashic texts in which the letters of the alphabet appear, sometimes to parade in front of God, as in Ekha Rabbah *Petiḥta* 24. In such texts, they always appear, of course, in alphabetical order.

Badger 1852, 369). Aphrahat's own prose writings are also organised into 22 books, each beginning with a letter of the alphabet. Dozens of Syriac poems are organised alphabetically. Dialogue poems in particular adopt the form, giving each speaker one line for each of the 22 letters (Brock 1991).

When lexicography comes into view in the Islamic world, alphabetical order is back in full force (for a comprehensive survey, see Baalbaki 2014).¹⁵ The first known Arabic lexicon, the *Kitāb al-ʿAyn* of al-Khalīl ibn Aḥmad al-Farahīdī (d. 786), is organised based on the letters' phonetic values (see discussion in Haywood 1960, 21–22, and Baalbaki 2014), and so the slightly later *Kitāb al-Jīm* is said to be “the first... lexicon known to us which uses the alphabetical system” (Baalbaki 2014, 330). But even the earlier *Kitāb al-ʿAyn* apologises for not being so organised: Al-Farahīdī's student and editor, Al-Layth ibn al-Muẓaffar, wrote:

he could not begin his composition from the beginning of the *ʿalif*, *bāʿ*, *tāʿ*, *thāʿ*, which is *ʿalif*, because the *ʿalif* is a sick letter.¹⁶ But when he passed the first letter, he was loath to begin with the second (which is *bāʿ*) without pre-text and careful consideration. He organised and observed all of the letters... And al-Khalīl inverted the *ʿalif*, *bāʿ*, *tāʿ*,

¹⁵ Baalbaki (2014) has sections on various types of works: specifically alphabetised works (112–20); proverb collections (329–63).

¹⁶ It should be noted that the original order of the Arabic alphabet was the inherited Aramaic/Hebrew order, *ʿalef–bet–gimel–dalet*, and so on, and this order is still reflected in the numerical use of the letters. Within Arabic the letters were secondarily reorganised to reflect commonalities of shape, and that is the order reflected here (*ʿalif*, *bāʿ*, *tāʿ*, *thāʿ*, etc.).

thāʾ, and he placed them in proportion to [the distance of] their articulation point from the throat. (Posegay 2021, 179–82)

Thus, at the very dawn of Arabic lexicography in the eighth century, the default assumption was that words would be in alphabetical order.

As we see in the *Kitāb al-ʿAyn*, the expectation of finding a work organised alphabetically was not always met. The decision of how to organise a work tells us something about the *purpose* of these lexica: for ease of consultation, alphabetical order was unmatched, but some were instead intended for systematic study, in which case other orders proved more practical (Dichy 2019). This pragmatic consideration was articulated by Al-Bandanijī (d. 897) in the introduction to his *Rhyme Dictionary* of rare words; as he explains, were it not alphabetised, it would be difficult for a user to learn from the book, “because the lexicon is vast and voluminous” (Gruendler 2021, 48).

It is not surprising, then, that most later Arabic lexicons were indeed in alphabetical order (Haywood 1960, 53, 98–99; Sanni 1992, esp. 157), although there was no uniformity concerning the details. Some were organised alphabetically by first letter, and others by last letter; some specialised lexicons were organised thematically, e.g., from head to toe in a monograph on the human body (Gruendler 2021, 45; 70–71). The most influential alphabetically arranged Arabic dictionary was that of al-Zamakhsharī (1074–1143), the *ʿAsas al-Balaghah* ‘The Foundation of Eloquence’.

The ubiquitous alphabetical order regularly crossed cultural and linguistic borders. Within medieval Jewish texts, alphabetical order structures Masoretic lists (Dotan 2005, 32–40, 77–83, and *passim*). Masoretic lists contributed to the rise of Hebrew lexicography, and some of the earliest such wordlists, too, display alphabetical order of at least the first letter (Dotan 2005, 150–64).

In the ninth and tenth centuries, the Jews Judah ibn Ḳuraysh in Algeria, Saʿadya Gaon in Baghdad,¹⁷ David Al-Fasi in Jerusalem, and Menaḥem ben Saruq in Cordoba all produced lexicographical works organised alphabetically (survey in Brisman 2000, 1–14).¹⁸ The antecedents to this practice appear in ninth-

¹⁷ Saʿadya's *ʿEgron* has a double alphabetical order: the first part is ordered according to the first two letters, the second, for use by poets searching for rhymes, according to the last letter.

¹⁸ Téné, Maman, and Barr (2007) note that alphabetical order was firmly established in the Jewish world by its use in the pinnacle of medieval Hebrew lexicography, the *Book of Roots* (*Kitāb al-Usūl*) by Ibn Janāḥ. *Kitāb al-Usūl* is the first dictionary in which alphabetical order is followed in careful detail, even to the third letter of roots. (There are some quirks in his system.) Dachman pointed out that in Ibn Janāḥ's work of medicines, *Kitāb al-Talḥiṣ*, the plants are separated by first letter, but not alphabetised beyond that (see Bos et al. 2020). Dachman further points out that Ibn Janāḥ's contemporary, Shmuel ha-Nagid, also wrote an alphabetically ordered dictionary entitled *Kitāb al-Istignāʿ*. The existence of the work is known from mentions by Abraham ibn Ezra, who even tells us that it is in 22 sections; the work itself is known from fragments published by Kokovtsov (1916, 207–24), and these show alphabetisation to the third root letter. There are also citations in

century Masoretic works which contain alphabetically ordered lists of words, such as a list of “pairs with different interpretations, which require that the scholar stop and memorise them, since their meanings are very close” (Martínez Delgado 2009; for the text, see 359–62). In a different linguistic milieu—but a similar cultural world—the tenth-century Byzantine *Suda* ‘Stronghold’, a massive Greek historical encyclopaedia of the ancient Mediterranean world, was also alphabetical.

A closer look at some of these works is particularly illuminating. Menaḥem ben Saruq’s dictionary is comprised of 22 ‘fascicles’ (*maḥbarot*), one for each letter of the alphabet.¹⁹ Alphabetisation extends beyond basic structure, serving as the default organisational principle on smaller scales, as well. For example, Menaḥem has a number of lists within his lexicon. Early on, he includes a list of biblical *hapax legomena*—in alphabetical order

an anonymous Psalms commentary partially preserved in the Cairo Geniza (Peretz 2000).) Since ha-Nagid was working in dialogue with Ibn Janāḥ’s ongoing work, the structure is presumably due to influence of his contemporary (see also del Valle Rodríguez 2009).

¹⁹ On the manuscript evidence for the order of entries in Menahem’s *Mahberet*, see Yahalom and Sáenz-Badillos (1985, esp. esp. 257–58). There are two traditions in two different groups of manuscripts. The oldest manuscripts, and eastern manuscripts, have two-letter alphabetisation. In a different group of manuscripts, the lexemes within each initial letter are divided into two groups: biliteral words followed by trilateral words—in full alphabetical order. Yahalom and Sáenz-Badillos suggest that it is impossible to know what the original order was, but Menaḥem uses alphabetical order even *within* his lexicon (see immediately below), suggesting that this was his default structuring tactic.

(Menaḥem ben Saruq 1986, 106*; the list is included by association in the entry s.v. גלב, which is a *hapax legomenon*). He also provides examples of Hebrew roots that contain three letters (אזר, (טרף, חטף, זרע, הרס, דרש, גדע, בחן, and roots that contain two letters (כל, יף, טע, חל, זע, הס, דש, גש, בר, אץ) (Menaḥem ben Saruq, 74*). In these cases, the lists are not comprehensive, but illustrative: he chooses one for each letter of the alphabet. When he needs to provide examples of words that begin with *taw*, they come in the order תלפיות, תכלית, תהפוכות, תודת, תגרת, תבונה, תאנה, תשום, תשומת, תשורה, תרמית, תמורתה.²⁰

Menaḥem's great critic, Dunash ben Labrāṭ, did not arrange the first half of his animadversions on Menaḥem's dictionary alphabetically, but in the middle of his work switches to alphabetical order, explicitly telling the reader that he is doing so: "Behold I will arrange for you the remainder / according to the alphabet" (Sáenz-Badillos 1980, 62*; translation from Dachman 2025). His alphabetisation extends only to the first letter, though, so אספות comes before אגורה, for example.

David al-Fāṣī writes in his introduction that his dictionary is organised in 22 parts, one for each letter of the alphabet, and then each is theoretically subdivided into a further 22 parts, so that the book is structured by the first two letters of the root. He

²⁰ All of the lists within Menaḥem's classification of the letters are in alphabetical order; see text and translation in Dachman (2022, 138–50). Dachman observed that Sa'adya, al-Fāṣī, and Menaḥem also sometimes present the letters themselves in alphabetical order when giving lists of letters that serve various grammatical functions.

then notes, however, that there are combinations that are not attested: there are no roots that begin אא, no roots that begin בך, and so on. His counting gives a total of 364 combinations (out of a possible 484), and these, he emphasises, are to be found in precisely this order—with the exception of words beginning with *waw*, which are at the beginning, because there are no verbal roots in that category (al-Fāṣī 1936, 1.2–4 [Judaeo-Arabic text] and lxvi–lxviii [abridged English translation, without the enumeration]; Blau 2020, 21–22 [my thanks to Joshua Dachman for this reference]).

The ability of alphabetical order to cross boundaries is also seen in a text which emerged from the Cairo Geniza a decade ago: a ‘medical text’ consisting of a list of plants and their medicinal properties (T-S K 14.22). Remarkably, the text is written in Syriac, but in Jewish script. Even more remarkably, the terms for the plants are first given in Greek (in Hebrew characters), then translated into Syriac, and finally glossed also in Middle Persian.²¹ The most remarkable fact, though, is that the list is in alphabetical order, apparently according to the Greek name. The editor even notes this in the middle of the text, when he writes: שלם סדרא דתרי עשר דאיתיו למד ואף השא או חביבן כתבינן סדרא דתלת עשר דאיתיו מים “Finished is the twelfth chapter, which is *lamed*. And also now, O our beloved, we write the thirteenth chapter, which is *mem*.”

²¹ See Bhayro (2012; 2014 with some corrections and additions); for greater detail see Müller-Kessler (2017), who disagrees with Bhayro on a number of important issues, which do not, however, affect the present discussion.

To complete the historiographical circle, it should be observed that other medieval European innovations in the structure of writing are the results of contact with eastern books, particularly Hebrew. Thus, for example, the biblical chapter divisions that appear first in England in around 1180 seem to have been inspired by the *sedarim* that divide the Hebrew text in Jewish Bible texts (Saenger with Bruck 2008; Saenger 2012; 2013). One particularly relevant manuscript, Corpus Christi College (Cambridge) 48, also has three columns of text on the page, comparable to Hebrew biblical texts. CCC 48 is particularly relevant for thinking about how alphabetical order may have gotten to Latin scribes of the late twelfth and early thirteenth centuries, because it has a beautiful double *'alef-bet* decorating the first page of Lamentations. The text of Lamentations—with acrostic structure—is then adorned in the margins with the Hebrew letters that begin each verse.²²

²² The manuscript is viewable at <https://parker.stanford.edu/parker/catalog/wx717zj2675>; the beginning of Lamentations is 121r (the section is still labelled “Jeremias” on the top of the page). I am grateful to Loraine Enslow and Prof. David Lavinsky for discussing this manuscript with me and for sharing their insights.

Figure 1: Corpus Christi College (Cambridge) 48



There is ample reason to think that alphabetisation, too, arrived in Europe around 1200 from the Semitic world.²³ The alphabetic thinking in this manuscript extends beyond this dramatic introduction: each verse in Lamentations 1-4 is marked in the margin by the Hebrew letter with which it begins, and in Lam. 3, this means marginal notes such as, “*Joth – Joth – Joth – Caph – Caph – Caph*,” and so on. The same practice is found in Prov. 31.10–31, although the Hebrew is nowhere evident in the

²³ See, too, Daly 1967, 74, noting the rise in alphabetisation in the twelfth and thirteenth centuries, and commenting, “To those familiar with the great burst of scholarly activity in the twelfth and thirteenth centuries the developments just discussed will not be surprising.”

text itself (158v–159r).²⁴ Finally, the manuscript ends (266r–276r) with an eleven-page, alphabetically arranged list of names of people and places.

The upshot of all this is that the Arabic tradition of alphabetisation, which drew on earlier traditions, is likely to be the source of the rise in Latin alphabetisation visible to medievalists beginning in the thirteenth century. This was probably mediated through Jewish books, which travelled, physically and intellectually, from the Islamic world to that of Latin Christendom, bringing many of their metatextual practices along with them. Thus, when historians inquire as to the origins of the practice of alphabetical order in the European Middle Ages, they need to begin to look south and east, where Hebrew and Arabic books were being produced at a much greater rate than Latin books. The vibrant book cultures of the Jews and Muslims left a deep impression on the Christian book culture of the High Middle Ages.

References

- Abrahami, Philippe, and Coulon, Laurent. 2008. 'De l'usage et de l'archivage des tablettes cuneiformes d'Amarna'. In *La lettre d'archive: Communication administrative et personnelle dans L'antiquité proche-orientale et égyptienne—Actes du colloque de l'Université de Lyon 2, 9–10 juillet 2004*, edited by Laure

²⁴ Here the scribe also marked the beginning of each verse with a red or blue rubric, as he sometimes does when—so it seems—each verse is seen to be a new unit; compare the practice in Exodus 21–23

- Pantalacci, 1–26. Le Caire: Institut français d'archeologie orientale.
- Arnold, W. R. 1901. 'The Composition of Nahum 1–2:3'. *Zeitschrift für die Alttestamentliche Wissenschaft* 21: 225–65.
- Assis, Elie. 2007. 'The Alphabetic Acrostic in the Book of Lamentations'. *Catholic Biblical Quarterly* 69: 710–24.
- Baalbaki, Ramzi. 2014. *The Arabic Lexicographical Tradition: From the 2nd /8th to the 12th/18th Century*. Handbook of Oriental Studies, Section One: The Near and Middle East 107. Leiden: Brill.
- Badger, Gorge P. 1852. *The Nestorians and Their Rituals: With the Narrative of a Mission to Mesopotamia and Coordistan in 1842–44, and of a Late Visit to Those Countries in 1850—Also, Researches into the Present Condition of the Syrian Jacobites, Papal Syrians, and Chaldeans and an Inquiry into the Religious Tenets of the Yezedees, Volume 2*. London: Masters.
- Bar-Ilan, Meir. 1987. *Sitre Tefila ve-Hekhalot*. Ramat-Gan: Bar-Ilan University Press.
- Berlin, Adele. 1985. 'The Rhetoric of Psalm 145'. In *Biblical and Related Studies Presented to Samuel S. Iwry*, edited by Ann Kort and Scott Morshauer, 17–22. Winona Lake, IN: Eisenbrauns.
- Bhayro, Siam. 2012. 'A Judaeo-Syriac Medical Fragment from the Cairo Genizah'. *Aramaic Studies* 10: 153–72.
- . 2014. 'Remarks on the Genizah Judaeo-Syriac Fragment'. *Aramaic Studies* 12: 143–53.
- Blau, Joshua. 2020. 'Translation of the Introduction and the Letter 'Aleph' in The Hebrew-Arabic Dictionary of the Bible

- (Kitab Jami' Al-Alfaz) of David ben Abraham Al-Fasi, ed. Solomon L. Skoss'. *Ginzei Qedem* 16: 9–152
- Bloch, Yigal. 2018. *Alphabetic Scribes in the Land of Cuneiform: Sēpiru Professionals in Mesopotamia in the Neo-Babylonian and Achaemenid Periods*. Piscataway, NJ: Gorgias.
- Bohak, Gideon. 1990. 'Greek-Hebrew Gematrias in 3 Baruch and in Revelation'. *Journal for the Study of the Pseudepigrapha* 7: 119–21.
- Bonfil, Robert. 1986. 'Edutu shel 'Agobard mi-Li'on 'al 'Olaman ha-Ruḥani shel Yehude 'Iro ba-Me'a ha-Tshi'it'. In *Mehqarim ba-Qabala be-Filosofya Yehudit u-ve-Sifrut ha-Musar ve-ha-Hagut Mugashim le-Yish'aya Tishbi bi-Mlot Lo Shiv'im ve-Hamesh Shanim*, edited by Joseph Dan and Joseph Hacker, 327–48. Jerusalem: Magnes Press.
- Bos, Gerrit, Fabian Käs, Mailyn Lübke, and Guido Mensching. 2020. *Marwān ibn Janāḥ: On the Nomenclature of Medicinal Drugs (Kitāb al-talkhiṣ)*. Islamic History and Civilisation 170. Leiden: Brill.
- Brisman, Shimeon. 2000. *History and Guide to Judaic Dictionaries and Concordances*. Jewish Research Literature 3/1. Hoboken, NJ: Ktav.
- Brock, Sebastian. 1991. 'Syriac Dispute Poems: The Various Types'. In *Dispute Poems and Dialogues in the Ancient and Mediaeval Near East: Forms and Types of Literary Debates in Semitic and Related Literatures*, edited by G. J. Reinink and H. L. J. Vanstiphout, 109–20. *Orientalia Lovaniensia Analecta* 42. Leuven: Departement Oriëntalistiek and Peeters.

- Brooke, George J. '4Q252 and the 153 Fish of John 21.11'. In *Antikes Judentum und frühes Christentum: Festschrift für Hartmut Stegemann zum 65. Geburtstag*, edited by Bernd Kollmann, Wolfgang Reinbold, and Annette Steudel, 253–65. Beihefte zur Zeitschrift für die Neutestamentliche Wissenschaft 97. Berlin: De Gruyter, 1998 (reprinted in Brooke, George J., *The Dead Sea Scrolls and the New Testament*, 282–97. Minneapolis: Fortress, 2005).
- Brug, John F. 1990. 'Biblical Acrostics and Their Relationship to Other Ancient Near Eastern Acrostics'. In *The Bible in the Light of Cuneiform Literature: Scripture in Context III*, edited by William W. Hallo, Bruce William Jones, and Gerald L. Mattingly, 293–304. Ancient Near Eastern Texts and Studies 8. Lewiston: Edwin Mellen.
- Canfora, Luciano. 1990. *The Vanished Library: A Wonder of the Ancient World*. Berkeley: University of California Press.
- Casson, Lionel. 2001. *Libraries in the Ancient World*. New Haven, CT: Yale University Press.
- Cohen, Boaz. 1935. *Mishnah and Tosefta, Part 1: Shabbat*. New York: Jewish Theological Seminary of America.
- Connor, Andrew. 2018. 'The Earliest Known Use of Alphabetization in Greek Documentary Papyri'. *Bulletin of the American Society of Papyrologists* 55: 21–37.
- Coogan, Michael D. 1974. 'Alphabets and Elements'. *Bulletin of the American Schools of Oriental Research* 216: 61–63.
- . 1990. '*LP, "To Be an Abecedarian"'. *Journal of the American Oriental Society* 110: 322.

- Cook, A. M. 1919. 'Virgil, *Aen.* 7.641 ff.'. *Classical Review* 33: 103–4.
- Cross, Frank Moore, and Thomas O. Lambdin. 1960. 'A Ugaritic Abecedary and the Origins of the Proto-Canaanite Alphabet'. *Bulletin of the American Schools of Oriental Research* 160: 21–26.
- Cross, Frank Moore, and John Huehnergard. 2003. 'The Alphabet on a Late Babylonian Cuneiform School Tablet'. *Orientalia* 72: 223–28.
- Curtis, John, Dominique Collon, and Anthony Green. 1993. 'British Museum Excavations at Nimrud and Balawat in 1989'. *Iraq* 55: 1–37.
- Dachman, Joshua. 2022. 'The Debate of Menaḥem and Dunash and a Framework for Non-Triliteral Hebrew Verbal Morphology'. *Journal of Semitic Studies* 67: 99–150.
- . 2025. 'Dunaš Ibn Labrāṭ and the Spanish School: An Annotated Translation of the *Tešubot* with Introduction and Critical Notes'. PhD dissertation, Yeshiva University.
- Dalley, Stephanie. 2009. *Babylonian Tablets from the First Sealand Dynasty in the Schøyen Collection*. Cornell University Studies in Assyriology and Sumerology 9. Bethesda, MD: CDL Press.
- Daly, Lloyd W. 1967. *Contributions to a History of Alphabetization in Antiquity and the Middle Ages*. Collection Latomus 90. Bruxelles: Latomus.
- David ben Abraham al-Fāsi. 1936. *Kitāb Jāmi‘ al-Alfāẓ (Agron)*. Edited by Solomon L. Skoss. New Haven, CT: Yale University Press.

- del Valle Rodríguez, Carlos. 2009. 'The Works of Kokovstov on Samuel ha-Nagid'. *Revue des Études Juives* 168: 195–200.
- Demsky, Aaron. 1977. 'A Proto-Canaanite Abecedary Dating from the Period of the Judges and Its Implications for the History of the Alphabet'. *Tel Aviv* 4: 14–27.
- . 2015. 'The Interface of Oral and Written Traditions in Ancient Israel: The Case of the Abecedaries'. In *Origins of the Alphabet: Proceedings of the First Polis Institute Interdisciplinary Conference*, edited by Christophe Rico and Claudia Attucci, 17–48. Newcastle upon Tyne: Cambridge Scholars.
- Devauchelle, Didier. 2014. 'L'alphabet des oiseaux (O. dém. DelM 4-2)'. In *A Good Scribe and an Exceedingly Wise Man: Studies in Honour of W. J. Tait*, edited by Aidan M. Dodson, J. J. Johnston, and W. Monkhouse; Demotic Consultant C. J. Martin, 57–65. Golden House Publications Egyptology 21. London: Golden House.
- Dichy, Joseph. 2019. 'The Intriguing Issue of Dictionary Arrangement in Medieval Arabic Lexicography'. In *The Foundations of Arabic Linguistics IV*, edited by Manuela E. B. Giolfo and Kees Versteegh, 123–32. Leiden: Brill.
- Dotan, Aron. 2005. *Niṣanim Rishonim be-Ḥokhmat ha-Milim: Min ha-Masora 'el Reshit ha-Milona'ut ha-'Ivrit*. Jerusalem: The Academy of the Hebrew Language.
- Drower, Ethel S. 1960. *The Secret Adam: A Study of Nasoraean Gnosis*. Oxford: Oxford University Press.
- Eshel, Hanan, and John Strugnell. 2000. 'Alphabetical Acrostics in Pre-Tannaitic Hebrew'. *Catholic Biblical Quarterly* 62: 441–58.

- Fales, Frederick Mario. 1986. *Aramaic Epigraphs on Clay Tablets of the Neo-Assyrian Period*. Rome: Università degli studi 'La Sapienza'.
- First, Mitchell. 2014. 'Using the Pe–Ayin Order of the Abecedaries of Ancient Israel to Date the Book of Psalms'. *Journal for the Study of the Old Testament* 38: 471–85.
- Flanders, Judith. 2020. *A Place for Everything: The Curious History of Alphabetical Order*. New York: Basic.
- Frahm, Eckart. 2005. 'Observations on the Name and Age of Sargon II and on Some Patterns of Assyrian Royal Onomastics'. *Nouvelles Assyriologiques Brèves et Utilitaires* 2: 46–50.
- Freedman, David Noel. 1986. 'Acrostic Poems in the Hebrew Bible: Alphabetic and Otherwise'. *Catholic Biblical Quarterly* 48: 408–31.
- Gaudard, François. 2012. 'Birds in the Ancient Egyptian and Coptic Alphabets'. In *Between Heaven and Earth: Birds in Ancient Egypt*, edited by Rozenn Bailleul-LeSuer, 65–70. Oriental Institute Museum Publications 35. Chicago: The Oriental Institute.
- Geller, M. J. 1997–2000. 'The Aramaic Incantation in Cuneiform Script (AO 6489 = TCL 6,58)'. *Jaarbericht van het Vooraziatisch-Egyptisch Genootschap Ex Oriente Lux* 35–36: 128–46.
- Gevirtz, Stanley. 1969. 'Abram's 318'. *Israel Exploration Journal* 19: 110–13.
- Goff, Matthew J. 2017. 'Students of God in the House of Torah: Education in the Dead Sea Scrolls'. In *Second Temple Jewish*

- ‘*Paideia*’ in *Context*, edited by Jason M. Zurawski and Gabriele Boccaccini, 71–89. Berlin: De Gruyter.
- Gordon, Edmund I. 1954. ‘The Sumerian Proverb Collections: A Preliminary Report’. *Journal of the American Oriental Society* 74: 82–85.
- Grant, Robert M. 1997. *Irenaeus of Lyons*. New York: Routledge.
- Gruendler, Beatrice. 2021. *The Rise of the Arabic Book*. Cambridge: Harvard University Press.
- Hagen, Fredrick. 2011. ‘The Hieratic Dockets on the Cuneiform Tablets from Amarna’. *Journal of Egyptian Archaeology* 97: 214–16.
- Hallo, William W. 1996. *Origins: The Ancient Near Eastern Background of Some Modern Western Institutions*. Studies in the History and Culture of the Ancient Near East 6. Leiden: Brill.
- . 2004. ‘Again the Abecedaries’. In *Sefer Moshe: The Moshe Weinfeld Jubilee Volume—Studies in the Bible and the Ancient Near East, Qumran, and Post-Biblical Judaism*, edited by Chaim Cohen, Avi M. Hurvitz, and Shalom M. Paul, 285–302. Winona Lake, IN: Eisenbrauns.
- Hamidović, David. 2014. ‘Alphabetical Inscriptions from the Sealand’. *Studia Mesopotamica* 1: 137–55.
- Haring, Ben. 2015. ‘*Halaḥam* on an Ostrakon of the Early New Kingdom?’ *Journal of Near Eastern Studies* 74: 189–96.
- Haywood, John A. 1960. *Arabic Lexicography: Its History and Its Place in the General History*. Leiden: Brill.
- Honeyman, A. M. 1952. ‘The Letter-Order of the Semitic Alphabets in Africa and the Near East’. *Africa* 22: 136–47.

- Irvine, A. K., and A. F. L. Beeston. 1988. 'New Evidence on the Qatabanian Letter Order'. *Proceedings of the Seminar for Arabian Studies* 18: 35–38.
- Iversen, Erik. 1958. *Papyrus Carlsberg Nr. VII: Fragments of a Hieroglyphic Dictionary*. Historisk-Filologiske Skrifter of the Kongelige Danske Videnskbernes Selskab 3/2. Copenhagen: Munksgaard.
- Jeffery, Lilian H. 1961. *The Local Scripts of Archaic Greece*. Oxford: Clarendon.
- Keaney, John J. 1969. 'The Alleged Alphabetisation of Aristotle's *Politeiai*'. *Classical Philology* 64: 213–18.
- Ketterer, Éliane. 2005. 'Otiyot Divre 'Aqiva (Nusah 'alef-bet): Mahuto shel Midrash Ze, Megamato, Ra'ayonotav u-Qsharav 'im Zeramim Shonim ba-Yahadut u-ba-Nasrut'. PhD Dissertation: Hebrew University.
- Kiley, Mark. 2008. 'Three More Fish Stories (John 21:11)'. *Journal of Biblical Literature* 127: 529–31.
- Knohl, Israel. 2012. 'Sacred Architecture: The Numerical Dimensions of Biblical Poems'. *Vetus Testamentum* 62: 189–97.
- Kokovtsov, Pavel K. 1916. *Novye materialy dlia kharakteristiki ĭekhudy Khaĩĩudzha, Samuila Nagida i nĩekotorykh drugikh predstaviteľĩ evreĩskoĩ filologicheskoi nauki v X, XI i XII vĩekĩe*. Petrograd: Tip. Imp. akademĩi nauk (Hebrew section reprinted as *Mi-Sifre ha-Balshanut ha-Ivrit b-Ime ha-Benayim*, edited by Nehemia Allony. Jerusalem: Qedem, 1969).
- Kuhn, Sherman M. 1968. 'The Preface to a Fifteenth-Century Concordance'. *Speculum* 43: 258–73.
- . 1972. Review of Daly 1967. *Speculum* 47: 300–1.

- Lieberman, Stephen J. 1987. 'A Mesopotamian Background for the So-called Aggadic "Measures" of Biblical Hermeneutics?'. *Hebrew Union College Annual* 58: 157–225.
- Macdonald, M. C. A. 1986. 'ABCs and Letter Order in Ancient North Arabian'. *Proceedings of the Seminar for Arabian Studies* 16: 101–68.
- Maloney, Leslie D. 2005. 'A Word Fitly Spoken: Poetic Artistry in the First Four Acrostics of the Hebrew Psalter'. PhD dissertation, Baylor University.
- Marcus, Ralph. 1947. 'Alphabetic Acrostics in the Hellenistic and Roman Periods'. *Journal of Near Eastern Studies* 6: 109–15.
- Martínez Delgado, José. 2009. 'Lexicographical Arrangement of Masoretic Material'. *Journal of Semitic Studies* 54: 333–63.
- Menaḥem ben Saruq. 1986. *Maḥberet*. Critical edition and introduction by Angel Sáenz-Badillos. Granada: Universidad de Granada and Salamanca: Universidad Pontificia de Salamanca.
- Meynet, Roland. 2015. *Les huit psaumes acrostiches alphabétiques*. *Rhetorica Biblica e Semitica* 6. Rome: Gregorian and Biblical Press.
- Millard, Alan R. 1962. 'Alphabetic Inscriptions on Ivories from Nimrud'. *Iraq* 24: 41–51.
- . 2009. 'Assyria, Aramaeans, and Aramaic'. In *Homeland and Exile: Biblical and Ancient Near Eastern Studies in Honour of Bustenay Oded*, edited by Gershon Galil, Markham J. Geller, and Alan R. Millard, 203–14. Supplements to *Vetus Testamentum* 140. Leiden: Brill.

- Molina, Manuel. 2016. 'Archives and Bookkeeping in Southern Mesopotamia during the Ur III period'. *Comptabilités: Revue d'histoire des comptabilités* 8. <http://journals.openedition.org/comptabilites/1980>
- Morenz, Ludwig D. 2019. 'Ein Trigger für "unsere" Alphabetschrift: Die kanaanäisch-ägyptischen Göttergleichungen El-Ptah und Baalat-Hathor'. *Themenhefte aus dem Ägyptischen Museum Bonn* 3.
- Mullaney, Thomas S. 2017. *The Chinese Typewriter: A History*. Cambridge, MA: MIT Press.
- Müller-Kessler, Christa. 2017. 'A Trilingual Pharmaceutical Lexical List: Greek – Aramaic – Middle Persian'. *Le Muséon* 130: 31–70.
- Nettleship, Henry. 1880. 'Verrius Flaccus. I'. *American Journal of Philology* 1: 253–70.
- O'Hara, James J., 1989. 'Messapus, Cycnus, and the Alphabetical Order of Vergil's Catalogue of Italian Heroes'. *Phoenix* 43: 35–38.
- Olesen-Bagneux, Ole. 2014. 'The Memory Library: How the Library in Hellenistic Alexandria Worked'. *Knowledge Organisation* 41/1: 3–13.
- Parsons, Peter. 2011. 'Callimachus and his Koinai'. In *The Brill Companion to Callimachus*, edited by Benjamin Acosta-Hughes, Luigi Lehnus, and Susan Stephens, 134–52. Brill's Companions to Classical Studies. Leiden: Brill.
- Paz, Yakir, and Tzahi Weiss. 2015. 'From Encoding to Decoding: The ATBH of R. Hiyya in Light of a Syriac, Greek and Coptic Cipher'. *Journal of Near Eastern Studies* 74: 45–65.

- Pearce, Laurie E. 1996. 'The Number-Syllabary Texts'. *Journal of the American Oriental Society* 116: 453–74.
- Perez, Maaravi. 2000. 'Muva'ot mi-tokh "Kitāb al-'Istigna" shel R. Shemu'el ha-Nagid be-tokh Perush Anonimi le-Sefer Tehilim'. *Shnaton le-Heqer ha-Miqra ve-ha-Mizrah ha-Qadum* 12: 241–87.
- Posegay, Nick. 2021. *Points of Contact: The Shared Intellectual History of Vocalisation in Syriac, Arabic, and Hebrew*. Cambridge: Faculty of Asian and Middle Eastern Studies and Open Book Publishers.
- Puech, Émile. 1980. 'Abécédaire et Liste Alphabétique de Noms Hébreux du Début du Ile S. A.D'. *Revue Biblique* 87: 118–26.
- Rhodes, Peter John. 1993. *A Commentary on the Aristotelian Athēnaion Politeia*. Oxford: Clarendon.
- Robins, Andrew. 2019. 'The Alpha Hypothesis: Did Lateralised Cattle–Human Interactions Change the Script for Western Culture?' *Animals* 9/638: 1–25.
- Rubin, Milka. 1998. 'The Language of Creation or the Primordial Language: A Case of Cultural Polemics in Antiquity'. *Journal of Jewish Studies* 49: 306–33.
- Saenger, Paul, in collaboration with Laura Bruck. 2008. 'The Anglo-Hebraic Origins of the Modern Chapter Division of the Latin Bible'. In *La fractura historiográfica: Las investigaciones de Edad Media y Renacimiento desde el Tercer Milenio*, edited by Javier San José Lera, Francisco Javier Burguillo López, and Laura Mier Pérez, 177–202. Salamanca: Smyr.

- Saenger, Paul. 2012. 'Jewish Liturgical Divisions of the Torah and the English Chapter Division of the Vulgate Attributed to Stephen Langton'. In *Pesher Naḥum: Texts and Studies in Jewish History and Literature from Antiquity through the Middle Ages Presented to Norman (Naḥum) Golb*, edited by Joel L. Kraemer and Michael G. Wechsler, with the participation of Fred Donner, Joshua Holo, and Dennis Pardee, 187–202. *Studies in Ancient Oriental Civilization* 66. Chicago: The Oriental Institute.
- . 2013. 'The Twelfth-century Reception of Oriental Languages and the Graphic *mise en page* of Latin Vulgate Bibles Copied in England'. In *Form and Function in the Late Medieval Bible*, edited by Eyal Poleg and Laura Light, 31–66. *Library of the Written Word – The Manuscript World* 27. Leiden: Brill.
- Sáenz-Badillos, Angel. 1980. *Tešubot de Dunaš Ben Labrat: Edición crítica y traducción Española*. Granada: Universidad de Granada.
- Sambursky, Samuel. 1976. 'Meqoro u-Mashma'uto shel ha-Mu-naḥ "Gemaṭriya"'. *Tarbiz* 45: 268–71.
- Sanni, Amidu. 1992. 'The Arabic Science of Lexicography: State of the Art'. *Islamic Studies* 31: 141–68.
- Sasson, Jack M. 1972. 'Some Comments on Archive Keeping at Mari'. *Iraq* 34: 55–67.
- Schironi, Francesca. 2009. *From Alexandria to Babylon: Near Eastern Languages and Hellenistic Erudition in the Oxyrhynchus Glossary (P.Oxy. 1802 + 4812)*. *Sozomena: Studies in the Recovery of Ancient Texts* 4. Berlin: De Gruyter.

- Skehan, Patrick W. 1951. 'The Structure of the Song of Moses in Deuteronomy (Deut. 32:1–43)'. *Catholic Biblical Quarterly* 13: 153–63.
- Smith, H. S., and W. J. Tait. 1983. *Saqqâra Demotic Papyri I (P. Dem. Saq. I)*. Texts from Excavations, Seventh Memoir. London: Egypt Exploration Society.
- Sokoloff, Michael, and Joseph Yahalom. 1999. *Shirat Bene Ma'araba*. Jerusalem: Israel Academy of Sciences and Humanities.
- Soll, William M. 1988. 'Babylonian and Biblical Acrostics'. *Biblica* 69: 305–23.
- Steiner, Richard C. 1996. 'The Two Sons of Neriah and the Two Editions of Jeremiah in the Light of Two *Atbash* Code-Words for Babylon'. *Vetus Testamentum* 46: 74–84.
- Sysling, Harry. 2006. "'Go, Moses, and Stand by the Sea": An Acrostic Poem from the Cairo Genizah to Exodus 14:30'. In *The Interpretation of Exodus: Studies in Honor of Cornelis Houtman*, edited by Riemer Roukema in collaboration with Bert Jan Lietart Peerbolte, Klaas Spronk, and Jan-Wim Wesselius, 139–54. Leuven: Peeters.
- Tal, Abraham. 2019. *Tibât Mârqe: The Ark of Marqe Edition, Translation, Commentary*. Studia Samaritana 9. Berlin: De Gruyter.
- Téné, David, Aharon Maman, and James Barr. 2007. 'Linguistic Literature, Hebrew'. *Encyclopaedia Judaica*, 2nd edition, edited by Michael Berenbaum and Fred Skolnik, 13:29–61. New York: Macmillan.

- Tsu, Jing. 2022. *Kingdom of Characters: The Language Revolution that Made China Modern*. New York: Riverhead.
- Verhoogt, A. M. F. W. 1998. *Menches, Komogrammateus of Kerke-osiris*. *Papyrologica Lugduno-Batava* 29. Leiden: Brill.
- Weiss, Tzahi. 2014. 'Otiyot she-Nivre'u ba-hen Shamayim va-'Areṣ: *Ha-Meqorot ve-ha-Mashma'uyot shel ha-'Isuq be-'Otiyot ha-'Alefbet k-Iḥidot 'Aṣma'iyot ba-Sifrut ha-Yhudit ba-'Et ha-'Atiqā ha-M'uheret*. Jerusalem: Bialik.
- . 2005. 'Tefisat ha-'Otiyot ba-Ḥibur ha-Shomroni "Tibat Marqē" u-Maqbiloteha be-Sifrut Ḥaza"l u-ve-"Sefer Yeṣira"'. *Jewish Studies* 43: 89–129.
- . 2011. 'He'arot Qeṣarot 'al Heqshero ha-Suri shel Sefer Yeṣira'. *Jerusalem Studies in Jewish Thought* 22: 75–89.
- . 2012. "'Ke-neged Rakh ve-Qashe": He'arot Nosafot 'al Heqshero ha-Suri shel Sefer Yeṣira'. *Qabala* 26: 229–42.
- . 2017. *Sefer Yeṣirah and its Contexts: Other Jewish Voices*. Philadelphia: University of Pennsylvania Press.
- Yahalom, Joseph. 1978. 'Azal Moshe'. *Tarbiz* 47: 173–84.
- Yahalom, Joseph, and Ángel Sáenz-Badillos. 1985. 'Late Redactions and Genuine Versions in the MSS of Maḥberet Menaḥem'. *Leshonenu* 48–49: 253–68. [Hebrew]

“EVERY GLANCE OF THEIR EYES—LIKE A FLAME, TWO FLAMES”: A CASE OF UGARITIC GT ’MR ‘SEE’ RECONSIDERED*

Tania Notarius

1.0. Introduction

The semantic analysis of the Gt-stem and its position in the development of the Ugaritic verbal system is a matter of intensive scholarly interest. Simply labelling the Gt-stem as de-transitive and reflexive is not enough: Ugaritic Gt verbs are dynamic, agentive, and transitive (cf. Krebernik 1991, 237–39; Sivan 2001, 128; Huehnergard 2012, 64; Tropper 2012, 531–32).¹ The main func-

*Acknowledgements: The interpretation was discussed with Prof. Dennis Pardee, and the preliminary draft of the paper was read by Dr Yitzhaq Feder (University of Haifa). The author has greatly benefited from their comments, as well as from the recommendations of two anonymous readers. My thanks also go to my research assistant, John Thuppayath (Polis Institute). Any remaining mistakes are mine.

This work is based on research supported in part by the National Research Foundation of South Africa (Tania Notarius UID 150167). The

tions of the stem are autobenefactive/intensifying (1), direct reflexive (2), indirect reflexive (3), reciprocal (4), and denominative (5) with an animate Agent used as a subject:²

- (1) *bʿl ytlk wyşd*
‘DN **scoured** and combed’ (KTU 1.12 I 34)
- (2) *trthş btl̄t ʿnt tptr̄ʿ*
‘the Virgin DN washed herself, **bathed herself**’ (KTU 1.13:19)
- (3) *mḥmšt yltsp ršp*
‘the fifth (wife) DN **gathered to himself**’ (KTU 1.14 I 18)
- (4) *w hln ʿnt tmthş b ʿmq thtşb bn qrytm*
‘and look! DN fought in the valley, **she fought** between (the) two cities’ (KTU 1.3 II 5–7)

grant holder acknowledges that opinions, findings, conclusions, or recommendations expressed in any publication generated by NRF supported research are those of the author, and that the NRF accepts no liability whatsoever in this regard.

The quotations of the examples are from *KTU*³. Many translations are harmonised with *DULAT*.

¹ A thorough formal and semantic analysis, along with a comprehensive list of the Gt-verbs in the corpus, is found in Notarius (2021).

² The autobenefactive usage, crucial for the present interpretation—also called ‘self-benefactive’, ‘self-referential dative’, ‘emphatic reflexive’, etc.—is a typologically common syntactic construction by which a beneficiary coreferential with the Agent is applied to emphasise the Agent’s position. If Agent–Beneficiary coreferentiality is less important, the event—or one of its stages—is intensified (see Kemmer 1993, 180–82; Kazenin 2001, 916–27; Kulikov 2010, 21–25; Smith 2010, 70–95; Zúñiga and Kittilä 2019, 82–119).

- (5) *w tmn ttmnm lk*

‘and eight (sons) she will give you’ (*KTU* 1.15 II 24)

The stem functions differently in the poetic and prosaic registers of the language. While the autobenefactive/intensifying usage is equally distributed in both registers, direct reflexive, indirect reflexive, reciprocal, and denominative usages are entirely poetic. On the other hand, the patientive, anticausative, and resultative interpretations are attested relatively rarely, and mainly in prosaic language, specifically in sentences with an inanimate subject:

- (6) *ytšl l ʾb bn il ytšl l dr bn il*

‘*may* (the sacrifice) *rise* to the father of the gods, *rise* to the family circle of DN!’ (*KTU* 1.40:24–5)

In view of these data, one case of Gt of the root *ʾmr* ‘see’ is particularly challenging:

- (7) *išt išt m yitmr hrb lšt [lš]nhm*

‘(like) a blaze, two blazes they *yitmr* (?), a sharpened sword is their tongue’ (*KTU* 1.2 I 32–33)

The case appears in a poetic context, and its interpretation—pertinent to the interpretation of the whole pericope—has engendered scholarly debate. Mark Smith (1994, 267, 306–7), along with many other scholars, reads Gt **ʾmr* in *KTU* 1.2 I 32 as patientive anticausative, translating it as ‘appear, show up’. In line with this interpretation, two of Yamm’s messengers arrived at Ilu’s assembly; the assembled gods lowered their heads before them; standing straight, and without bowing down, the envoys

“appeared” like “a fire (flame, blaze), two fires (flames, blazes).”³ However, this Gt-verb can have an agentive intensifying interpretation as well: “(like?) a blaze, two blazes he/they looked (glanced),” as suggested in several grammatical studies.⁴ One must admit that, as outlined above, the latter interpretation is more consistent with the functional scope and distribution of the Gt-stem in Ugaritic: the autobenefactive/intensifying usage with an animate Agent is distinctive of the poetic register, whereas an anticausative interpretation would require an inanimate subject and appears typically in prose.⁵

³ See also *DULAT* (69); Caquot, Sznycer, and Herdner (1974, 131); de Moor (1987, 33); Coogan and Smith (2012, 112); Tugendhaft (2018, 135). The passive interpretation ‘were seen’ is not usually suggested, perhaps because the Gt-stem does not generally have passive semantics.

⁴ Tropper (2012, 519–20) emphasises the basic intensifying function of the Gt-stem of this root and draws a comparison with a similar El-Amarna usage (EA 74:52; 237:16–18 ‘see, experience, look’); for the case in 1.2 I 32, Tropper hesitates between two interpretations—anticausative ‘appear’ (“aussehen”) and an agentive ‘look’ (“erblicken”). Sivan (2001, 130) insists on the Gt’s agentive intensifying function, translating as a transitive: ‘he views (a burnished sword)’. Krebern timer’s analysis (1991, 237–38, 241) reflects two options: the case is possibly passive “gesehen werden” = “erscheinen,” but could also be interpreted as a dynamic transitive “sehen” with Ilu as subject.

⁵ Ayali-Darshan (2020, 88) translates “(their) utterance is (like) a flame,” apparently based on the meaning ‘speak’ of the root *’mr*, but with little grammatical discussion, noting in fn. 62: “The Ugaritic *y’lmtmr* may also be translated in the sense of ‘sight’. In light of the subsequent parallels, however, the rendering above is preferable.”

In what follows I argue for the agentive intensifying interpretation of the Gt verb **'mr*—‘look at, glance, glimpse’—in *KTU* 1.2 I 32. I try to demonstrate that this interpretation is more linguistically sound, and that it matches the lexical meaning and grammatical function of this verb in Ugaritic (§2.1). This claim finds further support in a stylistic argument (§2.2). As part of the descriptive insertion within the narrative flow, the verse under discussion is one among the parallel bi-cola that depict elements of the envoys’ facial appearance, i.e., their eyes and tongue, communicating their speech intention. The depiction of the divine messengers is to be considered within wider ancient Near Eastern contexts (§3.0); it is claimed that these characters are not represented as fire deities, and that they do not acquire blazing appearances. The flame-like glance of their eyes—suggested by the interpretation advocated here—is an image that typically characterises a divine or monstrous figure who can employ their blazing eyes and tongues as weapons.

2.0. Gt *'mr* ‘glance, look at’ in Ugaritic: A Lexical and Grammatical Analysis

2.1. Lexical and Morphological Properties

The root *'mr* is common in Semitic for perception and speech. As a verb of perception it is attested in Akkadian *amāru* ‘see, behold’ (*AHW* 40ff.; *CAD* A/2: 5–27) and in Amorite *'mr* ‘see’ (Golinets 2018, 362–63); in the newly published bilingual Amorite-Akkadian tablets the verb in this root has the meaning ‘speak’ (cf. A. George and Krebernik 2022), text 1:29, text 2:12. In Ethiopic the

meaning of perception takes on the nuance of cognition or cognitive guidance and, subsequently, speech: *ʾaʾmara* ‘to know’, *ʾammara* ‘to show, tell’ (Leslau 1989, 134–35). The meaning of cognitive guidance is also attested in Ebla: IGI.ŠÈ.DU = *a-me-lum* ‘guide’ (Fronzaroli 1984, 135; cf. Müller 1984, 182; Krebernik 1988, 54; Kogan and Krebernik 2021, 901). In Hebrew and in Arabic, contrary to Akkadian, *ʾmr* is a root of speech (HALOT 65ff.; Lane 1863, 95ff.).⁶

The Gt-stem of the root *ʾmr* in Akkadian is not widely used: according to *AHW* (41), there is a plausible attestation in Neo-Babylonian with the meaning ‘see henceforth’ (“von nun an sehen(?)”) in “(das Kind) *li-ta-mar* das Sonnenlicht”. Kouwenberg (2010, 362, 398) claims that the verb may have had a reciprocal meaning ‘meet’ (starting from Old Assyrian).⁷ Golinets (2018, 193–94) claims that in Amorite onomastics the verb is attested as a verbal adjective *a-ta-am-rV*, *a-tam-rV*, *a-tam-ra* with a medio-passive meaning ‘is seen, appear’ (“angesehen”), whereas the form with a theophoric element—*a-tam-ri-DINGIR* and *a-tam-ri-el*—is hardly Amorite, but corresponds to the Akkadian perfect ‘I have seen god’.⁸

⁶ This meaning of the root is attested also in Sabaic (Beeston 1982, 6) and Phoenician (Krahmalkov 2001, 61).

⁷ Kouwenberg notes that the reciprocal of the *amāru* is regularly expressed by the N-stem.

⁸ Golinets compares Akkadian *ʾA-ta-mar-qāt-sa* and *A-ta-mar-ra-bu-sa* ‘Ich have ihre Macht/Größe gesehen’. In view of the present discussion, the medio-passive interpretation of the verbal adjective *a-ta-am-rV* in

In Ugaritic the verbal usages of the root 'mr in the meaning 'say' are uncertain, but a cognate noun means 'order, demand':⁹ *qmm ātr āmr* 'standing up they transmitted (their) demand' (*KTU* 1.2 I 31; see also *KTU* 1.16 IV 1; 2.33:13).¹⁰ The meaning 'see, look at' is attested twice altogether in the Gt-stem: in addition to the case under discussion—see ex. (7), further expanded in ex. (10)—there is another explicit case of the Gt-form in an agentive

Amorite is not self-evident; the usage in Amorite is beyond the scope of the present essay.

⁹ See *DULAT* (69) *āmr* (I) "order, command; word." The nominal lexeme *āmr* is attested in Ugaritic personal names in cuneiform writing: cf. *a-mar*-DIM (PRU 4 108 [RS 18.114]:6; PRU 4 166 [RS 17.129]:3, 5); and *a-mur*-DIM (Ug 5 51 [RS 20.158]:7). The verbal root 'see' is attested in Akkadian lexical lists from Ugaritic: *a-ma-ru* (Ug 5 133 [RS 23.493 +] obv. 7; Ug 5 134 [RS 20.426 D]:1).

¹⁰ The phrase *ātr āmr* (1.2 I 31) is textually debated: Smith (1994, 260–63, 267) follows the reading 'a°. 'amr, reconstructs and vocalises 'amāru (?) 'amarā 'they speak a speech', as a tautological infinitive with suffix conjugation. This is not accepted in other editions: cf. *KTU*³: *ātr.amr*, thus also in *DULAT* (69, 123): "they transmitted (their) demand". For D *ātr* as a verb of speech 'force to follow, transmit' cf. Dietrich and Loretz (1984).

Huehnergard (2012, 135) explicitly mentions both Ugaritic meanings of the root 'mr. Kogan (2015, 331) claims that "Ugaritic must be the only Semitic language where this archaic meaning ['see'] is attested virtually side by side with the innovative 'to say', 'to command', normal for the rest of C[entral]S[emitic]." According to Gelb (1980, 14), the Amorite onomasticon attests both meanings—'see' and 'say', similar to Ugaritic. *DULAT* (69) remains ambiguous about the relation between the two meanings and suggests 'mr I 'see' and 'mr II 'say'. On Ugaritic cf. Halдар (1964, 275), Sanmartín (1973, 263–70).

intensified meaning ‘look at’ in ex. (8)—both times in the prefix conjugation (de Moor 1987, 33; Smith and Pitard 2009, 97, 115; Tropper 2012, 52). The form *yámr*, which appears in a very broken and obscure passage—ex. (9)—is either D- or N-stem: the spelling with *á* precludes a translation (Tropper 2012, 546; cf. also Bordreuil, Pardee, and Roche-Hawley 2019, 241–43). Both cases of the Gt *’mr* ‘see’ are in poetic contexts—cf. exs (7)–(8).

- (8) *ytmr b’l bnth y’n pdry bt ár ápn tly bt rb*
 ‘Baal **looked at** his daughters, he saw Pdry, daughter of ’Ar, also Tly, daughter of Rb’ (KTU 1.3 I 22)
- (9) *]hn w l yámr*
 ‘?’ (KTU 1.172:22)

2.2. Syntactic and Stylistic Considerations

The case in *KTU* 1.2 I 32 comes in a narrative passage that reports the arrival of Yamm’s messengers at Ilu’s divine court. This report is a fulfilment of Yamm’s instructions for his messengers in lns 13–17. As is common in this stylistic pattern, the direct discourse and its narration present a nearly verbatim match. However, two parallel half-verses in lns 32–33 with the debated *yítmr* are a descriptive insertion within the narrative, with no precedent in the instructive section:

- (10) *áhr tmğyn mlák ym t’dt tpt nhr l p’n il l tpl l tšthwy p̄hr m’đ qmm átr ámr [tn]y d’šthm **ışt ıştm yítmr ḥrb lışt [lš]nhm** rgm...*
 ‘When Yamm’s messengers arrived, the legation of Judge River, at Ilu’s feet they did not fall, they did not bow down before the assembled council. Standing they transmitted their word, repeated their instruction. **(Like) a blaze, two**

blazes *y'tmr* (?), sharpened sword is their tongue. They said...' (KTU 1.2 I 30–33)

To start with, the subject of the *Gt*-form *y'tmr* in ex. (10) can be interpreted in different ways.¹¹ If the subject is *Ilu*, mentioned in the preceding context (*lp'n il* 'at *Ilu*'s feet'), the dynamic transitive interpretation of the verb *y'tmr* is preferable—'(as) a fire, two fires he (*Ilu*) looked at (them)'. This interpretation suggests an abrupt and obscure shift to a non-topical—otherwise marginal—agent *Ilu*, at a point where another agent—the messengers—is the explicit subject before and after this debated clause. The phrase "fire, two fires" as a subject would require a middle anticausative interpretation of the verb ("a fire, two fires appeared"), but this interpretation, at odds with the agreement pattern (*išt* is feminine), is to be rejected. The messengers are possibly the subject, in which case both dynamic agentive and middle anticausative interpretations are possible, as mentioned above. A dual agreement pattern is favoured in several interpretations (Dobrusin 1981, 8; Smith 1994, 306).¹² Although reasonable, the *y*-prefix for masculine dual in *y'tmr* contrasts with the *t*-prefix of other prefix-conjugation forms in the context in reference to the messengers: *tm'gyn*, *tpl*, and *tšthwy*. In view of this inconsistency, I interpret the singular "messenger" as the verbal

¹¹ On the subject in this case, see Dobrusin (1981, 8 note 12), Krebern timer (1991, 240–41), and Smith (1994, 306), and the references there.

¹² *DULAT* (69) notes that the subject may be *ištm* [FDU] or "messengers" [MDU], cf. the vocalisation *yī'tamarā* in *DULAT* (267).

form's subject, with a distributive function—each of the messengers *yītmr*.¹³ The phrase *īšt īštm* is a numeric formula in the singular and the dual “two fires” is used as a comparative phrase in the accusative.¹⁴

Furthermore, the descriptive insertion in lns 32–33 interrupts the course of the events immediately prior to the moment of delivery of the message and describes the messengers' appearance. The description, as part of the direct speech framework, communicates the speakers' illocutionary intentions.¹⁵ It focuses on the speech organs employed in the speech act: the second half-verse refers to the speakers' tongues, which are compared to a sharpened sword—*ḥrb līšt [lš]nhm*. The first half-verse apparently refers to a body part as well, namely eyes casting burning glances. I claim that the comparison “like a flame, two flames”

¹³ For the distributive use of the singular, cf. יְכַסֶּה ‘each one (of seraphim) cover’, אִתְּךָ ‘each one (of them) call’ (Isa. 6.2–3).

¹⁴ Cf. Smith (1994, 267) who vocalises it as a nominative *ʾīšitu ʾīšitāmi*, rather than as an accusative of adverbial comparison, *ʾīšita ʾšitēmi*, adding (306 fn. 157):

This stylistic repetition is reflected in *raḥam raḥmātayim*, “a girl, two girls” in Judges 5:30. It may be noted that just as the nouns of construct phrases may appear in poetic parallelism, so also two nouns together, the first singular, the second dual may appear in poetic parallelism as in *riqmā/riqmatayim* in Judg 5:30.

Cf. also Melamed (1961). According to *DULAT* (505), the second form in the phrase *īštm* is in the singular with an emphatic particle *-m*.

¹⁵ On patterns of representing direct discourse in Akkadian, see Vogelzang (1990). On BH, cf. Miller (1996).

refers not to Yamm's messengers as such, but metonymically to the flames in their eyes. Both components of this imagery—sword-sharpened tongue and flame-burning eyes—liken facial components to weapons, emphasising the imprudence and aggressiveness of the speech act.

The suggested translation of *īšt īštm yītmr* in ex. (10) is 'like a flame, two flames each one (of them) looked around/glanced at (the assembly)'. Just as their tongues struck like sharpened swords, so their eyes shot out, or burned like, flames.

3.0. Literary Context and Symbolism: Flames, Glances, and Divine Envoys

The patientive anticausative interpretation of the *Gt 'mr* in *KTU* 1.2 I 32–33 'to appear (as fire)' finds support in ancient Near Eastern contexts. According to Smith, it entails a view that "minor divinities embody fiery form"; they presumably appear as fire (Smith 1994, 306; cf. also de Moor 1987, 33 fn. 143). However, the agentive intensifying reading advocated here—'look at, glance'—also has literary parallels, but presupposes a different model: that fiery facial organs are used by divine figures as weapons of deterrence and punishment.

Ancient Near Eastern fire imagery is a broad topic that cannot be exhausted within the scope of this essay (Miller 1965; Watson 1999a, 331–32; 1999b, 335–36). Just a few observations may be offered in support of the present grammatical interpretation. A distinction is to be made between divinities that are fire themselves and those that appear in the shape of fire or have flaming limbs.

Fire-gods are found in different cultural contexts. Smith (1994, 306 fn. 158) compares the divine messengers in *KTU* 1.2 I 32 to the Babylonian divinities *Išum* and *Išatu* from Ebla. As George claims, the Babylonian deity *Išum* was considered an offspring of the sun-god *Šamaš*. He was “set alight and left in the street” at birth. His primary function (similar to that of his Sumerian counterpart, *Ĥendursanga*) was as a ‘Night Watchman’ who protects houses and streets, providing light in the dark. This light was either a burning torch or a firebrand. This was also the light that he used to lead gods into battle in the Late Babylonian poem “Erra and *Išum*,” one of the main literary sources about this deity. In line with this imagery, *Išum* is born light, and uses his staff to give light for practical purposes (George 2015).¹⁶

The feminine divine name *ì-sa-túm* (= ^dizi) /^ʔ*Išātum*/ ‘fire’ is attested in Ebla once in a lexical list and another time in an administrative text (Fronzaroli 1984, 143; Pomponio and Xella 1997, 201; Mander 2005, 23–24, 26, 34, 70). Not much is known about her functions, but evidence from Ugarit may provide some help: Anat reports that *mḥšt k{.}lbt ilm išt* ‘I crushed the Divine Bitch, *Ištu*’ (*KTU* 1.3 III 45).¹⁷ According to Pomponio and Xella (1997, 201), this female deity was probably connected to the primordial forces of chaos, but lost most of her relevance. Perhaps the West Semitic deity *Reshef* originally possessed some fire-gods properties, but developed other characteristics as well (Xella 1999).

¹⁶ According to Pomponio and Xella (1997, 201), the Ugaritic *ilm* (1.148:31) is a related deity; cf. *DULAT* (123).

¹⁷ On the syllabic reading of this name see Van Soldt (1991, 732).

Divine messengers or other creatures, who themselves are not fire-gods, can appear in the shape of fire or use fire for different purposes. In the Hebrew Bible, there are several unambiguous examples of divine messengers, or God himself, appearing in the shape of fire, presumably to attract attention, reveal his glory, or elicit reverence: in 'And the angel of the LORD appeared unto him in a flame of fire (בְּלֶבֶת-אֵשׁ) out of the midst of a bush: and he looked, and, behold, the bush burned with fire, and the bush was not consumed' (Exod. 3.2), God's messenger appears as a flame of fire to attract Moses's attention; 'Who makes winds his messengers; flames of fire (אֵשׁ לִהְיוֹת) his ministers' (Ps. 104.4) mentions God's ability to send wind and fiery-flame messengers;¹⁸ in 'The angel of the LORD ascended in the flame (בְּלֶהֱב) of the altar: and Manoah and his wife looked on; and they fell on their faces to the ground' (Judg. 13.20) God's messenger appears as a flame of fire to attract human attention and warn; in 'chariot of fire, and horses of fire (וְסוּסֵי אֵשׁ)' (2 Kgs 2.11) fiery transport is sent from the heavens to take Elijah.

Somewhat different is the image of a saviour-god in

(11) עָלָה עָשָׁן בְּאַפּוֹ וְאֵשׁ מִפִּי תֹאכַל גְּחָלִים בְּעֵרָו מִמֶּנּוּ

'There went up smoke out of his nostrils, and fire out of his mouth devoured; coals burned out from his (appearance).'
(2 Sam. 22.9; cf. also Isa. 30.27–33)

In contrast to fire-gods or fire-messengers, the fire in this passage is neither within god's essential nature nor a temporary

¹⁸ '...[P]erhaps demythologized minor deities, but more probably metaphors for lightning' (Watson 1999a, 332).

appearance, but an attribute associated with the face and its organs: nostrils, mouth, and perhaps eyes (גְּחָלִים). The function of these fiery organs is to signal danger, frighten, or potentially strike with speech. The eyes of Mesopotamian gods can be sparkling and dangerous: in the Old Babylonian Ishtar Hymn, her eyes are described as being multicoloured and iridescent—*bitrāmā ināša šit'arā* ‘her eyes twinkle and sparkle’ (Charpin, Edzard, and Stol 2004, 509–14). In Egyptian mythology the underworld demon Apopis wants to rob the fire-spewing eye of Rē⁵ (Borghouts 1973).

One finds similar imagery—but applied to a monstrous figure—in

- (12) עָטִישְׁתִּיו תִּהְלֵ אֹרֶךְ וְעֵינָיו בְּעַפְעָפִי-שַׁחַר: מִפִּיו לִפְיָדִים יִהְלְכוּ בִידֵי אֵשׁ
 יִתְמַלְטוּ: מִנְחִירָיו יֵצֵא עָשָׁן כְּדוֹד נִפּוֹחַ וְאִגְמָן: נִפְשׁוּ גְחָלִים תִּלְהֹט וְלֵהָב מִפִּיו
 יֵצֵא:

‘His sneezing flashes for the light, his eyes are like eyelids of the morning. Out of his mouth go burning torches, sparks of fire leap forth. Out of his nostrils smoke goes forth, as of a boiling pot over a fire of reeds. His breath kindles coals, and a flame goes forth from his mouth.’ (Job 41.10–13)

Leviathan is depicted here as a monster (perhaps originally a snake). The fire, attributed to his vision and speech organs—eyes, nostrils, and mouth—is frightening and dangerous. In both the Ugaritic and biblical worldviews, Leviathan is an associate of the Sea and the Abyss (Uehlinger 1999, 511–13; cf. Isa. 27.1).

The prototypical imagery of Leviathan is reminiscent of Humbaba—the giant monster defeated by Gilgamesh: cf. ^dhu-wa-wa ‘ri-ig’-ma-šu a-bu-bu / pi-šu ^dgirrum(GĪRA)-ma na-pi-su mutum

'Huwawa, his voice is the Deluge, his speech is fire, his breath is death' (Gilgamesh IV:197–98).¹⁹ The flame from the mouth is a common simile in the Babylonian snake-incantation: *a-pa-šu {šu} mu-tum pišu na-ab-lum / li-ša-na-šu bi-ir-bi-ir-ru-um* 'its nostrils spell death; its mouth is flame, its forked tongue—radiance' (VS 17,4).²⁰ Flaming eyes and mouths of fire were attributed to gods and demons in Egyptian magical literature (Borghouts 1973). This imagery of demons continues into the world of Late Antiquity, appearing in Babylonian Jewish Aramaic incantations: נורא לביש ונורא מכסי שלהביתא דנורא נפקא מיפומיה (angels who came to the presence of Shamash) are clad with fire and covered with fire, and a flame of fire comes out of their mouths' (Naveh and Shaked 1998, 202–3, bowl 13, lns 18, 21). The eyes of demons, on the other hand, can be scorched, flaming, and red (Ford 1999, 242, 264–66). The flame from the mouth is a common motif, further, in Coptic magical texts (Ford 1999, 213).

Strikingly, the closest parallels to the description of Yamm's envoys, as interpreted here, come in biblical וְעֵינָיו כְּלַפְיֵדִי אֵשׁ 'and his eyes as flaming torches' (Dan. 10.6) and in the New Testament in Revelation: cf. Rev. 12 with the description of the dragon, and,

¹⁹ Quoted from George (2003, 201–2); cf. also the quotations in *CAD* (G 93), e.g., *šaptāšu ina šutabbuli* ^dGIŠ.BAR *ittanpaḥ* 'when he moves his lips they emit fire' (Enuma eliṣ. I 96, cf. Lambert 2008, 39). See also Tallqvist (1938, 77).

²⁰ Quoted from Wasserman (2003, 40). For the parallel text, VAT 8363, cf. van Dijk (1969, 539–47). See also Lambert (1970) regarding the symbolism of fire as a hostile power; cf., e.g., Maqlû VI 127ff II, in Abusch (2015, 127ff.).

particularly, Rev. 19's depiction of the Rider on a white horse: οἱ δὲ ὀφθαλμοὶ αὐτοῦ [ὡς] φλόξ πυρός 'his eyes were as a flame of fire' (Rev. 19.12) καὶ ἐκ τοῦ στόματος αὐτοῦ ἐκπορεύεται ῥομφαία ὀξεῖα 'out of his mouth goeth a sharp sword' (Rev. 19.15) (Collins and Yarbro Collins 1993, 372).²¹

Altogether, Yamm's messengers are obscure figures in the epos of Baal; their function and attributes, therefore, are debated. In view of the present discussion, it does not seem plausible to represent the messengers as primordial fire deities. Their temporary fiery appearance could mean an intention to cause strong reverence, attract attention, or emphasise the urgency of the message. This interpretation is plausible, but it contradicts the most straightforward grammatical and stylistic evidence: the default meaning of the Gt-stem in the language of poetry is not patientive and anticausative, and the description of the mouth in the second half-verse is perfectly parallel to the focus on the eyes in the first half-verse, together contributing to the direct discourse framework. It makes better sense, then, to view Yamm's messengers as frightening demonic figures with flaming eyes and sword-like tongues.

²¹ On the parallelism to the Canaanite context, cf. Yarbro Collins (2001, 77). On the "sword of his mouth" in the context of apocalyptic literature, cf. Collins (1998, 277–79). For the wider Jewish context, cf. Bauckham (1993, 131, 212). On the wider Hellenistic background, cf. Gordon (1999, 399).

4.0. Conclusion

In this paper I have made a claim for the agentive and autobenefactive/intensifying interpretation of Gt *ʾmr* in *īšt īštm yītmr ḥrb lṭšt [lš]nhm* (KTU 1.2 I 32), translating it ‘like a flame, two flames each one looked around; the sharpened sword is their tongue’.

This claim is based, first, on a linguistic argument: while the agentive autobenefactive usage is typical of the Gt-stem in Ugaritic poetic language, the patientive anticausative interpretation is rare, coinciding with an inanimate subject, and is attested in prose language.

I secondly made a stylistic and pragmatic argument: two parallel half-verses in ln. 32 refer to the facial organs of the messengers, flaming eyes and the sharpened tongue, foreshadowing the threatening and imprudent message.

Moreover, the examination of the literary and cultural context of poetic imagery brings out the conclusion that the messengers of Yamm were neither similar to primordial fire-gods nor appeared in the form of fire as a means of attracting attention or eliciting reverence. The sword-sharpened tongue and the burning eyes are typical of some divine—particularly monstrous—figures, and are to be interpreted as weapons that can frighten or strike, physically or verbally.

References

Abusch, Tzvi. 2015. *The Witchcraft Series Maqlû*. Atlanta: Society of Biblical Literature.

- Ayali-Darshan, Noga. 2020. *The Storm-God and the Sea*. Orientalische Religionen in der Antike 37. Tübingen: Mohr Siebeck.
- Ahw = Wolfram von Soden. 1965. *Akkadisches Handwörterbuch*. Wiesbaden: Harrassowitz.
- Bauckham, Richard. 1993. *Climax of Prophecy: Studies on the Book of Revelation*. London: T&T Clark.
- Beeston, Alfred F. L., et al. 1982. *Sabaic Dictionary (English-French-Arabic)*. Louvain-la-Neuve: Editions Peeters.
- Bordreuil, Pierre, and Dennis Pardee, 2009. *A Manual of Ugaritici*. Linguistic Studies in Ancient West Semitic 3. Winona Lake, IN: Eisenbrauns.
- Bordreuil, Pierre, Dennis Pardee, and Carole Roche-Hawley. 2019. *Ras Ibn Hani II: Les textes en écriture cunéiformes de l'âge du bronze récent (Fouilles 1977 à 2002)*. Bibliothèque archéologique et historique 214. Beirut: l'Ifpo.
- Borghouts, J. F. 1973. 'The Evil Eye of Apopis'. *The Journal of Egyptian Archaeology* 59: 114–50.
- CAD = Gelb, Ignace J. (ed.). 1956. *Chicago Assyrian Dictionary (The Assyrian Dictionary of the Oriental Institute of the University of Chicago)*. 26 vols. Chicago: Oriental Institute.
- Caquot, André, Maurice Sznycer, and Andrée Herdner. 1974. *Textes ougaritiques: Mythes et légendes*, vol. 1. Paris: Cerf.
- Charpin, Dominique, Dietz Otto Edzard, and Martin Stol. 2004. *Mesopotamien: Die altbabylonische Zeit*. Orbis Biblicus et Orientalis 160/4. Göttingen: Vandenhoech & Ruprecht.

- Collins, John Joseph. 1998. *The Apocalyptic Imagination: An Introduction to Jewish Apocalyptic Literature*, 2nd ed. Livonia, MI: Eerdmans.
- Collins, John Joseph, and Adela Yarbro Collins. 1993. *Daniel: A Commentary on the Book of Daniel*. Hermeneia: A Critical and Exegetical Commentary on the Bible. Minneapolis: Fortress Press.
- Coogan, Michael D., and Mark Smith. 2012. *Stories from Ancient Canaan*, 2nd ed. Louisville, KY: Westminster John Knox.
- de Moor, Johannes C. 1987. *An Anthology of Religious Texts from Ugarit*. Religious Texts Translation 16. Leiden: Brill.
- Dietrich, Manfred, and Oswald Loretz. 1984. 'Ugaritisch 'tr, atr, atryt und 'trt'. *Ugarit-Forschungen* 16: 57–62.
- Dobrusin, Deborah. 981. 'The Third Masculine Plural of the Prefixed Form of the Verb in Ugaritic'. *Journal of Ancient Near Eastern Society* 13: 3–10.
- DULAT = del Olmo Lete, Gregorio, and Joaquín Sanmartín. 2015. *A Dictionary of the Ugaritic Language in the Alphabetic Tradition*. Translated by Wilfred Watson, 2nd ed. Leiden: Brill.
- Ford, James Nathan. 1999. "Ninety-Nine of the Evil Eye and One from Natural Causes": KTU 1.96 in Its Near Eastern Context'. *Ugarit-Forschungen* 30: 201–78.
- Fronzaroli, Pelio. 1984. 'Eblaic Lexicon'. In *Studies on the Language of Ebla*, edited by Pelio Fronzaroli, 117–57. Quaderni di Semitistica 13. Florence: Istituto di Linguistica e di Lingua Orieintale.

- Gelb, Ignace J. 1980. *Computer-Aided Analysis of Amorite*. Assyriological Studies 21. Chicago: University of Chicago Press.
- George, Andrew R. 2003. *The Babylonian Gilgamesh Epic: Introduction, Critical Edition and Cuneiform Texts*, vol. 1. 2 vols. Oxford: Oxford University Press.
- . 2015. ‘The Gods Išum and Ḫendursanga: Night Watchmen and Street-lighting in Babylonia’. *Journal of Near Eastern Studies* 74: 1–8.
- George, Andrew R., and Manfred Krebernik. 2022. ‘Two Remarkable Vocabularies: Amorite-Akkadian Bilinguals!’. *Revue d’assyriologie et d’archéologie orientale* 116/1, 113–66.
- Golinet, Viktor. 2018. *Das amurritische Onomastikon der altbabylonischen Zeit*, vol. 2: *Verbalmorphologie des Amurritischen und Glossar der Verblwurzeln*. Münster: Ugarit-Verlag.
- Gordon, Robert L. 1999. ‘Helios’. In *Dictionary of Deities and Demons in the Bible*, ed. Karel van der Toorn, Bob Becking, and Pieter W. van der Horst, 392–401. Leiden: Brill.
- Haldar, Alfred. 1964. ‘The Position of Ugaritic among the Semitic Languages’. *Bibliotheca Orientalis* 21: 266–75.
- HALOT = Koehler, Ludwig, and Walter Baumgartner. 1994. *The Hebrew and Aramaic Lexicon of the Old Testament*, 5 vols. Leiden: Brill.
- Huehnergard, John. 2012. *An Introduction to Ugaritic*. Peabody, MA: Hendrickson Publishers Marketing.
- Kazenin, Konstantin. 2001. ‘Verbal Reflexives and Middle Voice’. In *Language Typology and Language Universals: An International Handbook*, edited by Martin Haspelmath, 916–27. Berlin: De Gruyter.

- Kemmer, Suzanne. 1993. *The Middle Voice*. Amsterdam: John Benjamins.
- Kogan, Leonid. 2015. *Genealogical Classification of Semitic: The Lexical Isoglosses*. Berlin: De Gruyter.
- Kouwenberg, N. J. C. [Bert]. 2010. *The Akkadian Verb and Its Semitic Background*. Winona Lake, IN: Eisenbrauns.
- Krahmalkov, Charles. 2001. *A Phoenician-Punic Grammar*. Leiden: Brill.
- Krebernik, Manfred. 1988. *Die Personennamen der Ebla-Texte*. Berliner Beiträge zum Vorderen Orient 7. Berlin: Dietrich Reimer.
- . 1991. 'Gt- und tD-Stämme im Ugaritischen'. In *Text, Methode und Grammatik: Wolfgang Richter zum 65 Geburtstag*, edited by Walter Gross, Hubert Irsigler, and Theodor Seidl, 227–70. Ottilien: EOS.
- KTU³ = Dietrich, Manfred, Oswald Loretz, and Joaquín Sanmartín. 2013. *The Cuneiform Alphabetic Texts from Ugarit, Ras Ibn Hani and Other Places*, 3rd ed. Münster: Ugarit-Verlag.
- Kulikov, Leonid. 2010. 'Voice Typology'. In *The Oxford Handbook of Linguistic Typology*, ed. Jae Jung Song, 21–25. Oxford: Oxford University Press.
- Lambert, Wilfred G. 1970. 'Fire Incantations'. *Archiv für Orientforschung* 23: 39–45.
- . 2008. 'Mesopotamian Creation Stories'. In *Imagining Creation*, edited by Markham (Mark) Geller and Mineke Schipper, 15–59. IJS Studies in Judaica 5. Leiden: Brill.
- Lane, Edward W. 1863. *An Arabic-English Lexicon*, 8 vols. London: Williams & Norgate.

- Leslau, Wolf. 1989. *Concise Dictionary of Ge'ez (Classical Ethiopic)*. Wiesbaden: Harrassowitz.
- Mach, Rudolf, and John H. Marks. 1960. 'The Head upon the Knees: A Note to 1 Kings 18:42'. In *The World of Islam: Studies in Honour of P. K. Hitti*, edited by J. Kritzeck and R. B. Winder, 68–73. London: Macmillan.
- Mander, Pietro. 2005. *La Religione di Ebla (XXV/XXIV Sec. a. c.)*. Quaderni napoletani di Assiriologia 5. Rome: Aracne.
- Melamed, E. Z. 1961. 'Break-up of Stereotype Phrases as an Artistic Device in Biblical Poetry'. In *Studies in the Bible*, edited by Chaim Rabin, 125–26. Scripta Hierosolymitana 8. Jerusalem: Magnes Press.
- Miller, Cynthia. 1996. *The Representation of Speech in Biblical Hebrew Narrative: A Linguistic Analysis*. Atlanta: Scholars Press.
- Miller, Patrick D. 1965. 'Fire in the Mythology of Canaan and Israel'. *The Catholic Biblical Quarterly* 27/3: 256–61.
- Müller, Hans-Peter. 1984. 'Neue Erwägungen zum Eblaitischen Verbalsystem'. In *Il Bilinguismo a Ebla*, edited by Luigi Cagni, 167–204. Napoli: Consiglio Nazionale delle Ricerche.
- Naveh, Joseph, and Shaul Shaked. 1998. *Amulets and Magic Bowls: Aramaic Incantations of Late Antiquity*, 3rd edition with additions and corrections. Jerusalem: Magnes Press and the Hebrew University of Jerusalem.
- Notarius, Tania. 2021. 'The Gt-Stem in Ugaritic and the Middle Voice Semantic Domain'. *Journal of Semitic Studies* 66: 97–129.

- Pardee, Dennis. 2000. *Les textes rituels*, vol. Fascicule 1, Ras Shamra – Ougarit 12. Paris: Editions Recherche sur les civilisations.
- Pomponio, Francesco, and Paolo Xella. 1997. *Les dieux d'Ebla: Étude analytique des divinités éblaïtes à l'époque des archives royales du IIIe millénaire*. Alter Orient Und Altes Testament 245. Münster: Ugarit-Verlag.
- PRU=Nougayrol, Jean. 1956. *Le palais royal d'Ugarit* vol. IV: *Textes accadiens des archives SUD (archives internationales)*, edited by Claude F.-A. Schaeffer. Mission des Ras Shamra 9. Paris: Imprimerie Nationale.
- Sanmartín, Joaquín. 1973. 'Semantisches über 'MR "Sehen" und 'MR "Sagen" im Ugaritischen'. *Ugarit-Forschungen* 5: 263–70.
- Sivan, Daniel. 2001. *A Grammar of the Ugaritic Language*. Handbook of Oriental Studies. Near and Middle East 28. Leiden: Brill.
- Smith, Mark. 1994. *The Ugaritic Baal Cycle*, vol. 1. Leiden: Brill.
- Smith, Mark, and Wayne Pitard, 2009. *The Ugaritic Baal Cycle*, vol. 2: *Introduction with Text, Translation and Commentary of KTU/CAT 1.3–1.4*. Leiden: Brill.
- Smith, T. Y. 2010. 'Cross-Linguistic Categorization of Benefactives by Event Structure: A Preliminary Framework for Benefactive Typology'. In *Benefactives and Malefactives*, edited by Fernando Zúñiga and Seppo Kittilä, 70–95. Amsterdam: John Benjamins.
- Tallqvist, Knut L. 1938. *Akkadische Götterepitheta*. Studia Orientalia 7. Helsinki: Akateeminen Kirjakauppa.

- Tropper, Josef. 2012. *Ugaritische Grammatik*, Zweite, stark überarbeitete und erweiterte Auflage. Alter Orient und Altes Testament 273. Münster: Ugarit-Verlag.
- Tugendhaft, Aaron. 2018. *Baal and the Politics of Poetry*. The Ancient Word. London: Routledge.
- Uehlinger, Christoph. 1999. 'Leviathan'. In *Dictionary of Deities and Demons in the Bible*, edited by Karel van der Toorn, Bob Becking, and Pieter W. van der Horst, 511–13. Leiden: Brill.
- van Dijk, J. 1969. "‘Vert Comme Tišpak’". *Orientalia* 38/4: 539–47.
- Vogelzang, Marianna E. 1990. 'Patterns Introducing Direct Speech in Akkadian Literary Texts'. *Journal of Cuneiform Studies* 42/1: 50–70.
- Wasserman, Nathan. 2003. *Style and Form in Old-Babylonian Literary Texts*. Leiden: Brill.
- Watson, Wilfred G. E. 1999a. 'Fire 𐎗𐎕'. In *Dictionary of Deities and Demons in the Bible*, edited by Karel van der Toorn, Bob Becking, and Pieter W. van der Horst, 331–32. Leiden: Brill.
- . 1999b. 'Flame 𐎗𐎕𐎗'. In *Dictionary of Deities and Demons in the Bible*, edited by Karel van der Toorn, Bob Becking, and Pieter W. van der Horst, 335–36. Leiden: Brill.
- Xella, Paolo. 1999. 'Reshef'. In *Dictionary of Deities and Demons in the Bible*, edited by Karel van der Toorn, Bob Becking, and Pieter W. van der Horst, 700–3. Leiden: Brill.
- Yarbro Collins, Adela. 2001. *The Combat Myth in the Book of Revelation*. New York: Wipf and Stock Publishers.

- Zúñiga, Fernando, and Seppo Kittilä. 2019. 'Changing Syntactic Valency: Passives, Antipassives, and Related Constructions'. In *Grammatical Voice*, 82–119. Cambridge Textbooks in Linguistics. Cambridge: Cambridge University Press.

LOAN TRANSLATION OR INDEPENDENT DEVELOPMENT: THE FIGURA ETYMOLOGICA IN SEMITIC AND IN YIDDISH

Lutz Edzard

A perennial question in linguistics is the following: does the similarity of constructions in genetically related or even unrelated languages necessitate the assumption of a common origin in a source language with subsequent loan transfer (calque) to other languages, or is it equally legitimate to argue for the independent emergence of said construction? On the one hand, to start with the latter possibility, logical commonalities across languages allow for the independent and simultaneous emergence of linguistic phenomena. In this spirit, Fleischer (2008, 257) cites Lass (1997, 201), who argues that it is always preferable to look for an internal autochthonous explanation for a linguistic phenomenon, unless there is compelling evidence to take into account foreign influence. On the other hand, it is uncontested that whole constructions and phrases can be aptly transferred from language to language (cf. Thomason and Kaufman 1988). Contemporary German, for instance, abounds with Anglicisms, e.g., *es macht Sinn* ‘it is reasonable’ < *it makes sense*.

A case in point is the *figura etymologica*, more precisely, the tautological infinitive, well-known across Semitic, in Arabic also referred to as *mafʿūl muṭlaq*.¹ While the latter term, *mafʿūl muṭlaq*, is restricted to the combination of a finite verb with the cognate *maṣḍar* in the accusative (*naṣb*), corresponding to the combination of the infinitive absolute with a cognate active or passive finite verb (or vice versa) in Biblical Hebrew (also labelled ‘tautological infinitive’), the term *figura etymologica*, or *paronomasia*, is used in a broader sense, encompassing combinations of cognate words, such as in the Hebrew annexation *šūr haš-šūrīm* ‘(the) song of songs’ (i.e., ‘the especially beautiful song’), the Gəʿəz annexation *nəgusä nəgäst* ‘(the) king of kings’ (an honorific for Ethiopian emperors), and Arabic constructions of the type *qāla qāʾilun* ‘somebody (‘a saying one’) said’ or *ṣarrara-hū ṣuraran* ‘he wrapped it in packages’ (cf. notably Diem 2007, 316ff. for the further development and reception of Reckendorf’s concept of paronomasia in Arabic and Semitic linguistics). Other syntactic possibilities include, e.g., phrases like Gothic *haurnjans haurnjandans* ‘horns hornblowing’ (cf. Stutz 1966, 33ff.; for further Gothic examples cf. Quak 2020, 47). As Goldenberg (1971, 36) plausibly argues, the tautological infinitive, in contrast to the just mentioned cognate annexations, does not necessarily convey a notion of intensity, but may have other discourse functions. Of course, it may also simply be due to ‘syntax translation’ (i.e., calque). Here are a few examples from the classical (varieties of) Semitic languages:

¹ Goldenberg (1971, 482) sees different constructions at work here, but that does not matter for the viewpoint and purposes of this paper.

Akkadian (von Soden 1995, § 150a)

- (1) *ḥadûm-ma hadi*
‘he is very glad’
- (2) *alākum-ma ula nittalak*
‘we did not go at all’

Classical Arabic (Reckendorf 1909, 102)

- (3) *qad futilat fatlan*
‘it (F) was firmly twisted’
- (4) *tubbirū tatbīran*
‘they were completely broken’

Biblical Hebrew (Reckendorf 1909, 102)

- (5) *gunnōḇ gunnaḇtī*
‘indeed I was kidnapped’ (Gen. 40.15)

Syriac (Reckendorf 1909, 102)

- (6) *meḡbā gəḇe (h)wā*
‘he was chosen’

Modern Semitic features the same construction, as well. In Israeli Hebrew, the construction is fairly productive (though, unlike in Biblical Hebrew) with the infinitive construct or verbal noun), e.g.,

Israeli Hebrew (Pereltsvaig 2002, 109)

- (7) *Dani xiyex xiyux sameax.*
‘Danny smile a happy smile.’

Examples from Arabic dialects, Maltese, and Ethio-Semitic Amharic, consisting of a finite verb form and the cognate *maṣḍar*, include:

Maltese (Maas 2005, 416)

- (8) *yohrog hruġ*
 ‘he goes out a lot’

Moroccan Arabic (Maas 2005, 419)

- (9) *ka-išrib šrib*
 ‘he drinks a lot’

Amharic (Goldenberg 1971, 40)

- (10) *māmṭat-əss* *mätto-bb-əññ*
 come.INF-DM come.CVB-3SG.M-BENEF-1SG
 ‘as to coming, he had come to me’

This topic has been researched at depth within Semitic (starting with Reckendorf 1909) and beyond (starting with Pott 1862). Besides Semitic, Goldenberg (1971, 36) mentions Baltic, Slavic, Romance, and German dialects (Indo-European), as well as Hungarian (Finno-Ugric), and Turkish (Ural-Altaic). Shisha-Halevy (1990) has investigated this construction in Coptic. Here are relevant examples from Indo-European languages:

Lithuanian (Fleischer 2008, 256)

- (11) *girdėti* *girdėjau*, *laiko* *neturėjau*
 hear.INF hear.PST.1SG time NEG.have.PST.1SG
 ‘I did hear it, but didn’t have time.’

Russian (Fleischer 2008, 257)

- (12) *pet’* *ja* *bol’she* *ne* *poju*, *ja* *uže*
 sing.INF 1SG more NEG sing.PRS.1SG 1SG already
bol’she ne mogu
 more NEG can.PRS.1SG
 ‘I no longer sing, I can’t anymore.’

Italian (Goldenberg 1971, 37)

- (13) *Dispiacere non mi dispiacete*
 displease.INF NEG 1SG.OBJ displease.PRS.2PL
 ‘You (PL) don’t displease me.’

Northern Bavarian (Fleischer 2008, 249)

- (14) *sinə sij i ni mw, kon i*
 sing.INF sing.PRS.1SG 1SG NEG more can.PRS.1SG 1SG
a: ni mw
 also NEG more
 ‘I no longer sing, I just can’t anymore.’

The same construction also occurs with modal verbs in Bavarian and beyond, often with a contrastive connotation, e.g.,

- (15) *Ja kina ko’ ma’ scho, aba derfa derf*
 yes can.INF can.IPF.3SG one affirm but may.INF may.IPFV.3SG
ma’ net
 one NEG
 ‘One can/has the ability/possibility to [do it], but one may not [legally do it].’ (Fleischer 2008, 250)

Both Goldenberg (1971) and Fleischer (2008) also cite examples close to the standard language, though they are associated with special regions, e.g.,

- (16) *Schlafen schlief ich nicht, ...*
 sleep.INF sleep.PRET.1SG 1SG NEG
 ‘I (actually) did not sleep, ... (Hofmann 1930, 68ff., apud Goldenberg 1971, 38)

- (17) *Schaden schadt ihm das nichts.*
 damage.INF damage.PRS.3SG 3SG.M.DAT PRON.3SG.NT nothing
 ‘That doesn’t hurt him.’ (Fleischer 200, 245)

Modern English features the inner-object construction as well, also in colloquial registers. In Stanley Kubrick's film *Full Metal Jacket*, one soldier provokes another soldier by asking him: "You talk the talk. Do you walk the walk?"

The same holds for a number of other 'classical' languages, cf. constructions such as Latin *vitam vivere* 'to live a life' or Greek πόλεμον πόλεμίζειν 'to fight a battle' (cf. Boldt 2022, 73).

What is less clear and more controversial is the question as to whether Jewish languages, notably Yiddish, which feature this phenomenon as well, owe the *figura etymologica* (here the tautological infinitive) to Semitic (mainly Hebrew), or have developed this stylistic figure of speech autochthonously.

The pros and cons of various answers to this question will be addressed in the following. Jewish languages in the context of Semitic have always been a key focus in Geoffrey Khan's research, and it is in this spirit that this paper is offered on the occasion of Geoffrey's 67th birthday.

1.0. Discussion

1.1. Arguments for Loan Translation

While Bible translations constitute a literary genre *sui generis*, on the one hand, they are also apt to have an impact on the development of literary language in general, as was the case, for instance, with the Saxonian *Kanzleisprache* under the influence of Luther's Bible translation. There is no denying that the Hebrew Bible has had considerable stylistic impact on European languages, as translations, starting with the Septuagint (cf., e.g.,

Thackeray 1908; Shishkin 2018), have attempted to emulate certain syntactic features, among them the *figura etymologica*.

The tautological infinitive (or inner object or *figura etymologica*), a construction which may (but need not) stress the activity in question, is an obvious case in point here. The Biblical Hebrew *locus classicus* for this construction (infinitive absolute + finite verb) may be illustrated with the following:

- (18) הַמֶּלֶךְ תִּמְלֹךְ עָלֵינוּ אִם-מָשׁוּל תִּמְשָׁל בָּנוּ
hă-mālōk timlōk ʿālē-nū ʾim māsšōl
 INT-reign.INF.ABS reign.IPFV.2MSG upon-1PL if rule.INF.ABS
timšōl
 rule.IPFV.2MSG

‘Do you want to be king over us or rule over us?’ (Gen. 37.8); ‘Shalt thou indeed reign over us? or shalt thou indeed have dominion over us?’ (KJV)

Here, no attempt is made in the translations to emulate the tautological infinitive. The King James translation highlights the notion of intensity, though (twice using *indeed*).

In a different case, Ps. 68.19, which employs the cognate nominal object *šēbī* ‘captivity’ rather than an infinitive absolute, the translations do capture this circumstance (cf. Ruge 2015, 437ff.):

- (19) שְׁבִית שְׁבִי
šābītā šēbī
 catch.PF.2MSG captivity

‘Thou hast led captivity captive’ (Ps. 68.19); ‘vnd hast das gefengnis gefangen’ (Luther)

Ruge subsequently argues that in German the construction was already on the retreat in Luther's time and that Luther deliberately chose to imitate Semitic style. This line of argumentation indeed supports the notion of linguistic transfer.

The influence of the *figura etymologica* in biblical passages on translations, while clearly attested, is nevertheless debated. It is true that, for instance, the *figura etymologica* in Song 1.2 is reflected in both English and French translations of the passage:

(20) וְשָׁקְנִי מִנִּשְׁקֹת פִּיהוּ

yiššāqē-nī min-nəšiqōt pī-hū

kiss.JUSS.3MSGM-1SG.OBJ from-kiss.PL.CS mouth-3SG.M

‘Let him kiss me with the kisses of his mouth’; ‘qu’il me baise avec les baisers de sa bouche’

It was also rendered literally by the Septuagint, as well as other European translations.

Φιλησάτω με ἀπὸ φιλημάτων στόματος αὐτοῦ (cf. Aslanov 2001, 239)

The same holds for the true tautological infinitive in Josh. 17.13, which is rendered as such in the Septuagint, but not in European translations:

(21) וְהוֹרִישׁ לֹא הוֹרִישׁוּ

wə-hōrēš lō hōrīšū

and-expel.INF.ABS NEG expel.PF.3MPL

ἐξολεθρεῦσαι δὲ αὐτοὺς οὐκ ἐξωλέθρευσαν

‘but [they] did not utterly drive them out’ (cf. Hofmann 1930, 82)

However, in most other cases such a rendition is not found (cf. again Aslanov 2001; for statistical observations in this context cf. Shsishkin 2018).

In this context a brief excursus on the history of German Qurʾān translations is useful. In the nineteenth century, the German scholar and poet Friedrich Rückert emulated the *figura etymologica* (here *mafʿūl muṭlaq*) in his translation of parts of the Qurʾān. Vv. 9 and 10 of Sūrat aṭ-Ṭūr are a case in point:

(22) يَوْمَ تَمُورُ السَّمَاءُ مَوْرًا

yawma tamūru

s-samāʾu

day.ACC.CS to_move_back_and_forth.IPFV.3FSG DEF-heaven

mawran

to_move_back_and_forth.MAṢḌAR.ACC

‘Am Tage, da der Himmel wankt und schwankt’ (Sūrat aṭ-Ṭūr 9, Bobzin); ‘Wenn wank die Himmel wanken’ (Rückert 2000); ‘On the Day when the heaven will shake with a dreadful shaking’

(23) وَتَسِيرُ الْجِبَالُ سَيْرًا

wa-tasīru

l-ġibālu

sayran

and-travel.IPFV.3FSG DEF-mountain.PL travel.MAṢḌAR.ACC

‘und die Berge sich eilends in Bewegung setzen’ (Sūrat aṭ-Ṭūr 10, Bobzin 2010); ‘Und schwank die Berge schwanken’ (Rückert 2000); ‘And the mountains will move away with a (horrible) movement’

While one might consider these translations poetic, Reckendorf (1909, vii) argues that they attribute too much weight to the *figura etymologica* in the original, where these constructions are far

less marked than in European translations (cf. the caveat formulated by Goldenberg cited above).

Yiddish frequently features this construction. Examples include the following:

- (24) קומט ער נישט

kumen kumt er nit

come.INF come.PRS.3SG 3SG NEG

‘he does not come’ (cf. Fleischer 2014, 155)

- (25) טראָגן טראָג איך מיין אַלטן מאָנטל

trogn trog ikh mayn altn mantl

wear.INF wear.PRS.3SG 1SG 1SG.POSS old.ACC coat

‘I wear my old coat a lot’

- (26) אויפֿהערן האָט די גבירה שוין נישט אויפֿגעהערט צו לאַכן

oyfhern hot di gvire shoyn nit oyfgehort

stop.INF have.PRS.3SG DEF.F lady just NEG stop.PPP

tsu lakhn

to laugh.INF

‘the lady just wouldn’t stop laughing’ (cf. Mark 1978)

Still, Fleischer (2014, 155) ponders arguments for a Slavic origin of the construction in Yiddish, mainly, because he does not see synchronic attestation of the construction in contact regions relevant to the emergence and further development in Yiddish. In contrast, Goldenberg (1971) points to the occurrence of this construction in *both* German registers and Yiddish. The construction is also found in Judezmo, e.g., *vinir no vino* ‘he didn’t come’ (David Bunis, written communication). Goldenberg (1971, 39) cites several Jewish authors, who argued for a Hebrew origin of this construction, notably Gerzon (1902, 76), Miseses (1915, 103),

and Mark (apud Goldenberg 1971, 39), the last of whom pointedly uses the very construction to express the fact:

(27) קומן קומט ער פון לושן קודש אָבר ער האָט טיף אַריינגעדרונגען אין דער
 שפּראַך פון עמד אין אַלע דיאַלעקטן פון ייִדיש
kumen kumt er fon loshn qoydesh, aber er
 come.INF come.PRS.3SG 3MSG from language holy but 3MSG
hot tif arayngedrunge in der shprakh fun
 have.PRS.3SG deep enter.PPP in DEF.F.DAT language of
am-kho² in ale dialektn fun yidish
 common.people in all dialect.PL of Yiddish

‘It [the tautological infinitive, LE] comes from Hebrew (‘the holy language’), but is has deeply permeated the speech of the common [Jewish] people in all dialects of Yiddish.’

At any rate, there is no doubt that the tautological infinitive is a frequent stylistic feature in Yiddish (cf., e.g., Birnbaum 1918, 66, and Finkin 2021).

1.2. Arguments for Autochthonous Development in Yiddish

When one investigates the *figura etymologica* from a typological perspective, as Maas (2015) has done, going all the way back to Pott (1862), this construction does not strike one in any way as unusual. Rather it appears as something to be expected or at least as something belonging to the natural inventory of stylistic variants available. Ruge (2015) entitles his article about the *figura*

² The word *amkho* ‘the common [Jewish] people’ derives from Hebrew עַמָּךְ *‘amməḵā* or עַמְּךָ *‘amməḵā* ‘your people’.

etymologica ‘*einen slac slân...*’ (‘to beat a beat’), certainly not under the influence of the Arabic *mafʿūl muṭlaq* construction *ḍaraba ḍarban*, as one might assume from a Semiticist perspective, but simply since this construction is typical of Middle High German (and earlier) phraseology. Indeed, his first quotation is from the *Nibelungenlied* (Ruge 2015, 413):

- (28) *Der helt dô spranc dar nâher und
DEF.M hero then jump.PST.3SG there closer and
 sluoc im einen slac.
hit.PST.3SG 3SG.DAT INDEF.M.ACC hit
 ‘The hero then jumped closer and beat him a beat (i.e., hit him hard).’*

A further quotation is the following (Ruge 2015, 421):

- (29) *Vnd sluc im slac vber slac.
and hit.PST.3SG 3SG.DAT hit over hit
 ‘And he hit him hit after hit (i.e., repeatedly).’*

In modern Standard German, such examples only seem to be acceptable in a poetic context. In contrast to Middle High German, passivisation, however, is no longer possible, as was still the case in Middle High German (Ruge 2015, 417):

- (30) *Doch wart von im der slac geslagen.
however become.PST.3SG from 3SG.DAT DEF.M hit hit.PPP
 ‘However, the hit was hit by him.’*

Boldt (2022, 73ff.) offers an excellent overview from a broader Germanic perspective. Old Norse examples are the following:

- (31) *Sva scal gerða þan garð*
 like_this shall.PRS.3SG set_up_a_fence.INF DEM.M fence
 ‘One should set up this fence like this’
- (32) *Ef maðr rænir mann hanðrani*
 if someone rob.PRS.3SG man hand.robbing
 ‘If someone robs a man by hand’ (Boldt 2022, 74)

Certain phrases/collocations are specific to individual languages, e.g., Old High German *fruma frūmenti* ‘benefit [I] provide’ (cf. Boldt 2022, 75), others are attested across Germanic, e.g., ‘to repent’, *büßen* in modern German, surfaces as Old Norse *bōta bót* ‘to repent repentance’, as Old English *bōt gebētan* ‘repentance to repent’, and as Old Frisian *bōte bēta* ‘repentance to repent’ (Boldt 2022, 76). ‘To recompense’, *entgelten* in modern German, surfaces as Old Norse *gjalda gjald* ‘to recompense compensation’, Old English *āngild forgildan* ‘compensation to recompense’, Old Frisian *jelda mith jelde(m)* ‘to recompense with compensation’, and Old High German *weragelt geltan* ‘compensation to recompense’ (Boldt 2022, 77; for Old Frisian cf. notably Szadrowsky 1962).

Beyond Germanic, Celtic (Old Irish) also features copious examples (cf. Stüber 2012). In broader Indo-European perspective, one can point to examples such as ‘to give a gift’, surfacing in Latin as *dōnum dedit*, in Vedic as *dānam dā-*, and in Greek as *δῶρον διδόναι*, according to Euler (1982) reconstructible as Proto-Indo-European *dōnom dō-*, in more recent transcription **deh₃nom deh₃-* (cf. Boldt 2022, 76).

Fleischer (2008), in an overview of German dialectal as well as Balto-Slavic examples, makes an especially strong case for

the independent emergence of the *figura etymologica* in modern German dialects. As regards Yiddish (2008, 261ff.), he carefully weighs the theoretical possibility of a Hebrew adstrate, as he argues that the precursors of the modern German dialects that still feature this construction played no role in the development of Yiddish, due to lack of direct contact. Unlike Ruge (2015), he does not consider Middle High German, let alone older evidence. Already Hofmann (1930, 81ff.) clearly supports an autochthonous origin of the *figura etymologica* in both Balto-Slavic and German (dialects) (cf. also Goldenberg 1971, 39 fn. 9; ff. also Meyer-Lübke 1903).

Interestingly, the following text segment, often referred to as the oldest extant coherent example of Yiddish, features precisely this construction:

- (33) גוט טק אים בִּטְגָא שׁ וַיֵּר דִּישׁ מַחְזֹר אֵין בֵּית הַכְּנֶסֶת טְרָגָא
gut tak im betage s'waer dis
 good day 3SG.M.DAT shine.3SG.PRS.CONJ REL DEM.NT
maḥāzor in beyt ha-kneset trage
 prayer.book^H in house.CS^H DEF-assembly^H carry.3SG.PRS
 'May a good day come to him who carries this prayer book
 into the synagogue.'

The phrase (*figura etymologica*) *tak betage* is also attested in Middle High German. Ruge (2015, 416) cites the following example:

- (34) *owê, daz ie der tac betaget*
 woe comp some_time DEF.M day become_day.PRS.3SG
 'Woe, that some time the day will come'

2.0. Conclusion

As for the *figura etymologica* in European languages, Fleischer (2008, 250–54) supposes topicalisation as the crucial motive. What he labels “*Infinitivverdopplung*” thus corresponds to *tun*-phrases, such as the following:

- (35) *Schreiben* *tue* *ich,* *nicht* *lesen*
 write.INF do.PRS.1SG 1SG NEG read.INF
 ‘I am writing, not reading’

The point here is that such phrases semantically match comparable phrases with the tautological infinitive, *schreiben schreibe ich nicht*,.... The only difference can be seen in the focus/contrast that the *tun*-construction offers, as opposed to the mere reinforcement (“*Dopplung*”) of the tautological infinitive (keeping in mind that reinforcement is not the only function of that construction). The functional character of this analysis makes the independent emergence of such constructions highly plausible. What is more, inner objects are typologically nothing unusual (cf., e.g., Nakajma 2006 and Fritz and Meier-Brügger 2021, 270).

At any rate, we are not faced with a ‘us versus them’ scenario here, as far as the religious affiliation of the involved scholars is concerned. Rather, in the sense of Beider (2015, 10), one can speak of a contrast between a ‘Jewish languages perspective’ and a ‘Germanic linguistics perspective’, which need not, however, be divided along a Jewish/non-Jewish line, as the example of Goldenberg (1971) amply demonstrates. As I have argued (Edzard 2021), a combination or synthesis of these approaches is both feasible and meaningful.

Let us lastly consider the situation in Modern Hebrew. Interestingly enough, a column (by ‘Philologus’) in the *Forward* online newspaper, ‘To Hurt It Can’t Hurt’ (<https://forward.com/news/3213/to-hurt-it-can-e2-80-99t-hurt/>, 1 April 2005), proposes that the productivity of the tautological infinitive in Modern Hebrew is due to Yiddish influence, rather than inheritance from older stages of Hebrew. The first examples cited in this column correspond to the German example above, *Schaden schadt ihm das nichts* ‘that won’t hurt him’:

(36) Biblical Hebrew tautological infinite construction >

Schaden schadt ihm das nichts >

להזיק זה לא יזיק

le-haziq ze lo yaziq

to-damage.INF DEM.M NEG damage.IPFV.3MSG

‘that won’t hurt’ (Philologos 2005)

Truly enough, this construction ceased to be productive in stages of post-biblical Hebrew, and nowadays, if any infinitive is used in such cases, it is the ‘normal’ infinitive construct, not the Biblical Hebrew infinitive absolute, e.g., *la-lexet ’ani ’elex* ‘I will certainly go’, as opposed to Biblical Hebrew *hālōk ’ēlēk*. The latter seems to be relegated to a high stylistic register (cf. Schwarzwald 1989; for the historical stage cf. Waltke and O’Connor 1990, 584–88; see also Goldenberg 1971, 63–73; Kim 2009; and Shemesh-Raiskin 2014). If this is true, we are observing what in sociology is called a ‘pizza effect’ i.e., that a phenomenon, after having lost importance in its original environment, gains importance in a foreign context and is then re-imported to its original environment with higher prestige.

References

- Aslanov, Cyril. 2001. 'Camoufler la parenté: La figure étymologique estompée'. *Revue Romane* 36: 235–54.
- Beider, Alexander. 2015. *Origins of Yiddish Dialects*. Oxford: Oxford University Press.
- Bobzin, Hartmut (trans.). 2010. *Der Koran*. With the collaboration of Katharina Bobzin. Munich: C.H. Beck.
- Boldt, Ramon. 2022. 'Aspekte der vergleichenden Phraseologie der altgermanischen Sprachen untersucht und dargestellt am Beispiel der ältesten Rechtstexte'. PhD dissertation, University of Erlangen-Nürnberg.
- Birnbaum, Salomo A. 1918. *Grammatik der Jiddischen Sprache. Mit einem Wörterbuch und Lesestücken* (Reprint 1988, Hamburg: Buske).
- Diem, Werner. 2007. "'Paronomasie": Eine Begriffsverwirrung'. *Zeitschrift der Deutschen Morgenländischen Gesellschaft* 157/2: 299–352.
- Edzard, Lutz. 2021. 'Yiddish'. *Jewish Languages: Text Specimens, Grammatical, Lexical, and Cultural Sketches*, edited by Lutz Edzard and Ofra Tirosh-Becker, 297–367. Wiesbaden: Harrassowitz.
- Euler, Wolfram. 1982. *Dōnom dō-: Eine "figura etymologica" der Sprachen Altitaliens*. Innsbruck: Institut für Sprachwissenschaft.
- Finkin, Jordan D. 2021. 'The Case of the Tautological Infinitive'. In *A Rhetorical Conversation: Jewish Discourse in Modern Yiddish Literature*, 17–30. University Park: Penn State University Press.

- Fleischer, Jürg. 2008. 'Zur topikalisierenden Infinitivverdopplung in deutschen Dialekten: Trinken trinkt er nicht [sic!] aber rauchen raucht er (mit einem Exkurs zum Jiddischen)'. *Dialektgeographie der Zukunft. Akten des 2. Kongresses der Internationalen Gesellschaft für Dialektologie des Deutschen (IGDD) am Institut für Germanistik der Universität Wien, 20. bis 23. September 2006*, edited by Peter Ernst and Franz Patock, 243–68. Zeitschrift für Dialektologie und Linguistik. Beihefte 135. Stuttgart: Franz Steiner.
- . 2014. 'Slavic Influence in Eastern Yiddish Syntax: The Case of vos Relative Clauses'. *Jewish Language Contact*, edited by Ghil'ad Zuckermann, 137–61. Special Issue. *International Journal of the Sociology of Language* 226. Berlin: De Gruyter.
- Fritz, Matthias Andreas, and Michael Meier-Brügger. 2021. *Indogermanische Sprachwissenschaft*. Berlin: De Gruyter.
- Gerzon, Jacob. 1902. *Die jüdisch-deutsche Sprache: Eine grammatisch-lexikalische Untersuchung ihres deutschen Grundbestandes*. Frankfurt: J. Kauffmann.
- Goldenberg, Gideon. 1971. 'Tautological Infinitive'. *Israel Oriental Studies* 1: 36–85.
- Hofmann, Erich. 1930. *Ausdrucksverstärkung: Untersuchungen zur etymologischen Verstärkung und zum Gebrauch der Steigerungsadverbia im Balto-Slavischen und in anderen indogermanischen Sprachen*. Göttingen: Vandenhoeck & Ruprecht.
- Kim, Yoo-Ki. 2009. *The Function of the Tautological Infinitive in Classical Biblical Hebrew*. Leiden: Brill.

- Lass, Roger. 1997. *Historical Linguistics and Linguistic Change*. Cambridge: Cambridge University Press.
- Maas, Utz. 2005. 'Syntactic Reduplication in Arabic'. *Studies on Reduplication*, edited by Bernard Hurch, 395–429. Berlin and New York: Mouton De Gruyter.
- Meyer-Lübke, Wilhelm. 1903. 'Der intensive Infinitiv im Litauischen und Russischen'. *Indogermanische Forschungen* 14: 111–27.
- Mark, Yudel. 1978. *Grammatik fun der Yiddisher Klal-shprakh*. New York: Congress for Jewish Culture.
- Mieses, Matthias. 1915. *Die Entstehungsursache der jüdischen Dialekte*. Vienna: R. Löwit (Reprint 1979 Hamburg: Helmut Buske).
- Nakajma, Heizo. 2006. 'Adverbial Cognate Objects'. *Linguistic Inquiry* 37/4: 676–84.
- Pereltsvaig, Asya. 2002. 'Cognate objects in Modern and Biblical Hebrew'. *Themes in Arabic and Hebrew Syntax*, edited by Jamal Ouhalla and Ur Shlonsky, 107–36. *Studies in Natural Language and Linguistic Theory*. Dordrecht: Kluwer Publishing.
- Philologos. 2005. 'To Hurt It Can't Hurt'. *Forward*. <https://forward.com/articles/3213/to-hurt-it-can-e2-80-99t-hurt/>
- Pott, August Friedrich. 1862. *Doppelung (Reduplikation, Gemination) als eines der wichtigsten Bildungsmittel der Sprache, beleuchtet aus Sprachen aller Welttheile*. Lemgo: Meyer.
- Quak, Arend. 2020. 'Die Psalmen in gotischer Sprache'. *Amsterdamer Beiträge zur älteren Germanistik* 80: 25–65.

- Reckendorf, Hermann. 1909. *Über Paronomasie in den semitischen Sprachen*. Gießen: Töpelmann.
- Rückert, Friedrich (trans.). 2000. *Der Koran*. Edited by Hartmut Bobzin, with explanatory notes by Wolfdietrich Fischer. Würzburg: Ergon.
- Ruge, Nikolaus. 2015. 'einen slac slân: Kognate Objekte und figura etymologica in der deutschen Sprachgeschichte'. *Sprachwissenschaft* 40: 413–52.
- Schwarzwald, Ora. 1989. 'Modern Hebrew Absolute Infinitive'. *Leshonenu* 53/1–2: 107–12. [Hebrew]
- Shemesh-Raiskin, Rivka. 2014. 'The Inner Object in Biblical Hebrew: Aspects in Its Description and Approaches to Its Interpretation'. *Revue Biblique* 121/4: 481–505.
- Shisha-Halevy, Ariel. 1990. 'The "Tautological Infinitive" in Coptic: A Structural Examination'. *Journal of Coptic Studies* 1: 99–127.
- Shishkin, Valeriy. 2018. 'Towards the Usage of the Figura Etymologica in the Septuagint'. *Tirosh: Jewish, Slavic & Oriental Studies* 18: 15–29. [Russian]
- Stüber, Karin. 2012. 'Die Figura Etymologica des Altirischen im sprachgeschichtlichen Vergleich'. *Keltische Forschungen* 5: 229–60.
- Stutz, Elfriede. 1966. *Gotische Literaturdenkmäler*. Stuttgart: Metzler.
- Szadowsky, Manfred. 1962. 'Stil und Syntax der altfriesischen Rechtssprache'. *Beiträge zur Geschichte der deutschen Sprache und Literatur* 83: 80–131.

- Thackeray, Henry St. J. 1908. 'Renderings of the Infinitive Absolute in the LXX'. *The Journal of Theological Studies* 9: 597–601.
- Thomason, Sarah Grey, and Terrence Kaufman. 1988. *Language Contact, Creolization, and Genetic Linguistics*. Berkeley: University of California Press.
- von Soden, Wolfram. 1995. *Grundriss der Akkadischen Grammatik*. 3rd edition. Rome: Pontifical Biblical Institute.
- Waltke, Bruce K., and Michael P. O'Connor. 1990. *An Introduction to Biblical Hebrew Syntax*. Winona Lake, IN: Eisenbrauns.

ON THE PRONUNCIATION OF SACRED NAMES

Simon Hopkins

Sensitivity to sacred names is a universal phenomenon, reflected in various ways and to different degrees. In many cultures explicit mention of the deity is typically avoided, either partially or completely. Sometimes the divine name is sidestepped altogether by using a secular substitute, a neutral circumlocution, or a harmless epithet. These substitutes tend to acquire a new sanctity of their own and in due course may themselves make way for further replacements. Another device is to retain the divine name itself, but in an indirect form effected by introducing an intentional change, visible in orthography and often audible in pronunciation. By such means a respectful distance is created between the human and the divine. All this belongs to the “mysticism of language” (Jespersen)—holiness, uncleanness, taboo, euphemism, superstition, magic, etiquette, etc.—and the many aspects of the subject have generated a large linguistic, ethnographic, palaeographic, and halakhic literature. It is this reverential awe of the divine name and its substitutes (*šmot* ‘names’) that in Jewish tradition led to the institution of *geniza*.¹ Here, too,

¹ For Biblical names and epithets of God see Maimonides, *Guide*, Book I, chs 61ff.

in the broader scheme of things, belong *al-ʾasmāʾ al-ḥusnā* ‘the most beautiful names (of God)’ of Islamic tradition, the *asmāt* ‘names’ used by the Ethiopian sorcerer,² and the *nomina barbara* of Greek magical papyri, Gnostic amulets, Aramaic magic bowls, etc.

1.0. The Tetragrammaton, *El(ohim)*, G-d, etc.

The ancient Hebrew reluctance to pronounce the name of the Deity יהוה *yhwh* is well known. The times and places in which, and by whom, the Ineffable Name was permitted to be pronounced became more and more confined, ultimately restricted to priestly circles and Temple ritual, in particular, the High Priest on the Day of Atonement. In Jewish tradition utterance of the Tetragrammaton, השם בן/בעל ארבע אותיות *ha-šem ben/baʿal ʾarbaʿ ʾotiyot* ‘the name with four letters’ was avoided by substituting the pronunciations of אֲדֹנָי *ʾădōnāy* ‘my Lord’ (b. Pesahim 50a; b. Qiddushin 71a) or, according to circumstances, אֱלֹהִים *ʾēlōhīm* ‘God’. This practice is reflected in the technical term שם המפורש *šem ha-meforaš*, viz. ‘the name which has to be translated (i.e., substituted)’.³ According to the prescribed substitution, the letters יהוה

² Known in Amharic as *asmāt-ām* ~ *asmāt-aññā* ‘name man’, i.e., equivalent to the Hebrew בעל שם *baʿal šem*. Practically synonymous are the *qālāt* ‘words’ of the Ethiopian *qālāt-aññā* magician.

³ “Der beim Lesen zu ‘übersetzende’, d.h. durch etwas anderes zu ersetzende Name” (Polotsky 1932, 274, 283 fn. 1 = Polotsky 1971, 632, 641 fn. 1).

yhwh in the Hebrew Bible are vocalised יהוה or יהוה. The *qere perpetuum* יהוה, usually vocalised with initial *shewa*,⁴ has resulted in the modern spelling pronunciation ‘Jehovah’, which originated—and still persists—in certain Christian circles. The Samaritans solved the problem in a different way, by reading יהוה *yhwh* as *šēmā*, i.e., ‘the Name’ par excellence (Tal 2000, I:337, II:907, and the references there). This appears in Jewish tradition as ה' (with apostrophe, usually not written out in full = הַשֵּׁם, cf. Deut. 28.58). A common alternative is ד', a notation of uncertain origin. In current Jewish oral practice, the substitute for the Ineffable Name is *'adonay* in prayer, while *ha-šēm* is preferred in colloquial Hebrew speech: ברוך אתה אדני *baruk 'ata 'adonay* ‘blessed are you, Lord’ in a ritual context versus ברוך ה' *baruk ha-šēm* ‘blessed be the name’ in conversation.⁵ In Italian tradition the substitute for the Tetragrammaton is *Domedet* (and variants) written דומדת (*sic*, with ת) (Ryzhik 2021, 516 fn. 67, 524, 538, 546).

The customary square script of the Hebrew Bible makes no graphic distinction between the letters *y*, *h*, and *w* of *yhwh* and the same letters used in any other word. This is not so in the Dead Sea Scrolls, where sensitivity to the divine name was given graphic expression. Among the Qumran sectarians the four letters of the Tetragrammaton were often written, in contrast to the main body of the text, in palaeo-Hebrew script: 𐤅𐤅𐤅𐤅. The same

⁴ The reason for the irregular *shewa* simplex is unclear (Ewald 1870, 96) and in Jewish circles was sometimes disapproved (Reif 1979, 8–9).

⁵ For the distinction between prayer and daily speech, cf. below fns 10 and 11.

orthographic conservatism was continued in certain Greek transmissions of the scriptures, in which the Tetragrammaton *yhwh* appears in the (almost certainly deliberate) transformation as ΥΗΥΗ (*yhyh*) or $\pi\iota\pi\iota$,⁶ whence it subsequently entered Syriac in the forms ܡܬܡܬ or ܡܬܡܬܐ .⁷

For superstitious reasons it is the nature of taboos to be extended beyond their original context and applied ever more rigorously. Such a taboo on writing the Tetragrammaton (or—just to be on the safe side—anything resembling it) has been identified as responsible for the form ܠܗܘܐ *lehēwē* in Biblical Aramaic, the imperfect of *hwy*, for which one would have expected ܠܗܘܐ^* . Although various linguistic arguments have been advanced in justification of the anomalous ܠܗܘܐ , it seems fairly clear that in certain circles at least the regular form ܝܗܘܐ aroused pious scruples and was avoided by using the *l* prefix in preference to the sensitive *y(hw')*.⁸

In post-biblical Hebrew, as is well known, the Jewish Deity is often referred to by descriptive or circumlocutionary epithets: $\text{הַקָּדוֹשׁ בְּרוּךְ הוּא}$ *ha-qadoš baruk hu* ‘the holy one blessed be he’ (= ‘הַקָּב"ה’), $\text{רִיבוֹנוֹ שֶׁל עוֹלָם}$ *ribono šel ‘olam* ‘master of the universe’, הַמָּקוֹם *ha-maqom* ‘the place’, רַחֲמָנָא *rahmana* ‘merciful’, etc. Beside theonyms such as these, reverence for the Divine Name *yhwh*, שֵׁם הַיְיָ, together with its sacred substitutes, has generated a large

⁶ The Greek ideogram $\pi\iota\pi\iota$ was read $\kappa\upsilon\rho\iota\varsigma$ ‘Lord’, in accordance with the LXX rendering of יהוה (Burkitt 1897, 16; Taylor 1900, 26).

⁷ For full details of this and other methods of writing the Tetragrammaton in the scrolls see Tov (2004, chs. 5d, 6b[2], and Appendix 5C).

⁸ The taboo factor is not favoured by Fassberg (2015).

variety of deliberate graphic and phonetic alterations. From ancient to modern times, Jewish practice has found many creative solutions to the difficulty of writing and pronouncing the Divine Name; in cabbalistic circles especially this theme became very highly developed, sophisticated in both method and graphic design. A comprehensive chronological survey of the subject, with many examples and references to further literature, has been given by Sh. Sharvit (2008; see also, e.g., Steinschneider 1895–1896; Wieder 1962, 242–43 fn. 3.).

A common expedient to avoid explicit *ad literam* mention of the Tetragrammaton (i.e., השם באותיותיו *ha-šem be-ʾotiyotav* ‘the name with its letters’, השם ככתבו *ha-šem ki-ktavo* ‘the name according to its writing’) is the introduction of a change in the orthography.⁹ A vast number of variations is attested: יי, יי, יי, ..., יהוד, יוד, י-ה-ו-ה, etc. (further possibilities in Dalman 1905, 53 bottom). Theophoric proper names may be rendered inoffensive by an adjustment in the spelling, e.g., the sequence -יהו in the name ‘Elijah’ is avoided by writing אליאז instead of אליהו (Cohen 1925, 199, with reference to twentieth-century Singapore, reflecting the practice of Baghdad). The orthographical taboo is extended to any combination of letters which happens to occur in the Tetragrammaton, even when the Deity is not intended at all, e.g., יאודים instead of יהודים ‘Jews’ (Sabar 1991, 32 fn. 56); the same problem in the word for ‘Jews’ = اليهود was solved in the Yemen by writing יוד, יאוד, ירוד, or יוד (Piamenta 1990–1991, 535, 536, 538). Note also the preference in rabbinical Judezmo for

⁹ Cf. the alterations in the oath ‘substitutes’ (כינויים) in m. Nedarim 1.2.

final ם״- instead of ף״- (Bunis 2021, 430). Here belongs the writing of the numerals 15 and 16 indirectly as ט, i.e., 9 + 6, and ץ, i.e., 9 + 7, instead of ף, i.e., 10 + 5, and ץ, i.e., 10 + 6, respectively. In many communities the Tetragrammaton substitute *ʿadonay* has itself become taboo and the name changed in various ways: *aḏunay*, *aḏoḇay*, *aḏubayš*, *aḏoqay* (Tunisia) (Henshke 2007, 174; further cases in Maman 2019, 35–36). Not all of such variations met with general acceptance; the still-common *adoshem*¹⁰ has been explicitly singled out in halakhic literature for disapproval (*Qiššur Šulḥan ʿAruk*, ed. Ganzfried, §6.3, end).

The spelling of אלהים *ʿelohim* was altered by elongating the left upright of the ה of אלהים into אלקים and pronouncing the result accordingly as *ʿelokim*.¹¹ Alternatively, the same left upright of the letter ה may be (shortened and then) cancelled, producing אֵלִים and giving rise to the matching pronunciation *ʿelodim*. Spellings with ק are found in Jewish Neo-Aramaic tradition, where *ʾilāha* ‘God’, the word used in the spoken language, is written both directly with *h*—אֵיל(א)הא, אֵלֵאֵהא—and obliquely with *q*—אֵילֵאקֵא, אֵלֵקֵא (Sabar 1984, 249; 1991, 32).¹² The ק of אלקים, doubtless helped by association with קדוש *qadoš* ‘holy’, may be transferred to the word אֵל *ʾel* ‘God’, written קֵל and pronounced

¹⁰ “אֲדוֹשֵׁם *ʾadīšem* ‘Aussprache des Gottesnamens außerhalb des Betens’” (Birnbaum 1922, 51).

¹¹ “אלקים *ʾeloikim*, wie es ausserhalb des Gebetes im hebräischen Text ausgesprochen wird” (Birnbaum 1922, 21).

¹² The abbreviation ה is also used for ‘God’: ה׳ stands for אֵילֵאֵהא *ʾilāha* ‘God of...’ (Sabar 1984, 51:22).

kel (Wieder 1962, 242 fn. 3), e.g., בית קל ‘Bet Kel’ instead of the place name בית אל ‘Bethel’ (Sarfatti 2001, 269).¹³ This sacred ק has found its way into the Tetragrammaton יקוק and also into ה' צבקות (צבאות <) ‘the Lord of Hosts’. An unusual sensitivity to אל is reflected in an early Judaeo-Arabic translation of the Pentateuch. In this manuscript, proper names ending in אל- are not reproduced as they stand in the Hebrew text, but slightly altered so as to avoid writing אל at the end of the word. Thus, בתואל *bəṭū'āl* ‘Bethuel’ (Gen. 24.47) and בית-אל *bēt-ʿāl* ‘Bethel’ (Gen. 35.3) are translated בתוייל and ביתיל, respectively.¹⁴ Another solution to such words, attested in modern times, but perhaps of much earlier origin, is to hyphenate the troublesome ending, e.g., שמואל-ל, etc. (Sharvit 2008, 612–13).

In early Judaeo-Arabic texts, alongside the spelling אללה = الله, it is common to find the ligature ٱ (as opposed to אל) followed by a sign which usually resembles a large *qamets*: ٱٱ, but sometimes looks more like a *dalet* (Blau and Hopkins 2017, 28 and the references there). This sign represents the *qamets* of אדני; the *dalet*-like symbol may derive from the ד of אדני or אלהים. The ligature ٱ followed by a large *qamets*-like symbol also occurs in Aramaic Geniza MSS, in which repeated ٱ substitutes for the last two

¹³ A Google search for תודה לקל or ‘toda lakel’ (= תודה לאל ‘thank God!’) produces several results. This *kel* can be heard in hasidic songs, e.g., those sung by Avraham Fried.

¹⁴ Further leaves of this MS have been published in Butbul and Hopkins (2024, 26 fn. 89). In the light of the translator’s clear avoidance of אל- at the end of proper names, the footnote in Blau and Hopkins (2017, 290) should be deleted.

letters of אלהא, e.g., אלהא דשמיה 'in the name of the *memra* of the Lord God of heaven" (Palestinian Targum to Gen. 24.3) (Klein 1986, I:35, II:13, where the sign has been mistaken for and edited as a regular ד). The ligature ם alone (with no following symbol) is found in Neo-Aramaic tradition (Sabar 1976, xlv; 1991, 32). In old Karaite texts *qamets* is often added beneath the writing of 'God': ם or, in Arabic translation, الله. These Karaite texts also use special symbols in order to indicate the name of God (Hoerning 1889, 22, 29, 39; Khan 1990, 186, Index s.v. 'Tetragrammaton'); these symbols probably represent stylised monograms of الله. Some early Yiddish sources write the word *Gott* with two supralinear dots: גױט (Grünbaum 1882, 290).

There is nothing unusual in all of this. The name of God is likely to receive a special orthography or pronunciation in many cultures. This word, when referring to the Supreme Deity of the monotheistic religions, is written in English with an initial capital *G*. This is in contrast to polytheistic pagan 'gods', for which lowercase *g* is deemed more appropriate.¹⁵ Such reverential capitalisation may be extended to pronouns; 'Him', 'His', etc. with reference to God and Jesus (as opposed to secular 'him', 'his', etc.) are very frequent in English, though usage varies considerably according to time, place, religious affiliation, and personal taste. With reference to Muḥammad, the practice has been imitated by Muslims writing in English. In the English-speaking world 'G-d' has become rather common, particularly among Jewish writers;

¹⁵ Cf., too, cases such as "For their rock is not as our Rock" (Deut. 32.31 AV).

the word intended is perfectly obvious, even explicit, but the Divine name is not actually spelled out and thus no transgression committed. Another way of creating distance and avoiding direct mention is to introduce a deliberate disguise in pronunciation: Holy Cow, Gock, Gosh, Golly, by Gum, Great Scott, etc. or to omit mention of the Divinity altogether as ‘Oh My (scil. G-d)!’. Such things are well known.

To return to Hebrew and Semitic tradition, the Tetragrammaton substitute *ʾăḏōnāy* is in the Hebrew Bible consistently and deliberately vocalised with *qamets* in the final syllable: אֲדֹנָי.¹⁶ In Karaite transcriptions the word is written اذوناي, i.e., *plene* with *ʾalif* and often vocalised with *qamets* (Khan 1990, 135, 149, 169). This *qamets* is special, for the combination of אֲדֹנִים *ʾăḏōnīm*, the plural (*excellētiaē, majestatis*) of אֲדֹן *ʾăḏōn* ‘lord, master’, with the standard 1CSG pronominal suffix would be expected to yield אֲדֹנַי *ʾăḏōnay* with *pataḥ*. Biblical punctuation, however, consistently distinguishes between secular אֲדֹנַי *ʾăḏōnay* ‘my lords (PL)’ (Gen. 19.2) with *pataḥ* and sacred אֲדֹנָי *ʾăḏōnāy* ‘my Lord (SG)’ with *qamets*. This is the reason that Ibn Ezra, Kimḥi, and others felt compelled to explain the vocalisation with *qamets* of אֲדֹנָי *ʾăḏōnāy* in Gen. 19.18—not because it refers to the deity, but because this profane application of the word stands in pause.¹⁷ The

¹⁶ Notable, too, are vocalisations after monosyllabic prefixes of the type וַיְהוּהוּ, to be read וַאֲדֹנָי *w-ăḏōnāy* (< וַאֲדֹנָי* *wa-ʾăḏōnāy*) (GKC §102m).

¹⁷ Ibn Ezra *ad loc.*: חול ונקמץ בעבור שהוא סוף פסוק ‘Secular (i.e., ‘my lords’) and pointed with *qamets* (אֲדֹנָי) because it stands at the end of the verse’. This is at variance with the sacred understanding ‘my Lord’ of b. Shevuot 35b (as already Targum Onqelos). Interpretations also differed

distinction in vocalisation between secular and sacred אֲדָנִי, with *pataḥ* and *qamets* respectively, is firmly established in Rabbinic tradition and is even pre-Masoretic (Fleischer 1971–1972, 266–67).¹⁸ This holy *qamets* may well have its origin in vocative ‘O my God!’, with regular pausal *a* > *ā*, subsequently frozen and extended (Brockelmann 1908–1913, I:113, II:§178).¹⁹ Sacred and profane applications of the word are also kept separate in the Babylonian²⁰ and Samaritan transmissions of Hebrew.²¹

with regard to the reference of אֲדָנִי in Gen. 18.3; see, e.g., Kimḥi *ad loc.* and, for further details, e.g., Gesenius (1829–1858, 329a); König (1897, 206).

¹⁸ The grammatical term in question is *qmṣ* (בשפה קמוצה) with reference to the vowel of אֲדָנִי. In later mediaeval Hebrew poetry, in the same context, we find זָקוּף בִּלְשׁוֹן וְקָמוּץ בִּשְׁפָה (Ibn Gabirol). Since *qmṣ* here = ‘pronounced with *qamets* [ā]’ (and not with *pataḥ* [a]), the parallel *zqp* should be understood in a sense equivalent to Syriac *zqp* = ‘pronounce with the vowel *zqāfā* [ā]’ (East Syriac *ā*, West Syriac *ō*). Cf. below on the vowel *zqāfā* in Syriac *Māryā*.

¹⁹ To Brockelmann’s examples add Neo-Mandaic *m̄ore* (Mutzafi 2014, 186–87). For the special vocative accentuation of NA *ālaha* ‘God’ etc., see below.

²⁰ For the Babylonian *rafe* marking the sanctity of אֲדָנִי, see Yeivin (1985, 912). For the same usage applied to אֱלֹהִים, see below.

²¹ Yeivin (1985, 912 fn. 117) provides references to the work of Z. Ben-Hayyim for sacred Samaritan *Ādāni* versus secular *ādanni*.

2.0. Sacred Phonology

That it is the back vowel *qamets* that characterises sacred אֲדֹנִי is significant. The phenomenon is not an isolated oddity, but belongs to a pattern. This special use of *qamets* with reference to God may also lie behind the pointing of the Biblical oath הִי אֲנִי *hay 'ānī* ‘as I live’. The vocalisation of the pronoun אֲנִי with *qamets* is in principle a phonological feature typical of pausal position: אֲנִי 'ānī in context versus אֲנִי 'ānī in pause. In the combination אֲנִי הִי *hay 'ānī*, however, *qamets* is the norm, irrespective of position in the sentence (GKC 106). This may well be because הִי אֲנִי *hay 'ānī* is used self-referentially only by God Himself in direct speech, and the pronoun hence pronounced with the sacred, festive *qamets*, which, as we have seen, also distinguishes אֲדֹנִי.²²

The distinctive pronunciation of אֲדֹנִי is not confined to the Biblical vowel *qamets*. There is also a consonantal aspect to the question. A special articulation for the ד of this sacred name is found in various Hebrew reading traditions and also in the Hebrew component of Jewish languages. The Hebrew of the Jews of Baghdad does not as a rule distinguish between ד and דָ, both being pronounced as plosive [d]. This plosive pronunciation is used in every word except two: אֲדֹנִי as the realisation of the Tetragrammaton and אֶחָד ‘one’ in the recitation of the Shema: שְׁמַע אֶחָד | יְיָ אֱלֹהֵינוּ יְיָ אֶחָד. ‘Hear, O Israel: The Lord our God, the

²² Thus Bauer and Leander (1922, 248): “infolge der feierlichen Aussprache.” See below for festive *qamets* in the reading tradition of Cochin, Kerala (India).

Lord is one' (Deut. 6.4).²³ In these two highly charged religious contexts $\bar{\tau}$ is not only interdental [d̪], but usually also emphatic [d̪ˤ] (Blanc 1964, 141; Morag 1977, 3–4; Mansour 1991, 47 fn. 33), as if the words were written in Arabic with velarised ظ/ض . The Divine Name in Baghdad is pronounced *aḏōnāy* ~ *aḏōnāy*. Similarly anomalous interdental pronunciation in this particular word has been noted for other Sephardi traditions, e.g., Aleppo (Syria; Katz 1981, 4–5) and Constantine (Algeria; Maman 2016, 223).

The emphatic, i.e. velarised, [d̪ˤ] of *aḏōnāy* in Baghdad pronunciation has parallels elsewhere; other Hebrew traditions, too, pronounce this special word with added expressive velarisation, e.g., the Judaeo-Arabic of Tunisia.²⁴ Muslim Arabic, too, may use emphatic articulation for a similar affective purpose. A well-known peculiarity of Arabic pronunciation is the emphatic *l* (*mufaxxama*, *muḡallaḏa*) of the word *ʾallāhu* 'God' (Cantineau 1960 [1941], 51; Ferguson 1956 and the literature referred to in these places). In classical Arabic the independent phoneme *l* occurs only here. It is not a coincidence that such a special phonological feature should characterise such a special word. The em-

²³ The special pronunciation of τ in this case is due to (not fully clear) Rabbinical precept: see, e.g., Berliner (1879, 28–29); Kahle (1959, 180–81); *Qışsur Šulḥan ʿAruk* (ed. Ganzfried, §17.3). In some MSS and prints the τ of this $\tau\eta\aleph$ is included among the *litterae majusculae* and written large; the η may also be written with a gable-like top.

²⁴ Virtually all the variants in Henshke (2007, 174) are pronounced with the velarisation mentioned there (174–75 fn. 3).

phatic pronunciation is here without any phonological motivation; it is the exponent of the word's specialised, sacred meaning.²⁵ The Arabic term describing its function is *ta'dīm* 'exaltation, glorification'. It is a moot point whether the emphasis (*tafxīm, taḡlīḍ*) of *l(l)* in this word is an indigenous Arabic development or due to the influence of Syriac pronunciation—both possibilities have their advocates.²⁶

In connection with the emphatic pronunciation of *'allāh* it is worth mentioning that in the Babylonian transmission of Biblical and post-biblical Hebrew *rafe* and *dagesh* signs are applied to the *lamed* of the word אלהים in order to distinguish the God of Israel from the heathen gods of the nations: *rafe* for the former, *dagesh* for the latter (Yeivin 1985, I:357, II:908–10; cf. for אדני above fn. 20). The phonetic implications of this marking are not clear. If the meanings are to be distinguished by gemination (sacred *Elohim* versus profane *ellohim*), one might, *mutatis mutandis*, compare the semantic function of gemination in Syriac *'abā* 'biological father' versus *'Abbā* 'Father' as a clerical title. It is more probable, however, that the vocaliser had in mind a contrast between plain and emphatic *l* : *l(l)* (cf. Bergsträsser 1918, §10n fn.

²⁵ Feghali (1919, 67): "il s'agit ici d'une emphase d'origine psychologique"; Fischer and Jastrow (1980, 57): "als Ausdruck der Bedeutungshervorhebung." Cf. below fn. 28.

²⁶ See Blau (1972, 175–77 [= Blau 1988, 332–34]) and Ambros (1981), respectively; further details in Kiltz 2012. The emphatic pronunciation applies also to the vocative اَللّٰهُمَّ *'allāhumma* (< אלהים?), but, significantly, not to the heathen goddess اللات *al-Lāt* (who also appears in the Qur'ān).

4), the foreign, non-Jewish ‘gods’ being marked with the phonetics of alien Islamic *ʿallāh*. If so, we have here an early example of Islamic impact on Hebrew pronunciation. Emphatic *l̥* occasionally occurs in the word for ‘God’ in Neo-Aramaic, too. The Barzani forms *ʿula* ~ *ʿulha* would appear to be inherited native words (Mutzafi 2002, 45);²⁷ perhaps, however, Arabic provided a helping hand in the emergence of *l̥*.

Another point connected with the NA realisation of ‘God’ is its accentuation. Maclean (1901, 12b) tells us that the Urmi pronunciation of the word is “usually proparox.”, i.e., *ālaha*. He remarks on this because *ālaha* is against the predominant penultimate stress assignment of the dialect. The reason for the peculiarity is that *ālaha* is in principle a vocative form ‘O God!’ (Khan 2008, I:125–26; 2016, I:227 and cf. Maclean 1895, 13; for originally vocative ܐܠܗܐ see above fn. 19), its stress pattern perhaps having been extended beyond strictly vocative usage and thus calling for mention. Here too belongs WNA *alō* (Spitaler 1938, 76 top).

The expressive velarisation so very strongly associated with *ʿallāh* occurs elsewhere in Arabic. It is not uncommon in Arabic dialects to find contrasts of the kind *yā Rabb(i)* ‘O (my) Lord!’, pronounced with what M. Cohen terms “emphase psychologique,”²⁸ versus non-emphatic *rabbī*, being the imperative

²⁷ Mutzafi (2014, 187) gives NENA *ʿāla* and also quotes Turoyo *alō(ho)* with emphatic *l̥*.

²⁸ See Cohen (1912, 54), where it is stated that *r̥* is frequent “dans des mots psychologiquement emphatiques,” among them *rabb̥i* ‘le Seigneur,

of *rby* II²⁹ or the substantive ‘Jewish rabbi’.³⁰ In like manner, some bedouin dialects use velarisation to distinguish between plain *mḥammad* ~ *mḥimmid* as a secular personal name and emphatic *Mḥamḥmad* when reference is to the Prophet of Islam (Borg 2001; Shawarba 2012, 32, 58). Neo-Aramaic can show similar differentiating examples. In Jewish dialects, native תּוֹרָא ‘ox’ is pronounced plain, viz. *tora*, whereas sacred ‘Torah’ < (Hebrew תּוֹרָה) is always emphatic: ⁺*Tora* (Sabar 1974–1975, 278; 1991, 181; 2002, 308; Mutzafi 2004, 247, 248; 2008a, 390, 392).

In the Christian dialect of Urmi *mara* ‘owner’, with plain pronunciation, is a day-to-day secular word, but ⁺*Maran*, ⁺*Marya* with emphatic, backed pronunciation are sacred terms with the particular meanings ‘Our Lord, the Lord (God)’ (Khan 2016, III:209, 229).³¹ There is a historical background to this distinction. In classical Syriac, biliteral ܡܪܐ *mārā* is of secular application, whereas trilateral ܡܪܝܐ *Māryā* is sacred and specific to God and Christ—a variant root assigned to a particular meaning. These are ultimately but two manifestations of the ‘same’ word.

Dieu’. For the term ‘emphase psychologique’ see Cohen (1912, 51, 92, and 549 Index s.v.). Cf. above fn. 25.

²⁹ Thus for Palestinian Arabic, see Elihay (2005, 439) rabb ‘Lord’ versus rabba ‘bring up, raise (a child)’, the distinction being marked in this transcription by backed ‘a’ versus ‘a’ rather than *r* versus *r*.

³⁰ Destaing (1937, 224): *ṛḡbbi* ‘Dieu’ versus *rḡbbi* ‘rabbin’; Brunot and Malka (1940, 49): *ṛābb^wi* versus *rebbi*, taken up by Leslau (1945–1946, 67, 71, 73 [= Leslau 1988, 73, 77, 79]); Yoda (2005, 336–37): *rābbi* ‘rabbi’ versus *ṛābbi* ‘God’; Henshke (2007, 367 fn. 1).

³¹ Khan (2016, III:557) gives many examples of secular *marat*- ‘owner of...’. Cf. below fn. 45, on *marta* versus ⁺*Marta*.

The relationship between them, however, is not clear, for in Semitic languages, generally, and in Aramaic, in particular, the root vacillates between *mr'*, *mry*, and *mr(ø)* and the noun pattern between **qaṭl* and **qāṭil*. If, as seems likely, the basic form of the word can be posited as **mar'ā*, a *qaṭl* noun from the root *mr'* (cf. Arabic *al-mar'u* 'the man') (thus Fox 2003, 76), the long *ā* of *mārā* will be secondary, having arisen through familiar phonological developments: **mar'ā* > **marā* > *mārā*. Such a straightforward phonological explanation does not apply to triconsonantal *Māryā*, in which the *ā* of the closed first syllable is not easily compatible with a **qaṭl* origin. On the face of it, this looks like a **qāṭil* form and perhaps that is indeed what it is (or at least came to be).³² We would therefore have two noun patterns for the 'same' word. A possibility perhaps worth considering as a contributory factor is that the long *ā* of the first syllable of sacred *Māryā* is not (only) a reflex of the *ā* of **qāṭil*, but (also) a special (pausal, vocative?—cf. above fn. 19) pronunciation specific to the name of the Deity, viz. **maryā* (**qaṭl*) > *Māryā* with festive *zqāfā/qamets* in order to give enhanced expression to the sacred name. The contrast in Syriac between secular **mar'ā* (> *mārā*) and sacred *Māryā*³³ would then be typologically parallel to the aforementioned Biblical Hebrew contrast between secular מֶלֶךְ *'ādōnay* 'my lords' with *pataḥ* and sacred מְלֶכֶךְ *'ādōnāy* 'my Lord

³² For the fluctuating morphology cf. Bauer and Leander (1927, 190–91). The *ā* of the doublet *mārā* will also have played a role in the formation of *Māryā*.

³³ In Turoyo *moro* versus *Moryo* ~ *Muryo* ~ *Māryo*.

(God)’ with *qamets* (cf. above fn. 18, on the Hebrew use of *zqp* with reference to יְדָן).

If so, we might say that the modern flat, emphatic pronunciation of ⁺*Marya* in the speech of the Assyrian Christians of Urmi³⁴ is but the modern synharmonic reflex of the festive *zqāfā* vowel *ā* of old—both give added phonological expression to the sanctity of the Divine Name, i.e., Mother of Christ, already singled out by its conservative trilateral morphology.

‘Emphasis’ almost inevitably brings with it backed vowels. The velarised consonants and their concomitant retracted vowels are so intimately connected that scholars have often hesitated as to whether the phonological signal lies primarily in the consonants, in the vowels, or belongs equally to both (‘synharmonism’). Whatever the case, there is no doubt that the two go together and are in many respects two complementary sides of a single coin. Accordingly, backed vowels may be applied in order to produce an effect similar to the heightened expressive velarisation of Arabic *ʿallāh*. This is what seems to occur in the Hebrew reading tradition of the Jews of Cochin, Kerala (India), where the use of back vowels, especially of festive *qamets*, is used to enhance emotionally charged passages, e.g., when reading from the Scroll of Esther and the Passover *Haggada* (Forsström 2013, 462 and cf. Khan 2013, 346; Maman 2016, 221; for festive *qamets* in Biblical Hebrew, cf. above fn. 22). A similar affective function of back pronunciation has been held to account for the absence of a vocative form of ‘God’ in pagan Greek and Latin, in which the

³⁴ Note also *Marya* (with emphatic *r*) given for Christian NENA by Mutzafi (2014, 187).

expected vocative has been replaced by the respective nominative forms $\acute{o}$ θεός and *deus*. In order to address the deity, the ‘tiefe Stimmlage’ of the back case-vowel of $\acute{o}$ θεός was preferred to the thin front vowel of the vocative θεέ. The latter paradigm form is attested, but is marginal, apparently because it lacked sufficient solemnity for ritual use. This Greek usage, rooted in ancient cultic practice, was then followed by Latin *deus* (Havers 1931, 198–99 and the relevant literature on p. 268; Blass and Debrunner 1961, §147[3]).

Prominence to a sacred concept may also be imparted by the use of archaism; i.e., instead of introducing a novelty of orthography (e.g., ‘G-d’ incompletely written) or pronunciation (e.g., *ʿallāh* with added velarisation), a similar effect may be achieved by retaining an old or obsolete form. In Biblical Hebrew a sacred morphological archaism has been noticed in the book of Jeremiah. Jeremiah uses both short and long forms of the 1st person singular pronoun ‘I’, viz. אנִי and אֶנֶכִי, respectively. The distribution, however, is not arbitrary: when God is speaking, it is the fuller form אֶנֶכִי that is used (Hornkohl 2016, 36).³⁵ It is such deliberate archaism that lies behind the aforementioned use in the Dead Sea Scrolls of palaeo-Hebrew script for writing the Tetragrammaton.

The use of archaism in order to distinguish between profane and divine may also be given phonological expression. A well-established case in the Hebrew Bible is the oath formula

³⁵ Note that אֶנֶכִי (unlike changeable אֲנִי ~ אֵנִי) has a stable *qamets* in both context and pause.

opening with ח. This idiom is regularly pointed with *šere* in secular contexts: חַי פַּרְעֹה *ḥē par'ō* 'as Pharaoh liveth' (Gen. 42.15), but with *pataḥ* when the reference is to the Deity:³⁶ חַי הָאֱלֹהִים 'as God liveth' (2 Sam. 2.27). The two usages occur side by side in חַי־יְהוָה וְחַי נַפְשְׁךָ 'as the Lord liveth, and as thy soul liveth' (1 Sam. 20.3). Such use of marked archaic pronunciation in order impart distinctiveness to sacred names is common to many cultures, e.g., the fricative pronunciation [ɣ/x] of Russian *г* in forms of *Бог* 'God' and *Господь* 'Lord' and the ultimate stress of אֱלֹהִים and אֲדֹנִי in Ashkenazi Hebrew (Hommel 1917, 16).

A case of sacred phonetic archaism can be observed in both Christian and Jewish dialects of Neo-Aramaic. In the daily vernacular most Neo-Aramaic dialects have typically shifted **ḥ* to *x*. In the official, sacred vocabulary of religious life, however, much of which is naturally borrowed from classical Syriac or Hebrew, the original *ḥ* (and ܚ) may be retained (or re-introduced?). This is particularly true of dialects of the *fellihi* type spoken in the area of the Mosul plain. In these dialects, in which pharyngeal *ḥ* is part

³⁶ For this 'rabbinical refinement', see, e.g., GKC (270 fn. 1, 472 fn. 1). The diphthong of **ḥayy* was regularly preserved in the combination **ḥayy yhwḥ* and from there transferred to other sacred cases "in dogmatischen Interesse" (Bergsträsser 1918, 99) or as a "masoretische Finesse" (Bauer and Leander 1922, 204 fn. 3). For further details see Greenberg (1957) and Blau (1983, 79 [= Blau 1996, 194]). Similar sacred versus profane variants of this word occur in certain Yemenite reading traditions of Aramaic in which ܚܝܝܐ *ḥayyā* with dagesh applies to God, whereas ܚܝܐ *ḥayā* without dagesh is used with reference to created beings (Morag 1962, 189–90 [= Morag 2003, 268–69]); cf. the Yemenite hesitation at Lev. 13.14 in the reading of Targum Onqelos.

of the phonemic inventory,³⁷ there thus arises an audible contrast in the reflex of **ḥ* between the vernacular and religious registers.³⁸ This may be illustrated by the root מ"ש *mšḥ*. The word for ‘Messiah’ is pronounced with *ḥ*: *mšīḥa*. This *ḥ* marks the word as special; its elevated, spiritual meaning is underlined by its distinctive non-vernacular phonology. It is interesting to examine other derivatives of the same root, viz. the verb ‘anoint’ and the noun ‘oil’. The following table reveals only a sampling of the facts (which in any case may be somewhat fluid):

³⁷ The presence of *ḥ* (and ʿ) in such dialects is certainly connected with their proximity to Arabic; thus Maclean (1895, 316).

³⁸ For a similar (and far more pervasive) situation in Arabic see Holes (2004, 68–69, and many other places throughout the book, especially ch. 9 “Language Level”).

	‘Messiah’	‘anoint’	‘oil’
Yasso (1994)	<i>mšh</i>	<i>mšh</i>	<i>mšh</i>
Alqosh ³⁹	<i>mšh</i>	?	<i>mšh</i>
Rhétoré (1912) ⁴⁰	<i>mšh</i>	?	<i>mšx</i>
Aradhin ⁴¹	<i>mšh</i>	<i>mšh</i>	<i>mšx</i>
Qaraqosh ⁴²	<i>mšh</i> ~ <i>mšx</i>	<i>mšh</i>	<i>mšx</i>
J. Zakho ⁴³	<i>mšh</i>	<i>mšx</i>	<i>mšx</i>

The table shows two contrary influences at work in the words for ‘anoint’ and ‘oil’: on the one hand, the transparent association with the *mšh* root of ‘Messiah’ leads to generalisation of *h* across the board (possibly reflecting a purist tendency); on the other hand, normal vernacular usage favours *x*. The verb ‘anoint’ shares in the holiness of ‘Messiah’, viz. ‘the Anointed’, and by religious association is very likely to be pronounced with *h* too. This is much less so with ‘oil, butter’, which is associated more with the kitchen than the church. Its lower degree of sanctity is reflected by the *x* with which it is mostly pronounced.

³⁹ *Mšiḥa* ‘Messiah’ (Coghill 2003, 22, 213) and *mešhez-zeṯe* ‘olive oil’ (329 Text A §101).

⁴⁰ *Mchiḥa* ‘le Christ’ (Rhétoré 1912, 12–13) versus *mechkha* ‘huile’ (11).

⁴¹ *Mšiḥa* ‘Messiah’ (Krotkoff 1982, 138 ult.) versus *mišxa* ‘clarified butter’ (137). For the verb ‘anoint’, the glossary (138) has *mšaxa*, but this might be a mistake, for the textual example (98 §92) has *mšh*. On the other hand, it is quite possible that usage is not stable and that *h* and *x* here alternate.

⁴² Khan (2002, 41) has the expected *mšiḥa*, but the glossary (738) gives *mšiḥa* ~ *mšixa*; the word for ‘oil’ is *mšxa* (738). The verb ‘anoint’ is *mšh* (*mšh* in the glossary of verbs [717] seems to be a slip).

⁴³ Sabar (2002, 226a).

The main point is that the sacred Christian or Jewish ‘Messiah’ will (if possible⁴⁴) be pronounced with archaising *ḥ*, a sound typifying the sacred register of religious vocabulary, whereas other derivatives of the same root are liable to be pronounced with *x*. In this way *mšīḥa* ‘Messiah’ (and similar classicisms of religious import) acquires a phonological distinctiveness which marks its status as a significant sacred word. In dialects beyond the reach of Arabic, whose speakers do not possess the ability to pronounce *ḥ*, ‘Messiah’ undergoes the regular vernacular treatment and is pronounced *mšixa* with *x*, thus remaining phonologically unmarked. Among such non-differentiating *mšixa* dialects are those of the uprooted Assyrians resettled in the Khabur area in northeastern Syria (Talay 2008-2009, I:82 fn. 141) and the Assyrian Christians of Urmi.

3.0. Conclusion

These desultory notes, offered in grateful admiration to my friend Geoffrey Khan, are intended to show that the well-known ancient Jewish aversion to explicit writing and utterance of the Tetragrammaton is part of a larger picture, extending to modern times. That picture involves the pronunciation of sacred names, which

⁴⁴ Pharyngeal *ḥ*, however, is not always possible. Sinha (2000, 190 fn. 61) records for the dialect of Bēšpən *mšīḥa* ~ *mšīha* (*sic*). Speakers of the dialect of Sat have only the latter: *mšīha* (Mutzafi 2008b, 24). That the realisation of **ḥ* in these cases is [h] and not pharyngeal [ḥ] does not alter the marked status of *mšīha*—the point is that the secular reflex *x* is avoided. For the pronunciation of **ḥ* as [h] cf. Maclean (1895, 317); Rhétoré (1912, 13 fn. 1).

in several cultures are liable to be marked by deliberately distinctive phonology, imbuing them with an audible aura of sanctity. This sacred distinctiveness takes on different (sometimes overlapping) forms; examples have been given of the special use of interdental, velarisation of consonants, back vowels (festive *qamets*), and phonological archaism.

The association of heightened meaning with a special sound pattern belongs to the phenomenon of sound symbolism (*Lautsymbolik*). This subject has been treated by our honoured friend and colleague in his recent *magnum opus* (תרתי משמע) on the language of the Assyrian Christians of Urmi (Khan 2016, I:178–86, especially 178–80). There it is shown how the presence or absence of suprasegmental emphasis may affect the semantics of what are genetically the ‘same’ words. The motivation for plain or emphatic pronunciation is not always etymological; it may also have a psychological cause. Emphatic consonants with their concomitant back vowels may heighten, amplify, or specify the meaning: general *marta* ‘owner (F), mistress’ versus the particular proper name ⁺*Marta* ‘Martha’ (Luke 10.38, etc.) (Khan 2016, I:51; III:211);⁴⁵ *štx* ‘spread out’ (e.g., washing on the line) versus the stronger action ⁺*štx* ‘flatten somebody out, render him supine’ (Khan 2016, I:112–13, 178–79, III:292, 299). Conversely, the absence or removal of emphatic pronunciation may have just the opposite effect, connoting diminution, delicacy, endearment, etc.

⁴⁵ Cf. the aforementioned (fn. 31) profane *mara* versus holy ⁺*Maran*, ⁺*Marya*.

The details given in the preceding discussion are documented in different ways: those of Biblical Hebrew, especially in its Tiberian transmission, have written representation (יְדִאֲ), are systematically applied (*qere perpetuum*), and are backed by ancient authoritative Masoretic tradition. This applies in principle also to Arabic *ʿallāh*, the pronunciation of which (although lacking formal graphic expression) is bound by consistent conventions, formulated in Arabic philological literature and ubiquitously observed in Islamic life. Such uniformity applies in a far lesser degree to the unwritten living pronunciation traditions of Hebrew (Baghdad יְדִאֲ) and to various features of Neo-Semitic languages (*Mḥammad*). These are mostly known from modern oral sources and in their application considerable variety obtains: not every Jewish community pronounces יְדִאֲ with interdental *ḏ* (ḏ) and most Arabic dialects seem not to apply differentiating velarisation to the name of the Prophet Muḥammad. Modes of documentation and differences in distribution apart, all these phenomena have a common denominator: the investment of sacred names with special, distinctive pronunciation.

References

- Ambros, Arne A. 1981. 'Zur Entstehung der Emphase in *Allāh*'. *Wiener Zeitschrift für die Kunde des Morgenlandes* 73: 23–32.
- Bauer, Hans, and Pontus Leander. 1922. *Historische Grammatik der hebräischen Sprache des Alten Testaments*. Halle: Max Niemeyer.
- . 1927. *Grammatik des Biblisch-Aramäischen*. Halle: Max Niemeyer.

- Bergsträsser, Gotthelf. 1918. *Hebräische Grammatik*. Vol. 1: *Einleitung, Schrift- und Lautlehre* (= Wilhelm Gesenius' hebrä-ische Grammatik. 29. Auflage). Leipzig: F.C.W. Vogel.
- Berliner, Abraham. 1879. *Beiträge zur hebräischen Grammatik im Talmud un Midrasch*. Berlin: Julius Benzian.
- Birnbaum, Salomo. 1922. *Das hebräische und aramäische Element in der jiddischen Sprache*. Kirchain N.-L.: Zahn & Baendel.
- Blanc, Haim. 1964. *Communal Dialects in Baghdad*. Harvard Middle Eastern Monographs 10. Cambridge, MA: Harvard University Press.
- Blass, Friedrich, and Albert Debrunner. 1961. *A Greek Grammar of the New Testament and Other Early Christian Literature*. Translated by Robert W. Funk. Chicago: The University of Chicago Press.
- Blau, Joshua. 1972. 'Arabic Lexicographical Miscellanies'. *Journal of Semitic Studies* 17: 173–90 (reprint with Addenda in Blau 1988, 330–48).
- . 1983. 'Le-Veruran shel Maqbilot 'Arviyot le-'Oṣar ha-Milim ha-Miqra'i'. In *Hebrew Language Studies, Presented to Professor Zeev Ben-Ḥayyim*, edited by M. Bar-Asher, A. Dotan, G. B. Sarfatti, D. Téné, 67–82. Jerusalem: The Magnes Press, The Hebrew University of Jerusalem (reprinted in Blau 1996, 182–97).
- . 1988. *Studies in Middle Arabic and its Judaeo-Arabic Variety*. Jerusalem: Magnes Press, The Hebrew University.
- . 1996. *Studies in Hebrew Linguistics*. Jerusalem: The Magnes Press, The Hebrew University. [Hebrew]

- Blau, Joshua, and Simon Hopkins. 2017. *Early Judaeo-Arabic in Phonetic Spelling: Texts from the End of the First Millennium. Part I. General Introduction and Biblical Texts: Glossaries, Translations, Commentaries, and Discussions*. Jerusalem: Yad Ben-Zvi. [Hebrew]
- Borg, Alexander. 2001. 'Encoding the Boundary Between the Secular and the Sacred: A Phonological Note on the Prophet's Name in the Dialect of the Negev and Sinai Bedouin'. In *Linguistic and Cultural Studies on Arabic and Hebrew: Essays Presented to Professor Moshe Piamenta for his Eightieth Birthday*, edited by J. Rosenhouse and A. Elad-Bouskila, 49–59. Wiesbaden: Harrassowitz.
- Brockelmann, Carl. 1908–1913. *Grundriss der vergleichenden Grammatik der semitischen Sprachen*. 2 vols. Berlin: Reuther & Reichard.
- Brunot, Louis, and Elie Malka. 1940. *Glossaire judéo-arabe de Fès*. Rabat: École du Livre.
- Bunis, David. 2021. 'Judezmo/Ladino/Judeo-Spanish'. In *Jewish Languages*, edited by Lutz Edzard and Ofra Tirosh-Becker, 392–481. Wiesbaden: Harrassowitz.
- Burkitt, F. Crawford. 1897. *Fragments of the Books of Kings According to the Translation of Aquila*. Cambridge: Cambridge University Press.
- Butbul, Sagit, and Simon Hopkins. 2024. *Dapim Ḥadashim shel Targum 'Aravi-Yehudi Qadum le-Sefer Bereshit*. In "An Inspired Man": *Studies in Judeo-Arabic Culture—Dedicated to the Memory of Joshua Blau*, edited by M. Frenkel and P. I. Lieberman, 3–51. Leiden and Boston: Brill.

- Cantineau, Jean. 1960. *Cours de phonétique arabe*. Paris: Librairie C. Klincksieck (first published Algiers, 1941).
- Coghill, Eleanor. 2003. 'The Neo-Aramaic Dialect of Alqosh'. PhD dissertation, University of Cambridge.
- Cohen, Israel. 1925. *The Journal of a Jewish Traveller*. London: John Lane, The Bodley Head Limited.
- Cohen, Marcel. 1912. *Le parler arabe des juifs d'Alger*. Paris: H. Champion.
- Dalman, Gustaf. 1905. *Grammatik des jüdisch-palästinischen Aramäisch*. 2nd edition. Leipzig: J.C. Hinrichs'sche Buchhandlung.
- Destaing, E. 1937. *Textes arabes en parler des Chleuhs du Sous (Maroc): Transcription, traduction, glossaire*. Paris: Imprimerie Nationale.
- Elihay, J. (Yohanan). ca 2005. *The Olive Tree Dictionary*. Jerusalem: Minerva.
- Ewald, Heinrich. 1870. *Ausführliches Lehrbuch der hebräischen Sprache des Alten Bundes*. 8th edition. Göttingen: Dieterich.
- Fassberg, Steven E. 2015. 'לְהוֹיָא and Related Verbal Forms in Biblical and Qumran Aramaic in the Light of Aramaic Dialectology'. In *In Memoriam John Strugnell: Four Studies*, edited by Marcel Sigrist and Kevin Stephens, 7–18. Cahiers de la Revue Biblique 84. Pendé: Gabalda.
- Feghali, Michel T. 1919. *Le parler de Kfar'abîda (Liban-Syrie): Essai linguistique sur la phonétique et la morphologie d'un parler arabe moderne*. Paris: E. Leroux.
- Ferguson, Charles A. 1956. 'The Emphatic *l* in Arabic'. *Language* 32: 446–52.

- Fischer, Wolfdietrich, and Otto Jastrow (eds). 1980. *Handbuch der arabischen Dialekte*. Wiesbaden: Harrassowitz.
- Fleischer, Ezra. 1971–1972. ‘An Ancient Grammatical Term in a Poem by Qillir’. *Leshonenu* 36: 263–67. [Hebrew]
- Forsström, Jarmo. 2013. ‘Kerala, Pronunciation Tradition’. In *Encyclopedia of Hebrew Language and Linguistics*, edited by Geoffrey Khan et al., II:460–63. Leiden and Boston: Brill.
- Fox, Joshua. 2003. *Semitic Noun Patterns*. Winona Lake, IN: Eisenbrauns.
- Gesenius, Wilhelm. 1829–1858. *Thesaurus Philologicus Criticus Linguae Hebraeae et Chaldaee Veteris Testamenti*. Leipzig: C.W. Vogel.
- GKC = Kautzsch, Emil (ed.). 1910. *Gesenius’ Hebrew Grammar*. Translated by Arthur E. Cowley. Oxford: Clarendon.
- Greenberg, Moshe. 1957. ‘The Hebrew Oath Particle *ḥay/ḥē*’. *Journal of Biblical Literature* 76: 34–39.
- Grünbaum, Max. 1882. *Jüdischdeutsche Chrestomathie*. Leipzig: F.A. Brockhaus.
- Havers, Wilhelm. 1931. *Handbuch der erklärenden Syntax: Ein Versuch zur Erforschung der Bedingungen und Triebkräfte in Syntax und Stilistik*. Indogermanische Bibliothek 20. Heidelberg: C. Winter.
- Henshke, Yehudit. 2007. *Hebrew Elements in Daily Speech: A Grammatical Study and Lexicon of the Hebrew Component of Tunisian Judeo-Arabic*. Jerusalem: Bialik Institute. [Hebrew]

- Hoerning, Reinhart. 1889. *Descriptions and Collation of Six Karaite Manuscripts of Portions of the Hebrew Bible in Arabic Characters*. London: Williams and Norgate.
- Holes, Clive. 2004. *Modern Arabic: Structures, Functions, and Varieties*. Revised edition. Georgetown Classics in Arabic Language and Linguistics. Washington, D.C.: Georgetown University Press.
- Hommel, Eberhard. 1917. *Untersuchungen zur hebräischen Lautlehre*. Part 1: *Der Akzent des Hebräischen*. Leipzig: J.C. Hinrichs.
- Hornkohl, Aaron D. 2016. 'Transitional Biblical Hebrew'. In *A Handbook of Biblical Hebrew*, edited by W. Randall Garr and Steven E. Fassberg, I:31–42. Winona Lake, IN: Eisenbrauns.
- Kahle, Paul E. 1959. *The Cairo Geniza*. 2nd edition. Oxford: Basil Blackwell.
- Katz, Ktzia. 1981. *The Hebrew Language Tradition of the Aleppo Community: The Phonology*. Jerusalem: The Hebrew University of Jerusalem. [Hebrew]
- Khan, Geoffrey. 1990. *Karaite Bible Manuscripts from the Cairo Genizah*. Cambridge University Library Genizah Series 9. Cambridge: Cambridge University Press.
- . 2002. *The Neo-Aramaic Dialect of Qaraqosh*. Leiden and Boston: Brill.
- . 2008. *The Neo-Aramaic Dialect of Barwar*. 3 vols. Leiden and Boston: Brill.
- . 2013 'Biblical Hebrew: Pronunciation Traditions'. In *Encyclopedia of Hebrew Language and Linguistics*, edited by Geoffrey Khan et al., I: 341–52. Leiden and Boston: Brill.

- . 2016. *The Neo-Aramaic Dialect of the Assyrian Christians of Urmi*. 4 vols. Leiden and Boston: Brill.
- Kiltz, David. 2012. 'The Relationship between Arabic *Allāh* and Syriac *Allāhā*'. *Der Islam* 88: 33–50.
- Klein, Michael L. 1986. *Genizah Manuscripts of Palestinian Targum to the Pentateuch*. 2 vols. Cincinnati: Hebrew Union College Press.
- König, Fr. Eduard. 1897. *Historisch-comparative Syntax der hebräischen Sprache: Schlusstheil des historisch-kritischen Lehrgebäudes des Hebräischen*. Leipzig: J.C. Hinrichs.
- Krotkoff, Georg. 1982. *A Neo-Aramaic Dialect of Kurdistan: Texts, Grammar, and Vocabulary*. American Oriental Series 64. New Haven, CT: American Oriental Society.
- Leslau, Wolf. 1945–1946. 'Hebrew Elements in the Judeo-Arabic Dialect of Fez'. *Jewish Quarterly Review* (n.s.) 36: 61–78 (reprinted in Leslau 1988, 67–84).
- . 1988. *Fifty Years of Research: Selection of Articles on Semitic, Ethiopian Semitic and Cushitic*. Wiesbaden: Harrassowitz.
- Maclean, Arthur John. 1895. *Grammar of the Dialects of Vernacular Syriac*. Cambridge: Cambridge University Press.
- . 1901. *A Dictionary of the Dialects of Vernacular Syriac*. Oxford: Clarendon.
- Maman, Aharon. 2016. 'Modern Reading Traditions of Biblical Hebrew'. In *A Handbook of Biblical Hebrew*, edited by W. Randall Garr and Steven E. Fassberg, I: 215–27. Winona Lake, IN: Eisenbrauns.

- . 2019. *Synoptic Dictionary of the Hebrew Component in Jewish Languages*. 2nd revised edition. Jerusalem: The Hebrew University of Jerusalem. [Hebrew]
- Mansour, Jacob. 1991. *The Jewish Baghdadi Dialect: Studies and Texts in the Judaeo-Arabic Dialect of Baghdad*. Studies in the History and Culture of Iraqi Jewry 7. Or-Yehuda: Babylonian Jewry Heritage Center, The Institute for Research on Iraqi Jewry.
- Morag, Shelomo. 1962. 'On the Form and Etymology of Hai Ga'on's Name [Hebrew title: חיים = הַאִי]'. *Tarbiz* 31: 188–90 (reprinted with Addenda in Morag 2003, 267–70). [Hebrew]
- (ed.). 1977. *The Hebrew Language Tradition of the Baghdadi Community: The Phonology*. Publications of the Hebrew University Language Traditions Project 1. Jerusalem: Hebrew University Language Traditions Project. [Hebrew]
- . 2003. *Studies in Hebrew, Aramaic and Jewish Languages*. Edited by M. Bar-Asher, Y. Breuer, and A. Maman. Jerusalem: The Hebrew University Magnes Press. [Hebrew]
- Mutzafi, Hezy. 2002. 'Barzani Jewish Neo-Aramaic and Its Dialects'. *Mediterranean Language Review* 14: 41–70.
- . 2004. *The Jewish Neo-Aramaic of Koy Sanjaq*. Wiesbaden: Harrassowitz.
- . 2008a. *The Jewish Neo-Aramaic of Betanure*. Wiesbaden: Harrassowitz.
- . 2008b. 'The Neo-Aramaic Dialect of Sat (Hakkâri, Turkey)'. In *Neo-Aramaic Dialect Studies*, edited by Geoffrey Khan, 19–37. Piscataway, NJ: Gorgias.

- . 2014. *Comparative Lexical Studies in Neo-Mandaic*. Leiden and Boston: Brill.
- Piamenta, Moshe. 1990–1991. *Dictionary of Post-Classical Yemeni Arabic*. Parts 1 and 2. Leiden, New York, Copenhagen, and Cologne: Brill.
- Polotsky, Hans J. 1932. ‘Aramäisch *prš* und das “Huzvaresch”’. *Le Muséon* 45: 273–83 (= Polotsky 1971, 631–41).
- . 1971. *Collected Papers*. Jerusalem: Magnes Press, The Hebrew University of Jerusalem.
- Reif, Stefan C. 1979. *Shabbethai Sofer and His Prayer-book*. Cambridge: Cambridge University Press.
- Rhétoré, Jacques. 1912. *Grammaire de la langue Soureth ou Chaldéen vulgaire selon le dialecte de la plaine de Mossoul et des pays adjacents*. Mosul: Pères Dominicains.
- Ryzhik, Michael. 2021. ‘Judeo-Italian’. In *Jewish Languages*, edited by Lutz Edzard and Ofra Tirosh-Becker, 501–56. Wiesbaden: Harrassowitz.
- Sabar, Yona. 1974–1975. ‘The Hebrew Elements in the Aramaic Dialects of the Jews of Azerbaijan’. *Leshonenu* 39: 272–94. [Hebrew]
- . 1976. *Pəšaṭ Wayəḥî Bəšallah: A Neo-Aramaic Midrash on Beshallah (Exodus): Introduction, Phonetic Transcription, Translation, Notes, and Glossary*. Wiesbaden: Harrassowitz.
- . 1984. *Homilies in the Neo-Aramaic of the Kurdistan Jews on the Parashot Wayḥî, Beshallah and Yitro: Edition, Hebrew Translation, and Introduction*. Jerusalem: Israel Academy of Sciences and Humanities. [Hebrew]

- . 1991. *Targum de-Targum: An Old Neo-Aramaic Version of the Targum on Song of Songs: Introduction, Eclectic Text, English Translation, Comparative Notes, and Glossary*. Wiesbaden: Harrassowitz.
- . 2002. *A Jewish Neo-Aramaic Dictionary*. Wiesbaden: Harrassowitz.
- Sarfatti, Gad B. 2001. *Semantic Aspects of Hebrew*. Jerusalem: The Academy of the Hebrew Language. [Hebrew]
- Sharvit, Shimon. 2008. 'Jewish Traditions of Writing and Pronouncing Divine Names'. *Leshonenu* 70: 599–614. [Hebrew]
- Shawarba, Musa. 2012. *A Grammar of Negev Arabic: Comparative Studies, Texts and Glossary in the Bedouin Dialect of the 'Azāzmih Tribe*. Wiesbaden: Harrassowitz.
- Sinha, Jasmin. 2000. *Der neuostaramäische Dialekt von Bēṣpān (Provinz Mardin, Südosttürkei): Eine grammatische Darstellung*. Wiesbaden: Harrassowitz.
- Spitaler, Anton. 1938. *Grammatik des neuaramäischen Dialekts von Ma'lūla (Antilibanon)*. Leipzig: Deutsche Morgenländische Gesellschaft.
- Steinschneider, Moritz. 1895–1896. 'Miscelle. 37. Abbraviatur des Tetragrammaton durch drei Yod'. *Monatschrift für Geschichte und Wissenschaft des Judenthums* 40: 130–34.
- Tal, Abraham. 2000. *A Dictionary of Samaritan Aramaic*. 2 vols. Leiden, Boston, and Cologne: Brill.
- Talay, Shabo. 2008–2009. *Die neuaramäischen Dialekte der Khabur-Assyrer in Nordostsyrien*. 2 vols. Wiesbaden: Harrassowitz.

- Taylor, Charles. 1900. *Hebrew-Greek Cairo Genizah Palimpsests from the Taylor-Schechter Collection*. Cambridge: Cambridge University Press.
- Tov, Emanuel. 2004. *Scribal Practices and Approaches Reflected in the Texts Found in the Judean Desert*. Leiden and Boston: Brill.
- Wieder, Naphtali. 1962. *The Judean Scrolls and Karaism*. London: East and West Library.
- Yasso, Rev. Jacob O. 1994. *Engaliyon Qaddisha d Maran Isho' Mshiha*. Royal Oak: Aramaic Bible Translation, Inc.
- Yeivin, Israel. 1985. *The Hebrew Language Tradition as Reflected in the Babylonian Vocalization*. 2 vols. Jerusalem: The Academy of the Hebrew Language. [Hebrew]
- Yoda, Sumikazu. 2005. *The Arabic Dialect of the Jews of Tripoli (Libya)*. Wiesbaden: Harrassowitz.

THE SHAPE OF THE TEEN NUMERALS IN CENTRAL SEMITIC*

Benjamin D. Suchard

The numerals ‘eleven’–‘nineteen’ are the closest thing many Semitic languages have to nominal compounds. While the semantic connection to the numerals ‘one’–‘nine’ (henceforth: *digits*), on the one hand, and to ‘ten’, on the other hand, is clear, these teen numerals behave like single words in many respects, often undergoing unique sound changes and reductions, while sometimes preserving archaisms that have been lost elsewhere. As such, they furnish an interesting opportunity for linguistic reconstruction.

The topic of this paper is the reconstruction of the teen numerals as found in Central Semitic, defined as Northwest Semitic—Canaanite, Aramaic, Ugaritic, and their closest relatives—Arabic, and Sabaic (cf. Huehnergard and Pat-El 2019).¹ Unlike

* It is a great pleasure to dedicate this study, which is largely based on data from Arabic, Aramaic, and Biblical Hebrew, to Geoffrey Khan, whose work has incomparably advanced the study of these languages. I thank Marijn van Putten for his helpful comments on an earlier draft, as well as the anonymous reviewers and volume editors. All remaining errors are my own.

¹ The other Ancient South Arabian languages, viz. Minaic, Qatabanic, and Hadramitic, are also usually included. But they do not attest the **yaqtul-u* imperfect that is the key isogloss defining Central Semitic

other languages, Central Semitic forms its teens numerals in a digit-teen order with both the digit and the ‘teen’ word inflecting for gender (with some exceptions). I am not entirely convinced of Central Semitic as a genetic subfamily of Semitic, as the shared innovations characterising the group are limited (see the balanced discussion in Kogan 2015, 130–226). Hence, I have avoided the use of terms like ‘Proto-Central-Semitic’, leaving room for alternative scenarios, such as areal diffusion or the Central Semitic languages preserving the Proto-Semitic situation as far as the teen numerals are concerned.

We shall consider the reconstruction of the teen numerals in three steps, starting with the stems of the digits and of ‘one’ in particular, followed by the endings of both the digits and the ‘teen’ words, and, finally, the shape of the ‘teen’ words themselves, especially the feminine.

1.0. The Digit Stems

The reconstruction of the numeral stems ‘three’–‘nine’ is mostly uncontroversial (cf. Huehnergard 2019, 61).² Within Central Semitic, the digits used in the numerals ‘thirteen’–‘nineteen’ show

(Van der Poel 2022) and it has not been established that Ancient South Arabian forms a genetic grouping, in which case they would be admitted based on Sabaic’s credentials. In any case, they barely attest any forms that are relevant for our purposes here.

² Huehnergard reconstructs ‘three’ as **θalāθ*- instead of **śalāθ*-, the reconstruction I follow here. I prefer to explain forms with initial **θ* in Arabic and Northwest Semitic as resulting from complete assimilation to the stem-final **θ*; contamination of the initial **θ* of the preceding

the same forms as the corresponding numerals below ‘ten’. This includes the use of the feminine suffix **(a)t-* with the masculine instead of the feminine (‘chiastic concord’).³ For the reconstructed forms, see Table 1 at the end of this section.

The numeral ‘two’ should be reconstructed with a word-initial consonant cluster **θn-* in the masculine (Testen 1985). This is evidenced by the shift of **n > r* in this word in Aramaic (**θr-ēn*) and Modern South Arabian (e.g., Omani Mehri *θr-ōh*), the presence of a prothetic vowel with *hamzat al-waṣl* in Classical Arabic (*iθn-ā-ni*), and the lack of pretonic lengthening in Biblical Hebrew (*šn-áyim*; Suchard 2019, 42).

In the feminine, Arabic attests two forms, *iθn-at-ā-ni* and *θin-t-ā-ni*, which go back to the stems **θn-at-* and **θin-t-*, respectively. The former matches Aramaic **θr-at-ēn > e.g.*, Biblical Aramaic *tartēn*, with metathesis of **ra > ar*. The latter matches

numeral, ‘two’, may also have played a role. The alternative is to explain forms with initial **ś*, as in Ge‘ez and Modern South Arabian, through dissimilation from the second **θ* and/or partial assimilation to the **l*. This seems less likely, considering the historical attestation of the change from *ślθ* to *θlθ* in Sabaic (forms retrieved through the online Corpus of South Arabian Inscriptions, <https://dasi.cnr.it>).

³ Chiastic concord has been given up in Ugaritic prose: the unsuffixed, historically feminine form is used for both genders. The originally masculine forms in *-t* have been repurposed and are used only when counting shekels or days, when the word ‘shekels’ or ‘day(s)’ is elided. This holds for the independent digits, the digits in the teens, and the ‘-teen’ word itself (Tropper 2000, §§69.133, 143). In ‘twelve’, the masculine digit stem *tn* has been generalised to both genders (Tropper 2000, §62.22).

Ugaritic *tt* and Biblical Hebrew *št-áyim*, resulting from contraction of **šitt-áyim* (Bravmann 1952; Suchard 2019, 243; Khan 2020, 1:327–30). The form **θin-t-* may be more original, with **θn-at-* being modelled after the masculine, or **θin-t-* may have developed from earlier **θn-t-* through vowel epenthesis. The variable presence of **i* before the stem-final consonant is also seen in ‘five’:⁴ contrast Classical Arabic *ḥams(-at)-* with Biblical Hebrew *ḥāmēš*, *ḥāmišš-ā*. As with ‘two (F)’, this interchange may relate to the variation between **-t-* and **-at-*, the two forms of the feminine suffix, whose original distribution is yet to be determined.

While most West Semitic languages use the numeral **ʾaḥad-* ‘one’ as the digit in ‘eleven’, as in Biblical Hebrew *ʾaḥad ʿāśār*, the latter language also attests another morpheme. This is used in both the masculine, *ʿaštē ʿāśār*, and the feminine, *ʿaštē ʿśrē*. Ugaritic similarly attests both *ʿšt ʿšr* and *ʿšt ʿšrh*, as well as two instances of *ʿšt ʿšrt*. Ugaritic also has one attestation of *ʿšty* as ‘one’, apparently feminine, without a following ‘teen’ word. It has long been clear that these forms are related to Akkadian *ištēn* (M), *išteat* (F), as well as Sabaic *ʿs¹tn-m*, used only in dates (Stein 2011, 1052; also attested once in Qatabanic and, as *ʿs¹t*, in an unclear context in Minaic). Wilson-Wright (2014) convincingly argues that this lexeme represents the basic Proto-Semitic numeral ‘one’. The more common **ʾaḥad-* is not originally a numeral, but an adjective meaning ‘alone, sole’. The Hebrew and Ugaritic forms

⁴ Also in ‘six’ if Geʿez *sədas-t-* (M) and Akkadian *šediš* (F) are taken into account. Only the form without **i* is unambiguously attested in Central Semitic.

of ‘eleven’ mentioned above are thus archaic, having resisted the intrusion of **ʾaḥad-* into the numeral system. Based on the distribution in Ugaritic and Sabaic, the original word may have remained in use in Central Semitic when ‘one’ was substantivised and occurred without a governing noun, similar to the German distinction between *eins* and *ein*. A new distinction of this kind also arose in Classical Arabic after *ʾaḥad-* had ousted the Proto-Semitic word completely, only to be limited to substantivised contexts itself while ceding the attributive contexts to innovative *wāḥid-*.

Wilson-Wright reconstructs the original numeral ‘one’ as **ʿast-*, feminine **ʿast-ay-*, without providing any arguments for the vocalism. The **a* vowel is supported by Hebrew and possibly by Hurrian *ašt*, if this represents a borrowing from Semitic (Wilson-Wright 2014, 3 fn. 6). On the other hand, Akkadian attests an *i* that Wilson-Wright is hard pressed to explain. An *i* is also found in Arabic **iḥd-ay-*, which Wilson-Wright ingeniously suggests was patterned after the older numeral, as far as the feminine suffix **-ay-* is concerned (see also Sabaic *ʾḥdy*). All these forms are most easily reconciled by positing **ʿist-*, not **ʿast-*, as the stem. The Akkadian forms regularly derive from **ʿist-ān-* and **ʿist-ay-*, showing the same alternation between masculine **-ān-* and feminine **-ay-* as Classical Arabic adjectives like *ḡawʿ-ān-* (M), *ḡawʿ-ā* < **ḡawʿ-ay-* (F) ‘hungry’; the feminine then added a redundant suffix **-at-*, as also suggested by Wilson-Wright. The Sabaic and Qatabanic masculine forms similarly reflect **ʿist-ān-*. In Arabic and possibly Sabaic, the pattern of feminine **ʿist-ay-* was

retained, but the productive root replaced the archaic one, yielding **ʾiḥd-ay-* > Classical Arabic *ʾiḥd-ā*. In Hebrew, and perhaps in the source language of Hurrian *ašt*, the *a* vowel is then best explained as an ad hoc assimilation to the preceding pharyngeal. This leaves us with the reconstructed stems given in Table 1.

Table 1. The reconstructed Central Semitic digit stems, ‘one’–‘nine’

meaning	masculine	feminine
‘one’	* <i>ʿist-ān-</i>	* <i>ʿist-ay-</i>
‘two’	* <i>θn-</i>	* <i>θ(i)n-(a)t-</i>
‘three’	* <i>šalāθ-(a)t-</i>	* <i>šalāθ-</i>
‘four’	* <i>ʾarbaʿ-(a)t-</i>	* <i>ʾarbaʿ-</i>
‘five’	* <i>ḥam(i)s-(a)t-</i>	* <i>ḥam(i)s-</i>
‘six’	* <i>sidθ-at-</i>	* <i>sidθ-</i>
‘seven’	* <i>sabʿ-at-</i>	* <i>sabʿ-</i>
‘eight’	* <i>θamāniy-at-</i>	* <i>θamāniy-</i>
‘nine’	* <i>tisʿ-at-</i>	* <i>tisʿ-</i>

2.0. The Endings

In the numeral ‘twelve’, the digit ‘two’ should be reconstructed without nunation or mimation, terminating in a case ending. This is clear from Classical Arabic *iθn-ā/ay* ‘*ašar-a*, *iθnat-ā/ay* ‘*ašrat-a*, Ugaritic *tn* ‘*šr*, *tn* ‘*šrh*, Aramaic forms like Biblical Aramaic *trē* ‘*āšar*, Sabaic *tn-y* ‘*s²r*, and Biblical Hebrew *šnē* ‘*āšār*, *štē* ‘*ešrē*. The more common Hebrew forms *šnēm* ‘*āšār* and *štēm* ‘*ešrē* are modelled after *šnáyim*, *štáyim* ‘two’, with a different outcome of the diphthong **ay* in unstressed position. It is unclear whether a case distinction like that found in Arabic should be reconstructed, as it is lacking from the other teens.

‘Eleven’ and ‘thirteen’–‘nineteen’ have an uninflecting *-a* on both the digit and the ‘teen’ word in Arabic. According to Hetzron (1977), this shows that the digit-teen order is a late innovation, replacing the ten-and-digit order found in languages like Ge‘ez. More recently, scholars have preferred to identify uninflecting **-a* in several other forms and constructions as an archaism (e.g., Hasselbach 2013, 47). In the teen numerals, Arabic may similarly preserve an old construction in isolation from the rest of the case system.

A difference between the teens and the lower numerals in some languages is that nouns counted by a teen numeral may occur in the singular instead of the plural, e.g., Biblical Hebrew *’arba’* ‘*’ēsrē šānā*’ ‘fourteen years’ (Gen. 37.41). In Classical Arabic, this is the rule. The counted noun in such phrases occurs in the accusative, e.g., *iθn-ā* ‘*ašar-a šahr-an*’ ‘twelve months’ (Q 9.36), *iθnat-ā* ‘*ašrat-a ‘ayn-an*’ ‘twelve springs’ (Q 2.60); note that both examples occur in a context where the nominative is expected, as confirmed by the digits’ *-ā* ending. In other constructions, the accusative can be used to form adverbial phrases. This adverbial use probably also underlies the accusative in teen numeral constructions (cf. Joüon and Muraoka 2006, §127b).

Meanwhile, the *-a* ending is formally identical to the Proto-Semitic third person masculine singular stative ending as seen in the West Semitic Perfect **qaṭal-a*. The stative meaning is still seen, for instance, in Biblical Hebrew forms like *kāḇēd* < **kabid-a* ‘it (M) is heavy’. But this ending is probably also the source of the *-a* seen in Classical Arabic negated phrases of existence such as *lā ’ilāh-a* ‘there is no god’, *lā šakk-a* ‘(there is) no doubt’, etc.

In this construction, *-a* is synchronically best analysed as the accusative construct state ending.⁵ It also occurs following the feminine suffix *-at-*, just as in the teens. If we assume that it retains its inherited stative meaning in the teen numerals, an expression like *ʾaḥad-a ʾašar-a kawkab-an* ‘eleven stars’ (Q 12.4) could be understood literally as ‘it is one-ten, star-wise’. The preservation of marginal uses of the accusative in this construction argues for its antiquity.

The presence of **-a* on the teens is confirmed by Syriac. There, an unexpected *-a-* occurs between the digit and the ‘teen’ word, both in masculine forms, like *ḥdaʿsar* ‘eleven’, *tloṭaʿsar* ‘thirteen’, *arbaʿtaʿsar* ‘fourteen’, and feminine ones, like *ḥdaʿ(e)sre*, *tloṭaʿ(e)sre* (forms, transcribed here according to West Syriac pronunciation, taken from Nöldeke 1904). While these are but some of the teen numerals’ many different attested forms, the *-a-* following the digit is a constant (excepting the forms of ‘fourteen’, ‘seventeen’, and ‘nineteen’, where it would come between two instances of ʿ; these forms, like *arbaʿ(e)sre*, arose from forms like **arbʿaʿ(e)sre* through haplology). This *-a-* is unlikely to be an epenthetic vowel, as a straightforward digit-teen combination like ***ḥad-ʿsar* would be permissible according to the rules of Syriac syllable structure. In the masculine, a reconstruction matching Classical Arabic would produce exactly these forms according to the regular Aramaic rules of word stress and vowel

⁵ Fischer (1972, §318) cites the examples *lā laḏḏāt-i li-š-šibi* ‘there are no pleasures for old men’ and *lā ʾab-ā laka* ‘may you have no father!’, both of which show accusative construct endings other than *-a*.

reduction, e.g., $*'aḥad-a \ 'aśar-a > *ḥada'aśār > ḥda'sar$; $*'arba'(a)t-a \ 'aśar-a > *'arba'(a)ta'aśār > arba'ta'sar$.⁶

Most other Central Semitic languages do not provide much information on the ending of the teens (on the feminine 'teen' word and its suffix, see below). Sabaic shows a lack of mimation, e.g., $ḥms^1t \ 's^2r \ ymtm$ 'fifteen days' (Ir 13.25). In Biblical Hebrew, the tonic lengthening in the masculine 'teen' word $'āśār$ suggests that it goes back to a mimated form $*'aśar-am$ (Suchard 2019, 100–7, 244), but the mimation or the lengthening may be analogical here. The endings on the teen numerals should thus be reconstructed as $*-a$, as in Arabic.

A remaining issue is the ending of the archaic digit 'one', $'aštē$, in the Biblical Hebrew forms. The spelling אשתי with final *yod* suggests that the final vowel in Tiberian Hebrew goes back to a diphthong $*-ay$ without any following vowel, since both $*-ay-a > **-\bar{a}$ and $*-ay-i$ or $*-ay-u > -\bar{e}$ would have been spelled with *he*, as in אשתי^{**} (on these contractions, see Suchard 2019, 132–39). This $*-ay$ in $*'ist-ay$ must result from contamination with the oblique ending of the following numeral, $*\theta n-ay/*\theta int-ay$ 'two (M)/(F)'. As the case ending $*-ay$ is unmarked for gender, this also explains why $'aštē$ is used in both genders of 'eleven', as

⁶ In $arba'ta'sar$ and other numerals where the digit ends in $-t$, the epenthetic status of $-a$ is *a priori* more plausible than with 'eleven', as Syriac does not allow four consonants in a row, as in $**arba't'sar$. But Proto-Aramaic does not seem to have used the short allomorph $*-t$ word-finally, only when suffixes followed (cf. Suchard 2024). Without a following $*-a$ on the digit, the expected reconstruction would therefore be Proto-Aramaic $*'arba'at \ 'aśar$ or $*'arba'ā \ 'aśar$, which should have yielded $**arb'at'sar$ or $**arb(^c)o'sar$ in Syriac, not $arba'ta'sar$.

the **-ay* ending replaced the original gender-marking suffixes **-ān-* and **-ay-*.⁷

The form *ʕt* occurs in both genders in Ugaritic as well, although this is unremarkable for the Ugaritic teen numerals. While Syriac has replaced the stem with the productive digit ‘one’, gender marking on the digit seems absent here too: neither *ḥdaʕsar* (M) nor *ḥdaʕ(e)sre* (F) show any trace of a feminine suffix on the digit. As both parts of ‘eleven’ show gender agreement in Arabic (*ʕaḥada ʕašara* [M] versus *ʕiḥdā ʕašrata* [F]), the contamination of **ʕist-* by the following numeral may have been a shared Northwest Semitic development. Epicene Northwest Semitic **ʕist-āʔ/ay* then replaced the older Central Semitic forms of the ‘one’ in ‘eleven’, which we can reconstruct as masculine **ʕist-ān-a* and feminine **ʕist-ay-a*.

3.0. The ‘Teen’ Word

The masculine and feminine of both ‘ten’ and ‘-teen’ reflect different stems. In ‘ten’, the stems follow the rules of chiastic concord, whereas the ‘teen’ word takes a feminine suffix only in the actual feminine form.⁸ This gives us a set of forms like Classical Arabic *ʕašar-at-* ‘ten (M)’, *ʕašr-* ‘ten (F)’, *ʕašar-a* ‘-teen (M)’, and *ʕašr-*

⁷ This contamination may have been triggered by the already close resemblance between the feminine oblique forms, **ʕist-ay-a* and **θint-ay*, and then spread to the rest of the paradigm after the new **ʕist-ay* was analysed as *one-OBL* with no identifiable gender marker.

⁸ This is presumably because ‘ten’ takes a plural noun, while the higher numbers, including the teens, originally took the singular. Chiastic concord is limited to numerals which take plurals.

at-a ‘-teen (F)’. The masculine stem can unproblematically be reconstructed as **‘aśar(-at)-* based on these Arabic forms together with Biblical Hebrew *‘āśār-ā* ‘ten (M)’, *‘āśār* ‘-teen (M)’ and related forms in non-Central Semitic.

The feminine ‘teen’ word in Northwest Semitic is special in two regards. Comparing Biblical Hebrew *‘eśr-ē* to Classical Arabic *‘ašr-at-a*, we see discrepancies both in the vowel of the first syllable and in the feminine suffix. The Hebrew forms are supported by the other Northwest Semitic languages, when these attest the relevant features: note especially Syriac *-(e)sr-e*.

The **i* vowel seen in the Northwest Semitic stem was probably also present in feminine ‘ten’, although it cannot be distinguished from **a* there due to the effects of stress and vowel epenthesis, cf. Biblical Hebrew *‘eśer*, Syriac *‘sar*, both < **‘iśr-* or **‘aśr-* (for Hebrew *ε* from **i* in this position, cf. Suchard 2019, 141–67). The **i* vowel is once again unambiguously present in the related word ‘twenty’: Biblical Hebrew *‘eśr-īm*, Syriac *‘esr-in*. In this numeral, we also find it attested in Arabic and Ge‘ez: *‘iśr-ū/i-na* and *‘aśr-ā*, respectively. As the other decades are transparently derived from the feminine numerals ‘three’–‘nine’, it is likely that Hebrew and Aramaic preserve the older form of ‘-teen (F)’ compared to Arabic and that their words for ‘ten (F)’ go back to **‘iśr-*. Arabic *‘ašr-*, as well as Ge‘ez *‘aśru*, and—probably—Akkadian *ešer*, has undergone contamination of the masculine stem **‘aśar-*.⁹

⁹ The stem allomorphy between masculine **‘aśar-* and feminine **‘iśr-* may have been the model for the secondary set of feminine cardinal

The Hebrew and Aramaic form of the suffix has previously been identified (thus still Blau 2010, §4.5.1.9) with the Arabic *ʿalif maqṣūrah*, an unstressed *-ā* or (in some varieties) *-ē* suffix spelled *أ* and reflecting **-ay-*, as in *أحدى* *ʾiḥd-ā* alt. *ʾiḥd-ē* < **iḥd-ay-* ‘one (F)’. This identification cannot be squared with the data from Ugaritic, where we find *ʕr-h* with what is almost certainly a consonantal **h* (a difficulty which Blau duly notes).¹⁰ Tropper (2000, §62.201) sees three ways to explain the form with *-h*. Either it constitutes a separate feminine suffix, morphologically distinct from *-t*; or it is a terminative (corresponding to the Hebrew ‘locative *he*’); or, again, it might represent a phonetic development of **-at* > **-ah*. The last option has Tropper’s preference. But this sound change depends on the teens having had a zero ending, while we have reconstructed **-a*, making this an unattractive solution. I agree that the second option, interpreting *-h*

numerals in Geʿez, shaped like *śals* ‘three (F)’, *rəbʿ* ‘four (F)’, etc. (Tropper 2002, §43.12). These probably do not explain the origin of **iśr-* itself, as they appear to be a fairly recent innovation: cf. the lack of assimilation in *səds* ‘six (F)’ compared to inherited *səssu*. The regular zero (NOM-GEN)/-*a* (ACC) inflection of the CəCC numerals also looks less archaic than the uninflecting *-u* ending of the feminine numerals ‘six’–‘ten’ (no longer visible in *samāni* ‘eight’ < **θamāniy-u*). This *-u* presumably derives from the Proto-Semitic diptotic nominative **-u* (Suchard 2023), cf. the *-u* (NOM-GEN)/-*a* (ACC) inflection of the masculine numerals, like *śalast-u/a* ‘three (M)’, reflecting Proto-Semitic **-u* (NOM)/**-a* (OBL); word-finally, **-u* did not shift to *ə* in Geʿez, instead merging with **-ū* (Al-Jallad 2014).

¹⁰ Ugaritic also attests *ʕr-t*, with the same secondary distribution of *-t* as the digits (see fn. 3 above).

as the terminative, is unlikely, because it is both limited to the feminine and vocalised differently in Hebrew and Aramaic (for the terminative in Aramaic, see Butts 2022), where the terminative is unstressed *-ā*, not *-ē*. This leaves the first option, that of a distinct feminine ending.

Tropper rejects this possibility, on the grounds that no such feminine ending is attested elsewhere either in Ugaritic or in other Semitic languages. But perhaps it is. Based on the vocalisation in Tiberian Biblical Hebrew and Syriac as a consistently stressed final **-ē*,¹¹ the consonantal *-h* found in Ugaritic allows us to reconstruct the suffix as **-ihV* (cf. Suchard 2019, 244). In Classical Arabic, a common form of the demonstrative pronoun ‘this (F)’ is *hāḏihī*. As the corresponding masculine is *hāḏā*, everything following the *ḏ* functions as a gender suffix. While the final vowel is pronounced long, it is not reflected in the consonantal spelling *هذه*. The same suffix occurs on the rarer forms *ذو ḏihī* and *تيه tihī* (also *ḏih* and *tih*), both also ‘this (F)’, where it is also spelled defectively. The defective spelling of a long vowel preceded by *h* and a short vowel is exactly the same as that of the third person masculine singular suffixed pronoun following a short vowel, e.g., *به bi-hī* ‘in him’, *ابنه ibnu-hū* ‘his son’. This latter suffix is historically short **-hu*, which accounts for the defective spelling. In pause, both the final vowel of the third person masculine singular

¹¹ In Babylonian Hebrew, the word appears as *‘aśrē* and *‘aśrō* (Yeivin 1985, 1112). The *a* in the first syllable regularly corresponds to Tiberian *segol*. The final *-ō* in the second form is explained by Yeivin as a graphical error, as the Babylonian *tserē* and *holem* are quite similar in appearance, both consisting of two dots above the letter (עשרה versus עשר).

suffix and that of the feminine pronouns in *-ihī* is dropped,¹² further supporting their origin in short vowels. Apparently, the dialect that supplied these readings underwent a sound change of **-ṽhṽ > -ṽhṽ̄*, lengthening short vowels following a short vowel and *h*, while the dialect on which the spelling is based kept this vowel short or lost it. The feminine suffix in the demonstratives *t-ihī*, *ḏ-ihī*, and *hāḏ-ihī* would, similarly, seem to go back to **-ihī*, which matches our reconstructed feminine suffix in the Northwest Semitic ‘teen’ word.

The traditional explanation for the Arabic forms is that the *h* arose through pausal aspiration (Lane 1863 s.v. ١٣), with *ḏihī < *ḏihī < ḏih*, etc., deriving from the similarly attested demonstratives *ḏī* and *tī*. But given the frequent pre-nominal position of the demonstrative in Arabic, e.g., *hāḏihī ad-dunyā* ‘this world’ (Q 28.42), it seems unlikely that it would occur utterance-finally often enough for such a generalisation of the pausal form to occur. Moreover, as with *-h* in the Ugaritic ‘teen’ word, there is no reason why the *h* should be limited to the feminine. Masculine *hāḏā* could easily have yielded ***hāḏah(ā)* in the same way, yet this form does not exist.

Supporting evidence for **-ihī* as a feminine demonstrative suffix comes, once again, from Syriac. Like some forms of Classical Arabic, Syriac added **hā-* to the demonstrative pronouns. Based on the most common shape of the feminine singular near demonstrative, represented by Biblical Aramaic *dā*, this should yield Syriac *ho-ḏo*, and this is in fact the form when the pronoun

¹² I am grateful to Marijn van Putten for calling my attention to this point (personal communication).

is followed by a copular clitic: *hoḏo*=*y* ‘this (F) is’. The form *dā* is similarly preserved in the interrogative pronoun *aydo* ‘which? (FSG)’. The feminine singular demonstrative when not followed by =*y*, however, is *hoḏe*. The unexpected *-e*, spelled *-ʾ*, is both written and pronounced exactly the same as the feminine *-e* in *-(e)sr-e* ‘-teen (F)’. It may be, then, that the independent form *hoḏe* reflects **hā-ḏ-ihī*, just as proposed above for its Arabic counterpart. If that is the case, **-ihī* is attested as a feminine suffix on demonstrative pronouns both in Arabic and in Syriac, making the postulated **-ihV̄* of the feminine ‘teen’ word less isolated.

The ultimate origin of this morpheme remains uncertain. Based on its meaning, we might think of a reduced form of the demonstrative pronoun of far deixis **hīʾa* ‘that (F), she’. In that case, the suffix cannot be Proto-Semitic in origin, but must have grammaticalised after the Proto-West-Semitic change of **s* to **h* at word boundaries (Al-Jallad 2015).

The feminine ‘teen’ word with the suffix **-ihī* is only attested in Northwest Semitic. Arabic reflects **ʿīsr-at-a* instead. This form of the ‘teen’ word, containing the far more common feminine suffix **-at-*, can easily have been created analogically. The use of a different feminine suffix on ‘-teen (F)’ from that used with the digits also sits well with the different syntax of the numbers ‘three’–‘ten’ and the teens, which Arabic does attest. Together with the presence of the feminine suffix **-ihī* in Arabic demonstrative pronouns, this supports a Central Semitic reconstruction of ‘-teen (F)’ as **ʿīsr-ihī*.

4.0. Conclusion

Based on the reconstruction of the Proto-Semitic numeral ‘one’ as *‘istān- (M)/*‘istay- (F), of the ending on both parts of the teens (except the digit in ‘twelve’) as *-a, and of the feminine ‘teen’ word as *‘isrihi, we can now reconstruct the Central Semitic teen numerals as in Table 2. In Northwest Semitic, ‘eleven’ changed to *‘ist-āʔ/ay ‘ašara (M), *‘ist-āʔ/ay ‘isrihi (F) due to contamination of ‘twelve’. The word for ‘-teen (F)’ in Northwest Semitic can securely be reconstructed as *‘isrihi, but it is debatable how old this form is. If it is also a Northwest Semitic innovation, it should be replaced by *‘israta in the reconstructions given here.

Table 2. The reconstructed Central Semitic numerals ‘eleven’–‘nineteen’

meaning	masculine	feminine
‘eleven’	*‘istāna ‘ašara	*‘istaya ‘isrihi
‘twelve’	*θn-āʔ/ay ‘ašara	*θ(i)n(a)t-āʔ/ay ‘isrihi
‘thirteen’	*šalāθ(a)ta ‘ašara	* šalāθa ‘isrihi
‘fourteen’	*’arba‘(a)ta ‘ašara	*’arba’a ‘isrihi
‘fifteen’	*ḥam(i)s(a)ta ‘ašara	* ḥam(i)sa ‘isrihi
‘sixteen’	*sidθata ‘ašara	*sidθa ‘isrihi
‘seventeen’	*sab‘ata ‘ašara	*sab’a ‘isrihi
‘eighteen’	*θamāniyata ‘ašara	*θamāniya ‘isrihi
‘nineteen’	*tis‘ata ‘ašara	*tis’a ‘isrihi

References

Al-Jallad, Ahmad. 2014. ‘Final Short Vowels in Gəʿəz, Hebrew ʾattā, and the Anceps Paradox’. *Journal of Semitic Studies* 59/2: 315–27.

———. 2015. ‘Yusapʿil or Yuhapʿil, That Is the Question: Two Solutions to Sound Change *s¹ > h in West Semitic’.

- Zeitschrift der Deutschen Morgenländischen Gesellschaft* 165/1: 27–39.
- Blau, Joshua. 2010. *Phonology and Morphology of Biblical Hebrew*. Linguistic Studies in Ancient West Semitic 2. Winona Lake, IN: Eisenbrauns.
- Bravmann, Meïr M. 1952. ‘Hebrew *štayim* in the Light of Syriac and Turcic’. *Proceedings of the American Academy for Jewish Research* 21: 1–2.
- Butts, Aaron Michael. 2022. ‘An Aramaic Cognate to Akkadian *-iṣ*, Hebrew *-ṣ*, and Ugaritic *-h*’. In *‘Like ʾIlu Are You Wise’: Studies in Northwest Semitic Languages and Literatures in Honor of Dennis G. Pardee*, edited by H. H. Hardy II, Joseph Lam, and Eric D. Reymond. Chicago: Oriental Institute: 539–54.
- Fischer, Wolfdietrich. 1972. *Grammatik des klassischen Arabisch*. Porta Linguarum Orientalium 11. Wiesbaden: Harrassowitz.
- Hasselbach, Rebecca. 2013. *Case in Semitic: Roles, Relations, and Reconstruction*. Oxford Studies in Diachronic and Historical Linguistics 3. Oxford: Oxford University Press.
- Hetzron, Robert. 1977. ‘Innovations in the Semitic Numeral System’. *Journal of Semitic Studies* 22/2: 167–201.
- Huehnergard, John. 2019. ‘Proto-Semitic’. In *The Semitic Languages*, edited by John Huehnergard and Naʾama Pat-El, 2nd ed., 49–79. Routledge Language Family Series. London; New York: Routledge Taylor & Francis Group.
- Huehnergard, John, and Naʾama Pat-El. 2019. ‘Introduction to the Semitic Languages and Their History’. In *The Semitic*

- Languages*, edited by John Huehnergard and Na'ama Pat-El, 2nd edition, 1–21. Routledge Language Family Series. London and New York: Routledge Taylor & Francis Group.
- Joüion, Paul, and Takamitsu Muraoka. 2006. *A Grammar of Biblical Hebrew*. 3rd reprint of 2nd edition with corrections. Subsidia Biblica 27. Rome: Pontifical Biblical Institute.
- Khan, Geoffrey. 2020. *Description of the Tiberian Pronunciation Tradition*. 2 vols. Cambridge Semitic Languages and Cultures 1. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/OBP.0163>
- Kogan, Leonid. 2015. *Genealogical Classification of Semitic: The Lexical Isoglosses*. Boston: De Gruyter.
- Lane, Edward William. 1863. *An Arabic-English Lexicon*. London: Williams & Norgate.
- Nöldeke, Theodor. 1904. *Compendious Syriac Grammar*. Translated by James A. Crichton. London: Williams & Norgate.
- Stein, Peter. 2011. 'Ancient South Arabian'. In *The Semitic Languages: An International Handbook*, edited by Stefan Weninger, 1042–73. Handbooks of Linguistics and Communication Science 36. Berlin: De Gruyter Mouton.
- Suchard, Benjamin D. 2019. *The Development of the Biblical Hebrew Vowels*. Studies in Semitic Languages and Linguistics 99. Leiden: Brill.
- . 2023. 'Two More Contexts for Ge'ez **u* > *u* and Three for **a* > *ə*'. *Afrika und Übersee* 96: 96–110.

- . 2024. ‘The Old Aramaic “Feminine” Suffix *-t* as an Accusative Case Marker’. *Zeitschrift der Deutschen Morgenländischen Gesellschaft* 174/1: 53–76.
- Testen, David. 1985. ‘The Significance of Aramaic *r < *n*’. *Journal of Near Eastern Studies* 44/2: 143–46.
- Tropper, Josef. 2000. *Ugaritische Grammatik*. 1st edition. Alter Orient und Altes Testament 273. Münster: Ugarit-Verlag.
- . 2002. *Altäthiopisch: Grammatik des Ge‘ez mit Übungstexten und Glossar*. Elementa Linguarum Orientis 2. Münster: Ugarit-Verlag.
- Van der Poel, Johanna. 2022. ‘The Imperfect Pattern in Ancient South Arabian Languages’. MA thesis, Leiden University.
- Wilson-Wright, Aren. 2014. ‘The Word for “one” in Proto-Semitic’. *Journal of Semitic Studies* 59/1: 1–13.
- Yeivin, Israel. 1985. *The Hebrew Language Tradition as Reflected in the Babylonian Vocalization*. 2 vols. The Academy of the Hebrew Language Texts and Studies 12. Jerusalem: Hacohen.

THE GENDER OF PAIRED BODY PARTS IN SEMITIC*

Na'ama Pat-El

Gender is a morphosyntactic feature, or, more specifically, an agreement feature. Typically, one can identify the existence of gender with its various values through evidence from agreement patterns. Gender is unique as a feature: unlike number, each noun normally has only one value and it has no access to other values; in other words, it is invariant (Corbett and Fedden 2016). But how is gender assigned? Gender does not correspond to a straightforward formal or semantic interpretation; it is not interpretable outside of the grammatical system (Aquaviva 2020, 50).

* I am grateful for comments and assistance from several colleagues. Olla Al-Shalchi, Samy Ayoub, and Avigail Noy helped me find resources in Arabic. Aaron Rubin directed me to relevant studies in Modern South Arabian. John Huehnergard and Phillip Stokes read and provided invaluable comments on earlier drafts. Aaron Hornkohl and two anonymous reviewers provided additional useful comments, for which I am thankful. As always, I alone am responsible for the content and arguments in this paper.

Abbreviations used in this paper: D = dual; F = feminine; JBA = Jewish Babylonian Aramaic; M = masculine; MSA = Modern Standard Arabic; OA = Old Assyrian; OAkk = Old Akkadian; OB = Old Babylonian; PL = plural; RH = Rabbinic Hebrew; S = singular.

In canonical systems, where gender is maximally an agreement feature, gender cannot be derived entirely based on semantics—again, unlike number. Non-semantic gender is assigned either arbitrarily¹ or based on morphological² and phonological factors. However, grammatical gender of nouns in any language with such a system has a semantic core; namely, a subset of nouns is assigned gender on the basis of animacy, humanness, social gender, and/or biological sex (Kramer 2020, 47).

In Semitic, nouns which are assigned feminine gender may be marked with specific suffixes (*-at, *-t). Unmarked inanimate nouns, however, may be either feminine or masculine, and gender assignment is largely arbitrary (Watson 2008, 197-98). Referent-based gender, namely gender that matches biological sex, is assigned to humans and to animate nouns, to the latter in cases

¹ This can be seen in Hebrew nouns which share a pattern, but differ in gender, e.g., *qīr* ‘wall (M)’ and *‘īr* ‘town (F)’, *kə’ēb* ‘pain (M)’ and *bə’ēr* ‘well (F)’. This is also true for Semitic more broadly, e.g., **arʔ* ‘land (F)’ vs **raʔ* ‘head (M)’.

² E.g., in German, nouns with the suffix *-schen* are neuter: *Mann* ‘man, (M)’, but *Männchen* ‘little man (NT)’. In Semitic, the use of final *-t* marks a noun as feminine, e.g., Hebrew *דֶּלֶת* ‘door (F)’ and *קֶשֶׁת* ‘bow (F)’ and (and later, Jibbali *but* ‘house [F]’), even if the morpheme’s origin is not the same as the feminine suffix *-t*. Consider, in this vein, Hebrew infinitives of I-weak roots, like *שָׁבַת* ‘sit’ and *דָּעַת* ‘know’. They present superficially as morphologically feminine, but see *הִנֵּה מַה־טוֹב וּמַה־נָּעִים שָׁבַת* ‘how nice and pleasant is the gathering of siblings together’ (Ps. 133.1), where the infinitive triggers masculine singular agreement (see also Prov. 21.19; 25.24).

where gender has real-world relevance. Thus, gender is referential for domesticated animals, like ‘goat’, but generally not for wild animals, like ‘bear’.³ We can define referent-based agreement as semantic, and non-referent-based gender as lexical.⁴

In this paper I will address the gender of paired body parts in Semitic, namely nouns denoting body parts that occur naturally in pairs in the human body, and enquire whether they are assigned semantic gender. Nouns denoting these parts in the Semitic languages are described in the scholarly literature as having two unique properties. First, they may retain dual morphology, even when such a category is no longer productive in the language, e.g., Hebrew *raglayim* ‘legs’; Akkadian *upnānu* ‘the hollows of the hand’. Second, there is broad consensus that these nouns are as a rule feminine, although no wide-ranging comparative study has established as much (e.g., Albrecht 1896, 73; Brockelmann 1908–1913,

³ Such nouns may trigger masculine gender, even when their referent is feminine, or vice-versa. For example, Hebrew דָּב שָׂכֹל ‘a bear (M) bereaved of offspring’ (2 Sam. 17.8; Hos. 13.8; Prov. 17.12). See also וְתִצְאָנָה שְׁתֵּים דְּבִים (2 Kgs 2.24), where only numerical and verbal morphology indicate that the bears are feminine. For further examples of this phenomenon in the history of Hebrew, see Dubnov (2011). The category of ‘domesticated animals’ may be dependent on societal conventions. For example, Dhofari Arabic distinguishes lexically between a male cat (*‘urri*) and a female cat (*sinnāra*) (Davey 2016, 77), while Modern Hebrew does not make such a lexical distinction, and the feminine is derived from the masculine. Of course, a feminine noun can be regularly derived from a masculine via suffixation of the feminine morpheme: Arab. *kalb*- ‘dog > *kalb-at*- ‘bitch’.

⁴ By lexical, I mean that gender is assigned arbitrarily and has a purely grammatical function.

I:422b; Bauer 1914, 371; Moscati 1980, 86; Waltke and O'Connor 1990, 103, §6.4.1; von Soden 1995, 92, §60d; Kaye 2009, 571; Blau 2010, 263, §4.4.2.3; Rubin 2010, 34; Hasselbach 2014 fn. 51). Holger Gzella goes so far as to refer to this phenomenon as “the common principle that paired body parts are feminine in Semitic languages throughout” (2007, 561). Indeed, the most common examples, ‘eye’, ‘hand’, and ‘ear’, are feminine across most languages that retain gender as a functional category.⁵

Which of the semantic features of these paired body part nouns makes them feminine is not clear. The broader category of ‘body parts’, many of whose members are also unmarked nouns, is not inherently feminine. Body parts which do not appear in pairs can be masculine,⁶ **ra’s*- ‘head (M)’, **pū*- ‘mouth (M)’, **kisad*- ‘neck (M)’, **anp*- ‘nose (M)’, or feminine, **baṭn* ‘abdomen (F)’, **iṣba* ‘finger (F)’, **svnn* ‘tooth (F)’,⁷ **lisān* ‘tongue (F)’. So the

⁵ There are, however, exceptions here too. Akkadian *idu* ‘hand, arm, side’ has common gender and Hebrew several times treats the cognate יָד as masculine, e.g., וַיְדֵי מֹשֶׁה כְּבָדִים ‘Moses’s hands were heavy’ (Exod. 17.12); while regularly feminine, Hebrew עֵין ‘eye’ also has common gender, for example שִׁבְעָה עֵינַיִם ‘seven (M) eyes’ (Zech. 3.9); the noun in the phrase עֵינָא בִישָׁא ‘evil eye’ in some Jewish Aramaic dialects is also masculine.

⁶ Albrecht (1896, 72) argues that they are all masculine, but that would be an exaggeration.

⁷ A possible explanation for the gender of ‘finger’ and ‘tooth’ is that there are two sets of fingers (left and right) and two sets of teeth (upper and lower) and therefore, dual; this seems to be an *ex post facto* explanation, however, as the Semitic nouns are singular, not collective. In other words, their referent is a single digit or tooth, not a set.

association of paired body parts with feminine gender is specifically tied to the observed number of items in a typical body.⁸ However, paired items are not feminine in general; temporal nouns, where lexicalised dual forms are common in some Semitic languages, are not specifically feminine. Some lexemes with lexicalised dual are masculine, e.g., **yawm* ‘day (M)’, **wariḥ* ‘month (M)’, while others are feminine, e.g., **sanat* ‘year (F)’. The claim under investigation, therefore, concerns a very specific and restricted subset of nouns that both indicate body parts and come in natural groups of two. This phenomenon is quite peculiar, since aside from nouns denoting animals or humans with biological sex, paired body parts are the only semantic group that is thought to constitute an inherently feminine feature, thereby affording them referential gender. There are no such claims about any other inanimate semantic group.

For some scholars, the implication of the observation that paired body parts are feminine is that there is a causal connection between morphology and gender assignment. Bauer (1914) suggested that the assignment of feminine gender to paired body parts is a result of reinterpretation of the dual suffix *-ā as a feminine plural, which is also *ā, at least in the verbal system. Thus

⁸ The alleged gender/paired body part connection is not attested in other languages with an active dual; for example, in Sanskrit, most paired body parts are masculine: *hasta* ‘hand (M)’; *pāṇi* ‘hand (M)’; *bāhu* ‘arm (M/F)’; *bhuja* ‘arm (M)’; *akṣi/locana/netra/nayana* ‘eye (NT)’; *karṇa* ‘ear (M)’; *śrotra* ‘ear (NT)’; *jaṅghā* ‘leg, shank (F)’; *jānu* ‘knee (NT)’; *ūru* ‘thigh (M)’; *gulpha* ‘ankle (M)’; *aṅghri* ‘foot (M)’; *pāda* ‘foot (M)’. I am grateful to my colleague Donald R. Davis for his assistance with the Sanskrit evidence.

**yaqtulā yadā* ‘two hands killed’ is misinterpreted as FP **yaqtulā*, whose singular is therefore **taqtul yadum* ‘one hand killed’. The problem with Bauer’s proposal is twofold. First, this kind of reinterpretation should have happened in all cases of dual, if indeed the dual and FP are identical, and not be restricted to only a specific semantic subset. Second, it is more likely that in proto-Semitic, feminine plural verbs did not end with **-ā*, but rather with **-na* (Huehnergard 2005, 169–70). The feminine plural suffix **-ā* in Akkadian, Ethiopic, and Aramaic is better explained as a result of a four-part analogy with the stative/suffix conjugation:⁹ 3MP *qatl-ū* : 3FP *qatl-ā* :: 3MP *yaqtul-ū* : 3FP X < *yaqul-ā*. The dual and FP were thus not homomorphic in proto-Semitic and the reinterpretation proposed by Bauer is, therefore, unlikely.

In a more recent article, Hasselbach (2007, 132–33) suggests the opposite process, namely that the feminine gender of paired body parts is original and the dual developed secondarily. According to Hasselbach, the original feminine nominal plural in pre-proto-Semitic was **-ā*. It was later affixed with *-t*, which was interpreted as a feminine marker to create the suffix used in all attested Semitic languages **-ā-t*. This development allowed feminine plurals to host case suffixes, which **-ā-* was not able to do. The old feminine plural morpheme **-ā*, without the feminine suffix, was reinterpreted as a dual, differentiating it from the new feminine plural morpheme, **-āt* and assuming a new role. Thus,

⁹ Note that the suffix *-ā* is restricted to predicative FP adjectives, while attributive FP adjectives terminate in *-āt*.

Hasselbach suggests, the suffix **-ā* on paired body parts, originally simply marking feminine plural, was now interpreted as nominative dual.

There are a number of problems with this hypothesis. For example, there is no obvious reason why only paired body parts would retain the original feminine plural suffix **-ā*, once a new feminine plural had come into use. Furthermore, the dual morpheme in Semitic is attached *after* the feminine singular, but the feminine plural is attached *instead of* the feminine singular, e.g., OA FS *raqq-at-um* ‘fine garment’, but *raqq-at-ān* ‘two fine garments’ (CCT 5, 18b:10), while the plural is *raqq-āt-um*; similarly Hebrew feminine singular *קֶמֶץ* *’amm-ā* ‘cubit’, but feminine dual *קֶמֶצַיִם* *’amm-āt-ayim* ‘two cubits’ (Exod. 25.10), while the plural is *קֶמֶצִים* *’amm-ot*.¹⁰ Furthermore, the dual morpheme is internally case-marked (OA nom. *-ān*, oblique *-ēn*), like the masculine plural, while the feminine plural hosts case endings, like singular nouns. Given the different position and morphological behaviour of these morphemes, it is unlikely that the dual morpheme and the feminine plural morpheme had the same historical origin.

¹⁰ Other issues that remain unexplained are how the suffix **-āt*, an originally feminine plural according to Hasselbach, became gender-neutral (Pat-El 2021). Furthermore, not all nouns referring to paired body parts select **-āt* as their plural, even if they are feminine; in Hebrew among the nouns that select *-īm* as plural are *reḡel* ‘foot (F)’ and *leḥi* ‘cheek, jaw (F)’. Note also that in Akkadian, nouns in the dual have feminine agreement, since the verb lost dual inflection post-Old Akkadian. This is an indication that, if anything, feminine is secondarily associated with the dual, not vice versa. For an early discussion of the origin of the Semitic dual, see Fontinoy (1969, ch. 2).

These proposed reconstructions are based on the hypothesis that paired body parts are always feminine, a hypothesis that, as I have outlined above, is the consensus view among Semitists. In this paper I set out to review the evidence to confirm or reject this hypothesis. I aim to address two questions: (1) are the Semitic languages a ‘unicorn’, the sole example of a gender system that assigns gender based on the typical distribution of the referent in nature? (2) Is there a connection between duals and gender?

I will begin by examining the evidence in Semitic and point to cases where nouns denoting paired body parts are not feminine, or whose gender fluctuates between the different languages and/or dialects. The evidence does not support the hypothesis that paired body parts are as a rule feminine. I will follow with a brief discussion of grammatical gender assignment to substantiate my conclusion that paired body parts are assigned random gender, not referential gender.

Two issues need to be noted from the outset. First, throughout the attested history of the Semitic languages, gender assignment in the same language changed. For example, Procházka (2004, 239) notes that the only nouns which are consistently feminine across all Arabic dialects are ‘eye’, ‘ear’, ‘hand’, and ‘foot’, which constitute the basic senses and locomotion;¹¹ however, the majority of nouns denoting body parts in modern Arabic dialects are masculine. In Hebrew, the noun חֲלָה ‘hollow of the hand’ was

¹¹ This is similar to a list Streck (2010, 296) provides for OB, which includes also the non-paired ‘finger’ and ‘tooth’.

feminine all the way up to the early twentieth century.¹² In modern Hebrew, however, the word is masculine.¹³ It is not clear what mechanism causes changes in gender assignment, but gender shifting is indicative that speakers do not associate gender with semantics. Second, many nouns referring to body parts in Semitic are primary, namely they are not derived, do not have a verbal root associated with them, and are not morphologically marked for gender (Fox 1998, 6).¹⁴

The sample presented below includes nouns with significant gender fluctuation across the family. When different languages reflect conflicting genders for the same proto-Semitic lexeme, sometimes even reflecting internal variation, it is not obvious which gender is original and which is secondary. If we accept the hypothesis that paired body parts are assigned feminine gender as a matter of principle, we will need to account for the change, namely why would what we assume is a referential gender switch to a non-referential gender.

¹² ככל דברי המשא והחזון האלה נשא דון קישוט על חופן מלאה 'All these prophecies, Don Qixote declared over a full (FS) hand' (Bialik, translation of *Don Qixote*, 1912).

¹³ For example, on the website of the Academy of the Hebrew Language the word is defined thus: חופן הוא חלל כף היד כשהיא כפופה 'hofen is (MS) the space in the palm of the hand when it is curved' (<https://tinyurl.com/u82vbtgz>).

¹⁴ Fox (1998, 6) also suggests that the preponderance of *qatil to denote body parts (paired and non-paired) may lend support to the hypothesis that patterns have discrete semantic values.

1.0. Evidence

Since most of the nouns in the relevant category are not marked for gender, establishing gender must rely on the syntax of the noun in context, namely the type of agreement it solicits.¹⁵ Given our patchy textual evidence, it is not always possible to verify agreement, but wherever evidence is available, I will provide such context, and note when there is no such context. Proto-Semitic etymology will be provided when available. The most common nouns, ‘eye’, ‘ear’, ‘hand’, and ‘leg’, are consistently feminine in Semitic; therefore, they will not be treated here. The nouns selected are those where, by and large, the same Semitic noun is reflected in most of the languages in the sample. The list could be expanded, of course, but the following is sufficient to serve as proof of concept.

¹⁵ Gender is not discussed in major comparative lexical works on the Semitic languages. Militarev and Kogan (2000) do not discuss gender at all in their etymological dictionary, nor do they specify it when listing lexemes. Similarly, most studies of body parts do not mention gender (e.g., Dietrich 1844; Leslau 1945).

1.1. Nostril (**naḥīr*-)¹⁶

Hebrew – masculine and feminine¹⁷—the noun is attested in BH (Job 41.12) and QH (11Q10 36.5), but without evidence for its agreement pattern; masculine: ועשה לו שני נחירין ‘He made him two (M) nostrils’ (Shabbetai Donnolo, Hakmoni tenth c.); feminine—שתי עינים ושתי אזנים ושתי ‘two eyes and two ears and two (F) nostrils and a mouth’ (Sefer Yešira, fifth c. [?]).

Ugaritic – unattested.

Aramaic – masculine¹⁸—בתקליא נקיב נחירא ‘the nose is pierced with a snare’ (Targum Job 40.24); Syr. ܢܚܝܪܝܢ ܕܕܥܝܢܝܢ ‘two (M) golden nostrils’ (Pesh. Zech 4.12).

Akkadian – masculine—*naḥīrī-šu ša imitti salit* ‘his right (M) nostril is notched (?) (M)’ (HSS 15 112.2).

Arabic – masculine—a slightly different pattern from the same root, مَنْخَرٌ, is treated as masculine in *Aṣ-Ṣaḥḥāḥ fī l-Luḡa*: إِذَا ضَاقَ مَنْخَرُهُ عَنْ نَفْسِهِ ‘if his nostril is narrowed (M)’; other dictionaries do not discuss gender.¹⁹

¹⁶ In Modern South Arabian, the word refers to the nose and is masculine (Soqotri *nāḥrār*, Hobyot *naxrir*). Simeone-Senelle and Lonnet (1991, 1455) mention *finəs* ‘nostril (M)’ for Soqotri.

¹⁷ It is masculine in Modern Hebrew: קושי בנשימה דרך האף או דרך נחיר אחד ‘difficulty breathing through the nose or through one (M) nostril’ (Medical website; <https://tinyurl.com/5dvtmptm>).

¹⁸ This lexeme shifted to mean ‘nose’ in some dialects. See also Kogan (2015, 379).

¹⁹ Modern Arabic dialects use *munḥār/minḥār* (plural *manāḥīr*), which is usually masculine.

1.2. Eyelid²⁰

Hebrew – masculine—BH וְתִרְדָּנָה עֵינֵינוּ דְמָעָה וְעַפְפֵּינוּ יִלּוּ-מִים ‘our eyes will tear up, and our eyelids will shed (M) water’ (Jer. 9.17).

Ugaritic²¹ – no signs of agreement, listed as masculine in *DUL* 170.

Aramaic – masculine and feminine—šakin – masculine: ‘he protected them as the eyelid protects (M) the pupil of the eye’ (Neof., Deut. 32.10); feminine: נטרינון היכמה דשכינה נטרא בבי דעייניה ‘they protect us as the eyelid protects (F) the pupil of the eye’ (Ps.-J. Deut. 32.10).²²

Arabic – masculine—a different term is used, جَفْنُ, and it is treated as masculine. *Lisān al-‘Arab* treats it as masculine in all its different meanings; for example: وهذا الجَفْنُ غير الجَفْنِ ‘and this (M) *jafn* is not *jafn l-karm* (grapevine)’.

Akkadian – there is no specific word attested for this body part whose core meaning is ‘eyelid’; the two nouns used are *quliptu* ‘cover, bark (marked F)’ and *kappi ini* ‘palm of the eye (F)’.

²⁰ This lexeme has no obvious proto-Semitic etymon.

²¹ Kogan (2015, 285) suggests that *pʿp* is proto-Canaanite and means ‘pupil of the eye’. The word does not occur outside Hebrew and Ugaritic (which I do not consider Canaanite) and could indeed be considered Northwest Semitic.

²² This term in NENA is largely masculine: C. Urmi *xasət ʿayna* (Khan 2016, III:12); J. Urmi *xasət ena* (Khan 2008, 386); Zakho *elpapa* (Yona 1999).

1.3. Arm (**ḏirā*‘-)

Hebrew – masculine and feminine—masculine: BH וַיִּפְּזוּ וַיִּזְרְעוּ עַמִּים יִשְׁפֹּטוּ ‘his arms are agile (M)’ (Gen. 49.24), ‘my arms will judge (M) nations’ (Isa. 51.5); feminine: בְּזֵרְעָה ‘with an outstretched (F) arm’ (Exod. 6.6).

Ugaritic – there is no evidence for agreement; listed as feminine in *DUL* 285.

Aramaic – masculine and feminine—feminine: דרעיהא מא שפירן ‘her arms—how beautiful (F)’ (1QapGen 20.4); masculine: Syr. ܐܢܬܝܢ ܕܡܢ ܕܡܪܝܬܐ ܕܡܪܝܬܐ ܕܡܪܝܬܐ ‘I will lead them out of his land with a raised (M) hand’ (Pesh. Exod. 6.1); וגלגל ית אבנא בחדא מן אדרעוי ‘he rolled the rock with one (M) of his hands’ (Ps.-J. Gen. 29.10); ובאדרע מרמם ‘with a strong hand and a raised (M) arm’ (Onq. Jer. 32.21).²³

Arabic – masculine and feminine—in Classical Arabic it is feminine, but in MSA it is both; Lane (121) reports that even traditional Arab dictionaries are conflicted about the gender, with the meaning ‘cubit’ probably feminine; Penrice marks this noun as having both genders, as does *Lisān al-Arab* (أُنْثَى وَقَدْ تُذَكَّرُ).

²³ The noun is also masculine in some NENA, e.g., C. Urmi *drana* (Khan 2016, 14). In Zakho, *zanda* is feminine (Yona 1999).

Akkadian – *dura'u* appears only in NA and is likely a loan from West Semitic (CAD D 191); the typical words for arm are *idu* (M/F) (CAD I/J 10) and *aḫu* (F): *Á-šu ina siqīānišu šaknat* ‘his arm lays (F) in his lap’ (CAD A1 205); *Á-ki muttabbilāti* ‘your gesticulating (?) arms (F)’ (CAD A1 205); both nouns are represented with the logogram *Á*, which may create some confusion.

1.4. Hollow of the hand (**hupn-*)²⁴

Hebrew – feminine—no evidence for agreement in BH, but the noun is listed as masculine in dictionaries of both BH and post-biblical Hebrew; RH – feminine: נמצאת חופנו שלמשה קמצים ‘Moses’s palm has (F) eight thumbs’ (Gen. Rab. 5.7).

Aramaic – masculine and feminine—masculine: תרין חופנין ‘two (M) handfuls filled with food’ (Tg. Qoh. 4.6); מליין מיכלא ‘four (M) handfuls’ (Lev. Rab. 216.7, 1); feminine: לגבר ליומא קמה חפן חדה ‘for each man for each day, flour—one (F) handful’ (TAD 6 9.5).

Ugaritic – no evidence for agreement; listed as masculine in *DUL* 362.

Arabic – حَفْنَةٌ marked feminine in *Lisān al-Arab*: وَحَفَّنَ لَهُ مِنْ مَالِهِ حَفْنَةً: أَعْطَاهُ إِيَّاهَا ‘he gave him a handful of his money. He gave it (FS) to him.’

²⁴ The noun is attested in Sabaic as a definite dual (*hfnhnhn*), gender unknown.

Akkadian – feminine²⁵—*ibakkī-ma pêtā upnā-šu ušallā* ‘he cried and prayed with his palms open (FP)’ (Esarhaddon 33.oi6; see also Holma 1911, 118).

1.5. Testicle (*isk-)²⁶

Hebrew – masculine אֶשְׂכָּה, but no direct early evidence for agreement.²⁷

Ugaritic – *úšk*, no evidence for agreement; listed as masculine in *DUL* 113.

Aramaic – in Syriac and JBA it is marked feminine: אִשְׂכָּתָא; similarly in NENA *ʾəšcita* (Yona 1999; Khan 2016, 14).

Arabic – the term used is different, خُصْيَةٌ, which is marked feminine. See *Lisān al-Arab* إِذَا رَأَيْتُ خُصْيَةً مُعَلَّقَةً ‘if I saw an undescended (F) testicle’.

²⁵ In Akkadian the noun has two meanings: hollow of the hand, with the plural *upnū*, which usually occurs in the dual (*upnān*), and a measure (handful), with the plural *upnātu*.

²⁶ The Modern South Arabian words are from other roots, mostly *ʾāgrēz* (F), but also *karaʿil* (M) in Soqotri (Simeone-Senelle and Lonnet 1991, 1461). Several languages mark this noun as morphologically feminine: Aramaic, Akkadian, and Ethiopic (*ʾəskit*), with Arabic using a different lexeme which is also marked feminine.

²⁷ The earliest clear indication of gender is in a tenth-century medical composition, *Medical Practice*, by Shabbetai Donnolo: ויש לו שילשול עם כאב האשכים הם המבושים ‘and he has diarrhoea with pain in the testicles, which are (MPL) the privates’. This noun is masculine in Modern Hebrew, as an answer on the Hebrew academy website makes clear: אֶשְׂכָּה וּפֶיֶן הם ממין זכר ‘testicle and penis are masculine’ (<https://tinyurl.com/bm7nvnph>).

Akkadian *išku* – feminine—*lu ina šalte [iṣ-k]a šanīta tahtepe* ‘or in a fight she injures the other (F) testicle’ (KAV 1 i ...87).

1.6. Breast (**θady*-)

Most words denoting female breasts are masculine.²⁸

Hebrew – masculine²⁹—BH וְשָׁדַיִם צִמְקִים ‘and shriveled (M) breasts’ (Hos. 9.14); the noun continues to be treated as masculine throughout the history of Hebrew: מִה שָׁד זֶה תִּינוּק ‘what is a breast? A baby eats from it’ (b. Yoma 75a); כֶּשֶׁם שֶׁשָּׂדִים מְנִיקִים אֶת הַתִּינוּק ‘as breasts feed (M) the baby’ (Tanḥuma, Wayigash 3)

Ugaritic – masculine—*l̥yd hrh . [°] l̥dh̥* ‘her breast did not know (M) her conception’ (UDB1 13 31)

Aramaic – masculine—Syr. ܡܠܬܐܝܬܐ ܕܡܢܝܥܐ ‘the breasts which nourished (M) you’ (Pesh. Luke 11.27).

Arabic – masculine³⁰—تَدِيٌّ مُقْعَدٌ ‘a full (M) breast’ (Lane 333). *Lisān al-Arab* treats the noun as masculine, for example وهو للمرأة والرجل أيضاً، وجمعه أئدٍ وأئدي ‘it (M) belongs to both woman and man, and its (M) plural is ‘*aṭḍin* and *ṭuḍī*’.

²⁸ The only exception is some Modern South Arabian languages, e.g., Soqotri *tod’i*, Hobyot *θoodə*, where the word is feminine (Naumkin and Kogan 2018, II:608; Nakano 2013, 11).

²⁹ When a numeral is used with this noun, it is the masculine variant (e.g., Song 4.5).

³⁰ This is true also in some modern dialects, e.g., Dhofari Arabic *θawīdāt* ‘breasts’ conditions masculine agreement (Davey 2016, 77 fn. 7).

Akkadian – a different lexeme is used, *tulû* (< **tul*'), which is masculine (Holma 1911, 46);³¹ *ana* UBUR *ešši tunakkar-šū-ma* 'you will move it (=the baby) to a new (M) breast' (Labat 1951, 222, ex. 37).

1.7. Loin (**mVtn*-)³²

Hebrew – masculine³³—BH מְתַנִּיכֶם חֲגָרִים 'your loins girded (M)' (Exod. 12.11); וּמְתַנִּיו חֲגוּרִים מְכַנְסֵי בָד 'and his loins are girded (M) with cloth pants' (Josippon 66.351 [early tenth c.]).³⁴

Ugaritic – *mtn*—there is no direct evidence for agreement; listed as masculine in *DUL* 592.³⁵

Aramaic – masculine³⁶ – Mand מתניא גוויא (Drower and Macuch 1963, 257) 'inner loins'.

³¹ Less common nouns are *zīzu* (F) and *kirimmu* (M); see Holma (1911, 47–48).

³² The word is masculine in Modern South Arabian as well (Simeone-Senelle and Lonnet 1991, 1466).

³³ In Modern Hebrew the lexeme has common gender: המתניים הכי צרים 'the thinnest (M) waist you ever saw' (MAKO; <https://tinyurl.com/yckmf9zh>); הבחורה עם המותניים הצרות בעולם 'the girl with the thinnest (F) waist in the world' (Walla; <https://tinyurl.com/2yjjy95tb>).

³⁴ Albrecht (1896, 78) concedes that this word is an exception to the rule, but suggests that the noun was perhaps originally feminine, but due to misunderstanding later attracted masculine agreement.

³⁵ There is a secondary feminine derivation, *mtnt*, with the same meaning, which may indicate that the basic noun is not feminine. Without direct evidence of agreement, however, this is impossible to confirm.

³⁶ Aramaic also uses a different lexeme, *hraṣ*, which is masculine.

Arabic – masculine and feminine—مَتْنٌ refers to the side of the back; reported to have both genders in Steingass (953), and feminine in Kazimirski (1860, 1059). *Lisān al-Arab* reports both genders (والْمَتْنُ الظَّهْرُ، يذكر ويؤنث).

Akkadian³⁷ – masculine—the typical word for loins/hips is *qablu*: *qablē-šu našû* ‘the sides of his back were elevated (M)’ (Labat 1951, 124, ln. 25).

1.8. Thigh (**sa:q*-)

Hebrew – masculine and feminine—masculine: BH וָאֵת שׁוֹק וְאֵת הַתְּרוֹמָה אֲשֶׁר הוֹנֶה וְאֲשֶׁר הוֹרֵם ‘and the thigh of the offering which was lifted (M) and raised (M)’ (Exod. 29.27); feminine: QH ושוקיו ארוכות ודקות ‘and his thighs are long (FPL) and lean (FPL)’ (4Q186 f1ii.5); RH לֹא תִהְיֶה שׁוֹק הַיְמִינִי לְמָנָה ‘he will have (F) the right thigh as a portion’ (m. Zevah. 12.1).

Ugaritic – *šq*—no evidence for agreement, listed as masculine in *DUL* 826.

Aramaic – masculine and feminine—masculine: JBA גזירתניהו לשקך ‘I cut (it [M]) your leg’ (b. Bava Qama 81b); feminine: דיליה תהי שקא דימינא לחולק ‘his will be (F) the right thigh as a portion’ (Ps.-J. Lev. 7.33).³⁸

³⁷ The lexeme *matnu* ‘tendon (M)’ perhaps reflects a different etymon, related to Aramaic *mitna* ‘cord (M)’.

³⁸ The noun *šaka* (< *šāqā*) is masculine in NENA (Khan 2016, 14).

Arabic – masculine and feminine—masculine: *على ساقٍ واحدٍ* ‘on the one (M) thigh’ (Lane 1472); feminine *والتفت الساق* ‘one shank is twisted (F) with the other’ (Q 75.29); on the basis of the Qurānic verse, *Lisān al-Arab* determines that the noun is feminine (*السَّاقُ مؤنث*).

Akkadian³⁹ – *sāqu* (only in OAkk and Babylonian) and *sīqu* (only in Assyrian) have unclear agreement.

1.9. Heel (**aqib-*)

Hebrew – masculine—there is no direct evidence for agreement in BH; RH: *נִפְסַק עֲקִיבוֹ* ‘its heel broke off (M)’ (m. Kelim 26.4); *בסנדל שיש לו עקב בשר ושאיין לו עקב פסול* ‘in a sandal with an allowable (M) heel and no forbidden (M) heel’ (m. Yev. 12.1).

Ugaritic – *qb*—no evidence for agreement; listed as having both genders (?) in *DUL* 173.

Aramaic – masculine and feminine—masculine: Mandaic *עקבה גגא ברקא* ‘his heel stamped (M) on the ground’ (Drower and Macuch 1963, 356b); JBA *עוקבי בארעא נקיש לי* ‘my heel tapped (M) on the ground’ (Sokoloff 2002, 858); feminine: Syr. *ܐܪܥܐ ܕܥܝܪܝܟܐ ܚܬܝܠܐ* ‘your heels were revealed (FP)’ (Pesh. Jer. 13.22).

³⁹ The sibilant of this noun in Akkadian should be /š/ if it has the same etymology as the West Semitic nouns. The use of /s/ is peculiar and may indicate a borrowing, despite the fact that it is attested already in Old Akkadian. Holma (1911, 134 fn. 5) suggests that this perhaps reflects an Assyrian origin.

Arabic – masculine and feminine—Penrice (99) and Nadwi (404) mark it as having both genders; Lane lists the noun as feminine, but provides examples where the agreement is clearly masculine: *مِنْ أَيْنَ كَانَ عَقْبُكَ* ‘where are you from?’ (Lane 2100); Wehr suggests that the gender is dependent on the use; *Lisān Al-Arab* cites al-Azharī, who determines that the noun is feminine (الأزهرى: وَعَقِبَ الْقَدَمَ وَعَقْبُهَا: مُؤَخَّرُهَا،) (مؤنثة) and elsewhere notes that the heel of a shoe is feminine too (وَعَقِبَ النَّعْلِ: مُؤَخَّرُهَا، أُنْثَى).

Akkadian – *eqbu*—unclear: while *eqbu* is used in Akkadian, the common word for ‘heel’ is *asīdu*, which is masculine: *šumma amēlu asidā-šu purrur* ‘if a man’s heel is broken (M)’ (CAD A2 330).

1.10. Ankle⁴⁰

Hebrew – masculine and feminine—no evidence for agreement in BH; masculine: RH וקרסוליו וכנפיו חופין את רובו ‘and his ankles and wings encircle (M) most of him’ (t. Hul. 4.11); feminine: RH ארבע כנפים וקרסולים ‘four (F) wings and ankles’ (m. Hul. 3.7).⁴¹

Ugaritic – *hrzṣp*—no evidence of agreement; listed as masculine in *DUL* 403.

⁴⁰ Some Modern South Arabian languages use a potentially related word: Hobyot *karšin*. I suspect it is masculine, but I could not confirm it.

⁴¹ The noun is masculine in Modern Hebrew; for example, from a medical forum: הקרסול עדיין נפוח ועדיין יש טיפה כאבים ‘the heel is still swollen (M) and I have a bit of pain’ (<https://www.doctors.co.il/forum-11/message-454626/>).

Aramaic – masculine—Syr. ܠܐ ܡܥܬܝܠ ܡܥܬܝܠܐ ‘my ankles will not falter (M)’ (Pesh. 2 Sam. 22.37).

Arabic – a different term, رُسْغٌ, is treated as masculine—for example in *Lisān al-Arab*: الرُّسْغُ مُجْتَمِعُ السَّاقَيْنِ وَالْقَدَمَيْنِ ‘the ankle is connecting (M) the legs and feet’; the same term is used for the wrist.

Akkadian – feminine—šumma kišallum ša imittim palšat ‘if the right ankle is perforated (F)’ (YOS 10 47.65).

2.0. Discussion and Conclusion

The data presented here shows not only that there are masculine paired body parts, but that gender assignment may be inconsistent and fluctuate, sometimes even within the same branch. While I have included in this paper only nouns with solid and broad attestation in multiple branches, there are further examples with attestation only in a subset of the languages, such as **kisl* ‘side, loin’, which is masculine in Hebrew, e.g., כָּל שֶׁכְּסָלָיו ‘any whose sides burst (M)’ (t. Bekh. 4.10), but feminine in Ugaritic, e.g., *ksl* . *tṭbr* ‘the shoulder should buckle (F)’ (UDB1 3 III:33); **lahw* ‘cheek, jaw’, which is feminine in BH, e.g., לַחֵי-הַמָּוֶר ‘a fresh (F) donkey jaw’ (Judg. 15.15), but masculine in RH, e.g., נִטַּל לַחֵי הַתַּחְתּוֹן ‘the lower (M) jaw is removed (M)’ (m. Ḥul. 3b); **yarik* ‘thigh’, which is feminine in BH, e.g., אֶת-יָרֵכְךָ נָפַלְתָּ ‘your drooping (F) thigh’ (Num. 5.21), and RH, e.g., יָרֵךְ שְׁגִיד הַנֶּשֶׁה ‘a side in which (F) the thigh tendon is’ (m. Ḥul. 7.2), but masculine in Ugaritic, e.g., *k ypth yrk hnd* ‘when this flank (= side) was opened (M)’ (KTU 1.143:3); etc.

The variation in gender makes reconstruction of a specific proto-Semitic gender value difficult. In principle, it is equally as possible that nouns with fluctuating gender were originally masculine and switched to feminine as the reverse. The phenomenon of gender switching has not been studied in Semitic, but at the very least the existence of switching indicates that speakers did not perceive paired body parts as belonging inherently to a specific gender.⁴² This state-of-affairs supports the hypothesis that there is nothing in paired body parts which necessitates a specific gender. The fact that we encounter the feminine nouns ‘hand’, ‘eye’, ‘ear’, and ‘leg’ more often than other paired body parts should not lead us to conclude that *all* paired body parts share the same set of morpholexical features. The most logical explanation of the evidence presented here is that body parts, like most other nouns, do not have an inherent gender associated with their

⁴² Bettega and D’Anna (2023) seem to argue the reverse:

[i]t is interesting to note how concepts that tend to be conceived of as inherently feminine in Arabic retain their gender even in those dialects where they are referred to by means of a different lexical element. This is for instance the case of the F.SG noun *ḥarrāy* “sun” in Kordofanian Baggara Arabic. (ch. 2)

The examples they give of constituents of the physical world which are mostly feminine include ‘sky’ (**samāy*) and ‘rain’ (**maṭar*), both of which are masculine in Canaanite, Ugaritic, and Aramaic. The Semitic word for ‘sky’ is also masculine in Akkadian. The noun ‘rain’ is expressed in Akkadian by several nouns with both genders. Interestingly, Bettega and D’Anna note that the gender of unmarked nouns depends on the dialect.

semantic category. The fact that many of them are feminine is a result of random distribution. This is most obvious in nouns referring to typical female body parts, e.g., ‘breasts’, which are grammatically masculine, or typical male body parts, e.g., ‘fore-skin’ or ‘beard’,⁴³ which are grammatically feminine. If gender were assigned on the basis of semantics, nouns associated with biological sex should conform to the appropriate gender; yet they do not.

Granted, there is indeed a comparatively high proportion of feminine nouns among paired body parts, but uneven gender distribution is not unique to this semantic group. Other natural semantic categories also show a propensity for a specific gender; most nouns representing the elements, e.g., *’is ‘fire’, *’arḏ ‘earth’, are feminine, while celestial bodies, e.g., *kawkab ‘star’, *wariḥ ‘moon’, along with the cardinal directions, are masculine. This is also true for basic raw materials, e.g., *ṣūr ‘flint (M)’, *ṭiṭṭ ‘wet clay (M)’, *bāḏ ‘mud (M)’, etc.⁴⁴ The only study known to me that attempts to connect gender to semantic categories is Albrecht (1896), who assigns a causal relation between feminine

⁴³ For example, Hobyot *lahit*.

⁴⁴ See a longer list in Agmon (2010, 23–29).

gender and what he considers feminine features (maternity, fertility, etc.),⁴⁵ but even he is often stumped.⁴⁶

An association of grammatical gender with meaning necessitates a theory of gender; in other words, we first must understand what gender is supposed to represent. Gender is what we call a system which organises nouns into inflectional classes, which in turn regulate the morphology of their modifiers (adjective, demonstrative, relative marker), pronominal referents, and predicates. As was noted at the beginning of this article, in the case of nouns denoting biological sex—a small and restricted category—the inflectional category corresponds to a feature of the real-world referent. All other nouns, if they do not carry specific morphological markers, are assigned gender randomly. The hypothesis that the gender of **ʿayn* ‘eye’ corresponds to a feature of its referent in the real world means that gender is more than an inflectional category—it is in fact a classifier. Classifiers correlate with the extralinguistic characteristics of nouns, and include not only ‘animal’, ‘human’, ‘plant’, etc., but also form, shape, and

⁴⁵ In general, discussions of gender assignment in Semitic concentrate on feminine, mostly unmarked feminine, and ignore masculine (Procházka 2004; Streck 2010; Bettega and D’Anna 2023). This may make some sense if we think about feminine as secondary or derivative, but where neither gender is morphologically marked, there is no reason to assume the priority of one or the other.

⁴⁶ For example, when trying to explain why some natural phenomena are feminine he notes “[d]er Grund dieser Auffassung ist unklar, jedenfalls sind sie nicht als still und verborgen, der Frau gleich waltend” (41). The work of Albrecht provides multiple examples of semantic groups where most nouns belong to one gender, but there are still many exceptions.

structure (Aikhenvald 2000, 82). Classifiers are by and large semantically transparent and follow the cultural concepts of their speakers. Since Semitic has only two markers, masculine and feminine, it seems *prima facie* impossible that assigning one or the other is semantically determined. Given that the number of nouns to which the term 'classifier' applies is a small, closed category, that there are only two such markers, and that the evidence provided in this paper is indicative that not all paired body parts belong to the same 'class', it is far more economical to describe the Semitic system in terms of nominal gender, where, with the typologically common exception of biological sex, gender is non-referential.

To conclude, the assumption that paired body parts in Semitic are inherently feminine falls apart on empirical grounds. While the majority of nouns denoting paired body parts are feminine, the extant uneven distribution of gender assignment is found with other semantic groups and, statistically, is to be expected. Typologically, assigning gender to inanimate nouns based on non-sex-related semantics, regardless of morphology, is unparalleled crosslinguistically. Furthermore, paired body parts do not share any morphological features which could account for their gender assignment. Given the evidence presented here, specifically, that there are masculine paired body parts, and, more generally, the typological distribution of gender, we must conclude that the assignment of gender in inanimate nouns is random. Consequently, theories utilising the gender of paired body parts to explain proto-Semitic morphology are contradicted by the data.

References

- Agmon, N. 2010. 'Materials and Language: Pre-Semitic Root Structure Change Concomitant with Transition to Agriculture'. *Brill's Annual of Afroasiatic Languages and Linguistics* 2: 23–79.
- Aikhenvald, A. Y. 2000. *Classifiers: A Typology of Noun Categorization Devices*. Oxford: Oxford University Press.
- Albrecht, K. 1896. 'Das Geschlecht der hebräischen Hauptwörter'. *Zeitschrift für die alttestamentliche Wissenschaft* 16: 41–121.
- Aquaviva, P. 2020. 'Gender as a Property of Words and as a Property of Structures'. *Catalan Journal of Linguistics* 19: 49–74.
- Aṣ-Ṣaḥḥāḥ fī l-Luġa = Abū Naṣr 'Ismā'īl bin Ḥamād al-Ġawhariyy. *Aṣ-Ṣaḥḥāḥ fī l-Luġa*. <https://tinyurl.com/mtv7fhw2>
- Bauer, Hans. 1914. 'Semitische Sprachprobleme'. *Zeitschrift der deutschen morgenländischen Gesellschaft* 68: 365–74.
- BDB = Brown, Francis, Samuel Rolles Driver, Charles A. Briggs. 1962 (1906). *The Brown-Driver-Briggs Hebrew and English Lexicon: With an Appendix Containing the Biblical Aramaic*. Oxford: Clarendon.
- Bettega, Simone, and Luca D'Anna. 2023. *Gender and Number Agreement in Arabic*. Leiden: Brill.
- Blau, Joshua. 2010. *Phonology and Morphology of Biblical Hebrew: An Introduction*. Winona Lake, IN: Eisenbrauns.
- Brockelmann, Carl. 1908–1913. *Grundriss der vergleichenden Grammatik der semitischen Sprachen*. 2 vols. Berlin: Verlag von Reuther & Reichard.

- CAD = *The Chicago Assyrian Dictionary*. Chicago: The Oriental Institute.
- Corbett, G. and S. Fedden. 2016. 'Canonical Gender'. *Journal of Linguistics* 52: 495–531
- Davey, R. J. 2016. *Coastal Dhofari Arabic*. Leiden: Brill.
- Dietrich, Franz Eduard Christoph. 1844. *Abhandlungen für semitische Wortforschung*. Leipzig: FCW Vogel.
- Drower, E. S., and R. Macuch. 1963. *A Mandaic Dictionary*. Oxford: Clarendon.
- Dubnov, Keren. 2011. 'Gorging Cat and Other Animals: On the Development of Gender Inflection in Animal Names'. *Ha-Ivrit* 58/3: 127–45. [Hebrew]
- DUL = Del Olmo Lette, Gregorio, and J. Sanmartín. 2004. *A Dictionary of the Ugaritic Language in the Alphabetic Tradition*. Leiden: Brill.
- Fontinoy, C. 1969. *Le duel dans les langues sémitiques*. Paris: Société d'Édition "Les Belles Lettres".
- Fox, Joshua. 1998. 'Isolated Nouns in the Semitic Languages'. *Zeitschrift für Althebraistik* 11: 1–31.
- Gzella, Holger. 2007. 'Some Penciled Notes on Ugaritic Lexicography'. *Bibliotheca Orientalis* 64: 527–67.
- Hasselbach, Rebecca. 2007. 'External Plural Markers in Semitic: A New Assessment'. *Studies in Semitic and Afroasiatic Linguistics Presented to Gene B. Gragg*, 123–38. Chicago, IL: The Oriental Institute.
- . 2014. 'Agreement and the Development of Gender in Semitic (Part I)'. *Zeitschrift der Deutschen Morgenländischen Gesellschaft* 164/1: 33–64.

- Holma, Harri. 1911. *Die Namen der Körperteile im Assyrisch-babylonischen: Eine lexicalisch-etymologische Studie*. Leipzig: Suomalaisen Tiedeakatemian Kustantama.
- Huehnergard, John. 2005. 'Features of Central Semitic'. In *Biblical and Oriental Essays in Memory of William L. Moran*, edited by A. Gianto, 155–203. Rome: Pontifical Biblical Institute.
- Kaye, Alan S. 2009. 'Arabic'. In *The World's Major Languages*. 2nd edition. Edited by Bernard Comrie, 560–77. London: Routledge.
- Kazimirski, A. de. 1860. *Dictionnaire Arabe-Francais*. Paris: Maisonneuve et Cie.
- Khan, Geoffrey. 2008. *The Jewish Neo-Aramaic Dialect of Urmi*. Piscataway, NJ: Gorgias Press.
- . 2016. *The Neo-Aramaic Dialect of the Assyrian Christians of Urmi*. 3 vols. Leiden: Brill.
- Kogan, Leonid. 2015. *Genealogical Classification of Semitic: The Lexical Isoglosses*. Berlin: de Gruyter.
- Kramer, Ruth. 2020. 'Grammatical Gender: A Close look at Gender Assignment across Languages. *Annual Review of Linguistics* 6: 45–66.
- Labat, René. 1951. *Traité akkadien de diagnostics et pronostics médicaux*. Leiden: Brill.
- Lane = Lane, E. W. 1863–1893. *An Arabic–English Lexicon*. 8 vols. Edited by Stanley Lane-Poole. London: Williams and Norgate.
- Leslau, Wolf. 1945. 'The Parts of the Body in the Modern South Arabic Languages. *Language* 21/4: 230–49.

- Lisān al-‘Arab* = Ibn Manzūr. 1993. *Lisān al-‘Arab*. Beirut: Dar Sader.
- Militarev, Alexander, and Leonid Kogan. 2000. *Semitic Etymological Dictionary: Vol 1—Anatomy of Man and Animal*. Münster: Ugarit Verlag.
- Moscatti, Sabatino. 1980. *An Introduction to the Comparative Grammar of the Semitic Languages*. Wiesbaden: Harrassowitz.
- Nakano, A. 2013. *Hobyōt (Oman) Vocabulary*. Tokyo: Tokyo University of Foreign Studies.
- Naumkin, V., and Leonid Kogan. 2018. *Corpus of Soqotri Oral Literature*. 2 vols. Leiden: Brill.
- Nichols, Johanna. 2019. ‘Why Is Gender So Complex? Some Typological Considerations. In *Grammatical Gender and Linguistic Complexity: Volume I—General Issues and Specific Studies*, edited by Francesca Di Garbo, Bruno Olsson, and Bernhard Wälchli, 63–92. Berlin: Language Science Press.
- Pat-El, Na‘ama. 2021. ‘Comparative Semitic and Hebrew Plural Morphemes.’ In *New Perspectives in Biblical and Rabbinic Hebrew*, edited by Aaron D. Hornkohl and Geoffrey Khan, 117–44. Cambridge Semitic Languages and Cultures 7. Cambridge: University of Cambridge Faculty of Asian and Middle Eastern Studies and Open Book Publishers. <https://doi.org/10.11647/OBP.0250.06>
- Penrice, J. 1994. *A Dictionary and Glossary of the Qur’an*. Delhi: Low Price Publications.
- Procházka, S. 2004. ‘Unmarked Feminine Nouns in Modern Arabic Dialects’. In *Approaches to Arabic Dialects: A Collection of Articles Presented to Manfred Woidich on the Occasion of*

- his Sixtieth Birthday*, edited by M. Haak et al., 237–62. Leiden: Brill.
- Rubin, Aaron. 2010. *A Brief Introduction to the Semitic Languages*. Piscataway, NJ: Gorgias Press.
- Simeone-Senelle, M.-C., and A. Lonnet. 1991. 'Lexique soqotri: Les noms des partie du corps'. In *Semitic Studies in Honor of Wolf Leslau on the Occasion of his Eighty-fifth Birthday*, edited by Alan S. Kaye, 1443–87. Wiesbaden: Harrassowitz.
- Sokoloff, Michael. 2002. *A Dictionary of Jewish Babylonian Aramaic*. Ramat-Gan: Bar-Ilan University Press.
- Steingass, F. 2005. *Arabic–English Dictionary*. New Delhi: Asian Educational Services.
- Streck, Michael P. 2010. 'Feminine Gender on Old Babylonian Nouns'. In *Von Götten und Menschen: Beiträge zur Literatur und Geschichte des Alten Orients—Festschrift für Brigitte Groneberg*, edited by Dahlia Shehata, Frauke Weiershäuser, and Kamran V. Zand, 287–306. Leiden: Brill.
- von Soden, Wolfram. 1995. *Grundriss der akkadischen Grammatik*. Rome: Pontifical Biblical Institute.
- Waltke, Bruce K., and Michael O'Connor. 1990. *An Introduction to Biblical Hebrew Syntax*. Winona Lake, IN: Eisenbrauns.
- Watson, Wilfred G. 2008. Notes on the Gender of Nouns in Semitic. *Aula Orientalis* 26: 195–209.
- Yona, Mordechai. 1999. *Hebrew–Kurdish Aramaic/Kurdish Aramaic–Hebrew Dictionary*. Jerusalem: Mossad Bialik. [Hebrew]

FIELDWORK: CHANCE, CHOICE, CHANGE*

Janet C. E. Watson

Geoffrey and I have many things in common, and perhaps the most salient is that we have both collected and worked on our own fieldwork data over several decades. As I returned recently from Dhofar, clutching a Laryngograph microprocessor, a laptop, and a digital audio recorder, my mind slipped back to the first

* For support and help at various times before, during, and after fieldwork, I thank, among countless others, Werner Diem, Otto Jastrow, Gauthier Juynboll, Louise Johnson, Leoma Gilley, Tim Mackintosh-Smith, my BOCD colleagues, Bruce Ingham, Dick Hayward, Diana May, Samia Naïm, Alexander Sima, Werner Arnold, Ulrich Seeger, Abdullah al-Jarrash, Halimah Amin, Abd al-Salam al-Amri, Abd al-Wahhab al-Sayrafi and family, Abd al-Rahman Mutahhar, Abd al-Karim al-Arhabi, Nabil al-Maqalih, Askari Hujayran, Nwer, Miranda Morris, Domenyk Eades, Stephanie Petit, Mandana Seyfeddinipur, Saeed al-Mahri, Ali al-Mahri, Ali Musallam, Abdullah al-Mahri, Bxayta Musallam al-Mahri, Awxiyar, Ibrahim al-Mahri, Abd al-Aziz al-Mahri, Khalid Ruweya, Musallam Hazmay al-Mahri, Amer al-Kathiri, Nuur al-Mashani, Said Baquir, Bashir al-Jarrash, Barry Heselwood, Gisela Tomé Lourido, Fabio Gasparini, Andrea Boom, and Carlos Jair Martínez Albarracín. For financial support at various times over the years, I thank the British Academy and the Leverhulme Trust.

days of fieldwork in the Yemen Arab Republic, and to how fieldwork practice, my fieldwork practice, and I, have changed. I had spent a month of my two-month trip helping my PhD student, Andrea Boom, with her work on the flora of Dhofar and its relationship with traditional culture. Would this have happened in my day? I have never written these words up outside my personal diaries and notebooks. Now, as I contemplate retirement, I feel it is time. I have adopted the sub-title from Blevins (2004) *Evolutionary Phonology*. It works for her theory. It works for my fieldwork journey.

My hands are cold as I sit to approach this, up in my attic in Leeds, on an early January morning. I have written it in my sleep and in my awakenings, kicking through the cold, wet leaves of a late December in Leeds, toes sensing the hot desert sand of northern Dhofar, the blue Salalah waves.

Chance, I think, began when I spoke to my favourite lecturer, Dr Gauthier Juynboll, after the award of my BA degree. I knew I wanted to study Arabic dialects. I knew I wanted to study in the Peninsula. That was as far as it went. I had been offered a place at Exeter University. He told me not to stay. He told me to contact Prof. Werner Diem in Cologne. I would have loved to study in Germany—a choice I didn't make. Prof. Diem suggested I contact Bruce Ingham at SOAS—a good suggestion and a good choice. I registered at SOAS for a Diploma in Linguistics in 1984, which I started that academic year. The choice of Yemen came through multiple avenues: I wanted a region that was predominantly rural (the Yemen Arab Republic had a population of

7,813,475 in 1985 of which 81.63 percent was rural¹); I loved mountains; I wanted geographical diversity; I wanted a region that showed linguistic diversity. In the end, though, the choice was made for me when Louise Johnson, my friend and fellow student at Exeter told me, “Go to Yemen. I was born in Yemen.” That was it. For all the objective academic reasons, the crucial decision was subjective.

Before setting off for fieldwork in Yemen, another opportunity presented itself. My friend, Diana/Khadija May, also studying at SOAS, introduced me to Abdullah al-Jarrash, a Yemeni from Ibb who was working towards his doctorate in Cardiff. This provided me with an entrance to his family in Ibb and his relations in al-Junayd.

The fieldwork began in November 1985, landing in San‘a, Yemen, armed with a first-class degree in Arabic and Islamic Studies from Exeter University, a Diploma in Linguistics from SOAS, a small cassette recorder,² my readings of Goitein (1943; 1960), Diem (1973), Jastrow (1984; 1986), a handful of anthropological works, and an arrogance both that I could manage on my own and, having studied Generative Grammar at SOAS, that language was separable from culture. I knew nothing. I spent fifteen months in Yemen, travelling between San‘a, the mountains of Raymah, Ibb, Hubaysh and al-Junayd. My PhD on the phonology and verbal morphology of three rural Yemeni dialects of Arabic was completed and examined in 1989 (Watson 1989).

¹ <https://www.macrotrends.net/countries/YEM/yemen/rural-population>.

² I later used a reel-to-reel tape recorder loaned from SOAS.

With a PhD grant from the British Academy that would cover my Diploma year and two years of doctoral study, I attached myself to the British Organisation for Community Development (BOCD), the Yemen branch of the Catholic Institute for International Relations (CIIR), with connections to Oxfam, working on a feasibility study for women's literacy. That was my first mistake. I read avidly about literacy programmes and realised that, without first addressing the crucial question of what women would have to read at the end of the programme, without first asking what was being done for literacy on the local level, without understanding the local culture and people's expectations, any literacy programme was likely to fail. It did help me to travel, though, and I am very grateful to my development colleagues. It gave me the opportunity to stay in the western mountains in the centre of the Raymah governorate, al-Jabin, and to hear the dialect there—sketched tantalisingly by Werner Diem in his 1973 book. And opportunity—chance—is essential in fieldwork. I made mistakes—I remember in my arrogance walking around the ridge in al-Jabin and thinking I would be able to understand the dialect. I remember this years later when I spend the year in San'a with my husband and children. James, who had spent two years in Sudan and had excellent abilities in Arabic, would say, "I understand nothing. I hear no Arabic here." And that was San'a. In the *k*-dialect regions of Yemen, it was not just the *-k* ending for the first singular and second persons that was different. It was the phonology, the morphology, the syntax, and the lexicon. And I needed to be able to speak. My degree at Exeter equipped me with good reading and writing skills; listening and speaking,

though, were almost non-existent. And the Diploma did not help me much with phonetic transcription.

In those days, ethical consent was unheard of. Fieldworkers occasionally spoke of recording people without their knowledge, telling them (or not) afterwards. Risk assessment was unheard of. You seized every occasion. Recording was difficult. It was effectively impossible to explain the purpose of a doctoral research project to rural women, in particular, who had had no formal education. Men and women treated me with suspicion, and I lacked confidence. I also suffered from ADHD and depression. Not advisable attributes in a fieldworker. Most of my early work involved taking copious fieldnotes and working through them with local speakers.

I spent my early time in al-Jabin ‘the brow’, also written on the signposts الجبي, with the loss of final /n/, later in Kusmah and al-Ja‘fariyah. I stayed with BOCD colleagues in a Turkish fort on the brow. How different from Cairo, I thought! There it was assumed young women were out for a good time; here, as a woman, I would either be a doctor or a teacher. I chose ‘teacher’. Walking in the early morning, smelling the bread from clay ovens, and seeing beneath me the clouds—that I will never forget, and probably never experience again. At night, with no light pollution once the domestic generators had been turned off around 9pm, I would look up and see the stars as large as apples. Utter joy. That I will never experience again. During the day, I would walk from settlement to settlement. Steep, sheer mountains, houses perched, and then, without warning, a green opening. The green

openings, like the Austrian alms, felt like a fairy tale. I had travelled previously—Germany, Burgenland in Austria, Czechoslovakia, Spain, France—but I had never done what I had always wished for: I had never travelled backwards in time. This felt like that. I would sit with women and girls in dark, barely lighted rooms, they dressed in velvet gowns adorned with the silver jewellery typical of Northern Yemen. I sought to find some common ground. What could I say that would lessen the cultural divide between us? I had a mother and a father. I had my brothers. My short stature. Otherwise very little. I remember seeing friends from home in the faces and expressions of these girls. My friend, Carole, whom I would ride with in St Bees, and others. This would continue; it continues today.

Often in the field, I sense things I would never sense at home. The closeness to nature, sleeping in the open, sleeping on the roof. Perhaps it is this? I recall on the night of 14th–15th April 1986, sleeping on the roof in al-Hadiyyah, in Raymah, a place between the sheer, ragged mountains and the coastal plain of the Tihamah. I dreamt that planes came over the mountains and started dropping bombs. I woke the next morning to the news that US planes had bombed Libya from RAF Lakenheath in a raid code-named Operation El Dorado Canyon.³ More recently, as I landed in Salalah, a message would pop up on my phone from my friend, Ali, or from Awxiyar: *bār waṣṣlāṣ?* ‘Have you arrived?’

³ 1986 United States bombing of Libya - Wikipedia. Later that month, two British and one US citizen were kidnapped and killed in Beirut in retaliation. BBC ON THIS DAY | 17 | 1986: British journalist McCarthy kidnapped.

He knew, she knew, that I had arrived. Coincidence, too: on my first trip to Salalah in December 2009, I was hoping to meet Ali Musallam, the man with whom Tom Johnstone had worked. My friend Ali told me to show him the number; he said, he lives two doors up from here by the mosque.

Al-Junayd, several hours on unmade roads from Ibb, lay at a far lower altitude than Raymah. I think I was the first western woman to reach the village. Trust is essential in fieldwork. I trusted Halimah, who handed me off to the shared-taxi driver, who handed me off to an old man, who took me to his house in the middle of the night. His daughters hennaed my feet and gave me their rope bed. The man then handed off me to another driver to deliver me the next day to al-Junayd. I stayed in the headman's house with his wife and extended family. In the mornings, I walked with the women to collect sorghum and grass for the cows. On certain days, a group of women would take our washing down to the spring and lay it out to dry on the rocks. Water was plentiful here, in contrast to al-Jabin, where we paid for water to be fetched in buckets and only rarely washed clothes. I wore tailored nylon dresses over cotton *sirwāl*. Even today it is common for sisters or young friends to wear the same dresses, and I remember Halimah ordering two blue dresses for us. She was slight and beautiful, making me feel like the ugly twin, but she was happy we wore identical clothes.

I had two near-death experiences: one in the Raymah mountains near Kusmah in 1986, as I was walking by night during Ramadan with a male companion. He suddenly told me to duck, and as I did so a bullet hit the rock face above us. The

second was more extraordinary, perhaps more Yemeni, given the huge number of deaths by road: I had decided a few days before this incident never to ride in a shared taxi again. (I had just returned from Ibb to San'a in a car that did the journey in half the time it should have taken. I was terrified.) But this time, with a colleague I had to do the journey to Abs in the Tihamah by shared taxi. No one in the taxi trusted the driver. He was young and impetuous. As we drove up a hill behind a laden lorry, he decided—why?—to overtake on the right, veering off the road, mounting the ridge. Passengers screamed. And as we finished overtaking, a second lorry crashed head on into the one we had overtaken, turning it onto the path we would have been on had the driver not taken that decision. He had no idea, but his thoughtless impetuosity saved our lives.

The humour of Yemenis is remarkable, even in times of adversity, and it is this, I think, that will stay with me. Once returning in a bus along the notorious Sumārah pass, we passed a water carrier that had overturned. The bus driver yelled out, *man yišti mā* 'who wants water?' Another time a woman friend described, quite matter-of-factly, an acquaintance being blasted onto the roof by a gas canister.

I returned to London fifteen months later with my notebooks and my ragged cassette and tape recordings. Culture shock is often described in fieldwork books. What is not described is the reverse culture shock you experience upon return from the field. On the way home, I stopped in the Netherlands and spent a couple of days with Gauthier Juynboll. That helped. But back in London I wanted space to talk about my experiences—not what I had

done and seen, but how I had felt—I felt changed, but I looked the same: the noise of London; the damp pollution and the unremitting artificial light at night; missing the overwhelming kindness of Yemenis. I didn't know how to begin describing what I now felt. I called Diana/Khadijah. Abdullah al-Jarrash had called to see her, and I went round. A small bit of Yemen still here.

My work on San'ani Arabic began in 1990 with a British Academy Post-Doctoral Fellowship. This time I was to work on a functional approach to syntax (Watson 1993). The theoretical model and presentation relied partly on Cowell (1964) and Quirk and Greenbaum (1973). Again, choice of geographical region was not entirely objective. Now married with a young son, I wanted to go somewhere more accessible than the western mountains, somewhere where I could start work within a day, somewhere we could perhaps go together as a family at a later stage, somewhere from which I could return quickly if necessary. It was easier to approach San'ani consultants. Tim Mackintosh-Smith helped greatly with connections, including Abd al-Salam al-Amri, who collaborated on *Wasf Şan'ā'* (Watson and al-Amri 1999), and Abd al-Wahhab al-Sayrafi and his family. At one stage, there were forty extended families in the Old City whom I visited regularly. I spent several hours a day listening and talking to determine the interaction of syntactic categories. I continued to use hardbacked notebooks, but during the early period of working on San'ani also relied heavily on file cards. The cassette recorders lacked robustness, such that each trip required a new recorder. I still have all the cassettes, a number of which were kindly digitalised by Ulrich

Seeger during my visiting professorship in Heidelberg 2003–2004; a large number still require digitalisation.

For work on *Waṣf Ṣan‘ā’* in 1997, with funding from the British Academy, I brought over a language consultant to the UK for the first time. From this time, I began to compensate consultants for their time by the hour, ensuring language consultant fees were included in grant applications. Abd al-Salam al-Amri and I would sit in my office and go over texts he or others had already recorded. Where additional texts were needed, we would discuss the content before he recorded, and we would then transcribe and translate together.

Between 2000 and 2001, we stayed as a family in the heart of the old city, between *sūg al-xaṣāb* and *sūg al-‘irg*, the donkey *sūg*. Our children, Alistair, aged 10, and Sarah, aged 6, went to a Yemeni school on Zubayri Street. They knew no Arabic when we arrived, but after a year passed their end-of-year exams with good results. Early one morning shortly before we left, I walked through the *sūg* with Alistair. A dreadful, deep feeling swelled up inside me at the time telling me this moment would never happen again. We would never again walk through the *sūg* in the cold, sharp morning. This was a moment suspended in time.

Roll forward the years. I began to work on Mehri in 2006. This decision was due to chance, tragic chance, not choice. My good friend, Alexander Sima, with whom I had worked while holding a visiting professorship in Heidelberg, had been killed in a freak car accident between Hawf and al-Ghaydhah on 3rd September 2004. He had gone to al-Ghaydhah after a conference in San‘a to collect final data for his *Habilitation*. For years I would

dream that he recovered. Occasionally I still do. Werner Arnold and I arranged to complete his book of texts from Jōdāb and Rēhān (Sima 2009). I worked through the typescript in Heidelberg in summer 2006 and went to al-Ghaydhah in early 2008 to read through and edit all the texts with Askari Hujayran, Alexander's main consultant. I stayed with Askari's family for six weeks, working with a single consultant, Askari, for three hours a day each afternoon. By now, I had stopped using cassette recorders and recorded extra material directly onto the laptop with an external microphone. Thanks to advice from Ulrich Seeger, my labelling of audio files now took the form YEARMONTHDAY_SPEAKER_TOPIC.

In 2009, Saeed al-Mahri contacted me from Salalah, thanking me for the work Werner Arnold and I had done on Alexander's texts and offering to find me consultants in Salalah for my work on Mehri syntax. Chance again, and choice to travel. I travelled to Salalah for the first time in December 2009 and, with considerable help from Saeed, his brother, Ali, his mother, and Ali Musallam, began work on the Mehri of Dhofar. The next year I met up with my second Dhofari family, Bayt al-Muforag, in the desert village of Rabkut. These are my families in Dhofar.

In the early days of studying Mehri, data collection in cases of working with women involved direct transcription into hard-back notebooks, and then reading back what I had written; where I worked with men, data was collected on a digital audio recorder, an Olympus LS-10, and material transcribed the next day together with the speaker. Transcription and translation were produced in Word documents. Since 2010, I have been able to

gain the trust of several older women. I record them, transcribe, and then check the transcriptions with them and/or with literate members of their families.

My fieldwork on Mehri and, from 2013, on Shehret has benefitted enormously from a greater general awareness of language documentation methods and from technological advances. I shudder to realise that it was only in early 2013 that I created metadata in a form that would make sense to others. Between January 2013 and December 2016, with co-investigators Miranda Morris and Domenyk Eades and with Saeed al-Mahri as the local research assistant, I led a community-based documentation study of the continental MSAL: Bathari, Harsusi, Hobyot, Mehri, and Shehret—the Leverhulme Trust-funded ‘Documentation and Ethnolinguistic Analysis of Modern South Arabian’ (DEAMSA). The main aim of this project was to collect, archive, and annotate monologue and dialogue texts relating to traditional ways of life. Working within a team for the first time, it was essential to label files systematically and produce consistent, coherent metadata using a system all agreed on. Files were labelled in the form YEARMONTHDAY_LANGUAGE_DIALECT_SPEAKERCODE_TOPIC, ensuring that much information about the file was retrievable from the file label. Metadata in Excel for audio and video files included date, speaker code, topic, file description, key words, place of recording, quality of recording, recording equipment, recording issues; metadata for speakers included date of birth (approximate in the case of older speakers), code name, place of birth, current location, education level, travel, languages spoken,

tribal affiliation. No more flimsy cassette recorders or cumbersome reel-to-reel recorders, the equipment used by the team were Olympus LS-11 audio recorders, Marantz Professional solid-state PMD660 recorders with external Audio-technica microphones, and Everio JVC camcorders. Several Olympus LS-11 recorders were left with key data collectors when the western researchers left the field. Local data collectors would record topics the main investigators had requested, label files according to the agreed system, and upload to Dropbox folders which were used as a conduit for material. The resulting metadata was produced by the main team members or by Saeed al-Mahri. The Olympus LS-11 has continued to work well for both the main investigators and local data collectors since January 2013.

Video recordings, produced for Mehri, Shehret, and Harsusi, have made me and my colleagues aware of both the importance of communicative gesture in speech, and the degree to which gesture is language specific. The use of camcorders and video recorders has also opened up interesting new potential for error—light problems, shaking, general movement, failing to capture the whole body—quite apart from the fact that the more equipment one has, the greater the chance of forgetting that one vital lead. The audio and audio-visual material collected during the DEAMSA project has been archived in the Endangered Languages Archive (ELAR) in five separate archives: Bathari, Harsusi, Hobbyot, Mehri, and Shehret. Transcriptions relating to archive material are produced using ELAN,⁴ a freely available

⁴ [ELAN | The Language Archive \(mpi.nl\)](http://mpi.nl).

programme whereby transcriptions, translations, and annotations can be aligned directly with the audio or audio-visual media.

A secondary aim of the DEAMSA project and its precursor was to examine the phonetics and phonology of Mehri and Shehret, a project continuing through my later Leverhulme Major Research Fellowship (2019–2023). For this, data has been collected acoustically, through a Laryngograph microprocessor (Lx) (also known as an electroglottograph [EGG]), which measures the degree of vocal fold contact. Since 2011, when I brought individual speakers with their individually made palates over to the University of Leeds, data also includes Electropalatography (EPG), which shows patterns of tongue–palate contact. Analysis of the instrumental phonetic material resulting from Lx and EPG recordings is conducted by Barry Heselwood. Acoustic data are segmented and annotated through Praat (Boersma and Weenink 2017), with assistance from Andrea Boom and Carlos Jair Martínez Albarracín. Quantitative analysis is conducted by Gisela Tomé Lourido using Praat scripts and R. For the current project, fieldwork preparation involves collaboratively drawing up word lists on the basis of identified data gaps.

The digital revolution has had a major effect on fieldwork methods. If I ever needed extra data while working on San‘ani, I would write to Tim Mackintosh-Smith, asking him to check a word or a paradigm with language consultants. I would then wait for the answer, Yemeni and British post permitting. Any extra data I would have needed from al-Jabin, Kusmah, or al-Junayd I could gather only by returning to the field. Today I can send a

WhatsApp message to friends and consultants and receive an answer within the day. I can check answers from consultants with other consultants. Digital recorders left in safekeeping with consultants mean I can request data that is sent and downloaded from Dropbox. The digital revolution also allows the fieldworker to check in with colleagues at home: sharing files on OneDrive, acoustic and Lx recording quality was checked by Barry and Gisela during the 2021 fieldwork trip before I continued to record, word lists were adjusted to account for new findings, and a joint decision was made to include audio-visual data in order to examine silently articulated final sonorants.

But the digital revolution comes at considerable cost: in my early years of travelling with no affordable means of contacting home, total immersion was possible. Total immersion enabled me not only to learn the language variety in question, but also helped keep my ADHD at bay. It would take a brave fieldworker to leave behind their smartphone today. The smartphone has resulted in decreasing attention spans of both fieldworker and consultants: while in my early days of studying Yemeni Arabic and Mehri, people would sit around the fire in the evening and chat, today many sit, hugging their smartphones. A bit of a story and then YouTube or someone calls.

Other changes in fieldwork include the need to obtain risk assessment clearance and ethical approval from the University. One time, shortly before the Covid-19 pandemic, ethical approval took over two months to obtain. Patience is still one virtue I strive for. Today I can get a visa for Oman online with visa approval within 24 hours. For Yemen, I would either travel to the Embassy

or send my passport, hoping it would return on time. Physical exercise has also changed. When I look back, I realise that the amount of exercise I have done during fieldwork decreased exponentially: in the 1980s, I would walk or climb every day, often long distances; in San'a, I would walk across the old city, climbing stairs of the tower houses to visit families, shopping, or visiting with friends; in al-Ghaydhah, I sat in Askari's house, and any physical exercise involved playing with the children to practise Mehri imperatives; in Rabkut, I would walk out with Bxayta to tend the goats, before the rains failed, occasionally taking goats out to graze in the afternoon; in Salalah, any walking is planned exercise and I frequently count turning the steering wheel of my hired car or tidying up after friends' children as exercise. This drop in exercise, in movement, is partly due to change in fieldwork location from the western mountains of Northern Yemen to cities and towns; partly due to urbanisation and socio-economic change, such that the people I work with no longer practise livestock husbandry or engage directly with the natural world.

My fieldwork practice has also changed through learning and gaining from colleagues: Miranda Morris told me in the early days of the DEAMSA project that she always checked new terms and phrases with at least three speakers of the language variety. Only if three people agreed independently would she record the term or phrase. My connections in Dhofar, initially kindly shared with me by Miranda Morris, mean it is far easier to connect with new consultants than it ever was in Yemen.

When I ask my good women friends in Dhofar, "Was life better in the past?" they say, "No. We had nothing." Asked the

same question, my grandmother would have replied, "Yes. It was." 'Nothing' means that nothing was given: water, fuel, and fodder had to be fetched; food was gathered, raised, or hunted; livestock was herded by girls and women in the case of goats, by men in the case of camels; water was sourced. Modernisation means that life is easier; but so much has also been lost: a life lived predominantly out of doors is now lived mainly within four walls and under a roof; knowledge of plants and fauna is rarely found among the younger generations; nature is something you visit for a picnic; the symbiotic relationship between nature and human life has been lost; the mobile phone has resulted in ever decreasing attention spans. Far more prosaically, for the fieldworker, although the equipment is more affordable, portable, and better, recording conditions are not. Today the fieldworker has to contend with noise from all angles: the plane flying overhead, the battery of mobile phones, air conditioning in the next room, television, the fridge, traffic, horns, children's cries bouncing off bare walls in sparsely furnished homes. On one fieldwork trip, I collected the first recordings in my hotel room, reasonably well-furnished, but disturbed on occasion by the hum of the fridge next door, the neighbour's television, or the sea, if the wind was strong. In my upstairs flat, the clacking water pumps and ventilation systems on the roof and the lift spilt extraneous sound into the recording. Said Baquir kindly offered me his office, and we scurried around turning off the air conditioning throughout the building. On several occasions I recorded in the car, throwing a shawl or blanket over the speaker's head and hoping against hope

that that blasted motorbike would not speed by during the recording.

My consultants are my friends and, as friends, we look for similar experiences that bind us. We worked out that Bxayta, nicknamed ‘the Mehri Dictionary’, was born in the same month as I—in May 1959 during what is known locally as ‘the Year of the Drowning’, in reference to the capsizing of two boats off the Dhofar coast and resultant loss of life. I would share stories of my grandmother, thinking the social differences between the UK and southern Arabia would have been far fewer in her days. And I feel the tugging need to maintain connections: Halimah, the ex-wife of Diana/Khadija’s friend whom I first stayed with in Ibb in 1986, is about the same age as me. I would always go to see her when I visited Yemen, travelling down to Ibb from San’a the day after landing before the fear of tackling the Sumārah pass became too great. In 2008, Halimah moved house and I lost contact with her. In January 2020, I was invited to meet Ali Salim al-Huraizi, the leader of the Mahrah resistance in Yemen. With him was a journalist from Ibb who wanted to interview me. During the interview, I appealed to Yemenis for information about Halimah. By Yemeni custom, I should not have used her name, but I needed to, if I were to receive any news. A month after my return, an email popped up in my inbox, “I am Bashir, the son of Halimah. She sends her regards.” We spoke by video that afternoon and remain in touch.

Fieldwork is difficult, often frustrating and full of potential for error. We often feel alone, but as this essay shows, the fieldworker is never alone. I have learnt through the kindness of

strangers that anyone can be your teacher. I continue to travel back in time, though not as I did in the western mountains of Northern Yemen. My time travel now is through my memories and through the stories of my older women friends. How fantastically wonderful it would be to take them by the hand and return to their youth, if just for one day.

References

- Blevins, Juliette. 2004. *Evolutionary Phonology*. Cambridge: CUP.
- Boersma, Paul, and David Weenink. 2017. Praat: doing Phonetics by Computer (uva.nl)
- Cowell, Mark W. 1964. *A Reference Grammar of Syrian Arabic (based on the Dialect of Damascus)*. Washington, D.C.: Georgetown University.
- Diem, Werner. 1973. *Skizzen jemenitischer Dialekte*. Beirut: Orient-Institut der Deutschen Morgenländischen Gesellschaft and Wiesbaden: Franz Steiner.
- Goitein, Shelomo D. 1934. *Jemenica: Sprichwörter und Redensarten aus Zentral-Jemen*. Leiden: Brill.
- . 1960. 'The Language of al-Gades: The Main Characteristics of an Arabic Dialect spoken in Lower Yemen'. *Le Muséon* 73: 351–94.
- Jastrow, Otto. 1984. 'Zur Phonologie und Phonetik des San'ānischen'. In *Entwicklungsprozesse in der Arabischen Republik Jemen*, edited by Horst Kopp and Gunther Schweizer, 289–304. Wiesbaden: Dr Ludwig Reichert.

- . 1986. 'Alles über Qāt: Ein Text im arabischen Dialekt von Jiblah (Nordjemen). *Zeitschrift der Deutschen Morgenländischen Gesellschaft* 136: 23–55.
- Quirk, Randolph, and Sidney Greenbaum 1973. *A University Grammar of English*. Longman: Harlow.
- Sima, Alexander. 2009. *Mehri-Texte aus der jemenitischen Šarqīyah: Transkribiert unter Mitwirkung von Askari Hugayran Saad*. Edited, annotated, and introduced by Janet C. E. Watson and Werner Arnold. Wiesbaden: Harrassowitz.
- Watson, Janet C. E. 1989. 'Aspects of the Phonology and Verb Morphology of Three Yemeni Dialects'. PhD thesis, SOAS, University of London.
- . 1993. *A Syntax of Šanʿānī Arabic*. Wiesbaden: Harrassowitz.
- Watson, Janet C. E., and Abd al-Salam al-Amri. 2000. *Waṣf Šanʿā: Texts in Šanʿānī Arabic*. Wiesbaden: Harrassowitz.

‘THE COBBLER MADE MONEY FROM THE TOWN OF ‘IFĀČ’: A SATIRICAL POEM IN IRAQI ARABIC ON CORRUPTION IN THE IRAQI PARLIAMENT

Clive Holes

Invective poetry and lampoon (هجاء *hiğāʿ*) has a long history in Arabic literature, going back at least as far as the seventh century *naqāʾid* ‘flytings’ of the Umayyad poets Jarīr and Farazdaq. In the modern Arab World, we note the ubiquity of colloquial poetry as a vehicle for social and political satire. In Egypt, the works of such popular poets as Maḥmūd Bayram al-Tūnisī (1893–1961), Ṣalāḥ Jāhīn (1930–1986), and Aḥmad Fuʾād Nig̃m (1929–2013), and in Iraq, those of ‘Abbūd al-Karkhī (1861–1946), ‘Azīz ‘Alī (1911–1995), and ‘Abbās Jījān (1951–) span more than a century of tumultuous political events in which the two countries emerged from British colonial control to espouse various incarnations of self-determination (*taqrīr al-maṣīr*, as the 1960s MSA jargon termed it). They provided an often highly amusing running commentary on the events and personalities of their time, written in the language of the street, not of an educated elite, which earned them the opprobrium of colonial occupiers and

home-grown politicians alike. In the case of four of the six named above, their reward was exile (al-Tūnisī, Jijān) or prison (‘Azīz ‘Alī, Nigm). Another of them, al-Karkhī, who founded a newspaper (*al-Karkh*) to express his opposition to the British and support the cause of Iraqi nationalism, had it closed down by the British on multiple occasions, and the water supply to his farms south of Baghdad cut off for good measure. Earlier, under the Ottomans, he had been a wanted man, forced to live in the desert for his own safety. Political poetry has been the weapon of choice of many perfectly ordinary people, too, and the modern communications of today, especially the internet, have provided them with a means of reaching a much wider audience than was possible hitherto. Such ‘poetry of the little people’ is of course not produced, disseminated, and consumed in an artistic vacuum—it references popular traditions of poetic form and language which are more or less well-known to ordinary readers, as I hope to show briefly in this paper, which is affectionately dedicated to my long-time friend and colleague Geoffrey Khan.

In Iraq, the former Saddam favourite and one-time General Secretary of the Assembly of Iraqi Popular Poets, ‘Abbās Jijān, living since 1993 in self-imposed exile in the Netherlands, has been particularly vocal not just about Saddam’s iniquities, but in his critique of the post-Saddam settlement in Iraq, notably in his lengthy 2010 poem, written in the form of a letter to the then newly elected President of the United States, Barack Obama,⁵¹² and first aired on Saudi television. The present article focuses on

⁵¹² See Holes (2011) for the Arabic text, an English translation, and a commentary.

a poem by a much less well-known Iraqi poet, which first appeared on several Iraqi internet web-sites in the aftermath of the American invasion of the country at roughly the same time as Jijān's broadside, and then 'went viral'. The poem is about corruption in the Iraqi parliament set up by the Americans. The language is authentically Iraqi and the poem makes use of several well-known Iraqi adages in such a way that on internet bulletin boards the poem was at first widely—but wrongly—assumed to have been written by the father-figure of Iraqi popular poetry, 'Abbūd al-Karkhī, who died in 1946. Many internet posters (copying each other) commented that "it was written 70 years ago, but it is as if it was written today."

Despite some superficial similarities to al-Karkhī's work,⁵¹³ it could not have been written by him, as a few moments' careful perusal of the text would have shown. For example, there is an allusion to the payment of Iraqi parliamentarians in American currency (v. 2), something unknown in al-Karkhī's time; and although oil was first struck in Iraq in the late 1920s, the country wasn't 'swimming in oil' (v. 6) until many years after al-Karkhī's death; 'diabetes and high blood-pressure' (also v. 6), those modern scourges, were not public health issues in the dirt-poor Iraq of the 1920s and 1930s; and some of the Arabic idioms, e.g.,

⁵¹³ The poem has the same rhyme scheme and metre as Al-Karkhī's most famous composition, *Al-Mağraša* 'The Hand Quern', which seems to have been sufficient reason to convince many internet bloggers that it must be by him. Also, al-Karkhī does use the proverb which is the refrain of the poem and the title of this article at least once in his collected works, as noted by Al-Ḥajjiyya (2004, 302).

يُجي كل يوم افلم *yīḡi kull yōm bi filim* ‘he comes every day with a (different) film’ (v. 9), i.e., with a different fabricated story, were not current in al-Karkhī’s day, and nor was he in the habit of using MSA phrases, like *al-fasād al-mālī* ‘financial corruption’ (v. 8) in his poetry. The poem was, in fact, composed by the living Iraqi school-teacher and popular poet Sāmi ‘Abdul-Mun‘im,⁵¹⁴ and is an attack on the corruption of the present-day Iraqi parliament, not that of the Hashemite era of the 1920s/1930s (also set up by an invading foreign power, the British), with which its content does, however, have some similarities.⁵¹⁵

The title of the poem is *Gayyam ar-Raggā‘ min Dīrat ‘Ifač* (Al-Ḥanafī 1962, 1:296), an Iraqi proverb which literally means ‘The Cobbler Made Money from the Town of ‘Ifač’. This saying is applied sarcastically to anybody who practises a trade in a place where there are no customers for it, and, more broadly, to anybody engaged in a task which is by definition fruitless (McCarthy and Raffouli 1965, 373). The point is that the inhabitants of ‘Ifač, a town in southern Iraq, were Bedouin who always went bare-foot—so how could a cobbler ever make any money there? The

⁵¹⁴ A list of over eighty of the poet’s poems is at <http://www.al-nnas.com/ARTICLE/SAbdMunam/index.htm>. See also <http://www.al-nnas.com/ARTICLE/SAbdMunam/18m3.htm>, accessed on 6 September 2021, for a ‘clarification’ (*tawḍīḥ*) in which the poet points out that the poem discussed in this article is his and his alone and has been mistakenly attributed to al-Karkhī.

⁵¹⁵ Al-Karkhī’s poem *Al-Hirr wa l-Ġrēdiyya* ‘The Cat and the Rats’, written in the mid-1920s, attacks the duplicity of the British Mandate authorities in Iraq and the puppet parliamentary system they set up to do their bidding. See Holes (2019).

- Whenever they feel someone's squeezing their seat;
 Did the cobbler make money from Bedouin's feet?
- (2) Parliament's full of soft shoes and gold bling:
 In the past, money-grubbers, they'd do anything
 Now relaxed, on the fiddle, they live like a king!

من ابحس المقعد اشويه اندحج⁵²⁰

قيم الرگاع من ديرة عفج

برلمان اهل المحابس⁵²¹ والمدس⁵²²

عگب ماچانوا يدورون الفلس

هسه هم⁵²³ يمحخ⁵²⁴ وهم يختلس

⁵²⁰ اندحج *indaḥač* and *inda'ač* 'to be crowded out, pushed out'. What is meant here is that the MPs don't hesitate to blacken the character of anyone trying to muscle in and take their seat.

⁵²¹ محابس *maḥābis* SG محبس *miḥbas* 'gold ring'.

⁵²² مدس *midis* SG مداس *mdās* 'soft shoe, slipper'.

⁵²³ هم... وهم... *ham... wa ham* 'both... and...', throughout Iraq and the Gulf, a Persian borrowing.

⁵²⁴ In the internet version, the word يرتشي *yartaši* 'takes bribes' appears here, but the author rejects this as a third-party invention which, in any case, does not scan. He says in his *tawḍīḥ* that the correct text is يمحخ *yimaxmix*, which has the sense of being relaxed, taking things easy (Enam al-Wer, p.c.). But in the Youtube performance he says يفخفخ *yi-faxfix*, which has the meaning of showing off, acting ostentatiously. Either word would fit the metre and suit the context.

- If their salary's short by one cent, though, they bleat;
 Did the cobbler make money from Bedouin's feet?
- (3) One wears a headdress, so staid and sedate;
 But his history's shady, this old reprobate;
 In the space of three years he's made millions... but wait—
 His trick's to pull fast ones on all whom he meets...
 Did the cobbler make money from Bedouin's feet?
- (4) I can't tell if this fever's endemic or what...

⁵²⁵ سنت *sant* '(American) cent'. The US sent 12 billion dollars into Iraq after the invasion. It was never properly accounted for. See 'How the US sent \$12bn in money to Iraq. And watched it vanish' (<https://www.theguardian.com/world/2007/feb/08/usa.iraq1>).

⁵²⁶ انعقج *in'acaqāč* 'to feel hurt, upset'.

⁵²⁷ امعگل *m'aggāl* 'wearing a traditional head-dress with a rope (عگال *igāl*)'.

⁵²⁸ عالوادم *ala l-awādim* 'on people' < *a l-awādim* 'على الوادم'.

⁵²⁹ ايعبرله چلج *yi'abbir lih čalač* 'he pulls a fast one on him, cheats him'; چلج *čalač* in Iraqi is a 'trick, deceit'.

⁵³⁰ A reference to the Iraqi saying الحمى تجي من الرجلين *il-ḥimma tiġi min ir-riġlēn* 'the fever starts from the feet', i.e., problems originate from

- ‘Grab what you can’—that’s fair-play, is it not?
 Of turnips and radish we import a lot;
 And everyone’s looking for fat on their meat;
 Did the cobbler make money from Bedouin’s feet?
- (5) We’ve lost track of the truth in the fog of their lies;
 They seem so all-powerful, their words mesmerise.
- يا هو التكهضه اهو ايمثل العدل⁵³¹
 وگمنه نستورد الشلغم والفجل⁵³²
 لان کلها ضلت اتدور ودچ⁵³³
 قيم الرگاع من ديرة عفچ
 والله ضيعنه الصدگ من الچذب
 اتشوفه هيبه وحچيه المصفط
 عذب⁵³⁴

oneself or from one’s nearest and dearest, not from outsiders. The belief that fevers enter the body via the feet (and makes them feel cold) was once common in Iraq. See al-Shalji (1982, 1:600); Al-Ḥanafi (1962, 1:157). ‘Aziz ‘Alī, in one of his sung ‘monologues’ (*Yā Duktūr!*), first broadcast on Baghdad radio in 1939, makes use of the same proverb in a similar context when retailing the sad state of Iraq under the British-backed Hashemite monarchy: دا تجينه الحمه من رجليه! *da tiġīna min riġlēna* ‘this fever comes from our feet’. See Holes (2014, 229).

⁵³¹ يا هو التكهضه اهو ايمثل العدل *yāhu il tiguḍḍah əhwa yimattil il-‘adil* lit. ‘whatever you can grab, that represents fairness’.

⁵³² Implying that Iraq’s need to import such basic foodstuffs, which it once produced in abundance, shows the level to which it has sunk.

⁵³³ ودچ *widač* is the fat on cheap cuts of meat which can be extracted for further culinary use by boiling, something only a poor person would normally be driven to do.

⁵³⁴ حچيه المصفط عذب *ħačih al-muṣaffaṭ ‘aḍib* lit. ‘his carefully crafted words are sweet’.

- From the east to the west ياخذك وايردك ابشرق وغرب
they'll take you for a ride,
Then stick their knives in you, ⁵³⁵ وبسچاچينه يدچك حيل دچ
stab hard and repeat.
Did the cobbler make money قيم الرگاع من ديرة عفج
from Bedouin's feet?
- (6) Their meaningless talk's put ⁵³⁶ حيل دوخني الحچي الماله ربط
my head in a spin,
Diabetes, blood-pressure, and وصار عندي سكر وحصبه وضغط
spots on my skin!
How come, when a river of oil ⁵³⁷ اشلون احنا النسيح ابشط النفط
we swim in,
We've spines for our mattress ⁵³⁸ نفترش عاگول ونتغطه ابسچ
and thorns for our sheet?
Did the cobbler make money قيم الرگاع من ديرة عفج
from Bedouin's feet?
- (7) I can't tell the wolf from the گمت ما اميز الذيب امن الحمل
lamb anymore,
Wherever I turn, my heart امنين ما التففت گلي يشتعلم
burns to its core—

⁵³⁵ *bi sačāčīnah yidiččak ḥēl dačč* lit. 'he will stab you violently with his knives'; *ḥēl* is an adverb meaning 'strongly, with force'.

⁵³⁶ *il-ḥači il mā lih rabaṭ* < *il-ḥači illi mā lih rabaṭ* 'talk which has no coherence'.

⁵³⁷ *iḥna il nisbaḥ* < *iḥna illi nisbaḥ* 'we who swim'.

⁵³⁸ *niftiriš 'āgūl* 'we lie on camel's thorn' (a prickly shrub found in the desert).

- It's never seen folk follow
madmen before;
My hair has gone grey and I'm
lost on the street,
Did the cobbler make money
from Bedouin's feet?
- (8) O government members, saga-
cious and shrewd,
Financial corruption's your
real aptitude;
We knew when their tanks
brought you here we were
screwed!
But why, like big fish, must
you little fish eat?
Did the cobbler make money
from Bedouin's feet?
- (9) We need to distinguish the
good men and true,
Elect just the honest and eru-
dite few;
- انه ما شايف شعب يتبع خيل⁵³⁹
شاب راسي وتيهت كل السچچ⁵⁴⁰
قيم الرگاع من ديرة عفچ
يا حكومتنه الرشیده ام الوقار
الفساد المالي عنوان الچ صار
ندري جابوكم ابدابه وقطار⁵⁴¹
ليش ضليتوا سمچ يا كل سمچ
قيم الرگاع من ديرة عفچ
لازم انميز الزين امن الزلم
وننتخب كل من شهم صاحب علم

⁵³⁹ *xibal* = 'lunatic behaviour'; *mxabbal* means 'madman'.

⁵⁴⁰ *tayyaht kull is-sičač* 'I've lost all my bearings'; *سچچ sičač*, SG *sikka* is 'road, street, alleyway'.

⁵⁴¹ The line says literally 'tanks and trains'. He means the present-day parliamentarians, who were installed as a result of elections set up by the Americans.

And cock-and-bull stories from ⁵⁴²ونرفض اللي يجي كل يوم ابفلم
 chancers eschew,
 When they face the loss of من ايشوف المنصب اشويه اندرج
 their well-padded seat;
 Did the cobbler make money قيم الرگاع من ديرة عفج
 from Bedouin's feet?

2.0. Commentary

Verse 1

As is often the case in poems composed of quatrains, the opening line of the first stanza references the refrain which occurs at the end of each. Here it is reworded to focus on the poem's target: *هاي اللحه* *hāy l-liḥa* 'these beards', further specified in the second line as *liḥa msarraḥa* 'manicured' or 'well-tended' beards. The poet is referring to the MPs in the new Iraqi parliament. There is the possibility in the use of *liḥa* *لحه* that he is specifically referring to the Shi'i religious leaders who were elected in the framework of American notions of what proportional representation should look like in Iraq. The phrase *اتشوفه هييه* *tšūfah hēba*, repeated in v. 5, means literally 'you see him (= the average MP) as a figure of awe, deserving fear and respect', but this impression is undermined in the next line by his claimed tendency to insult any critic out of fear that the criticism is aimed at removing him from his comfortable parliamentary seat and all the perks that go with it.

⁵⁴² Lit. 'he brings a (different) film every day', said of someone who changes his version of events to suit the agenda of whoever is listening.

Verse 2

The connotations of the words used to describe the new parliamentarians (اهل المحابس والمدس *ahl al-maḥābis wa l-midis*) indicate that they are ‘new money’ who have been feathering their own nests, عگب ماچانوا يدورون الفلس *ogub mā čānū yidawrūn il-filis* ‘after they had once chased every penny’, i.e., scrounged a living by fair means or foul, by hook or by crook. But now هم يمنمخ وهم *ham yimaxmix u ham yixtilis* ‘they feel totally chilled out and embezzle (government) money’—the implication is ‘large amounts of it’. But old habits apparently die hard: if their government salary is even ‘one cent’ short, they feel hurt and upset (*in‘aqac̣*).

Verse 3

This takes the negative picture of MPs a stage further by focusing on one who wears traditional dress in an effort to look ‘venerable’ (امعگل بالوقار *m‘aggal bi l-waqār*), but who in fact has a shady history filled with shameful behaviour (كله عار *kullah ‘ār*). He made his millions in double-quick time by ‘pulling fast ones’ (ايعبرله چلچ *yi‘abbir lih čalač*).

Verse 4

The poem now takes a more introspective turn and asks the question, ‘how can we have allowed this to happen?’ A well-known Iraqi proverb is used: ‘Did this fever we suffer from start in our feet?’, i.e., is it home-grown and our own fault? Whatever the answer to that, the modern philosophy of ‘Grab what you can when you can’ is thought by most to be justifiable. One result is

that Iraq has been reduced to importing شلغم وفجل *šalgām u fiğil* ‘turnips and radishes’—cheap basic vegetables which were once produced in abundance in the Iraqi سواد *sawād* ‘alluvium’, the highly fertile lands of central Iraq between the Tigris and Euphrates. Just as bad is the fact that ordinary Iraqis these days must search hard to find the cheapest, fatty cuts of meat, as they cannot afford anything more expensive.

Verses 5–7

In these verses, the poet returns to the rhetorical tricks of the parliamentarians—they come out with honeyed words that sound plausible حچيه المصفت *ḥačīh al-muṣaffaṭ*), but which are calculated to deceive, and behind their lies and distortions lurks a ruthless brutality. Their arguments are an incoherent babble حچي الماله ربط *ḥači il mā lih rabaṭ*), and their incompetence is enough to make people ill and turn their hair prematurely grey. Who is acting in Iraq’s best interests, the poet asks, and who is the enemy within? It is no longer possible to tell, as truth and lies can no longer be distinguished. The fact of the matter is that Iraq, once a rich country (‘swimming in oil’), is being mismanaged for the benefit of a few profiteers.

Verses 8–9

The poet ends with a direct and sarcastic plea to the ‘big fish’ of the ‘rightly guided’ رشیده *rašīda*) and ‘dignified’ ام الوقار *umm al-waqār*) Iraqi government, put there by an unnamed ‘them’ (= the USA) with its ‘tanks and trains’, to take pity on the ‘little fish’ of

Iraq. He makes a further appeal, this time to his fellow countrymen, to elect only ‘decent and expert’ (شهم صاحب علم *šahim šāhib ‘ilim*) Iraqis and eject the opportunistic liars who currently occupy parliament. A forlorn hope, he obviously feels: he ends as he began, with the words which are proverbial in Iraq for an enterprise which has no prospect whatsoever of success: قيم الرگاع من ديرة عفج *gayyam ar-raggā‘ min dīrāt ‘ifač* ‘Did the cobbler make money from the town on ‘Ifač?’, or as we say in English, ‘And pigs will fly’.

References

- Al-Ḥajjiyya, ‘Azīz. 2004. *Al-ʿAmṭāl wa l-Ḥikāyāt al-ʿĀmmiyya al-Baghdādiyya fī Shiʿr al-Mullā ʿAbbūd al-Karkhī*. Beirut: Dār al-ʿArabiyya li l-Mawsūʿāt.
- Al-Ḥanafī, Jalāl. 1962. *Al-ʿAmṭāl al-Baghdādiyya*. 2 vols. Baghdad: Maktabat al-Muṭannā.
- Al-Shālījī, ʿAbbūd. 1982. *Mawsūʿat al-Kināyāt al-ʿĀmmiyya al-Baghdādiyya*. 3 vols. Beirut: Maṭbaʿat Dār al-Kutub.
- Holes, Clive. 2011. ‘Letter to Obama’. *Middle Eastern Literatures* 14/2: 185–95.
- . 2014. “Azīz ʿAlī, Iraqi “Monologist”. *Quaderni di Studi Arabi* (n.s.) 9: 229–37.
- . 2019. ‘Mullā ʿAbbūd al-Karkhī (1861–1946), Vernacular Poet of Early Twentieth Century Baghdad’. *Middle Eastern Literatures* 21/2–3: 225–39.
- McCarthy, Richard J., and Faraj Raffouli. 1965. *Spoken Arabic of Baghdad. Part Two (A) Anthology of Texts*. Beirut: Librairie Orientale.

ATTRIBUTIVE POSSESSION IN SOQOTRI: THE EVIDENCE OF THE ‘VIENNA CORPUS’*

Leonid Kogan and Maria Bulakh

Soqotri, a Modern South Arabian language spoken on the island of Soqatra (Gulf of Aden, Yemen; for a general overview, see Kogan and Bulakh 2019), displays a complex system of possession markers. While nominal possession (where both possessum and possessor are nouns) is consistently expressed with the genitive marker (*nota genitivi*) *di-* attached to the possessor (henceforth ‘*di*-marking’), pronominal possession (where the possessum is a personal pronoun) can be marked by three different devices:

- (1) an independent personal pronoun combined, sometimes with slight phonetic changes at juncture (Naumkin et al. 2014, 523), with *di-* (also referred to here as ‘*di*-marking’);
- (2) a pronominal suffix combined with the ablative preposition *men* (labelled ‘*men*-marking’) (Naumkin et al. 2018, 610);

* The article is written in the framework of the project 22-18-00163 supported by the Russian Science Foundation.

- (3) a pronominal suffix directly attached to the base of the possessum (with a restricted number of nouns only).

While *di*-marking is semantically unrestricted, *men*-marking covers various instances of the part–whole relation, most typically involving body part terms as possessums.¹ Even here, however, *di*-marking can be used, with non-rigid complementary distribution: if the possessive pronoun is not coreferent with any other constituent in the clause, *men*-marking is usually preferred; otherwise, a *di*-marked possessive pronoun is employed, which can often be omitted. With 3rd-person pronouns, this opposition functions as a device of referential aid (Kibrik 2011, 62–63): a *men*-marked possessive pronoun indicates that its referent is ill-accessible, and, in the case of referential conflict, it suggests the choice of the otherwise less likely candidate.

In recent years, the present authors have been intensely dealing with possession in Soqotri. As a result, a comprehensive description based on their fieldwork findings has been prepared (henceforth Bulakh and Kogan 2025).² The present article elabo-

¹ On the part-whole relation as a special type of possession, which is distinct from both ownership relation (possession proper) and kinship relation, see Aikhenvald (2013, 3–4). Crosslinguistically, part-whole relation and kinship relation often receive the same marking and are distinct from ownership relation. The opposition is usually described in terms of ‘alienable’ versus ‘inalienable’ possession (Koptjevskaja-Tamm 2001, 961; see Heine 1997, 10 for a brief survey of alternative terms).

² To appear soon in a collection of MSA studies edited by Sabrina Benjaballah and Julien Dufour.

rates previously achieved results, now using textual evidence collected and published by the great Austrian Orientalist and Semitist David Heinrich Müller, the virtual pioneer of research into the Modern South Arabian group. As elsewhere in our publications on Soqotri, we conventionally label the whole of Müller's texts 'the Vienna corpus', since all the pertinent sources (Müller 1902; 1905; 1907; and Bittner 1918) were published in the Austrian capital (many were also recorded and analysed there).

Generally speaking, the grammar and lexicon of the Vienna corpus, considerably larger than that so far collected and published by the Russian-Yemeni fieldwork team (CSOL I-II), is very close to those of the Soqotri variety spoken by our language consultants from the Da'rho tribe. Therefore, it is very helpful to clarify the linguistic facts observed and analysed in the course of our fieldwork—including possession marking. Unsurprisingly, some divergencies are also in evidence. Some of them may be attributed to the chronological gap of ca 120 years between the two corpora, but the possibility of dialectal differences should not be excluded.

The present study is based on an exhaustive perusal of the Vienna corpus, which has yielded an impressive number of more than 720 tokens of possessive constructions of various types. The aim of the subsequent sections is twofold. On the one hand, they present evidence on *di*- and *men*-marking in the Vienna corpus, thus considerably broadening the picture obtained from CSOL I–

II.³ On the other hand, it reveals a few positions where usage in the Vienna corpus differs from what has been recorded by the Russian-Yemeni team. Müller's transcription of Soqotri has been preserved, in slightly modified form, together with his German translations.

1.0. *Men*-marking in Product–Source Relations between Nouns

In the sources analysed in Bulakh and Kogan (2025), the ablative preposition *men* can link two nouns in a product–source relation. The same employment is found in the Vienna corpus.

- (1) *wu-ksó'o sis rey we-ílbib min esféroh*
 '...und fanden bei ihr den Kopf und das Herz des Vogels'
 (SAE VII 53.23–25)

In this example, the possessive meaning 'the heart of the bird' (*das Herz des Vogels*) clearly derives from—and is *de facto* identical to—the ablative 'the heart (taken) from the bird'.⁴

³ The use of pronominal possessive suffixes in the Vienna corpus (to some extent broader than in today's language) is treated in Bulakh and Kogan (2025, §3.6) and will not be discussed here.

⁴ There is one seeming example of *men* functioning as a true genitive marker introducing the non-agentive argument of a deverbal noun ('the story of X' = 'the story about X'): *istó'oh temtíloh min férehim di mískín* 'Beendet ist die Geschichte von der Tochter des Armen' (SAE VII 69.28–29). Its relevance is, however, undermined by the fact that the story is bilingual (Jibbali-Soqotri) and the Jibbali version, which presumably served as a kind of *Vorlage* for the Soqotri one, also displays *min*.

2.0. The Semantic Scope of *men*-marking in Pronominal Possession

2.1. *Men*-marking for Kinship Relations

Unlike modern Soqotri, the Vienna corpus features a few examples of *men*-marking introducing kinship relation (and similar types of social relations). The by no means numerous examples of this category are listed below.

‘mother’ [bíyyo]

- (2) *wu-firími déki di-téy máyhi bíoh ṭhadémo ... wu-férihim di mes bíoh ḥšes ál tenáfah ši*

‘Und die beiden Töchter, **die eine Mutter hatten**, waren emsig... die Tochter aber, **die allein eine Mutter hatte**, arbeitete nicht’ (SAE VI 354.19–22)⁵

‘children’ [embórye]

- (3) *‘ážeh di-ba‘áloh wu-bíroh embóriye wu-bé‘el mes embóriye minṭá wa-minṭá*

‘Eine Frau heiratete und gebar Kinder, und **ihre Kinder** heirateten dahin und dorthin’ (SAE VI 299.18–19)

‘children’ [megóšše]

- (4) *wu-elhé ‘egehéten ’órbeḥ wu-mésin megáši irbá‘ah*

‘Und diese Frauen sind vier und **ihre Kinder** sind vier’ (SAE VI 91.18–19)

⁵ Literally, ‘the girl whose mother was only one’.

‘husband’ [ʕag]

- (5) *wa-més ‘ag meš šem sá‘din*

‘Und **ihr Mann** hieß Saʕdin’ (SAE VI 140.12)

- (6) *‘eméroh heš dihé fírehim šḥarómk toš tió tke ‘anébe sa‘íd ménhi ‘aig*

‘Da sprach zu ihm seine Tochter: Er sei mir verboten so wie du, und nur Said ist **mein Mann**’ (SAE VII 94.1–3)

‘friend, lover’ [máḥref]

- (7) *‘ážeh di-tebóre féreh wu-més máḥref be-di-kidíri*

‘Eine Frau gebar einen Bastard,⁶ und **ihr Geliebter** war aus Di-Kidiri’ (SAE VI 278.7–8)

The Arabic loanword *wakīl* ‘the male parent to whom a girl’s marriage agreement is delegated’ may belong here, too.

- (8) *mon mes wukīl*

‘Wer ist **ihr Bevollmächtigter?**’ (SAE VI 150.25)⁷

2.2. *Men*-marking for Part–Whole Relations

Exactly as in CSOL I–II, most examples for *men*-marking come from the domain of the part–whole relation. This involves not only prototypical instances, but also a few other peripheral types of possessive constructions. Some of these show preference for *men*-marking, while others employ it only sporadically. As will be shown, the preference for *men*-marking in various subtypes is

⁶ In fact, likely a plural (‘bastards’), cf. the singular *forḥ* in SAE VI 236.9.

⁷ In this example, *men* can be alternatively interpreted as an ablative preposition (‘a representative from her’), cf. *men*-marking with *wukále* ‘marriage rights’ (SAE VI 148.9), where the bride is understood as the ‘cause’ of the event (Bulakh and Kogan 2025, ex. (102) with fn. 37).

not identical in the two corpora. Thus, unlike CSOL I–II, the Vienna corpus consistently uses *men*-marking in the domain of place–inhabitant relations, as well as in relations between names of action/state and argument. Conversely, ‘non-physical body parts’ display vacillation between *men*-marking and *di*-marking in both CSOL I–II and the Vienna corpus.

2.2.1. Body Part Relations

As in CSOL I–II (Bulakh and Kogan 2025, §3.2.1), the most conspicuous and frequent use of *men*-marking involves possessums referring to body parts. The following concepts from this category are attested with *men*-marking in the Vienna corpus (words not attested in CSOL I–II are marked with *).

‘back’ [tádaʃ] (SAE VI 71.5+), ‘beard’ *[láḥye] (SAE VI 89.7.11),⁸ ‘beard’ *[díḳehon] (SAE VII 26.10–11+), ‘belly’ [mər] (SAE VI 33.5), ‘body’ [gad] (SAE VI 211.5–6), ‘breast’ [gêḥe] (SAE VI 33.4+), ‘buttocks, anus’ [ʕánḳeher] (SAE IV 155.30–32+), ‘buttocks, backside’ [gózer] (SAE VI 254.16–17+), ‘ear’ [ídḥen] (SAE VI 9.19+), ‘eye’ [ʕayn] (SAE VI 17.30–31+), ‘face’ [féne] (SAE VI 9.1–2+), ‘feet’ [šérhon] (SAE VI 248.17+), ‘finger’ [éṣbeʃ] (SAE VI 107.12+), ‘fist’ *[ḏátem] (SAE VI 193.3–4+), ‘foot’ [šəb] (SAE VI 33.7+), ‘front leg’ *[ídbeh] (SAE VI 325.4–5), ‘hand’ [ed] (SAE VI 10.14+), ‘head’ [ri] (SAE VI 41.9+), ‘heart’ [élʔbeb] (SAE VI 21.7+), ‘heel’ *[médreḥem] (SAE VI 309.6–7), ‘lap’ *[ḏánaḥ] (SAE IV 79.24–26), ‘lock of hair’ *[raʔt] (SAE VI 227.16–17), ‘mouth’ [ḥe] (SAE VI 68.28+), ‘nail’ [tífer] (SAE VI 63.16), ‘neck’ [feḳréro] (SAE VI 325.4–5), ‘neck’

⁸ An Arabism (LS 231, Simeone-Senelle and Lonnet 1991, 1454).

[ʃáreb] (SAE VI 315.17–18+), ‘nose’ [náħrer] (SAE VI 3.14+), ‘penis’ [ʃázgeħel] (SAE VI 91.5+), ‘pubic hair’ *[ménsob] (SAE VI 312.3), ‘rib’ [žalʃ] (SAE VI 120.27), ‘side (of body)’ *[fer] (SAE VI 276.19–20), ‘small of the back’ *[móten] (SAE VI 169.3+), ‘teat’ [tódi] (SAE VI 91.21+), ‘testicle’ [kérʔħel] (SAE IV 155.30–32+), ‘thigh’ [erbébo] (SAE VI 33.5), ‘tooth’ [ʃále] (SAE VI 281.11), ‘tail’ [dénob] (SAE VI 324.20–21)

2.2.2. Part–Whole Relations with Inanimate Possessors

As in CSOL I–II (Bulakh and Kogan 2025, §3.2.2), *men*-marking is consistently used with possessums referring to parts of inanimate wholes, such as plants.

‘sprouts’: *meš šigéf* (SAE VI 29.16), *meš id šigéf* (SAE VI 101.8) (LS 425)

‘root’ [šerīħo]: *meš šérah* (SAE VI 29.17)

(9) *dórib šírehom húfor meš šérah*

‘Dorib ist ein Baum, dessen Wurzeln ausgegraben werden’
(SAE VI 281.13)

‘stem’ [gódiʃ]: *meš gódeħ* (SAE VI 29.18)

‘pollen’ [nébot]

(10) *lahyéren lehó meš nébit*

‘Schön wär’ es wenn ich dich befruchten könnte’ (SAE VI 238.16)⁹

Examples from other semantic groups attributable to this category are also in evidence.

⁹ *lehó meš nébit* ‘if I were your pollen’.

‘rice’ [írhez] (in a cooking pot)

- (11) *dihó sferíyye libínih wu-més írehez dehéb*

‘Der Kessel weiß * Golden die Speis’ (SAE VI 360.6–7, a riddle for ‘egg’)¹⁰

‘dirt’ [diyáf] (in the circumcision wound)

- (12) *‘af linká mes dur wa-més díah*

‘...bis es rein von Blut und Schmutz wird’ (SAE VI 292.14–15)¹¹

‘sources (of water)’ [šeb]

- (13) *rího di-díbeni minmáleḥ heb ke-més št’ob il-rího min gírgēh*

‘Das Wasser von Dibení ist gesalzen, obgleich **des Wassers Urquellen** in Gírgēh... sind’ (SAE VI 272.4–5)

Finally, in the following examples the possessum is perceived as a subset (without clearly defined boundaries) of a non-discrete whole. This employment can alternatively be interpreted as partitive use of ablative *men* (Bulakh and Kogan 2025, §4.2).

‘abundance; majority’ [dolk]

- (14) *gēleménoh nóyhir meš dólḵ be-ṭeyrébeh*

‘Die Fledermäuse sind Vögel, **deren Menge** sich in Höhlen aufhält’ (SAE VI 227.14–15)

- (15) *é’efo il-ye’ómer ‘ídihaḥ wa-dólḵ máyhīn ‘eghéten il te’ámerinš*

‘Die Leute bearbeiten das Drachenblut und **meistens** sind es Frauen, die es bearbeiten’ (SAE VI 232.232)¹²

¹⁰ *més írehez dehéb* ‘its rice is gold’.

¹¹ *mes dur wa-més díah* ‘its blood and its dirt’.

¹² *dólḵ máyhīn* ‘eghéten ‘most of them are women’.

‘half, part’ [fákh]

- (16) *te‘óšim mes le-fákh*

‘Binde fest **dessen Hälfte**’ (SAE VI 313.14)

- (17) *wu-tzá‘an disén ekeníoh mes fákh*

‘Sie nahmen von ihrer Speise **die Hälfte**’ (SAE VI 229.17–18)¹³

2.2.3. Spatial Relations

As in CSOL I–II (Bulakh and Kogan 2025, §3.2.3), spatial relations are compatible with *men*-marking in the Vienna corpus.

‘surroundings’ [háylíhil]

- (18) *iblég-ihin kehór itéher id ku‘haríten w-id hádoyb lil men le-háylíhil*

‘Du schickest sie, damit sie gehen in die Dörfer und in die Städte, die rings um uns herum sind’ (Bittner 1918, 136.36)¹⁴

- (19) *wa-kón etíhi íz‘em may le-háylíhil*

‘Und es saß da die Menge in **seinem Umkreise**’ (Bittner 1918, 72.32)

‘side’ [nášf]

- (20) *wa-‘énher tho meš le-inšáfoh*

‘Und er führte mich um sie rings herum’ (SAE VI 21.19)¹⁵

- (21) *wa-‘áže iz‘émo may le-nášf*

‘Und die Frau ihm zur Seite’ (SAE VII 70.7–8)¹⁶

¹³ *mes fákh* ‘half of it’.

¹⁴ *men le-háylíhil* ‘in our surroundings’.

¹⁵ *meš le-inšáfoh* ‘on its sides’.

¹⁶ *may le-nášf* ‘on his side’.

‘side’ [défɛ]: *ménhi le-défeh* ‘mir zur Seite’ (SAE VI 92.3)¹⁷

‘lower part’ [géme]

- (22) *iḥúfor káber ráḥab wa-méš be-géme ye‘úmor láḥad k(y)ófid*
 ‘Wird ein breites Grab begraben und am **untern Teil desselben** wird eine Schmale Höhlung gemacht’ (SAE VI 265.15–16)

‘middle’ [ʕamk]

- (23) *ṭhar ‘óben rékfif di-‘eykíloh maḥin be-‘ámk*
 ‘Auf einen breiten Stein, der in der Mitte aufgestellt ist’
 (SAE VI 269–70)¹⁸

- (24) *wa-ye‘úmor méš id-‘ámk ‘ébehon kenhíten*
 ‘Und in **deren Mitte** kleinere Steinen gelegt werden’ (SAE VI 310.19–20)

2.2.4. Abstract Properties

As in CSOL I–II (Bulakh and Kogan 2025, §3.2.4), *men*-marking is frequently used to introduce the holder of an abstract property. The prime example is *men*-marking of the bearer of a name. In the Vienna corpus—exactly as in modern Soqotri—*šem* ‘name’ consistently governs a *men*-marked possessive pronoun (ca. 80 examples). Unexpected *di*-marking (contradicting the distributional rules outlined above) for this noun is attested in four examples only, all adduced below.

¹⁷ *ménhi le-défeh* ‘on its side’.

¹⁸ *maḥin be-‘ámk* ‘in their midst’.

- (25) *tió 'eyríboh dse le-šém*
 'Wie man schon aus dem Namen erkannt' (SAE VI 232.13)¹⁹
- (26) *dihó šem kor išē'óli*
 '...damit **mein Name** groß werde' (SAE VI 286.14)
- (27) *iném di-ě šém*
 'Wie ist **dein Name**?' (SAE VI 16.25)
- (28) *ló'o tré'ihin dihó 'an šem*
 'Warum fragst du nach **meinem Namen**?' (SAE VI 16.27–28)
- Terms for 'appearance, shape', 'sort, kind', and 'colour' also introduce their pronominal possessors via *men*-marking (with sporadic exceptions).
- 'kind, sort; breed, pedigree; color' [kɔn]
- (29) *'aig di-šoté'e... íken mes [sic!] kân háher*
 'Ein Mann, der traurig ist... **dessen Gesichtsfarbe** ist schwarz' (SAE VI 274.8–10)
- (30) *wu-'ére tken 'alm be-'élhe di-díye mes kân*
 'Ere bedeutet ein Zeichen an einer Kuh von guter Gattung' (SAE VI 313.6–7)²⁰
- (31) *wa-'éygek lahré meš min kân*
 'Ich möchte aber **dein Ebenbild** suchen...' (SAE VI 196.2–3)
- (32) *mek ken hálhal*
 'Sieh den Tölpel!' (SAE VII 10.16)²¹

¹⁹ *dse le-šém* 'from **her name**'.

²⁰ *di-díye mes kân*, literally 'its **breed** is good'.

²¹ Literally, 'your kind is idiot' (= 'the kind of person you are is an idiot').

‘appearance’ [šenéh] (LS 431)

(33) *wa-meš šéne tió šéne di-mlák*

‘Er war anzusehen wie ein Engel Gottes’ (SAE VI 15.13)²²

(34) *wa-meš šíneh mifzá‘eh*

‘Und **sein Ansehen** war furchtbar’ (SAE VI 33.1–2)

(35) *wu-més šenéh díye*

‘das Aussehen ist hübsch’ (SAE VI 175.22)²³

Other pertinent possessums are designations of sizes and prices.

‘length’ [rímo]

(36) *di-lémi še‘úrok mer-rínhem wu-méš rímo diráh wu-šézir*

‘Di-lemi wird im Meere gefangen, er ist eine Elle und eine Spanne lang’ (SAE VI 324.20–21)²⁴

(37) *‘éziž... meš rímoh šézir*

‘Eine Angel wird... eine Spanne lang’ (SAE VI 209.15–17)

(38) *dihé rey meš rímoh baḥ*

‘Sein Kopf ist eine Spanne lang’ (SAE VII 98.16)

‘breadth’ [róḥbo]

(39) *wa-min ḥémseh ’om mes réḥboh dirá‘ain*

‘Eine große Schildkröte ist zwei Ellen breit’ (SAE VI 325.20–21)²⁵

²² *meš šéne* ‘his appearance’.

²³ *més šenéh* ‘her appearance’.

²⁴ *méš rímo*, literally ‘its length (is)’.

²⁵ *Mes réḥboh* ‘its breadth’. Note that the pronominal possession (*mes réḥboh*) is anticipated by the nominal one (left dislocation), where the *men*-marking is copied (*wa-min ḥémseh ’om*).

- (40) *‘éžiž... méš réhboh íšbah wa-faḫ*
 ‘Eine Angel wird... einen Finger²⁶ breit’ (SAE VI 209.15–18)
 ‘weight’ [mízān]
- (41) *‘émor heh be-mos be-mízān*
 ‘Und er sagte zu ihm: Um **ihr Gewicht**’ (SAE IV 150.4–5)²⁷
 ‘bride-price’ [mhar]²⁸
- (42) *kem mes mhar*
 ‘Wie hoch ist der Kaufpreis?’ (SAE VI 150.27)²⁹
- (43) *iném mes mhar*
 ‘Was ist **ihr Werbepreis**?’ (SAE VII 23.5)
 ‘price’ [ḥáyhor]³⁰
- (44) *dī-[te]áraḫ mes ḥáyhor mu’iéno*
 ‘...welches einhundert wert ist’ (SAE VII 74.8–9)³¹

²⁶ Correct to ‘one finger and a half’.

²⁷ Cf. SAE IV 150.6–7, 9–10. Interestingly, in 6–7 and 9–10 Müller adduces *dī-* as a variant for *men*. As far as lines 6–7 are concerned, the use of *dī-* is actually expected according to the distributional rules outlined in §1: *ezá‘es be mos be-mízān (be-dse mízān)* ‘I take her for (the price amounting to) her weight’ (the possessive pronoun is coreferent with the object pronoun of the verb ‘to take’).

²⁸ But note *dī*-marking in *bīši ši kâl dī-í mhar* ‘Ich hatte nur deinen Werbepreis’ (SAE VII 76.20).

²⁹ *mes mhar* ‘her bride-price’.

³⁰ Glossed by Arabic *qīma* ‘price’ in the edition. Cf. LS 173 (‘nombre’).

³¹ *mes ḥáyhor* ‘her price’. Contrast *dī*-marking in *wa-‘á tīb‘ol kâl dse mhar mu’iénoh* ‘Und heirate nur eine, deren Werbepreis hundert ist’ (SAE VII 73.18).

‘price’ [kíme]

(45) *w-išédion mes kímeh*

‘...und teilen den Erlös dafür unter sich’ (SAE VI 13.5)³²

(46) *gāliyah mésen kímeh*

‘**deren Preis** hoch ist’ (SAE VI 44.5)

The noun ‘*ed*, when used with the meaning ‘age’, must also belong here. It appears with *men*-marking twice (SAE VI 145.22 and 147.1–2), as against one instance of *di*-marking (SAE VI 146.5).

The noun *néfa*‘, when it designates a constant characteristic, namely, a person’s job or permanent occupation, may also belong here (see below, §2.2.9, for the relevant passages).

2.2.5. Body Parts Detached from Their Hosts

In CSOL I–II, the contexts in which the canonical body parts are detached from the body and are thus no longer integral parts, display vacillation between *di*-marking and *men*-marking (Bulakh and Kogan 2025, §3.2.5). In the Vienna corpus, the pertinent examples are rare,³³ and in most of them, *men*-marking is employed.

³² *mes kímeh* ‘its price’.

³³ Passages in which *men* is governed by a verb of separation and, therefore, best interpreted as an ablative preposition, are not treated in the present section.

‘bone’ [šóħlo]: *mes/meš/may ’éšħal* (SAE VI 108.1, 2, 3, 4, 10), *may l-éšħal* (SAE VI 119.5)

‘skull’ [kaħémoh] (LS 375; Simeone-Senelle and Lonnet 1991, 1462): *meš kaħémoh di rey* (SAE VI 119.7)

‘skull’ [gemgémo]

(47) *wu-kešomk meš be-gémgemó*

‘...und zum Frühstück den Kopf gegessen’ (SAE VI 353.12)³⁴

‘eye’ [ʔayn]

(48) *we-heyátoħ mes le-‘aíni be-šéfħah*

‘[Die Tante] nähte **ihre Augen** in ein Tuch’ (SAE VII 65.17–18)

In the following example, *di*-marking is employed.

(49) *dihó ‘aíni bé-’ed di-fírehim dihó di-ħéloh*

‘**Meine Augen** sind in der Hand meiner Cousine’ (SAE VII 69.7–8)

2.2.6. ‘Non-physical Body Parts’ and Other Non-physical Inalienable Possessums

The noun ‘*ed*’ ‘life, life duration, endpoint of life’ is compatible with *men*-marking. However, there is a good deal of vacillation in those contexts where *men*-marking would be expected for a ‘canonical body part’ (note similar vacillation for ‘*ed*’ with the meaning ‘age’ in §2.2.4).

(50) *loyk moy be-’ed*

‘Ich habe ihm die Seele genommen’ (SAE IV 62.5–6, 7–8)³⁵

³⁴ *kešomk meš be-gémgemó* ‘I had its skull for breakfast’.

³⁵ *loyk moy be-ed* ‘I’ve caught his soul’.

(51) *tzá'a ménhi 'ed*

‘Nimm **mein Leben**’ (SAE VI 27.17)

(52) *l(y)itár maš 'ed*

‘Gott erhalte **dein Leben**’ (SAE VI 51.25)

For *men*-marking see also SAE VI 91.10; 139.17; SAE VII 84.19–20. For *di*-marking see SAE IV 77.7; 95.13; 100.5–6; 153.6–8; SAE VI 28.12; 31.1; 34.5; 64.27–28; 83.13; 177.5; 200.18.

Another potential example of a ‘non-physical body part’ term is *kébšeb* ‘luck’.³⁶

(53) *díyye mak kíbšib*

‘**Dein Stern** ist gut glücklich’ (SAE IV 102.10–11)

Finally, *ó'orem* ‘road, way’, figuratively employed in SAE VI 200.8 as ‘meaning, sense’ (cf. example (83) in Bulakh and Kogan 2025), can well be seen as an instance of non-physical inalienable possessum:

(54) *itá meš 'órim dé di-méthál*

‘Dies ist der Sinn des Gedichtes’ (SAE VI 200.8)³⁷

2.2.7. Place–Inhabitant Relations

Place–inhabitant relations are consistently marked with *men* in the Vienna corpus, as opposed to CSOL I–II, where *men*-marking

³⁶ According to a personal communication from Miranda Morris, *kébšeb* ‘lucky star, destiny’ is never used in the literary meaning ‘star’ and is thus opposed to *kébkeb* which can mean both ‘star’ and ‘luck’.

³⁷ *itá meš 'órim* ‘Thus is its meaning’.

is only rarely observed in such contexts. The most instructive examples involve *ká‘ar* ‘house’. In the Vienna corpus, its possessor is always introduced by *men* when it is used with the meaning ‘place of residence’, apparently perceived as a constant quality, similar to such characteristics as name or size (for which see §2.2.4).

- (55) *wa-més ká‘er be-‘amḵ di-’órim*
 ‘... **deren Haus** an der Mitte des Weges war’ (SAE VI 53.13)
- (56) *hó’o mak ká‘er*
 ‘Wo ist **dein Haus**?’ (SAE VI 66.9)
- (57) *’éhe bug may ká‘er*
 ‘Hier ist **sein Haus**’ (SAE VI 81.6)
- (58) *wa-ye‘úrob may ká‘er*
 ‘Und **sein Haus** wird erkannt werden’ (SAE VI 87.5)
- (59) *wa-may ká‘er be-kām*
 ‘**Sein Haus** war in Kām’ (SAE VI 140.5)

Di-marking is used when the noun designates the structure itself.

- (60) *kesé‘enš h(y)éraḵ di-ḥan min ká‘er*
 ‘Wir haben ihm stehend in **unserem Hause** gefunden’
 (SAE VI 122.20–21)
- (61) *wu-nkóbihin diḥin be-ká‘er*
 ‘Wir wollen... sie in **ihr Haus** eintreten lassen’ (SAE VI 124.3)
- (62) *tšáyah be-díse be-ká‘ar*
 ‘Leuchtet es hell in **ihrem Gemach**’ (SAE VI 186.6)

- (63) *ldí e‘ámer heš meséǵid le-thér di-í di-ḵá‘er*
 ‘O könnte ich Moscheen dir bauen vor der Türe **deines Hauses**’ (SAE VI 204.16)
- (64) *ldi esóbiš dihá ḵá‘er*
 ‘O könnte ich wegtragen dich, **mein Haus**’ (SAE VI 251.15)
- (65) *ldi e‘áḵab sérambīleh be-‘ámḵ be-di’í be-ḵá‘er*
 ‘O dass ich ein Strickbett werde in der Mitte **deines Zimmers**’ (SAE VI 286.18)
- (66) *ḵalhéten di-í be-ḵá‘er*
 ‘die kleinen Kinder in **deiner Stube**’ (SAE VI 287.6)

Perhaps the same semantic nuance explains *di*-marking for *mášen* ‘house’ in SAE VI 226.5.

- (67) *rud salām dihá le-mášen*
 ‘Grüße mir **mein** geliebtes **Haus**’

The nouns *ḵalf* ‘place’ and *methálhel* ‘residence’ likewise consistently receive *men*-marking.

- (68) *wu-díš ‘ážeh mes ḵalf le-’amt rínhem*
 ‘Und diese Frau war von der Seite des Meeres’ (SAE VI 177.15–16)³⁸
- (69) *wa-‘aig di-ḵān meš ḵalf be-mtáḵo‘oh*
 ‘Und ein Mann, der **seinen Sitz** auf M. hatte’ (SAE VI 179.23–24)
- (70) *‘ážeh di-més ḵalf le-’amt rínhem*
 ‘Eine Frau, **deren Wohnort** an der Meeresküste lag’ (SAE VI 216.17)
- (71) *méyhen methálhel be-ḵágeher*
 ‘...**dessen Wohnort** im Haghergebirge ist’ (SAE VI 161.9)

³⁸ *mes ḵalf* ‘her (native) place’.

(72) *‘āli bar sínah may methálhel be-ḥadību*

‘A. b. S.s Wohnsitz war Hadibu’ (SAE VI 245.19–20)³⁹

Unlike in CSOL I–II, in the Vienna corpus practically all instances of *di*-marking with *ḥalf* can be explained by the rules of referential choice, as in SAE VI 179.25; 206.20; 232.16, 17; 258.12; 259.10; 283.13; 291.19; 295.13; 300.21; 311.4; 318.19; 329.5; 334.22; 335.2. The only anomalous case of *di*-marking is in SAE VI 339.1.

(73) *ye‘āmer dihé ḥalf biš šírmehin*

‘Er sagt: In **seinem Lande** ist ein dichter Baumwuchs’

2.2.8. Personal Belongings in Close Physical Contact with Their Possessor and Other ‘Body Parts by Association’

Items of clothing can sporadically feature *men*-marking (for similar examples in modern Soqotri, see Bulakh and Kogan 2025, §3.2.8).

‘clothes’ [fīkḥa]

(74) *wa-‘ām tšámah be-yesû‘ gedóho id etíhi min sáriš wu-lehémoh meš fīkeha*

‘Und als sie hörte von Jesu, kam sie hin zur Menge von hinter ihm her und betastete **sein Kleid**’ (Bittner 1918, 114.27)

Contrast *di*-marking in the following passages.

³⁹ *may methálhel* ‘his residence’.

- (75) *ber se* ‘eméroh ke láhamk *ḥeb dihé fīkeha* terofk
 ‘Denn sie sagte: Wann ich betaste nur **sein Kleid**, werde ich
 gesund!’ (Bittner 1918, 114.27, on the same page as (74))
- (76) *mon léhem dihó fīkeha*
 ‘Wer hat betastet **mein Kleid**?’ (Bittner 1918, 114.30)
- ‘pillow’ [ʕéymed] (LS 313)

- (77) *nehát mes* ‘éymed (rey)
 ‘ihr zu Häupten’ (SAE VI 41.21)⁴⁰

In the following examples, *men*-marking is perhaps motivated by the fact that the actual reference is to the ear which functions as “blanket” in a fairy tale.

‘blanket’ [míškel]

- (78) *wa-énkef ídihīn de* ‘aig wa-škel *may min míškel*
 ‘Und er breitete das Ohr des Mannes aus und hüllte sich in
seine Hülle’ (SAE IV 102.17–18)⁴¹
- (79) *názef may min nízaf ū škól may min míškel*
 ‘Breite aus sein Gewand und hülle dich in **seine Hülle**’ (SAE
 IV 103.6–7, see also 9–10)⁴²
- ‘bed’ [nízaf]

- (80) *názef may min nízaf ū škól may min míškel*
 ‘Breite aus **sein Gewand** und hülle dich in seine Hülle’
 (SAE IV 103.6–7, see also 9–10)

⁴⁰ *nehát mes* ‘éymed ‘under her pillow’.

⁴¹ Note *di*-marking in the version of the same text in the Abd al-Kuri variety (SAE IV 102.17–18).

⁴² See the preceding fn.

By extension, a few other objects closely associated with their possessors can be used with *men*-marking. Thus, *eḵníyo* ‘food’ is once attested with *men*-marking.

- (81) *mékin eḵonío dihá men ḵá‘er tzé‘e*
 ‘Eure Speisen sollt ihr aus meinem Hause hohlen’ (SAE VI 88.3)

Contrast *di*-marking in SAE VI 79.8 and 11 (in accordance with the distribution rules).

- (82) *nóki‘en ínhi dihá ‘eḵonío itok*
 ‘Bring mir mein Essen dorthin’ (SAE VI 79.8, see also 79.11)

The designations of “shadow” and “image” are likewise used with *men*-marking in the Vienna corpus, perhaps being perceived as parts of the object they reflect/represent.⁴³

‘shadow’ [mihl’ófo]

- (83) ‘af l-yédir nḥaṭ *mes miló‘oh*
 ‘Bis daß er wohnt unter seinem Schatten’ (Bittner 1918, 94.32)

‘something similar, commensurate; image’ [ḵadár]

- (84) *ledí edóy meš min ḵádár*
 ‘O könnte ich dein Bildnis schicken...’ (SAE VI 195.20)

At the same time, *gétta* ‘body, shape’ is once unexpectedly attested with *di*-marking in the Vienna corpus, perhaps to be explained by the fact that the term belongs to the periphery of the

⁴³ It is noteworthy that *mihl’ófo* is once marked with a possessive suffix (Bulakh and Kogan 2025, §3.6).

part-whole relation (contrast *men*-marking in CSOL as discussed in Bulakh and Kogan 2025, Section 3.2.1).

(85) *gédeḥ wu-zégid dihé gítteh*

‘...kamen sie und hoben auf **seinen Leichnam**’ (Bittner 1918, 134.29)

Compare also *di*-marking in the following example, where the close association between the two objects could otherwise have triggered *men*-marking.

(86) *wa-‘éymer ṭháreš šéřeš se wa dsé di-ríkob*

‘Man legte auf ihn den Bauch mit dem Magen’ (SAE VI 298.20)⁴⁴

2.2.9. Relation between the Name of an Action/State and Its Argument

The Vienna corpus yields several clear cases of *men*-marking introducing the argument of a verbal noun, a feature only seldom attested in CSOL I–II (Bulakh and Kogan 2025, §3.2.9). Thus, there are six examples in which the argument of a monovalent deverbal derivative is encoded as a pronominal possessor.

‘sleeping’ [démi]

(87) *wu-díš ‘ážeh mes ḥalf le-’amt rínhem*

‘Und diese Frau war von der Seite des Meeres’ (SAE VI 177.15–16)⁴⁵

⁴⁴ The exact translation is ‘the rumen (first stomach) and its (the rumen’s) omasum (third stomach)’. Good photographic illustrations of the underlying picture can be found in CSOL II.658–61.

⁴⁵ *mes ḥalf* ‘her (native) place’.

‘staying’ [déro]

(88) *kân meš déroh be-ḵóbehor*

‘Es war **sein Aufenthalt** in den Gräbern’ (Bittner 1918, 102.3)

‘nakedness’ [miftítaḥ]

(89) *wa-di-íz‘em mes le-fáne išóni mes miftítaḥ*

‘Derjenige, der von hir sitzt, kann **ihre Blöße** sehen’ (SAE VI 323.6–7)

‘aggression, struggle’ [šeniḥo]

(90) *wa-yhé rázaḥ wa-šíri mes min šiniḥoh*

‘Und er wurde müde und abgemagert wegen **ihrer Widerspenstigkeit**’ (SAE VI 299.4–5)

‘dining’ [taḏímo] and ‘sleeping’ [mšíʔef]

(91) *méki teḏáimoh ṭey wu-méki mšíʔef ṭād*

‘Wir essen das Nachtmahl zusammen und schlafen zusammen’ (SAE VII 86.28–29)⁴⁶

The following nouns, arguably bivalent, are also recorded with the agent encoded as the possessor (and the patient unexpressed).

‘help’ [méded]

(92) *médéd ménhi be-gúnhin*

‘In Gunhin suche bei mir Hilfe!’ (SAE VI 310.16)⁴⁷

⁴⁶ *méki teḏáimoh ṭey wu-méki mšíʔef ṭād* ‘our dinner (is) one and our sleeping (place) is one’.

⁴⁷ *médéd ménhi* ‘my help’ (= ‘help I can provide’).

- (93) *ná'e ménhi médéd ál béhel... sémak tekóse ménhi médéd*
 'Meine Hilfe ist jetzt noch nicht fertig ... dann wirst du bei mir Hilfe finden' (SAE VI 311.3–5)

'friendship' [ʔéyhín]

- (94) *trā ma'tiž(y)áni béne wu-lól yé'te méhi 'éyhín ál imóle kufýye wāl bíleh d(y)ahšís*
 'Zwei sind ineinander sehr verliebt, und wenn man ihre Freundschaft absammelt, füllt sie nicht eine Mütze oder eine andere Sache' (SAE VI 364.11–13)

'meaning' [žífiš]⁴⁸

- (95) *diól man mankaínah ye'órib mes be-žéyleh*
 'Wer nicht tóricht ist, wird seine [dieses Gedichten] Deutung wissen' (SAE VI 155.15)

- (96) *meš žéylaḥ tió dé di-min nišére*
 'Der Sinn ist wie der des vorangehenden Verses' (SAE VI 296.3)⁴⁹

- (97) *més žéyleh mébroi di-šédd*
 '...dessen Erklärung (ist) "die zwei Kinder des Donners"' (Bittner 1918, 64.17)

In the following example, the patient of the verbal noun is encoded as the direct object ("entering GN"), whereas the agent is encoded as the possessor ("their entering").

⁴⁸ This is the verbal noun of *žála* 'to tell' (note that the semantic shift 'to tell' > 'to mean' is known for the noun, but not for the source verb).

⁴⁹ *meš žéylaḥ* 'its meaning'.

- (98) *wa-kon mihí líkbe Bêt-Laḥem*

‘...als sie in Betlehem ankamen’ (SAE IV 48.19)⁵⁰

Remarkably, it is not always the subject which is encoded as the possessor. Compare the two examples below, both involving *rēbne* ‘decision; order, command’.

- (99) *wa-yhén ʾāl hēmeḥ mes rībneh*

‘Sie aber gehorchten **ihrem Befehl** nicht’ (SAE VI 177.10–11)

- (100) *mes rībneh dsé-ke bíoh*

‘**Die Entscheidung über sie** ist bei ihrer Mutter’ (SAE VI 41.29)

In the first example, the possessor of *rībneh* ‘advice’ is the agent, but in the second one it is an adjunct (“her decision” = “decision about her”).

In the following two examples, the direct object of the verbal noun is encoded as the possessor.

‘watching’ [maʿtībher]

- (101) *menhe maʿtībher be-míʿet ríyal*

‘Ich bin zu sehen um hundert Thaler’ (SAE IV 155.1–3, see also 9–10)⁵¹

⁵⁰ *mihí líkbe* stands for **méyhi ʾle-k^ebe* ‘at their entering’, cf. ‘*inda duḥūlihīmā* in the parallel Arabic text.

⁵¹ *menhe maʿtībher* ‘my watching’ (= ‘to watch me’).

‘kiss(ing)’ [mišréʔiš]

(102) *‘émor í meš mišréʔiš ‘ar ḥfaš ḥey be-ne‘ésoh di-šóde*

‘Er sagte: ‘Du, dein Kuß ist nur leicht, um ein bißchen Fische’ (SAE VII 20.11–13)⁵²

A few other possessive constructions can be seen as encoding the relation between the action/state and an argument. The difference between these cases and those discussed above is that there is no immediate verbal source for the head nouns – which, nevertheless, refer to actions or states and, as such, can be seen as semantic equivalents of verbal nouns.

‘condition’ [šarṭ]⁵³

(103) *wu-ntúḥo dé ye‘ámer mak šarṭ meb‘éloh wu-dež te‘ámer ménhi šarṭ ‘áže*

‘Und sie stritten, der sagte: **Dein Bedingnis** ist die Sklavin, und der sagte: **Mein Bedingnis** war die Frau’ (SAE VII 82.8–10)

‘need’ [ḥágeh]⁵⁴

(104) *ménhi ḥágeh ‘eyk lib‘ól di-é fírehim*

‘**Mein Begehr** ist, deine Tochter zu heiraten’ (SAE VII 75.25–26)

‘strength’ [láfi]

(105) *l(y)ítbur mak láfi*

‘Gott zerbreche dich’ (SAE VII 20.13–14)⁵⁵

⁵² *meš mišréʔiš* ‘your kiss(ing)’ (= ‘to kiss you’).

⁵³ An Arabism (LS 422).

⁵⁴ An Arabism (LS 166).

⁵⁵ Literally, ‘may your strength be broken!’.

‘illness’ [gólɛ]

(106) *ldi ehámaḥ meš be-g(y)óleh*

‘O könnt’ ich hören von **der Krankheit dein...**’ (SAE VI 223.16)⁵⁶

The *men*-marked possessor of *órem* ‘way, road’ can also be seen as the semantic exponent of the agent in the following example.

(107) *wa-máyhi ’órim déher le-múḏaha*

‘Sie... mußten immer Mudaha passieren’ (SAE VI 304.8–9)⁵⁷

In the following example, the semantic relation between the participant introduced by *men* (the Arabic loanword *duwē* ‘medicine’) is to be interpreted as that of an action and its patient (“my medicine” = “the medicine which cures me”).

(108) *’émor hēs iném moš duwē*

‘Er sprach zu ihr: Was ist **deine Heilung?**’ (SAE IV 96.22–23, see also 98.4–5)⁵⁸

⁵⁶ Contrast *di*-marking in *w-ehóši di-í min g(y)óleh* ‘...und so erkunde [ich] deine Krankheit’ (SAE VI 233.4).

⁵⁷ *máyhi ’órim* ‘their way’.

⁵⁸ Contrast *di*-marking in the same phrase, *wa-’émero heh diho duwē ’aṣab diḥ mīn šérhom* ‘Sie sprach zu ihm: Mein Heilmittel ist ein Zweig jenes Baumes’ (SAE IV 96.23–25, as well as *bīši dihó duwē kāl hal-yéḥye* ‘Mein Heilmittel ist Hal-yéḥye’ (SAE IV 97.23). In the parallel Abd al-Kuri version, the first passage displays the *men*-marking both in the question and the answer, whereas the second example employs *di*-marking exactly as does the main Soqotri text.

Finally, *néfa*‘, a verbal noun of *náfa*‘ ‘to do’, introduces the agent via *men*-marking in the following examples, where its meaning is ‘deed’ or ‘way of doing, behaviour’.

(109) *wa-loṭ šīni állāh maīhin nefe‘héten*

‘Als nun Gott **ihr Tun** gewährte...’ (SAE VI 27.4)

(110) *itá ménhi néfaḥ wu-’e‘águb d-íryem mífdok*

‘Dies ist **meine Art**, ich liebe lange Knäule’ (SAE VI 115.18)⁵⁹

The same noun can refer to a person’s occupation as a constant characteristic (thus, rather belonging to §2.2.4).

(111) *iném mak náfaḥ*

‘Was ist **dein Gewerbe?**’ (SAE VI 24.10)

(112) *ménhi néfaḥ kéyū*

‘...so ist **mein Geschäft** Stricke’ (SAE VI 115.7)

Still another meaning of *néfa*‘ is ‘the (amount of) work to be done (for somebody)’,⁶⁰ with the beneficiary introduced via *di*-marking. As in CSOL I–II (Bulakh and Kogan 2025, §3.2.9 fn. 35), it is unclear whether *men*-marking is possible here: the choice of *di*- may be explained by the presence of the antecedent (*ínhi* ‘to me’) within the same clause.

⁵⁹ Contrast *di*-marking in *ho ḥtīlihik... ló’o... di-é min néfāḥ* ‘– Ich machte ein Fehlgeburt. – Warum? – Durch deine Tat’ (SAE VI 118.8–9), *waláken dhēt néfaḥ kēmīl ken állāh* ‘Und es sei dir voller Lohn von dem Herrn’ (SAE IV 51.12), *kal tādēhen é’efo be-ḳá’er šiš dihé néfaḥ* ‘...[daß] jeder im Hause seinen Dienst leiste’ (SAE VI 217.13–14).

⁶⁰ *émo(r)k ínhi dihó néfāḥ* ‘Hast du mir meine Sachen gemacht?’ (= ‘the objects I have ordered from you’) (SAE VI 84.23).

Finally, there are two examples in which the *men*-marked possessive pronoun refers to the direct object of *néfa*‘ (note that the verb *náfa*‘ can be used as a transitive verb with the meaning ‘to treat [somebody], to process [something]’).

(113) *iném may néfa*‘

‘Was soll mit ihm geschehen?’ (SAE VI 16.9)⁶¹

(114) *ū be-régeb ibóde may be-néfa*‘

‘Und im Monate Regeb beginnt die Arbeit’ (SAE VI 43.20)⁶²

2.3. Ambiguous *men*

If the *men*-marked possessive construction syntactically depends on a verb of detaching, *men* can be understood as a true ablative preposition dependent directly on the verb. This can be illustrated via the following examples.

‘skin, hide’ [gad]

(115) *iṣúlob fá‘har wa-izú‘a meš gad*

‘Es wird geschlachtet und man zieht ihm die Haut ab’ (SAE VI 249.2–3) = ‘**its skin** is taken off’ or ‘**the skin** is taken **from it**’

(116) *ṣétar ‘oiégħen le-kálb wa-dóħes may šérihi*

‘Und der Jüngling schoß einen Hund und zog sein Fell ab’ (SAE VII 62.21–22) = ‘he flayed **his skin**’ or ‘he flayed **the skin from it**’

⁶¹ Literally, ‘what (is) his deed’ (= ‘what will be done to him’).

⁶² Literally, ‘they start with its (frankincense’s) work’ (harvesting of frankincense is meant).

‘dates’ [béʔi]

(117) *zéʔayk mes béʔi*

‘...von dem ich halbreife Datteln nahm’ (SAE VI 120.19) =
 ‘I took **its dates**’ or ‘I took **the dates from it**’ (about a
 branch of a tree)

(118) *ikúʃe ʔékre min míʃer wa-izúʔa meš ʔéyʃob*

‘...und wird davon... ein Zweiglein genommen’ (SAE VI
 311.9) = ‘**its branch** is taken’ or ‘**a branch** is taken **from**
it’

For similar examples in CSOL I–II see Bulakh and Kogan
 (2025, §3.3).

2.4. Terms for Bodily Liquids/Excretions/Exhalations and the ‘Product–source’ Relation

The use of *men* in certain contexts can be seen as a neutral position between the ablative *men*, marking the product–source relation, and the synchronic possessive marker *men*, marking certain peripheral instances of the part–whole relation (their marginality arising from contexts where the part is being/has been detached from its whole).

In the first place, this involves bodily liquids, excretions, secretions, and exhalations, as well as those body parts which are more frequently mentioned when they are separated from the body itself.

‘blood’ [dor]: *mes dur* (SAE VI 58.2–3, 14, 22), *may dur* (SAE VI 87.30)

‘excrement’ [ʃob]

(119) *lik‘ód mak le-medrémi * may ‘eb háher di-bámbe*

‘Es fließe nieder auf die Fersen dir * der schwarze Dreck von deiner Hirse’ (SAE VI 309.6–7)⁶³

(120) *di-yúta may ‘eb*

‘Der Dreck wessen wird gegessen?’ (SAE VI 360.19)⁶⁴

(121) *wu-géleménoh šem di-nóyhir wa-šém mes di-‘éb wa-yizú‘a mes ‘eb wa-ye‘úmor le-bámbe kehór tken díye*

‘G. wird sowohl von der Fledermaus als auch von **ihren Exkrementen** gesagt. **Ihre Exkremente** werden geholt und auf die Bambesaat gelegt, damit sie gedeihe’ (SAE VI 227–228)

‘mucus, slime’ [níšyet]

(122) *mes níšyet íken míšḥaš d(y)ehéb*

‘Ihr Nasenauswurf wird Goldmünze’ (SAE VII 64.11–12)

‘warmth’ [šéhem]

(123) *ke-šetó‘oh mak šáham * lónšek hek id ma‘féneh*

‘Wenn es spürt **deine Wärme** * Pißt es dir in das Gewand’ (SAE VI 338.7–8)

(124) *náfah tho min ser ‘arébeh * min ser máḥderá mes šáham*

‘Ich fühlte durch die Mauer * und durch den Vorhang **ihre Wärme**’ (SAE VI 236.22–23)

⁶³ The internal form of the latter part of the couplet—and, therefore, its relevance for our issue—is uncertain. Since *bámbe* ‘millet’ is feminine, *may* cannot relate to it. The millet’s ‘black dung’ is, evidently, the bat guano used as fertiliser (see below, present subsection).

⁶⁴ A riddle for hand-mill, its grain, and flour.

‘Voice’ and ‘speech, words’ can also be classified together with body products (see Bulakh and Kogan 2025, §3.4).

‘voice’ [ʕárho]

(125) *wa-hó húmaʕ may ʕárhoh*

‘Ich habe **seine Stimme** gehört’ (SAE VI 212.12–13)

‘word, speech’ [métaʕ]

(126) *lol igódiḥen mak méthal*

‘Wenn **dein Wort** eintrifft...’ (SAE VI 16.7–8)

(127) *karáme ál teḥómil ménhi méthal*

‘Wenn du **meine Rede** nicht verträgst...’ (SAE VI 64.6–7)

(128) *wál teʕórib máyhīn méthal*

‘Und sie kennt nicht **deren Sprache**’ (SAE VI 357.18)

(129) *karáme mes méthal kon ʔímehen dížen mes méthal iken ʔímehen*

‘Wenn **ihre Rede** wahr ist, wird auch die Rede der andern wahr sein’ (SAE VII 61.27–29)⁶⁵

(130) *mes méthal ʔímehen*

‘**Thre Rede** ist wahr’ (SAE VII 69.2–3)⁶⁶

(131) *himáʕken meš méthal*

‘Höret ihr **seine Rede**’ (SAE VII 87.4–5)

Contrast a few rare examples of *di*-marking with the same lexeme:

(132) *karáme igódiḥen di-é méthal*

‘Wenn **dein Wort** eintrifft...’ (SAE VI 16.25–26)

⁶⁵ *mes méthal* ‘her speech’.

⁶⁶ Note *di*-marking in a similar context in *di-é méthal ʔímehen* ‘Deine Rede ist wahr’ (SAE VII 81.9–10).

- (133) *āl kán de dihó méthal*

‘War dies nicht **meine Rede...**’ (SAE VI 27.11)

This type of relation involves body parts of animals which can be used, as food or material, after being detached from the animal’s body.

‘milk’ [šhaf]

- (134) *hélóbk mes šhof*

‘Und ich melkte **ihre Milch**’ (SAE VI 120.13)

- (135) *‘émor mésin šhof id gízeher*

‘Er tat **ihre Milch** in den Butterschlauch’ (SAE VI 128.27; 130.7)

- (136) *wa-tió ‘éyrob mésin šhof id gízeher*

‘Und als **ihre Milch** in den Butterschlauch kam...’ (SAE VI 128.28–29)

- (137) *di-āl toméžog ‘ážeh mes šhof*

‘...**deren Milch** eine Frau nicht trinken darf’ (SAE VI 128.31)

- (138) *hélébo mésin šhof*

‘[Sie] melkten sie’ (SAE VI 129.7)⁶⁷

- (139) *nholib mésen šhof*

‘Wir melkten **ihre Milch**’ (SAE VI 147.6–7)

‘meat’ [tɛ]

- (140) *wāl yúte may té*

‘Und wird **sein Fleisch** nicht gegessen’ (SAE VI 12.8–9)

- (141) *ū-měš te ‘émor id menékahal*

‘Und **dessen Fleisch** tat er in Wassereimer’ (SAE VI 87.31)

⁶⁷ *mésin šhof* ‘their (the goats’) milk’.

(142) *wu-féšiš mēsin be-té*

‘Er warf **ihr Fleisch**’ (SAE VI 123.20)

‘contents of a ruminant’s stomach’ [fort]⁶⁸

(143) *wa-‘émor may dur ū-méš fort id nógir*

‘Er tat **dessen** Blut und **Mist** in die Grube’ (SAE VI 87.30)

The same ambiguity can arise with a few other instances of the part-whole construction.

‘flour (from a hand-mill)’ [daḵīḵ]

(144) *dé ráḥa wa-yúta may daḵīḵ d-išrágaḥ may min mer*

‘Das ist die Mühle **deren Mehl** wird gegessen, welches herauskommt aus ihrem Bauch’ (SAE VI 360.20–21): ‘its flour’ or ‘the flour from it’

‘fragments’ [tíbihor]

(145) *ho šink máyhi tíbihor*

‘Ich sah **die Trümer derselben**’ (SAE VI 176.11): ‘their fragments’ or ‘the fragments (left) from them’, about two ships after a shipwreck

This involves, in particular, parts of plants and especially their fruit.

‘ziziphus fruit’ [žiréme]

(146) *wu-tók (toyk) mes žíreham*

‘[Ich] aß **dessen Früchte**’ (SAE VI 120.5)

⁶⁸ German *Mist* in the translation is not quite exact, see Naumkin et al. (2018, 662) for an image.

‘bark, peel’ [ḵalífo]

(147) *wāl tá‘la li-ḵóḥkoḥ meš ḵalífo tió šáḥez*

‘Und es ist nicht nötig die Rinde anzuschalen, wie beim Weihrauchbaum’ (SAE VI 232.6–7)⁶⁹

‘tamarind fruit’ [ḥóubheḷ]

(148) *šúbehor di-yúte meš ḥóbehal*

‘eine Tamarinde ... **deren... Früchte** gegessen werden’ (SAE VI 205.5–6)

‘inflorescence’ [ráḵaḥ]

(149) ‘*a tgérim mes ráḵaḥ*

‘Pflücket **ihre Früchte** nicht’ (SAE VI 312.10)

‘sprig of male inflorescence’ [ʔáṣab] (SAE IV 96.24–25)

In each of the pertinent passages, *men* can be interpreted in two ways—as a possessive marker or ablative preposition. It may well be that it was via this position that the possessive function of *men* developed (Bulakh and Kogan 2025, §4.2).

As in CSOL I–II, *di*-marking is also possible in contexts of this type.

(150) ‘*aíni di-díhi ídmeḥ di-tiḵó‘ed méhi*

‘Die beiden Augen, in denen die Tränen sind, die aus ihnen niederfließen’ (SAE VI 363.14–15)⁷⁰

(151) *ber-yhé á‘aḥan wu-diḥán te*

‘Denn er ist unser Bruder und **unser Fleisch**’ (SAE VII 49.23)

⁶⁹ *meš ḵalífo* ‘its bark’.

⁷⁰ ‘*aíni di-díhi ídmeḥ di-tiḵó‘ed méhi* ‘the two eyes whose tears flow from them’.

(152) *di-í fonš ber ál-še‘dlikk*

‘Denn **deinen Atem** liebe ich gar sehr’ (SAE VI 220.23)

3.0. The Choice between *di*-marking and *men*-marking for the Part–Whole Relation

As a whole, the evidence of the Vienna corpus agrees with the trends previously outlined by us for CSOL I–II: *di*-marked possessive pronouns are mostly used with highly accessible referents (thus, a *di*-marked pronoun is typically co-referent with another constituent within the same clause, most frequently its subject), whereas *men*-marked possessive pronouns are almost exclusively employed with referents of low accessibility.

To illustrate the essential agreement between the two corpora at this point, we will compare the extant evidence with *é‘ed* ‘hand, arm’ as the possessum. For CSOL I–II, see Bulakh and Kogan (2025, §3.5.2). In the Vienna corpus, the distribution outlined above is observed in the following cases.

3.1. *Men*-marking (22 examples)

(153) *wu-tkéno tri meš bé-‘ed*

‘Und es sind nun zwei in **seiner Hand**’ (SAE VI 195.16)

(154) *‘aig di-zé‘e kómeh di-‘akároh wu-més ħěh k(y)ófid wa-‘éygib l(y)ihrék mes wāl ‘ekéboh meš ‘éed id kéne*

‘Ein Mann, der ein großes Gefäß, dessen Öffnung schmal ist, nahm und daraus stehlen wollte, **dessen Hand** aber ins Innere nicht eindringen konnte’ (SAE VI 319.5–7)

(155) *wa-húmaḥ ihin e-‘háyhén dé-eb wenfériš máyhen mìn údi*

‘Da hörte es Ruben und wollte ihn aus **ihren Händen** retten’ (SAE VII 48.20–22)

- (156) *wu-‘á takán men ’edhéten* ‘eš
 ‘Unsere Hände aber sollen sich an ihm nicht vergreifen’
 (SAE VII 49.22–23)⁷¹
- (157) *wu-tároh meš bé-ed*
 ‘Und sie packte ihn an der Hand’ (SAE VII 80.29–30)⁷²
- (158) *wu-lé mes be-éd*
 ‘Er ergriff ihre Hand’ (Bittner 1918, 26.31)
- (159) *wa-kón bug ‘ayg di-měš éed* ƙešó‘o
 ‘Und es war dort ein Mann, dessen Hand vertrocknet war’
 (Bittner 1918, 56.1)
- (160) *‘af teƙó‘od meš le-ídi á‘žož tyó elhé*
 ‘...bis daß niedersteigen auf seine beiden Hände Kräfte
 wie diese’ (Bittner 1918, 120.2)

3.2. Di-marking (13 examples)

- (161) *fkots dse be-ídi wu-néfhót dse ‘ain*
 ‘Sie rieb es in ihren Händen, hauchte ihr Auge an...’ (SAE VII 69.11–12)
- (162) *ye‘ámer sen dihé bé-’ed*
 ‘Er tut sie in seine Hand’ (SAE VI 195.11)
- (163) *izá‘a ƙey dihé min ’ed*
 ‘Er nimmt eines von seiner Hand’ (SAE VI 195.13)
- (164) *ráhaž dihé ’ídi*
 ‘...er seine Hände gewaschen hat’ (SAE VI 203.15)
- (165) *wa-telóhom hóhi dse bé-’ed*
 ‘Sie berührt den Boden mit ihrer Hand und küßt ihre Hand
 mit dem Munde’ (SAE VI 226.15)

⁷¹ The editor adduces *di-hán* as a variant in brackets.

⁷² *meš bé-ed* ‘in his hand’.

- (166) *izégod dihi ʔidi wa-yúṭab dihé be-ʔidi dihé id bérki... wāl iṣṣáfṣef dihi be-ʔáni*
 ‘...erhebt er **seine Hände** und schlägt mit **seinen Händen** auf seine Knie... zuckt nicht mit den Augen’ (SAE VI 290.17–21)
- (167) *wa-ʔémor e ʔayg šābaḥ diê be-éd*
 ‘Und er sagte zu dem Manne: Du streckest aus **deine Hand!**’ (Bittner 1918, 58.5)
- (168) *tegódiḥen we-te-ákal diê ed ʔes*
 ‘Du kommst und legst **deine Hand** auf sie’ (Bittner 1918, 112.23)
- (169) *ʔar ber yhe ʔékal dihé idi le-gáʔiher ḥarúrihen wutrefiḥin*
 ‘...nur daß er legte **seine** beiden **Hände** auf wenige Krenke und sie gesund machte’ (Bittner 1918, 122.5)
- (170) *tšéfétaih dhê bi-ʔid*
 ‘Stich ihn in die Hand’ (SAE IV 70.7)⁷³

Just three exceptional examples violate these rules—as against the 36 ‘correct’ ones—are in evidence.

- (171) *wa-dihó ʔidi tenatáfo ímrher*
 ‘Und **meine Hände** troffen von Myrrhe’ (SAE VI 30.19)
- (172) *ʔaf taḳír dihá be-ʔidi*
 ‘...bis auf **meinen Händen** du groß werdest’ (SAE VI 205.20)
- (173) *ḥaúweróti dího ʔidi*
 ‘Schwarz sind **meine** beiden **Hände**’ (SAE VI 238.3)

⁷³ *dhê bi-ʔid* ‘in his hand’.

Remarkably, no examples of ‘incorrect’ *men*-marking have been detected: in each case, it is rather *di*-marking that is unexpectedly used. This is compatible with the distribution obtained for *’éd* ‘hand’ on the evidence of CSOL I–II (15 ‘correct’ examples versus two ‘exceptions’).

These statistics reflect the general picture. Indeed, the majority of the more than 700 tokens explored in the framework of the present investigation agree with the syntactic/referential rules outlined above. The total number of exceptions is 55, thus ca 8 percent of the whole number of the possessive tokens considered. Among these, very few pertain to unexpected *men*-marking in contexts where *di*-marking is predicted: only six reliable examples (one of them attested twice in a single story) of *men*-marking introducing the possessor coreferent with the subject of the clause have been detected in the entire Vienna corpus.

(174) *wa-’éšom dihé gága moy ke-tádaḥ*

‘Er band seinen Bruder an **seinen Rücken**’ (SAE IV 88.21–22)

(175) *erḳóḥo ḥaúlhel meš min éd*

‘Sie zog den Siegelring von **ihrer Hand**’ (SAE VII 30.10–11)

(176) *mékin eḳonío dihá min ḳá’er tzé’e*

‘**Eure Speisen** sollt ihr aus meinem Hause holen’ (SAE VI 88.3)

(177) *’ažíti ḳaṭaníti... ḥarírehen máyhi be-gádi*

‘zwei kleine, zarte Frauen’ (SAE VI 211.5–6)⁷⁴

⁷⁴ *máyhi be-gádi* ‘in their bodies’.

(178) *kése* ‘aig inʒef yhē idín wa-škel **moy idín**

‘Der Jungling fand einen Mann, dessen Ohren ausgebreitet waren und der sich in **seine Ohren** hüllte’ (SAE IV 102.13–15, see also 103.3–5)⁷⁵

(179) *wa-lót sett meš le-ḥáylihil*

‘Und hierauf blickte er auf in **seinem Umkreis**’ (Bittner 1918, 72.34)

These six ‘irregular’ cases are probably to be supplemented with the following example, where the use of *men*-marking is also not quite canonical.

(180) *wu-elhé egehéten mésin tídehe* ‘aṭobínsin le-kízeho

‘Und diese Weiber legen **ihre Brüste** auf die Schulter’ (SAE VI 91.21)⁷⁶

The majority of the ‘exceptions’ involve *di*-marking used instead of expected *men*-marking. Practically all the examples collected below involve core body part terms (in one case, example (193), a part of a tree).

⁷⁵ *Di*-marking in the first part of the sentence is predictable insofar as the verb is interpreted as active: ‘énʒef dīyhe ‘idéni ‘he spread his (own) ears’ (theoretically, Müller’s ‘énʒef could also stand for the passive ‘ínʒaf). *Di*-marking would also be expected in the second part, instead of the attested *men*-marking (*wa-škel mey ‘idéni* ‘he wrapped himself with his ears’). Note that in the Abd al-Kuri version *di*-marking is employed throughout.

⁷⁶ The sentence is arranged as a chain of left-dislocated constituents: ‘these women—their breasts—they put them upon their shoulders’. Accordingly, the possessive pronoun and its antecedent formally belong to different clauses (for similar examples of the *men*-marking with left-dislocated possessors see Bulakh and Kogan 2025, §3.5.2, with fn. 52).

The first subsection comprises the examples in which *the possesum is the subject of the clause*.

- (181) *ḥaúweróti dího ‘aíni*
 ‘Schwarz sind **meine** (beiden) **Augen**’ (SAE VI 198.15)
- (182) *ho tébehor wa-dihó tódii tió kóti*
 ‘Ich bin eine Mauer und **meine Brüste** Türmen gleich’ (SAE VI 220.13)
- (183) *dihêt ‘aíni ta‘tíbero le-digdêge*
 ‘**Deine Augen** [richte] auf das Feld’ (SAE IV 50.9)
- (184) *dihé ‘ázghel ál tetámah*
 ‘...ist **sein Membrum** impotent’ (SAE VI 295.1)
- (185) *ḥaúweróti dího ‘ídi*
 ‘Schwarz sind **meine** beiden **Hände**’ (SAE VI 238.3)
- (186) *wa-dihó ‘ídi tenatáfo ímrher wa-‘ili-hó ašābeh ímrher inátat*
le-di wu-le-biš le-merád
 ‘Und **meine Hände** troffen von Myrrhe und **meiner Finger** Myrrhe floss auf die Griffe des Riegels’ (SAE VI 30.19)⁷⁷
- (187) *ifól dié díkehon líbehon wa-é ita*
 ‘Warum ist **dein Bart** weiß und du so?’ (SAE VII 26.13–14)
- (188) *ber dihé rey míle’ žáyrob wa-dihó ra‘t min šégek d(y)a-hté*
 ‘Denn **mein Haupt** ist voll Taus, **meine Locken** voll nächtlicher Feuchte’ (SAE VI 30.10)
- (189) *hó’o li-í ‘ít(y)ob*
 ‘Wo sind **deine Euter**?’ (SAE VI 103.27)
- (190) *karámen égdahk ḥêkum suwá sellém dhēt reh*
 ‘Wenn du ein gerechtes Urtheil sprichst, ist **dein Kopf** gerettet’ (SAE IV 66.12–14)

⁷⁷ As in the original biblical text, the second part is a noun phrase (lit. ‘my fingers (are) the myrrh which is flowing’).

- (191) *‘émor heh dhet fêne*
 ‘Da sprach er zu ihm: **Dein Angesicht!**’ (SAE IV 100.21, 110.11)
- (192) *ná‘e ’éhes šéħlo dihá min ’éšħal wa-té dihá min té*
 ‘Diese nun ist Gebein von **meinem Gebein** und Fleisch von **meinem Fleische**’ (SAE VI 5.8–9)
- (193) *riómeh díse fótir meṭáḵanoh be-kéfiḥ*
 ‘Langgestreckt ist **deren Ast**, süße Palme, die in Kefif’ (SAE VI 299.16–17)

In the following examples, *di-* marks ‘part-whole’ (body part) possession in which *the possessum is not the subject of the clause* (and its possessor is not coreferent with the subject). Note especially the first two examples, where *di*-marking is employed in spite of the referential conflict (Kibrik 2001, 1129–30; 2011, 62–67; on the opposition of *di*-marking and *men*-marking as a means of avoiding referential conflicts see Bulakh and Kogan 2025, §3.5.2).

- (194) *wa-gazz dihé ‘ásgel wa-karâ‘il*
 ‘Er schnitt ihm **seinen Penis** und seine **Testikel**’ (SAE IV 127.11–12)
- (195) *wa-‘ám išóniš íntef dihé le-šér‘ehan*
 ‘Und als er ihn sah, fiel er auf **seine Füße** hin’ (Bittner 1918, 110/22)
- (196) *‘an gírbog tit di-é ‘ázgehel*
 ‘...wenn die Katze **dein Glied** frißt’ (SAE VII 70.14)
- (197) *‘af ta‘ḵír dihá be-‘ídi*
 ‘...bis auf **meinen Händen** du groß werdest’ (SAE VI 205.20)

- (198) *wa elâkaṭ subûl sêri de d-ekêse šêṭaifo de-hê be-‘aîni*
 ‘...und Aehren lesen hinter dem her, vor **dessen Augen** ich
 Gefallen finden werde’ (SAE IV 49.2)
- (299) *wa-‘émero ṭárb min ṭaírob nháta dihé reh*
 ‘...legte dann ein Holzstück unter **sein Haupt**’ (SAE IV
 82.10–11)
- (200) *ifôd kísek šêṭaifo dhêt be-‘aîni*
 ‘Wie habe ich Gnade gefunden vor **deinen Augen**?’ (SAE
 IV 50.10)
- (201) *lá‘meho ekôse šêṭaifo dihêt be-‘aîni*
 ‘Möge ich Gnade finden vor **deinen Augen**’ (SAE IV 51.13)
- (202) *âl ye‘áraḥ ṭífer dihó di-šab*
 ‘Er kommt gleich dem Nagel **meines Fußes**’ (SAE VII 21.8)
- (203) *wa tekôšif la-’amt dihé šâfi*
 ‘Und deck ihn an **seinen Füßen** auf’ (SAE IV 53.4, see also
 54.7–8; 55.9–10)
- (204) *dū’e diho d-idfēf îlbib de ḥail insýye*
 ‘Das Heilmittel gegen meinen Seitenschmerz ist das Herz
 der menschlichen Stute’ (SAE IV 76.8–10)⁷⁸
- (205) *wu-š’ófotš dse be-žánaḥ wa-šo’ótoh dse mîbrhe di-šáme dihó
 be-žánaḥ*
 ‘Sie legte es an ihren Busen, ihr totes Kind aber legte sie an
meinen Busen’ (SAE VI 20.12)⁷⁹

⁷⁸ *dū’e diho d-idfēf*, literally ‘the cure of my sides’. The use of *di*-marking is perhaps motivated by the preceding *inémoš dū’e dhet d-idfāf* ‘Was ist das Heilmittel gegen deinen Seitenschmerz?’ (SAE IV 76.6–7), where *di*-marking is accounted for by the possessor introduced at the beginning of the phrase (*inémoš* = ‘*iném heš*, literally ‘What is for you?’).

⁷⁹ *Di*-marking is predictable in the first clause (‘she put [my child] on her lap’), but not in the second one (‘she put her dead child on my lap’).

- (206) *wa-‘émor heh állāh díbbēh wa-sedígtoḥ ṭhar yūnān keḥór tken miló‘oh **dihé** le-réy*
 ‘Und es machte ihm Gott einen Kürbis, und er wuchs über Johna empor, damit er Schatten bilde über **seinem Haupte**’ (SAE VI 28.3)
- (207) *állāh d’isra’īl de gídaḥš koḥôṛ tšakêri neḥát **dihé** gêhi*
 ‘...dem Gotte Israels, unter **dessen Fittigen** du Zuflucht suchst’ (SAE IV 51.12)
- (208) *šoté’e le-rébd **dihín** di-elbhebétēn*
 ‘Er war besorgt über die Bosheit **ihrer Herzen**’ (Bittner 1918, 58.5)
- (209) *igódihēn dídehe méḥle wu-izá’a méthal di-hináuwi **dihín** be-élbhebétēn*
 ‘...kommt der Teufel rasch und nimmt den Spruch, das gesät wurde in **ihren Herzen**’ (Bittner 1918, 82.15)
- (210) *wa-kóbo dse dínob id-ḱéne **dihé** di-náḥrīr*
 ‘Und [die Maus] steckte ihren Schweif in das Innere **seiner Nase**’ (SAE VI 50.16)
- (211) *ē **dihó** šáḥlo wa-dihó té*
 ‘Du bist von **meinem Bein** und **meinem Fleisch**’ (SAE VI 8.22–23)
- (212) *ber yhe ’égah **dihín** díah **dihó** le-fáne*
 ‘Denn ihre Bosheit ist emporgestiegen vor mich!’ (SAE VI 23.8–9)⁸⁰
- (213) *láḥmod ‘ánki **dího** ‘aíni*
 ‘Ich liebe euch, ihr **meine Augen**’ (SAE VI 259.19)

⁸⁰ *dihó le-fáne* ‘at my face’.

- (214) *ékşęş di-ê min gad déle di-ḥámoš deráhem*
 ‘...werde ich von **deinem Körper** abschneiden das Gewicht
 von fünf Dirhem’ (SAE VII 74.16–18)
- (215) *kehór ineféřiš diḥín min ’edhéten*
 ‘...um ihn aus **ihrer Hand** zu retten’ (SAE VII 49.1)
- (216) *bi-ráṭel min diḥét fáḥid*
 ‘ein Pfund [Fleisch] **deines Schenkels**’ (SAE IV 150.35–36)
- (217) *erágeḥ ráṭel diḥét min fáḥid*
 ‘So will ich ein Pfund aus **deinem Schenkel** nehmen’ (SAE
 IV 151.17–18)
- (218) *wa-diḥé min di-fḥid tígziz ráṭel*
 ‘Und schneide ein Pfund aus **seinem Schenkel**’ (SAE IV
 152.30–31; 153.5–6)
- (219) *ū šéraḳo dse reh wa-šígaho šfê dse men reh*
 ‘Und sie kämmte **ihr Haupt** und es fielen Haare aus von
ihrem Haupte’ (SAE IV 84.2–4)⁸¹
- (220) *wa-šírqaḥ dur dse min ’išbeḥ*
 ‘Und es wich das Blut von **ihrem Finger**’ (SAE VI 107.22)
- (221) *wu-zé’e diḥó míbrhe diḥó min ’amt*
 ‘[Sie] nahm mein Kind von **meiner Seite**’ (SAE VI 20.10)
- (222) *éhek eblég diḥó melák diê min fáne*
 ‘Ich möchte senden meinen Engel vor dir her’ (Bittner 1918,
 6.2)⁸²

⁸¹ *Di*-marking is predictable in the first clause (‘she washed her head’), but not in the second one (‘hair fell from her head’), where it may have emerged via attraction.

⁸² *Diê min fáne* ‘at your face’.

(223) *wu-zé'e tād min ilhé min dihé⁸³ min žéylaḥ*

‘Und er (Gott) nahm eine **seiner Rippen**’ (SAE VI 5.5)

In the last ten examples, the appearance of *di-* instead of the expected *men* could be explained by the presence of the ablative *men* within the same collocation: **mek men fáne* ‘from your face/presence’ in the final example could have been considered tautological and, accordingly, replaced with *díʔe men fáne*. However, in the Vienna corpus there are plenty of examples in which possessive *men* is employed side by side with ablative *men* (such as *ménhi min iṣbeḥ* ‘von meinem Finger’ in SAE VI 107.12) so that this solution can scarcely be correct.

In the following cases *di-*marking appears side by side with more ‘correct’ *men*-marking.

(224) *wa-dsé náḥrīr rīhom tió mezingua wa-més giréb yehóre meš di-káre dé méthal*

‘**Ihre Nase** ist lang wie ein Getreidesack und **ihren Korb** möge jeder suchen, der diesen Vers liest’ (SAE VI 316.24–25)⁸⁴

⁸³ The repetition *min ilhé min dihé* cannot be grammatical: presumably, the informant gave two alternative versions of the phrase, one with number concord of the possessive pronoun and one without. Such alternative readings are not uncommon on the pages of SAE VI, but usually one of the two variants is put in brackets by Müller.

⁸⁴ That *giréb* ‘basket’ receives here the *men*-marking is undoubtedly due to the fact that it is used as a euphemism for female genitalia—that is, treated as a body part.

- (225) ‘emor hês ‘ek lšef **dehêt l’erbêbo** wa-šêf **môs l’erbêbo**
 ‘Er sprach zu ihr: Ich möchte auf **deinem Schosse** schlafen,
 und er legte sich auf **ihren Schoss**’ (SAE IV 82.6–8)

Di-marking is twice employed, in one short passage, with a noun attaching a pronominal suffix.

- (226) **di-ê** le-**rešk** ’âhzizk
 ‘Hast du **deinen Kopf** (verwirkt), ich schlage ihn ab’ (SAE VII 29.3–4, see also SAE VII 29.5)

The use of *di*-marking here goes along the rules outlined above: it is superfluous as long as the pronominal suffix is the main marker of the pronominal possessor and can be freely omitted with no change of meaning. Note that “double” possessive marking involving *men* is actually attested in modern Soqotri (Bulakh and Kogan 2025, §3.6.2, ex. (180)).

4.0. Conclusions

The Vienna corpus provides rich material on possessive constructions in Soqotri. By and large, the available evidence does not significantly differ from what may be gleaned from CSOL I–II, but provides important additions and refinements to what has been described in our first study on this topic.

The most interesting features of the Vienna corpus absent from CSOL I–II can be summarised as follows.

- A handful of *men*-marked possessive pronouns in the domain of kinship possession are attested.
- Contexts in which *men*-marking prevails over *di*-marking include the ‘place–inhabitant’ relation.

- Reliable examples of *men*-marking introducing the argument (usually agent) or adjunct of a verbal noun are available.

These features can hardly be understood as reflecting an earlier stage of the development of the possession system. Rather, they are to be regarded as alternative paths of development, which were not pursued further by the dialect spoken by our language consultants. In the first place, this concerns the use of *men* for kinship possession, which has no continuation whatsoever in CSOL I–II.

Besides, the Vienna corpus shows a somewhat broader employment of the possessive suffixes than CSOL I–II: these are compatible with a wider scope of lexemes and occur in a greater number of syntactic contexts (see Bulakh and Kogan 2025, §3.6 for a comparative overview). In this case, we are clearly faced with gradual decay of the head-marking of pronominal possession.

References

- Aikhenvald, Alexandra Y. 2013. 'Possession and Ownership: A Cross-Linguistic Perspective'. In *Possession and Ownership: A Cross-Linguistic Typology*, 1–64. Oxford: OUP.
- Bittner, Maximilian. 1918. *Vorstudien zur Grammatik und zum Wörterbuche der Soqotri-Sprache. III. Eine Soqotri-Version der ersten sechs Kapitel aus dem Marcus-Evangelium*. Vienna: Hölder.
- Bulakh, Maria, and Leonid Kogan. 2025. 'Attributive Possession in Soqotri: The Evidence of Today's Language'. Forthcoming in *Arabian Humanities*.

- CSOL I = Naumkin, V., et al. 2014. *Corpus of Soqotri Oral Literature*. Volume 1. Leiden: Brill.
- CSOL II = Naumkin, V., et al. 2018. *Corpus of Soqotri Oral Literature*. Volume 2. Leiden: Brill.
- Haspelmath, Martin, Ekkehard König, Wulf Oesterreicher, and Wolfgang Raible (eds). 2001. *Language Typology and Language Universals*. 2 vols. Berlin: De Gruyter Mouton.
- Heine, Bernd. 1997. *Possession: Cognitive Sources, Forces, and Grammaticalization*. Cambridge Studies in Linguistics 83. Cambridge: CUP.
- Kibrik, Andrej A. 2001. 'Reference Maintenance in Discourse'. In Haspelmath et al., 2: 1123–41.
- . 2011. *Reference in Discourse*. Oxford: OUP.
- Kogan, Leonid, and Maria Bulakh. 2019. 'Soqotri'. In *The Semitic Languages*, edited by John Huehnergard and Na'ama Pat-El, 280–320. London: Routledge.
- Koptjevskaja-Tamm, Maria. 2001. 'Adnominal Possession'. In Haspelmath et al., 2: 960–70.
- LS = Leslau, Wolf. 1938. *Lexique Soqotri*. Paris: C. Klincksieck.
- SAE IV = Müller, David Heinrich von. 1902. *Die Mehri- und Soqotri-Sprache*. I. *Texte*. Vienna: Hölder.
- SAE VI = Müller, David Heinrich von. 1905. *Die Mehri- und Soqotri-Sprache*. II. *Soqotri-Texte*. Vienna: Hölder.
- SAE VII = Müller, David Heinrich von. 1907. *Die Mehri- und Soqotri-Sprache*. III. *Šhauri-Texte*. Vienna: Hölder.

Simeone-Senelle, Marie-Claude, and Antoine Lonnet. 1991. 'Lexique soqotri: Les noms des parties du corps'. In *Semitic Studies in Honor of Wolf Leslau*, edited by Alan Kaye, 1443–87. Wiesbaden: Otto Harrassowitz.

CHRISTIAN PALESTINIAN ARAMAIC BETWEEN GREEK AND ARABIC

Holger Gzella

Among the three Western Aramaic literary traditions of Late Antiquity, Christian Palestinian Aramaic is arguably the one least studied from a historical-linguistic point of view. And yet, it offers a number of insights into the language situation in Byzantine Palestine that cannot easily be gained from Jewish Palestinian and Samaritan Aramaic. A less well-known but significant point is the substrate evidence that, cumulatively, documents a certain presence of Arabic in the region already in pre-Islamic times. Such data ties in with both very recent work on the diversity and diffusion of Old Arabic varieties and ongoing interest in identifying the still under-researched factors that eventually led to the creation of another Christian Aramaic written language besides Greek and Syriac by the fifth century CE at the latest.

Excepting some thirty short inscriptions that date from the period between the fifth and the eleventh centuries CE and originate in an ecclesiastical milieu of monasteries and parishes,¹ the

¹ The treatment of the epigraphic material in the recent dictionary by Sokoloff (2014) is less reliable than the discussion of the vocabulary of the literary texts; Nebe (2016a; 2016b) makes a number of essential

corpus of Christian Palestinian Aramaic exclusively consists of translations from Greek, which results in a substantial number of lexical borrowings. Its roots in a regional Aramaic vernacular, which was spoken until about the eighth or ninth century CE, are nonetheless evident (Gzella 2015, 317–26; Stadel f.c.). First, this variety, like its two Palestinian Aramaic sister languages, simultaneously exhibits a number of innovations common to members of the Western Aramaic branch—such as third-person feminine plural forms ending in *-ē* or *-ī*, agent nouns according to the pattern /qāṭōl/ acting as by-forms of the inherited basic-stem active participle /qāṭel/, and derived-stem infinitives with an /m-/ prefix—as well as a few instances of local micro-variation—in particular, the shift of *o* and *e* in the vicinity of a preceding *i* vowel to *u* and *i*, respectively. Many lexical isoglosses of the Western dialects that still occur in Western Neo-Aramaic are also attested here.² Judging from the find-spots of the material, the dialect that underlies Christian Palestinian Aramaic originated in Transjordan, near Amman, and spread to the vicinity of Jerusalem.

Second, the syntax of the translated texts is highly idiomatic in character, especially as far as the rendering of verbal forms is concerned, despite the many differences in the marking

corrections. An overview of this subcorpus can be found in Hoyland (2010, 37–39).

² E.g., the by-form *ʾnh* ‘we’ instead of *ʾnn*; the passive participle of the root *yhb* ‘give’ with the sense ‘be, exist’; the noun **kōtl* ‘wall’; the by-form of the root *zbr* ‘prune’ instead of *zmr*; the allomorphic root *ḥmī* ‘see’ instead of common Aramaic *ḥzī*; the roots *ḥsl* ‘end’, *nqī* ‘pick, choose’, and *qṣr* ‘be short’; and the noun **ṣadaqā* in the sense ‘alms’.

of tense, aspect, and modality in Aramaic as opposed to Greek. The use of periphrastic conjugations consisting of a finite form of the verb ‘be’ and an active participle of the main verb in order to render ongoing or repeated events in the past or future is a case in point (Li 2013, based on an analysis of the Gospels).

And third, various passing remarks by Greek and Latin writers on aspects of daily life among Palestinian Christians make it clear that, at least outside urban centres, Aramaic served as the normal means of ordinary communication. Such words include, among others, *gubba* ‘cistern’ in Jerome’s (347–420) *Vita Pauli* (Migne PL 23, 22), a word directly attested in Christian Palestinian Aramaic as well (Sokoloff 2014, 69); *barech* ‘Bless!’ in the same author’s *Vita Hilarionis* (Migne PL 23, 42; the Greek and Old Church Slavonic translations even have the longer reading βάρεχ, μαρί and парехъ мари ‘Bless, oh Lord!’, respectively, which, in light of the preservation of word-final -ī, exhibits a characteristically Western-Aramaic form), which supplements other forms of the same root that occur in the corpus of Christian Palestinian Aramaic with the imperative (Sokoloff 2014, 63);³ and a few stray lexemes in Epiphanius of Salamis, especially *voupa* ‘fire’

³ A more detailed discussion of these textual variants and their implications can be found in Gippius et al. (2020, 6–10), but the meaning becomes clear from the gloss *id est, benedic* in the Latin text. Note that the manuscript evidence for the reading in the Old Church Slavonic translation of Jerome’s *Vita Hilarionis* varies between парехъ маpa (with an erroneous final -a in маpa, apparently under the influence of the vowel in the preceding syllable), пархъ марїи, and пархъ мариин, but the expected spelling мари appears in a citation of the same expression on the walls of the St Sophia Cathedral in Novgorod.

(Sokoloff 2014, 260) and presumably $\kappa\omicron\delta\delta\alpha$ ‘jar’ (from **kadd*), both in the emphatic state (Dummer 1968). Systematic scrutiny of the *Nebenüberlieferung* of Palestinian Aramaic in Greek and Latin ecclesiastical writers, which has been unduly neglected by lexicographers of Christian Palestinian Aramaic (such transcriptions feature in neither Schultheß 1903 nor Sokoloff 2014), will, in all likelihood, uncover more non-onomastic evidence.

There are also several passages that report the use of spoken Aramaic without citing actual words or phrases in transcription. In another section of the *Vita Hilarionis*, Jerome comments on the native pronunciation of Aramaic words in the mouth of a traveller who knew only Franconian and Latin, but, thanks to demon possession, was capable of flawless pronunciation of the typical fricative and guttural sounds of Aramaic as well as idiomatic expressions (Migne PL 23, 41). Jerome’s contemporary Egeria, a late-fourth-century pilgrim to the Holy Land from Gaul or Northern Spain, notes in her Latin itinerary that portions of the population spoke Greek, Aramaic, and both. For this reason, speeches given by the bishop—who, she adds, knew but avoided active use of Aramaic—and liturgical readings were translated on the spot from Greek into Aramaic (47, 3–4; the Latin text and an annotated German translation are easily accessible in Röwekamp 1995, 302–3). The latter furnishes precious indirect evidence of the existence of fully bilingual Greek-Aramaic dragomans in Byzantine Palestine.

Latin writers commonly used terms like *sermone Syro*, *voce Syra* or, *siriste* literally ‘in Syriac’, for Aramaic, but this is simply a convention of nomenclature (as Dummer 1968, 398–99, has

shown for Jerome) and does not imply any underlying classification of Aramaic into distinct varieties. Jerome, Egeria, and others certainly all meant the Palestinian vernacular and not literary Syriac, which was hardly spoken in Palestine anyway. The same usage recurred when earlier scholarship employed labels such as ‘Modern Syriac’ for Neo-Aramaic languages, or ‘Palestinian Syriac’ for Christian Palestinian Aramaic, respectively.⁴ Conversely, Jews and Christians in the Byzantine period tended to avoid the umbrella term ‘Aramaic’, which would cover both Syriac and Christian Palestinian Aramaic, no doubt because it had by then assumed the meaning ‘pagan’ alongside the older linguistic sense.⁵ Another possible designation for Aramaic in Antiquity, ‘Chaldaean’, was probably deemed unsuitable for similar reasons, though Jerome employed it a few times in parallelism and, as it appears, synonymously with ‘Syriac’ for the Aramaic parts of the book of Daniel (*In Daniele* 2.7; 4.10; 7.47). For ‘Chaldaean’ by and large referred, often in a derogatory way, to soothsayers and

⁴ It was Nöldeke (1868) who felicitously coined the term ‘Christian Palestinian Aramaic’, but his use of ‘Neusyrisch’ for the written form of Urmia Neo-Aramaic was less than ideal (*sit venia verbo*, for many years ago, Geoffrey Khan shared with the present writer a memory of his own teacher Edward Ullendorff, who did not suffer lightly student disagreement with Nöldeke in class!).

⁵ The nuance ‘pagan’ for ‘Aramaic’ is well-attested in Christian Palestinian, too (the references are listed in Sokoloff 2014, 29), where it also serves as a rendering of Greek ἑλλην with the same connotation.

diviners in Classical Latin (its older, geographical, meaning, referring to inhabitants of Babylonia also remained in use, but crops up much more rarely).⁶

While one, therefore, cannot reasonably doubt that a significant proportion of ordinary Palestinian Christians normally spoke a regional variety of Aramaic in their daily lives throughout the Byzantine period, it is more difficult to say why exactly it was eventually promoted to a written code with a script and a set of spelling conventions of its own. Roman imperial orthodoxy in Palestine employed Greek as the official ecclesiastical language, and Syriac, which had already developed a rich written tradition by that time, was available if Aramaic was preferred. The dialect on which Syriac is based belongs to a branch different from that of Palestinian Aramaic, to be sure, but, given Syriac's wide coverage across the Syrian and Mesopotamian speech area, it would presumably not have been incomprehensible to speakers of the Western varieties either.⁷ Since the Christian Palestinian script had been modelled on the Syriac letterforms, the monastic environment in the eastern Jordan area, where Christian Palestinian Aramaic arose, obviously could have had access to the West-Syriac writing tradition had they so desired.

⁶ Pease (1977, 43–4) has a survey of the relevant attestations of the term *Chaldaei* in Latin with a few concise remarks on the history of its use.

⁷ According to an anecdotal story in Flavius Josephus's *Bellum Iudaicum* (IV:1.5), Roman legionaries recruited from Syria, who in all likelihood spoke an Eastern Aramaic dialect closely related to the Edessan one on which Syriac is based, could understand the table talk of Palestinian Jews conducted in their Western Aramaic vernacular.

The motivation for the decision to create a proper written form may lie in the more modest purposes for which Christian Palestinian Aramaic was employed. Presumably, it was not intended to serve as a means of an overarching ecclesiastical infrastructure of advanced theological literature, but to cater for the needs of parishioners whose communal lives would revolve around the churches and monasteries in the immediate vicinity of their homes. This would also have been the background from which the monks and members of the local clergy came. Hence the decisively down-to-earth character of the texts and the lack of a rigorous top-down standardisation. The epigraphic material consists of short building, memorial, and funerary inscriptions, in addition to a concise papyrus letter, whereas the manuscripts contain biblical, liturgical, catechetical, and hagiographic material of a generally unassuming kind, but by and large no sophisticated exegetical or philosophical treatises.

In addition, the largely phonetic spelling conventions (with the exception of ' as a regular means of indicating final *-ā* in the emphatic state, just as in Syriac) represent a complete break from the earlier Achaemenid chancellery language. They show that Christian Palestinian Aramaic did not evolve in a learned milieu, and no direct connection with any prior writing tradition of Aramaic in the region can be established.⁸ Quite the contrary is the

⁸ Beyer (1984, 50, 406) considered the language of a very short pagan dedicatory inscription from 7/6 BCE found at Elmal, half-way between the Sea of Galilee and Damascus, a witness to the ancestor dialect of Christian Palestinian Aramaic. While this is theoretically possible in

case for Syriac, which originated in circles of Edessan administrators and evolved in an unbroken developmental chain into a Christian literary language, presumably following the conversion of chancellery scribes. The large number of religious and administrative terms that Christian Palestinian Aramaic borrowed from Greek, or from Latin via Greek,⁹ underscores not only the latter's prominence as the official ecclesiastical language in Roman Palestine, but also points to the lack of a native terminological apparatus in this particular Aramaic variety.¹⁰ Rather, it was presumably geared towards transmitting basic knowledge of the orthodox Christian faith and religious practice to a predominantly rural Aramaic-speaking public with little or no access to ecclesiastical high culture.

terms of linguistic geography, the text itself does not exhibit any trait that might prove (or, indeed, disprove) such an affiliation.

⁹ Latin loanwords in Christian Palestinian Aramaic mostly pertain to the domain of Roman provincial administration and the army, such as *speculator* (Sokoloff 2014, 23), *scutum* (23), *sudarium* (282), *signum* (285), *sicarius* (286), *strata* (292), *patricius* (327), *palatium* (332), *praetorium* (332), *fascia* (336), *piscina* (336), *flagellum* (339), *quadrans* (364), *caesar* (372), *census* (372), *cella* (374), *calamus* (375), *Kalendae* (375), *centurio* (377), *custodia* (378), *castra* (378–79), and *cassida* (379). To these add now *prt* 'bowl', from Latin *paterna*, attested in a fragment of the *Dormitio Mariae* not yet known to Sokoloff (CP3 fol. 4 verso, col. a, ln. 8, in Müller-Kessler 2018).

¹⁰ For another Greek loan not yet included in Sokoloff (2014), see *'gps*, in all likelihood an accusative plural *ἀγάπη* 'agape meals' in a new fragment of the *Dormitio Mariae* (Müller-Kessler 2018, 86, who translates imprecisely with 'memorials').

This is not to say that ordinary Greek words do not surface in Christian Palestinian Aramaic, but they do not indicate a high degree of general bilingualism. The noun *nysws* ‘island’ (Sokoloff 2014, 264) from *νησος*, for instance, may reflect the characteristically Greek interest in seafaring. Such a connection appears all the more plausible when one considers that the substantivised adjective *nysny* ‘islander’ explicitly refers to Greeks in ‘the Syrian from the East will waste away the island-dwellers from the West’ (Isa. 9.11), as becomes clear from the wording in the Septuagint that underlies this rendering.¹¹

Conversely, the borrowings of many Greek function words, such as *ʾ* from *ἢ* ‘or’, *gr* from *γάρ* ‘but, indeed’, *qygr* from *καὶ γάρ* ‘for indeed’, and several others seem, at first glance, to relate to spontaneous use rather than technical terminology. Upon closer examination of their distributional pattern, however, it emerges that they, too, may have entered the language via written Bible translations, because it is there that they occur particularly frequently, in contradistinction to their noteworthy absence from the inscriptions. The straightforward diction of the latter no doubt more faithfully reproduces the Aramaic dialect on which Christian Palestinian is based, so one may seriously question whether people actually used these originally Greek particles in their ordinary and spontaneous speech. Instead, the language of

¹¹ Sokoloff’s scepticism (2014, 202) as to the etymology of *nysny* seems unwarranted given the incontestable attestation of the loan *nysws* ‘island’ and the general productivity of the substantivising affix *-ān*. The preposition *l-* would then mark the direct object (see Sokoloff 2014, 190, entry *l-*, item 2, for parallels).

the inscriptions seems to reflect a register different from that of the literary texts in translation. A description of the epigraphic corpus in its own right would thus be of value.

Hence, borrowings of this kind do not by themselves prove widespread active use of Greek among the Christian inhabitants of the countryside east of the river Jordan. Moreover, widespread full bilingualism would have rendered the creation of an Aramaic written language for that particular target group otiose, because everybody would have known Greek anyway. Yet the swift erosion of Greek in Palestine during the decades following the adoption of Arabic as the state language around 700 CE suggests that the idiom of urban and ecclesiastical elites had not struck deep roots in the rural parts of the region. By contrast, the use of Aramaic as a language of liturgy and religious literature continued among Jews, Christians, and Samaritans for hundreds of years after Arabic had become the dominant vernacular, by about the mid-tenth century CE.

It has been pointed out that general similarity in linguistic structure, basic vocabulary, and means of word-formation between Aramaic and Arabic, but unlike Greek, facilitated a considerably high degree of functional bilingualism and, eventually, a smooth transition from the one to the other (Hoyland 2004, 194–98). On grounds of the same similarity, Syriac translations of Greek philosophical and scientific treatises presumably played such an important role as intermediaries in transmitting these works to the emerging Muslim elites. Around 800 CE, for instance, the Eastern-Syriac Patriarch Timothy I pointed out in a Syriac letter on the production of an Arabic version of Aristotle's

Topics that a translation based on the Syriac was more satisfactory than earlier ventures based directly on the Greek. The latter were considered *brbryn* ‘barbaric’, presumably due to excessively literal and unidiomatic style (see Heimgartner 2012, 65–6, for the Syriac text and Brock 1999 for an annotated English translation).

However, Palestinian Christians seem to have switched to Arabic as the dominant language somewhat earlier and more rapidly than Jews and Samaritans. The manuscript transmission of Christian Palestinian Aramaic continued until the thirteenth century, it is true, but the amount of linguistic contamination in witnesses dating from this later period clearly shows that knowledge of Aramaic rapidly declined after the eighth century. Even so, a comparison of the reactions of Christians, Jews, and Samaritans to Arabic’s advance has not yet been the focus of scholarly attention, owing to the conventional association of Arabic with Islam. Such an association is nonetheless misleading for the period immediately preceding the advent of Islam, because the three sixth-century inscriptions from Syria that are clearly identifiable as Arabic in terms of script and language were all produced in a Christian context (Mascitelli 2006, 176–87). The one from Zabad near Aleppo, dated to the year 512 CE, also contains more extensive parallel versions in Greek and in Syriac (*ibid.*, 176–78), and the one from Harran, dated to the year 568 CE (*ibid.*, 183–87), has a facing Greek text. They show that Arabic was on its way to becoming a written language besides Greek, though with a lower status, among Arabic-speaking Christians.

Against the background of important recent work on the prominence of early forms of Arabic in pre-Islamic Syria-Palestine, one may suppose that Christians in the eastern Jordan area, too, comprised a certain number of people who regularly spoke Arabic as a first or second language, even though it did not evolve into a written code there. In such a situation, regular instances of Arabic substrate pronunciation in Aramaic provide some clues as to the pragmatically dominant language of the writer. The most conspicuous of them is the rendering of original Semitic */p/ as [b], which, as is widely accepted, presumably results from approximation. Since */p/ had shifted to [f] in Arabic by that time, it would have been unfamiliar to speakers accustomed to conversing in Arabic, so they tried to reproduce it with the closest equivalent in the phonetic repertoire of their language. Several examples from literary texts concern Greek loanwords, such as *ʾbšlmwš* ‘Psalm’ (Sokoloff 2014, 3), *btryrk* ‘patriarch’ (45), *brwty* ‘at first’ and *brwpyty* ‘prophecy’ (62), *dʾsbwtys* ‘master’ (79), *tbzywn* ‘topaz’ (144), *mṭrʾbwlyṭ* ‘metropolitan’ (219), or *rbydwn* ‘fan’ (389), similarly βᾶσιν instead of πᾶσιν ‘all’ in Greek lamp inscriptions (Gzella 2015, 325).

While these tend to occur in late manuscripts that were composed in a period after the shift from Aramaic to Arabic had long taken place throughout Syria-Palestine and Mesopotamia, the word *ʾwb* for Aramaic *ʾap* ‘even’ in a ninth–eleventh-century tomb inscription from Gerasa near Amman exhibits the same phenomenon (Beyer 1984, 403, with additional notes on the date in Müller-Kessler 1991, 14). The use of the ‘perfect of wish’ *nʾḥt* ‘may rest (sc. the soul of)’ in the same inscription is another clear

Arabism, because a deontic-modal function of the perfect is alien to Aramaic (excepting Nabataean, which had undergone similar Arabic influence), but very normal in Arabic (Gzella 2015, 325).

At least one additional Arabic loan, possibly two, can be found in a papyrus letter from Mird, written by a frightened hermit to his abbot in the eighth century: *ʾhl* ‘people’ and perhaps *rš* ‘to tremble’ (Beyer 1984, 403–4).¹² Both lexemes belong to the basic vocabulary, and the emotional tone of voice suggests that the writer was in a stressful situation, in which the dominant language for spontaneous communication normally comes to the fore, especially since the style of the letter does not bear the mark of a highly educated author. One may take this as evidence that Arabic was well-established as an ordinary language among Palestinian Christians as early as the eighth century CE. The incorrect use of the emphatic and the absolute state in Aramaic in a building inscription from 1058 CE shows that language attrition had progressed considerably since then (Beyer 1984, 402).

The Arabic component in the lexicon of Christian Palestinian Aramaic is actually more extensive than the incomplete etymological information in dictionaries suggests.¹³ The entry on the verb *bdl*, for instance (Sokoloff 2014, 40), specifies neither the origin nor the meaning of the word in its sole attestation in Mt. 4.3 and refers only to Schultheß’s (1903, 22) old conjecture

¹² There is some discussion about the reading of the second word; see Müller-Kessler (1991, 15). It is also omitted from Sokoloff (2014).

¹³ For explicit references to Arabic words, see Sokoloff (2014, 6, 258, and 320) on *ʾhl* ‘crowd, people’ (without a translation gloss), *nḥš* ‘pierce’, and *ʾrbs* ‘be troubled’.

ytʿbdwn ‘that they (i.e., the stones) should be made (sc. to bread)’ corresponding to *γέινωται* in the Greek original. However, such a change is unnecessary, because, as already Schwally had realised (1893, 9–10), *bdl* corresponds to Arabic *badala* ‘change, exchange’, presumably in the factitive stem (compare Wehr and Kropfitsch 2020, 52). In addition, the attestation comes from Codex A of the Christian Palestinian Gospels, now in the Vatican Library, that is, a manuscript dating to the late period of the eleventh–thirteenth centuries, where Arabisms abound anyway.

A comparably simple explanation can be applied to the verb *yqn*, which, following a proposal by Müller-Kessler (1991, 212), has been argued to derive from Greek *εἰκών* ‘image’ (Sokoloff 2014, 166). This is most implausible on both phonological and semantic grounds, however. First of all, the spelling of, e.g., *ʿyqy* for *εἰκῆ* ‘in vain’ suggests that a verb derived from *εἰκών* would rather appear with an initial ʿ-. Moreover, the semantic development remains completely obscure. The occurrence of the factitive stem in the story of Eulogios the Stonecutter curiously lacks a translation gloss in the dictionary, but it seems to mean ‘make sure’ in the context in which it occurs, as indeed the most recent edition of the text suggests (Müller-Kessler and Sokoloff 1996, 86, 119, where the same unconvincing derivation is given).

However, the correct etymology can already be found in the *editio princeps* (Smith Lewis 1912, 35): *yqn* was not borrowed from Greek, but from Arabic *yaqina* ‘be certain’ (see also Wehr and Kropfitsch 2020, 1038), hence the factitive stem means

‘make certain’.¹⁴ As one expects, the corresponding Št-reflexive causative stem is used with the sense ‘be fully convinced’ in Rom. 4.21 for Greek πληροφορηθείς, literally ‘be full of confidence’. The manuscripts in which both attestations occur predate the eleventh century; indeed, the one in Rom. 4.21 is from the Aramaic underwriting of the *Codex Climaci Rescriptus* and thus dates from some point in the period between the fifth and seventh centuries, which would make this verb an early loan.

These two etymologies were established hundred or more years ago and have been unduly neglected in recent scholarship. To these can be added new suggestions, among which those gleaned from textual witnesses that belong to the early period, between the fifth and eighth centuries, are especially relevant for tracing pre-Islamic Arabic influence. For this was the time when the vernacular underlying Christian Palestinian Aramaic was still actively spoken, whereas later manuscripts contain many instances of secondary contamination.

The origin of *gryn* ‘chattering’, corresponding to Greek ἀδολεσχία, is as yet unexplained (its etymology is unclear according to Sokoloff 2014, 76, and had already eluded Duensing 1906, 157, who remarked: “Unklar, wie zu verstehen oder zu ändern”). However, a connection with Arabic *ḡarā* ‘flow, run out’ gains

¹⁴ Unfortunately, the Greek original has an entirely different wording (ἀπενύσταξα ‘I dozed off’) and is of little help here (see Clugnet 1901, 35 line 1; Dahlman 2007, 158 ln. 145). It is unclear where the reference to an allegedly underlying Greek ἐγνώρισα in Smith Lewis’s glossary (1912, 35) comes from.

credibility from the use of the same verb for ‘lament, talk nonsense’ in Western Neo-Aramaic, which belongs to the same dialect branch as Christian Palestinian Aramaic, and in the Arabic vernaculars of Syria (Arnold 2019, 300). One of the two possible occurrences, 1 Sam. 1.16, even stems from a manuscript apparently dating to the early period (at least, this is how it is classified in Sokoloff 2014, xxvii), so the underlying verb *grī* may be an Arabic loan of considerably antiquity in Western Aramaic.¹⁵ This is just one example for the light which a study of Western Neo-Aramaic can shed on Christian Palestinian Aramaic.

Finally, the curious expression *bkwl ḥšb*, literally ‘with the whole mind’, as an equivalent for ἀσέμνως ‘gladly’ in Acts 21.17 is by no means “unclear” (according to Sokoloff 2014, 141), if one takes into consideration that the Arabic cognate *ḥasaba* can be used with the meaning ‘be content’, and the corresponding noun *ḥasb* for ‘contentment’ (Wehr and Kropfitsch 2020, 190). A Nabataean contract from the Dead Sea, where, as is well known, Arabisms occur frequently, contains an instance where *ḥšb* means ‘recognise, accept’ (P. Yadin 36, 3.24, see Beyer 2004, 244–47, 402). From there, it is but a small step to the nuance ‘heartfelt

¹⁵ The other possible attestation in Ps. 54.3 occurs in a manuscript written at the end of the twelfth century. The reading *bgrʾmy* ‘in my bones’ is palaeographically certain, but presumably corrupt, and can hardly be derived from the wording ἀδολεσχία μου of the Greek *Vorlage* (see the note by Black 1954, 18, on the difficulty). An emendation into *bgry* in the light of 1 Sam. 1.16 is an easy remedy, as Goshen-Gottstein and Shirun (2008, 18, in the corresponding note in the apparatus) and, subsequently, Sokoloff (2014, 76) plausibly suggest.

welcome' in Acts 21.17, so it turns out that the Greek and the Christian Palestinian Aramaic texts do not differ much in the end.

The root *ḥšb* obviously belongs to the basic vocabulary of Aramaic, but this particular sense, which seems otherwise unattested in pre-modern Aramaic and has hitherto puzzled editors and lexicographers, may well have been influenced by the use of its cognate in Arabic; at least, this is what the distribution of the relevant occurrences suggests. Once again, the attestation in Acts comes from the *Codex Climaci Rescriptus* and thus from a manuscript that can confidently be dated to the earliest attested period of Christian Palestinian Aramaic.

Onomastic evidence does not have the same diagnostic weight for determining the vernacular in a particular region, but as far as Christian Palestinian Aramaic is concerned, it does further corroborate the various instances of contact-induced phonological, syntactic, and lexical influence that point to the presence of Arabic speakers among Palestinian Christians already in the pre-Islamic period. Several typically Arabian names on tombstones from es-Samra near Amman occur as early as the sixth century CE. For instance, *ʿwmyrw*, *qymw*, and *šlymw* (Beyer 1984, 404) all contain a reflex of the nominative ending *-u*. This ending belongs to the most distinctive hallmarks of Arabian personal names (it also appears in all names in the Arabic version of the Zabad inscription from 512 CE) and, in the case of the most popular one, *ʿAmr* (*ʿmrw*), even survives into Classical Arabic spelling practice (Spitaler 1979).

The combination of Arabic influence already in early Christian Palestinian Aramaic texts, on the one hand, and the presence

of characteristically Arabian names in the speech area of this particular Aramaic dialect, on the other, permits further insights into the linguistic setting in which this literary idiom evolved. More precisely, the cumulative evidence strongly suggests that Arabic gained some currency among Christians in the region between Jerusalem and further to the east as far as Amman in the pre-Islamic period, possibly even to a greater extent than Greek. This is also the kind of scenario where instances of structural convergence between languages in contact arise, for instance, as Stadel (2022) has argued convincingly, the loss of the infinitive in Christian Palestinian Aramaic and its replacement by the imperfect on analogy with Arabic. Comparable phenomena are unattested in contemporaneous Jewish Palestinian or Samaritan Aramaic material. This seems to reflect the overarching demographic situation. Since the majority of the Palestinian population between the fifth century and the early Islamic period were Christians, it is only to be expected that this group included the most sizeable segment of Arabic speakers.

In addition, the distributional pattern of Old Arabic inscriptions outside Arabia (a summary of the evidence can be found in Al-Jallad 2018, 322–24) supports the hypothesis of a significantly more prominent presence of Arabic varieties in Transjordan than elsewhere in Palestine. For want of a common supra-regional writing tradition before the latter part of the fifth century, they were composed in several different scripts. Speakers of Arabic in this area, too, would have been adequately serviced by an Aramaic literary language, because it was linguistically closer to their vernacular than Greek. The wish to cater also for their

needs may have been another consideration involved in the decision to create a written standard for Christian Palestinian Aramaic besides Greek as the official ecclesiastical language.

As a result of the early presence of Arabic, the shift from Aramaic to Arabic appears to have been completed earlier, perhaps by about a century, among Christians in the eastern Jordan area than among Jews, Samaritans, and Christians in other parts of Palestine. Individual Arabic lexemes or syntactic features thus cannot serve as a reliable criterion for dating Christian Palestinian Aramaic texts, because not all of them necessarily result from secondary contamination. Their frequency nonetheless increases over time, so it is concentration rather than sheer presence that offers some guidance for diachronic analyses.

More importantly, they bring to the fore the extent to which Arabic was part of the linguistic fabric of Byzantine Palestine. Interactions between Aramaic and Arabic in pre-Islamic times are fertile ground for future research, but anyone who wishes to embark on such work would be well-advised to learn from the philological precision, sound judgment, and clarity of exposition that Geoffrey Khan himself so admirably applies in his many precious contributions to these and other languages in the medieval and modern periods!

References

- Al-Jallad, Ahmad. 2018. 'The Earliest Stages of Arabic and its Linguistic Classification'. In *The Routledge Handbook of Arabic Linguistics*, edited by Elabbas Benmamoun and Reem Bassiouney, 315–31. New York: Routledge.

- Arnold, Werner. 2019. *Das Neuwestaramäische. Teil VI: Wörterbuch*. Semitica Viva 4,6. Wiesbaden: Harrassowitz.
- Beyer, Klaus. 1984–2004. *Die aramäischen Texte vom Toten Meer samt den Inschriften aus Palästina, dem Testament Levis aus der Kairoer Genisa, der Fastenrolle und den alten talmudischen Zitaten. Aramaistische Einleitung. Text, Übersetzung, Deutung. Grammatik / Wörterbuch. Deutsch-aramäische Wortliste*. 3 vols. Göttingen: Vandenhoeck & Ruprecht.
- Black, Matthew. 1954. *A Christian Palestinian Syriac Horologion (Berlin MS. Or. Oct. 1019)*. Texts and Studies. Contributions to Biblical and Patristic Literature 1. Cambridge: Cambridge University Press.
- Brock, Sebastian P. 1999. 'Two Letters of the Patriarch Timothy from the Late Eighth Century on Translations from Greek'. *Arabic Sciences and Philosophy* 9: 233–46.
- Clugnet, Léon. 1901. *Vie (et récits) de l'Abbé Daniel le Scétiote*. Bibliothèque hagiographique orientale 1. Paris: Picard.
- Dahlman, Britt. 2007. *Saint Daniel of Sketis: A Group of Hagiographic Texts Edited with Introduction, Translation, and Commentary*. Acta Universitatis Upsaliensis; Studia Byzantina Upsaliensia 10. Uppsala: Uppsala University Library.
- Duensing, Hugo. 1906. *Christlich-palästinisch-aramäische Texte und Fragmente nebst einer Abhandlung über den Wert der palästinischen Septuaginta*. Göttingen: Vandenhoeck & Ruprecht.
- Dummer, Jürgen. 1968. 'Die Sprachkenntnisse des Epiphanius'. In *Die Araber in der Alten Welt*, edited by Franz Altheim and Ruth Stiehl, vol. V/1: 392–435. Berlin: De Gruyter.

- Gippius, Alexei A., Holger Gzella, Savva M. Mikheev, and Jos Schaeken. 2020. 'Semitic Inscriptions in the St. Sophia Cathedral in Novgorod: A Reply to Alternative Interpretations'. *Russian Linguistics* 44: 1–12.
- Goshen-Gottstein, Moshe H., and Hanan Shirun. 2009. *The Bible in the Syropalestinian Version: Part II: Psalms*. The Hebrew University Bible Project Monograph Series 5. Jerusalem: Magnes Press.
- Gzella, Holger. 2015. *A Cultural History of Aramaic: From the Beginnings to the Advent of Islam*. Handbook of Oriental Studies I/111. Leiden and Boston: Brill.
- . 2021. *Aramaic: A History of the First World Language*. Translated by Benjamin D. Suchard. Grand Rapids, MI: Eerdmans.
- Heimgartner, Martin. 2012 *Die Briefe 42–58 des ostsyrischen Patriarchen Timotheos I*. Corpus Scriptorum Christianorum Orientalium 644, Scriptores Syri 248. Louvain: Peeters.
- Hoyland, Robert. 2004. 'Language and Identity: The Twin Histories of Arabic and Aramaic (and: Why did Aramaic Succeed where Greek Failed?)'. *Scripta Classica Israelica* 23: 183–99.
- . 2010. 'Mount Nebo, Jabal Ramm, and the Status of Christian Palestinian Aramaic and Old Arabic in Late Roman Palestine'. In *The Development of Arabic as a Written Language: Papers from the Special Session of the Seminar for Arabian Studies Held on 24 July, 2009*, edited by Michael C. A. Macdonald, 29–46. Supplement to the Proceedings of the Seminar for Arabian Studies 40. Oxford: Archaeopress.

- Li, Tarsee. 2013. *Greek Indicative Verbs in the Christian Palestinian Aramaic Gospels: Translation Technique and the Aramaic Verbal System*. Perspectives on Linguistics and Ancient Languages 3. Piscataway, NJ: Gorgias Press.
- Mascitelli, Daniele. 2006. *L'arabo in epoca preislamica: Formazione di una lingua*. Rome: "L'Erma" di Bretschneider.
- Müller-Kessler, Christa. 1991. *Grammatik des Christlich-Palästinisch-Aramäischen. Teil 1: Schriftlehre, Lautlehre, Formenlehre*. Texte und Studien zur Orientalistik 6. Hildesheim etc.: Olms.
- . 2018. 'Three Early Witnesses of the "Dormition of Mary" in Christian Palestinian Aramaic: Palimpsests from the Cairo Genizah (Taylor-Schechter Collection) and the New Finds in St Catherine's Monastery'. *Apocrypha* 29: 69–95.
- Müller-Kessler, Christa, and Michael Sokoloff. 1996. *A Corpus of Christian Palestinian Aramaic, Vol. III: The Forty Martyrs of the Sinai Desert, Eulogios, the Stone-Cutter, and Anastasia*. Groningen: STYX Publications.
- Nebe, G. Wilhelm. 2016a. Review of *Texts of Various Contents in Christian Palestinian Aramaic* and *A Dictionary of Christian Palestinian Aramaic*, by Michael Sokoloff. *Orientalistische Literaturzeitung* 111: 44–46.
- . 2016b. Review of *A Dictionary of Christian Palestinian Aramaic*, by Michael Sokoloff. *Orientalistische Literaturzeitung* 111: 46–48.
- Nöldeke, Theodor. 1868. 'Über den christlich-palästinischen Dialekt'. *Zeitschrift der Deutschen Morgenländischen Gesellschaft* 22: 443–527.

- Pease, Arthur Stanley. 1977. *M. Tulli Ciceronis De divinatione libri duo*. Darmstadt: Wissenschaftliche Buchgesellschaft (originally published in: *University of Illinois Studies in Language and Literature* 6 [1920] 161–500 and 8 [1923] 153–474).
- Röwekamp, Georg. 1995. *Aetheria: Itinerarium = Reisebericht / Egeria. Mit Auszügen aus De locis sanctis = Die heiligen Stätten / Petrus Diaconus*. Fontes Christiani 20. Freiburg et al.: Herder.
- Schultheß, Friedrich. 1903. *Lexicon Syropalaestinum*. Berlin: Reimer.
- Schwally, Friedrich. 1893. *Idioticon des Christlich Palästinischen Aramaeisch*. Gießen: Ricker.
- Smith Lewis, Agnes. 1912. *The Forty Martyrs of the Sinai Desert and the Story of Eulogios. From a Palestinian Syriac and Arabic Palimpsest*. Horae Semiticae 9. Cambridge: Cambridge University Press.
- Sokoloff, Michael. 2014. *A Dictionary of Christian Palestinian Aramaic*. Orientalia Lovaniensia Analecta 234. Louvain: Peeters.
- Spitaler, Anton. 1979. 'واو عمرو' und Verwandtes'. In *Die islamische Welt zwischen Mittelalter und Neuzeit: Festschrift für Hans Robert Roemer zum 65. Geburtstag*, edited by Ulrich Haarmann and Peter Bachmann, 591–608. Beirut: Orient-Institut der Deutschen Morgenländischen Gesellschaft (reprinted in: Spitaler, Anton. 1988. *Philologica. Beiträge zur Arabistik und Semitistik*, 351–368. Diskurse der Arabistik 1. Wiesbaden: Harrassowitz).

- Stadel, Christian. 2022. 'The Loss of the Infinitive and Its Replacement by the Imperfect in Christian Palestinian Aramaic'. In *The IOS Annual Volume 21. "Carrying a Torch to Distant Mountains"*, edited by Yoram Cohen, Amir Gilan, Letizia Cerqueglini, and Beata Sheyhatovitch, 274–310. Leiden and Boston: Brill.
- . Forthcoming. 'The Formative Milieu and Linguistic Profile of Christian Palestinian Aramaic'. In *Christian Palestinian Aramaic: Not Quite the Right 'Syriac'—An International Online Workshop, 3 July 2021*, edited by Riccardo Contini and Emiliano Bronislaw Fiori.
- Wehr, Hans, and Lorenz Kropfitsch. 2020. *Arabisches Wörterbuch für die Schriftsprache der Gegenwart*. 6th edition. Wiesbaden: Harrassowitz.

ARAMAIC: LINGUA FRANCA, KOINE, OR BOTH?

John Healey

Geoffrey Khan has made a remarkable contribution to Semitic linguistics and will, no doubt, continue to do so for many years beyond his 65th birthday. Perhaps his most lasting contribution to Aramaic studies is his shifting of the agenda from Aramaic as an object of philological study, mostly concerned with the history of and changes in Aramaic over the three millennia of its attestation, to Aramaic in its modern manifestations as an object of linguistic analysis. Geoffrey is also a master of the *longue durée* of Aramaic and what follows is a stumbling attempt to keep up!

The distinctive contribution of Aramaic to linguistics arises from the fact that it is attested over such a long span of time and large breadth of geography. Although there can be no doubt that Aramaic in some form was in use in the second millennium BCE, it can be specifically documented from the ninth century BCE in an already mature literary form—though preserved on stone monuments: the Tell Fekheriyeh inscription (Abou-Assaf, Bordreuil, and Millard 1982) and Tel Dan inscriptions (Biran and Naveh 1993; 1995). At the other end of the timespan, Aramaic is, of course, still in use as a spoken language in Christian villages in northern Mesopotamia, to the study of which Geoffrey Khan

has made a distinguished contribution, and in a small area of Syria. In its longevity its only rivals in Europe and the Mediterranean are Greek and Hebrew.

Greek, Hebrew, and Aramaic (along with Latin and Arabic) have another linguistic 'life' apart from vernacular usage, since they are religious languages preserved and used also in believing communities. Their religious importance is related to their use in the transmission of scriptures, as well as their employment for liturgy and prayer. In both aspects there is inevitable conservatism and archaism, which keeps alive forms of the language which are different from the vernacular in those places where a form of the same language is spoken. Religious tradition has, however, the peculiarity that many users of the language are not native speakers of it, just as Latin was widely used in every Latin-rite Catholic church in the world until the 1960s. In the case of Arabic, it is quite normal in cities like Manchester for Muslim children to learn to recite the Quran in 'Classical' Arabic, while speaking English (and, to some extent, Urdu in a domestic context) as a vernacular.

This situation creates *diglossia* even among those whose vernacular is a form of Aramaic: Christians in northern Mesopotamia use Neo-Aramaic in the village streets, but Classical Syriac in the village church. One of the great unknowns in Syriac is the tracing of this bifurcation historically. We might assume that at some point in history the difference between the literary and vernacular forms of the language was less stark or even that at one

stage there was no difference. Unfortunately, there is little surviving evidence for non-religious, non-literary use of Syriac in the first millennium CE (see below).

Like Latin and Arabic (and, in modern times, English), Aramaic was often written in places where, so far as we can judge, it was not spoken (or spoken only in rarefied artificial environments, such as religious institutions). This Aramaic colonisation of non-Aramaic-speaking and ethnically diverse areas reflects Aramaic's emergence in certain limited periods as an international language, used for commerce, law, imperial administration, religion, and literature. In this context, it is often called a *lingua franca* (see below on this nomenclature). The three main episodes of this widespread use of Aramaic were:

1. Aramaic in the service of the Achaemenid Persian Empire;
2. Aramaic as the most important linguistic medium shared by the Middle Eastern Jewish communities in Late Antiquity and the Middle Ages (later displaced by Arabic);
3. the Syriac dialect of Aramaic, used as the common language of the Middle Eastern Christians from Late Antiquity and with a continuing role even today.

Although there are shared features in all three, there are also particularities of circumstance which set them apart from each other. In the case of Aramaic in the service of the Achaemenids, what was created was a communicative koine, used internationally for diplomacy, administration, commerce, and, to some extent, literature. In the case of Jewish Aramaic, what emerged was an ethnic, religious, academic, and literary koine,

restricted in its particular features to the Jewish community. In the third case, that of Syriac, we have a religious and academic koine which was used, like Latin in medieval Europe and Arabic in the Islamic World, irrespective of ethnic boundaries, by Christian communities which spoke a variety of languages (some speaking local Aramaic dialects different from Syriac, some speaking related Semitic languages, like Arabic, some speaking totally unrelated languages, like Farsi and Malayalam).

1.0. Aramaic: Koine and Lingua Franca

All three of these episodes of international Aramaic have features of communicative koines and some aspects which have often attracted the label 'lingua franca'. However, the labels koine and lingua franca refer to very different phenomena, despite the functional overlap between the two categories (see Bloomfield 1935, 468–75; Calvet 1981; Thomason 2001, 269; Matras 2009, 275–88).

Lingua franca is a term which is used rather freely even in the linguistics literature. Thomason (2001, 269), for example (and with justification), gives two completely different definitions of lingua franca in her glossary. On the one hand, it is “a language that is used for communication between groups who do not speak each other’s languages.” On the other, it refers also to an Italian-based pidgin (i.e., a *mixed* language which is not the native language of any individual community).

A lingua franca in this second, narrower sense is an idiom developed by speakers of different, often unrelated, languages for specific purposes, usually connected with trade. Such a lingua

franca may be dominated by the language of the controllers of that trade: it is thus a kind of minimalistic compromise between acceptance of the controllers' language and the native languages of the other groups. Such a *lingua franca* typically has its own forms, which are never combined in the everyday *native* language of any of the individuals who use the *lingua franca*.

A stabilised *lingua franca* of this kind is similar to a pidgin, an *ad hoc* combination of elements from different linguistic traditions, designed to ease communication for specific purposes. Where such a mixed language *does* become a native language (the main language spoken by a population group), it is called a creole, i.e., a formalised language passed on as the native tongue of a second generation.

The 'parade-ground' example of a *lingua franca*, the original *lingua franca* in the narrow sense, which gave its name to the phenomenon, is the shared language among Eastern Mediterranean seafarers and traders in the early modern period (Bloomfield 1935, 473; Calvet 1981, 22–23; Thomason 2001, 269; see also Wansbrough 1996). This *lingua franca*, Romance-based and Romance in most of its lexicon, was developed for a limited sphere of usage and became stabilised, but it was never used as anyone's main language. It was written down to some limited extent, but it was never used outside its immediate commercial sphere. In French, the term 'langues véhiculaires', used for *linguae francae* (see Calvet 1981), represents their character well: these are languages of conveying, a support for trade and general practical intercourse. *Linguae francae* of this kind are *simplified*

languages, developing special vocabulary related to the technical fields they are concerned with.

A koine, by contrast, is a particular register or variety of a *specific* language which is turned into a communal idiom by a linguistic community, transcending dialect boundaries. The whole of this wider community speaks, or originally spoke, some form of the specific language as its native tongue. The term *koinē* is, of course, Greek, and in that context refers to a special type of Greek which was developed by the speakers of a large number of divergent Greek dialects as a linguistic medium which bound them all together as Greeks (Horrocks 2010², 79–123, etc.). *Koinē* Greek is sometimes called ‘the *koinē* dialect’, but is a transdialectal *standardised version* of Greek (see Davies 1987 and, on dialect, Chambers and Trudgill 1998², 3–12).

Koines share with *linguae francae* the characteristic of being used for communication over a wide area, but they are based entirely on the natural resources of the linguistic community from which they derive. The motivation for the emergence of such a koine may, again, originally have been commercial, but other shared cultural institutions, such as those of religion and law, would also benefit from the shared idiom. The Greek *koinē* flowered so as also to produce a vast literature in this standardised idiom and it spread with Alexander’s armies to become a hegemonic official language throughout the Seleucid Empire and, subsequently, the Roman East. For non-Greeks who used Greek as a second language, adopting it for its prestige, this Greek was just ‘Greek’, the only Greek they were generally aware of, unless they had had a full Hellenic education.

Returning to the three situations in which Aramaic came to have a special non-local usage, Aramaic began in the early first millennium BCE to displace an earlier, non-Aramaic Middle Eastern *lingua franca*, Akkadian, which in its various dialects had spread to the areas where cuneiform culture came to dominate (see further below). This displacement had already begun before the Achaemenid period (Hackl 2021), but the new political circumstances of that period accelerated the process and brought it to a new level.

1.1. The Achaemenid Persian Empire

The Achaemenid Persian Empire (539–330 BCE) adopted Aramaic as its diplomatic and commercial language, forming what Gzella (2015, 169) calls “a supra-regional *koiné*,” though it did not replace the local Aramaic dialects. Why and how it was deliberately chosen for this role is hard to pin down, but Aramaic, in various dialects, had been used already in Syria and Mesopotamia for many centuries before the Persians arrived on the scene, as we have seen. All the subject peoples of the Empire on its western side spoke non-Iranian languages and for many of them some form of Aramaic was the vernacular. Aramaic had already been used by the Assyrians and Babylonians as a medium of communication with western allies and in their own administrations. So the emergence of Imperial Aramaic as an international language was a gradual process and had earlier stages. In fact, it was never totally uniform (Folmer 1995), but sufficiently unified to serve its communicative purpose.

Perhaps most surprising is the fact that a language which had never been that of any significant state or international power came to have such an important role, becoming a literary as well as chancellery language (Gzella 2017)—it has often been said that the Aramaeans left little behind them except their language! (This is an exaggeration, but it is certainly true that the language itself has always been the main feature of Aramaeanness.)

It will be clear that the situation of Achaemenid-period Aramaic does not fit the narrow definition of a *lingua franca*. Imperial Aramaic was not a ‘made up’ language used for minimal commercial communication, but a fully-developed international language used by native speakers of different languages (such as Hebrew, Babylonian Akkadian, Lycian, and other Anatolian languages, as well as Iranian and north Indian languages—and, of course, Aramaic itself). It was not a mixture, like the Mediterranean *lingua franca*, or a pidgin or a creole, and it produced its own literature. The best analogies for it in the Mediterranean and Middle Eastern spheres are Greek, Latin, and Classical Arabic, though in those cases, cultural sharing (literary, religious, legal) was more important than diplomatic or commercial need. This Achaemenid Aramaic dissolved into local forms of Aramaic soon after the ‘glue’ which held it together, the Achaemenid Empire, disappeared. Local forms of Aramaic reasserted themselves, resulting in due course in the formation of “new local chancellery languages” (Gzella 2015, 214), later evidenced in Jewish Aramaic, Nabataean Aramaic, and Edessan Aramaic legal papyri and parchments.

1.2. The Late Antique and Medieval Periods

In the Late Antique and Medieval periods Aramaic became the language of religion, second only to Hebrew (and of equal practical import), for the Jews of the Middle East, with evidence extending from Egypt to Babylonia and beyond. It became, in effect, a sacred language alongside Hebrew, the vehicle for much of the Jewish cultural memory of community history and identity.

Although at first there were two main dialects of Jewish Aramaic, a Palestinian one (Jewish Palestinian Aramaic) and a Mesopotamian one (Jewish Babylonian Aramaic), the development of the great Jewish academies in Mesopotamia and the consolidation of Judaic learning there in the fifth to eighth centuries CE gave Jewish Babylonian Aramaic a dominant role (Gzella 2015, 348–57). There was much mixing of linguistic traditions between Babylonia and Palestine, leading to what Gzella (2015, 309) calls “a new, supra-regional... and highly standardised written code.” Most of the Jews who used it initially were probably native speakers of one Aramaic dialect or another (so that it would qualify for the term *koiné*—compare Greek above), but in its religious role, this communal Jewish Aramaic was also taken up by Jews who did not speak *any* form of Aramaic, but some other language: they learned both Hebrew and Aramaic as second languages, probably using both only in limited religious contexts. ‘Jewish Aramaic’ could be compared perhaps with Latin in medieval Europe or Classical Arabic, as a learned language essential for participation in what had become international Judaism.

Like Classical Arabic and Latin, Jewish Aramaic enjoyed a special sanctity, not so much because part of the so-called 'Hebrew Bible' is in fact written in Aramaic, but because the Targums (Aramaic translations of the Bible) and, more importantly, the Rabbinic literary tradition used Aramaic as a vehicle of the religion. Its theological discussions were often conducted in Aramaic, exemplified by the Masoretic annotations which surround and ensure the accurate preservation of the biblical text. Discussion of them was conducted in Aramaic.

1.3. Classical Syriac

Similarly, Classical Syriac, based on the local Aramaic of the Edessa region, became from about 200 CE the main communal language of the largest block of Middle East Christians. This variety of Aramaic was later labelled 'Edessan', though it must have been used over a much wider area: neither of the earliest stars of Syriac literature, Ephrem and Aphrahaṭ, was in fact Edessan in origin (though Ephrem moved to Edessa from Nisibis).

This dialect of Aramaic is the one in which the Syriac Bible (the Peshiṭtā) was promulgated under Bishop Rabbūlā of Edessa (411–435). It quickly achieved a high level of linguistic as well as religious authority, the latter in the context of the Christological disputes which entrenched an East-West division. It also grew in prestige as the vehicle of the most important of the Syriac Christian texts, becoming a sacred language whose style or register Syriac-writing Christians thereafter imitated, even if their own local Aramaic dialect was rather different from it. It was in this sense a koine like *koinē* Greek.

However, because of missionary activity, Syriac was also taken to Iran and the Gulf and beyond to India and China along the Silk Route. Monks and bishops of the Church of the East became fluent in Classical Syriac as part of their commitment to the Church, even if they were native speakers of Farsi or Malayalam or Chinese. So again, like *koinē* Greek, Classical Syriac became a koine so far as Christian Aramaic speakers were concerned, though it extended beyond that role and came to be used by non-speakers of Aramaic.

The Syriac Bible, the Peshiṭṭā, of which the individual books are of disparate origins which reveal traces of early dialectal variation (Weitzman 1999; van Peursen 2008; see below), became the model of the literary register of this koine, prompting the standardisation of the ‘Classical Syriac’ of later times, but it is quite difficult to know how far this Syriac was used in everyday affairs outside the religious context. There is little surviving evidence of everyday documents being written in Syriac after the third century CE (from which we have legal texts drawn up in a Roman context: see, conveniently, Drijvers and Healey 2009, 231–48). A few ostraca from Tell Tuneinir in Byzantine-era Syria (Fuller and Fuller 1998, 73, with information kindly provided by Prof. Michael Fuller) and of the eighth/ninth century CE from Tikrit in Iraq (Harrak 2010, 614–23, nos FA.01.09–16) survive, as well as a few papyri (so the seventh-century P.Berol. Inv. 8285: Brashear 1998, 93–100, pl. xiii; Brock 1999). These suggest that Syriac was in everyday use. Some of these texts are hard to classify linguistically, but can be interpreted as reflecting the contin-

uing development of local dialects of Aramaic in the Syro-Mesopotamian region, developments which led to the great variety of modern dialects which have been extensively described in recent years (Ṭūrōyō and North-Eastern Neo-Aramaic [NENA]).

2.0. Koines or *Linguae Francae*

An oddity of scholarly tradition is the fact that the term *lingua franca* is constantly used, especially of Imperial Aramaic (e.g., Healey 2009, 44; Gzella 2015, 39–40, 162–65, etc.; most recently Folmer 2020), though there is little similarity to the Mediterranean *lingua franca* from which the term itself arose. Nor is it similar to any of the other ‘*langues véhiculaires*’ described by Calvet (1981), such as Swahili. Despite this, there is a certain similarity to *linguae francae* in that all three of the above forms of Aramaic served the function of international communication, whether in trade or in administration or in religion and literature. So we may refer to Aramaic in each of the three phases as a *lingua franca* of diplomacy or commerce or religious discourse, though bearing in mind that this gives the term the wider definition.

The term *koine* fits better in all three cases, though again the fit is imperfect. Arguably, Achaemenid Aramaic was a *koine*, though its precise origins in Babylonia are still obscure and there remains some debate about how standardised it was (see especially Folmer 1995). ‘Jewish Aramaic’ is quite varied too, though arguably within certain limits which, especially so far as written texts were concerned, did not risk mutual incomprehension (e.g., between Jews in Palestine and Babylonia). Classical Syriac is

much more uniform across the whole world of Syriac Christianity, mainly, one supposes, because of the dominant position which the Peshittā came to have, providing a standard or model of good Syriac, and because of the centralising structures of the Syriac Churches, where communication with and travel to the main administrative centres of the Churches in Syria and Mesopotamia was always important as an expression of ecclesiastical identity. (The differences of pronunciation tradition with regard to vowels reflects the east-west division of the Syriac church, but this variation does not constitute two independent dialects.)

3.0. Local Forms of Aramaic in the Roman Period

One is tempted to use the term ‘global’, using this term within the framework of the ancient Near Eastern *oikoumenē*, for the wide spread of Aramaic under the Persians. Jewish Aramaic and certainly Syriac enjoyed geographically widespread currency, though within particular faith communities. Different local forms of Aramaic remained widespread into the period of Middle Aramaic (ca. 300 BCE–200 CE). The Aramaic of this period consisted of some sort of dialect continuum rather than a clear division into eastern and western (see Boyarin 1981; Butts 2021, 224–25). Within this context, intercommunal use of Aramaic also existed, situations in which separate communities—pagan, Jewish, and Christian—used shared, common forms of Aramaic—local *koinēs*—for legal and official purposes (as one part of a wider ‘cultural koine’ of shared habits), even when those communities maintained their own variety of the language.

The evidence of close integration alongside variation includes the situation in Palestine/Transjordan in the first and second centuries CE. The Nabataeans wrote their inscriptions and legal documents in what we call Nabataean Aramaic, as Judaeans used Jewish Aramaic in Roman Palestine. The Babatha archive (Yadin et al. 2002) and other contemporary archives (e.g., Cotton and Yardeni 1997) suggest a free flow of documentary Aramaic across this political and cultural divide. Babatha's archive contains several purely Nabataean documents (Nabataean dialect and Nabataean script), but also, of course, Judaeans Aramaic documents (in the Judaeans script).

P.Yadin 8, recording the purchase of a donkey, the transfer taking place between two Jewish brothers, with no evidence of any Nabataean involvement, is written in the Jewish script, but was claimed by Klaus Beyer (2004, 224) to be in the Nabataean dialect. It was drawn up by the scribe Yōḥanān son of Makkūtā, who was also the scribe of Nabataean document P.Yadin 9 (and probably P.Yadin 6: Yadin et al. 2002, 269), as well as a Greek document, P.Yadin 22 (Lewis 1989). P.Yadin 6 represents a transaction between Jews which is written in Nabataean Aramaic and the evidence suggests that scribes were happy to write in either dialect using either script.

A number of documents which are in the *Jewish* form of script—P.Yadin 7, P.Yadin 8, and even P.Yadin 10 (Babatha's *ketubba*)—were claimed by Beyer (2004, 217–24, 226–28) to be composed in the Nabataean dialect of Aramaic. The arguments advanced by him are suggestive, but not entirely definitive, and this is not the place to engage with them in detail. The envisaged

situation would not, however, be out of line with the intercommunal commonality we know from the content of the archives. This would provide an example of an Aramaic koine of a more restricted kind than the three major examples discussed above, a local, but still an intercommunal common language of law and commerce, arising from the fact that Jews and Nabataeans lived side by side in the area around Zoar and Maḥōzā at the southern tip of the Dead Sea. All were under the rule of the Nabataean kings (until 106 CE) and they had different forms of writing. Their legal culture (certainly in terms of the law of sale and other everyday transactions) was a shared one.

Another, slightly different, intercommunal Aramaic seems to have existed in the areas where Syriac emerged. The most direct evidence consists of several inscriptions from a Jewish necropolis at Kırk Mağara near Edessa written by Jews, as is indicated by a Jewish form of script, Jewish personal names (Joseph, Samuel), a listing of named individuals in a bilingual as *Ἰουδέων* (= *Ἰουδαίων*, genitive plural) (Pognon 1907, 79, no. 42), and the carving of a menorah on a tomb nearby (Segal 1970, 27, pl. 16a). Despite the natural inclination to count these texts as different from the dozens of contemporary early Syriac inscriptions, the Aramaic of these inscriptions in the Jewish script has grammatical features which are characteristic of Syriac (Pognon 1907, 78–79, nos 40, 41, 42–43, the last being the bilingual in Syriac and Greek; Noy and Bloedhorn 2003, 128–32, nos Syr78, Syr79, Syr80; for the Greek Canali de Rossi 2004, 18–19, no. 26).

The first lines of two of these inscriptions are *hn' byt 'lm'* d... (Pognon no. 40) and *hn' by'lm' d...* (no. 43), 'This is the tomb

of ...'. The demonstrative *hn'* is distinctively Syriac and common in early Edessan inscriptions in introductory phrases of this kind (Drijvers and Healey 1999, As5, As23, As24, As29, etc.), while *d-* (rather than *dī*, with *plene* writing as *dy*, as normally in western Aramaic) is the Syriac form of the possessive particle. The form *by(t)ʿlm'*, though known elsewhere (including P.Yadin 7.15, 71; P.Yadin 10.15; P.XHēv/Se 51a.2) is particularly common in the Edessan Syriac inscriptions (Drijvers and Healey 1999, nos As7, As9, Am2, Am3, etc., and in some subsequently published inscriptions, such as those in Brock 2013; Rumscheid 2013, 120–24; Gioia and Healey 2023). These Jewish inscriptions should be treated as Syriac, as already suggested tentatively by Pognon (1907, 78 on no. 40) and could be added to the corpus in Drijvers and Healey (1999).

To this epigraphic evidence we can add the broader evidence of the Peshiṭtā Old Testament (henceforth P). There is widespread scholarly consensus that it has Jewish or, perhaps in the case of some biblical books, Jewish-Christian origins. The Hebraisms in P certainly reflect direct translation from Hebrew. It is in some sense a Jewish Syriac *targum*, though in a different tradition from that of the Targums themselves (see especially Weitzman 1999, 234–37, 258–62, emphasising its divergence in many respects from the known Targums; in general Brock 2006², 23–27, 109–10). This view implies, necessarily, that there was a literate Jewish population in the Edessa region speaking and writing Syriac.

The Syriac of P is not, however, entirely uniform. Distinctive characteristics can be identified in different biblical books

and the lack of uniformity is reflected in some of the earliest manuscripts (van Peursen 2008). Weitzman distinguished books with ‘conservative’ and ‘modern’ translational characteristics (Weitzman 1999, 167–81). In general, these translations reflect the pre-Classical stages of Syriac, prior to the formation of Classical Syriac in its standard form (van Peursen 2008, 238–39). Butts has recently reasserted this broad interpretation, while adding an argument for a gradual process of convergence which led to the definitive form of Classical Syriac (Butts 2019, 224–27).

The Jewish Syriac of some of the translations in P may not have been totally identical with the early Syriac spoken by pagans in the Edessa region and we know from the so-called ‘Old Syriac’ or Edessan inscriptions that Syriac in this, its earliest epigraphic manifestation, was not uniform: it displays minor divergences from Classical Syriac, interpretable as dialectal variants (Healey 2008), and a Jewish variant probably existed also (cf. the Jewish inscriptions above, though they are very brief, and hard to distinguish from the normal Edessan ‘Syriac’, as we have seen).

The variability within P is reflected in the non-Syriac feature of the use of the accusative particle *yāt* sixteen times in P Song of Songs and Qoheleth, though only three times otherwise in the whole of the Bible (and extremely rarely in later Syriac). Traditionally this particle was seen as an archaism or a western Aramaic feature (for *yt* in western Aramaic see Khan 1984, 468; Beyer 2004, 413; see discussion in van Peursen 2008, 241). Weitzman (1999, 184–85) explained its appearance and other distinctive features of these books (such as the more frequent use of the

construct) as indicating a different translator, in line with his general conclusion on P that a variety of translators explains the differences between the books. As noted above, he used the terms ‘conservative’ and ‘modern’ to characterise individual translations (Weitzman, 167–81; van Peursen 2008, 241–43). However, alongside this argument for ‘archaisms’, there is the possibility that different *contemporary* speakers of Aramaic in the Syriac-speaking area spoke and wrote in slightly different variations of the language, even if, as Weitzman concludes, the translators were “colleagues in a single school” (see Weitzman 1999, 164–205, specifically 205).

4.0. Concluding Remarks

In the discussion of koines, it is difficult to avoid making a brief comparison with other international languages known from the Middle East. As noted above, during the ascendancy of the great Mesopotamian empires which preceded the Achaemenids, Akkadian and Mesopotamian culture created for some earlier periods a linguistic and cultural koine. Places like Ebla, south of Aleppo, and Alalakh and Ugarit, close to the Mediterranean coast, became outposts of this Mesopotamian scribal culture and used a western form of Akkadian written in cuneiform script as a vehicle for international communication, even while local languages continued as the vernaculars (Vita 2020; 2021 on Syria and Canaan). Becoming a lingua franca in the later second millennium BCE, Akkadian extended as far as Egypt (Müller 2021), used by Amarna period rulers in communication with Palestine and Syria, though

Akkadian was spoken as a vernacular in neither Egypt nor Palestine (see also Malbran-Labat 2021 on Akkadian in Elam). Here we have the use of a culturally hegemonic language as a language of diplomacy, similar to the use of French and English in modern times.

The other inevitable *comparandum* is Arabic. It owed its rise in importance to the spread of Islam and the highly regulated (and rather artificial) Classical Arabic came to be used as a ‘high’ language, replacing for this purpose, in religious discourse and ultimately also in general literature, local dialects which were of a similar Arabian character, as well as non-Arabic languages, such as forms of Aramaic, Iranian languages, Coptic, Berber, etc. In the case of Aramaic, as with some of the other local languages, such as Coptic, this led to a rapid decline in use of those local languages for literary purposes: Syriac-speaking Christians had no theological objection to the use of Arabic, and many used it even in the liturgy. The cultural pre-eminence of Classical Arabic led to its spread as a supra-dialectal koine, extending itself, because of its religious prestige, to areas where no form of Arabic was spoken as a vernacular.

The historic role of Aramaic as a Semitic *lingua franca* stands alongside that of Akkadian and Arabic. It has a longer history than both, though its periods of full functioning as a *lingua franca* and *koine* have been relatively brief (the Achaemenid period) and it was only a *lingua franca* later in a more restricted sense, i.e., for religious communities (Jewish and Christian). According to the evidence available to us, it also had in the Middle

Aramaic period an important intercommunal role in relation to particular cultural spheres (notably legal, funerary, and literary).

References

- Abou-Assaf, Ali, Pierre Bordreuil, and Alan R. Millard. 1982. *La statue de Tell Fekheriye et son inscription bilingue assyro-araméenne*. Études assyriologiques: Cahier n°7. Paris: Éditions Recherche sur les civilisations.
- Beyer, Klaus. 2004. *Die aramäischen Texte vom Toten Meer* 2. Göttingen: Vandenhoeck & Ruprecht.
- Biran, Avraham, and Joseph Naveh. 1993. 'An Aramaic Stele Fragment from Tel Dan'. *Israel Exploration Journal* 43: 81–98.
- . 1995. 'The Tel Dan Inscription: A New Fragment'. *Israel Exploration Journal* 45: 1–18.
- Bloomfield, Leonard. 1935. *Language*. London: George Allen.
- Brashear, William M. 1998. 'Syriaca'. *Archiv für Papyrusforschung* 44: 86–127, pl. xiii.
- Boyarín, Daniel. 1981. 'An Inquiry into the Formation of the Middle Aramaic Dialects.' In *Bono Homini Donum: Essays in Historical Linguistics in Memory of J. Alexander Kerns*, edited by Yoël L. Arbeitman and Alan R. Bomhard, 613–49. Amsterdam: John Benjamins.
- Brock, Sebastian. 1999. 'A Syriac Letter on Papyrus: P.Berol.Inv. 8285'. *Hugoye: Journal of Syriac Studies* 2/2: 163–65.
- . 2006. *The Bible in the Syriac Tradition*. 2nd edition. Gorgias Handbooks 7. Piscataway, NJ: Gorgias Press.

- Butts, Aaron M. 2019. 'The Classical Syriac Language'. In *The Syriac World*, edited by Daniel King, 222–42. The Routledge Worlds. London and New York: Routledge.
- Calvet, Louis-Jean. 1981. *Les langues véhiculaires: Que sais-je?* Paris: Presses universitaires de France.
- Chambers, John K., and Peter Trudgill. 1998. *Dialectology*. 2nd edition. Cambridge Textbooks in Linguistics. Cambridge: Cambridge University Press.
- Cotton, Hannah M., and Ada Yardeni. 1997. *Aramaic, Hebrew and Greek Documentary Texts from Naḥal Ḥever and other Sites (The Seiyâl Collection II)*. Discoveries in the Judaean Desert 27. Oxford: Clarendon.
- Davies, Anna M. 1987. 'The Greek Notion of Dialect'. *Verbum* 10: 7–28 (reprinted in *Greeks and Barbarians*, edited by Thomas Harrison, 153–71. Edinburgh: Edinburgh University Press, 2002).
- Drijvers, Han J. W., and John F. Healey. 1999. *The Old Syriac Inscriptions of Edessa and Osroene*. Handbook of Oriental Studies I/42. Leiden, Boston, and Cologne: Brill.
- Folmer, Margaretha L. 1995. *The Aramaic Language in the Achaemenid Period: A Study in Linguistic Variation*. Orientalia Lovanensia Analecta 68. Leuven: Peeters.
- . 2020. 'Aramaic as *Lingua Franca*'. In *A Companion to Ancient Near Eastern Languages*, edited by Rebecca Hasselbach-Andee, 373–99. Chichester: Wiley Blackwell.
- Fuller, Michael J., and Neathery Fuller. 1998. 'Archaeological Discoveries at Tell Tuneinir, Syria'. *Journal of Assyrian Academic Studies* 12/2: 69–82.

- Gzella, Holger. 2015. *A Cultural History of Aramaic from the Beginnings to the Advent of Islam*. Handbook of Oriental Studies I/111. Leiden and Boston: Brill.
- . 2017. 'Von der Kanzlei- zur Kultursprache: Die Anfänge der aramäischen Weltliteratur'. *Theologische Quartalschrift* 197/2: 107–32.
- Hackl, Johannes. 2021. 'The Death of Akkadian as a Written and Spoken Language.' In *History of the Akkadian Language*, edited by Juan-Pablo Vita, 1459–77. Handbook of Oriental Studies I/152. Leiden and Chicago: Brill.
- Harrak, Amir. 2010. *Receuil des inscriptions syriaques (Académie des Inscriptions et Belles-Lettres). Tome 2. Iraq: Syriac and Garshuni Inscriptions*. Paris: Diffusion de Boccard.
- Healey, John F. 2008. 'Variety in Early Syriac: The Context in Contemporary Aramaic.' In *Aramaic in its Historical and Linguistic Setting*, edited by Holger Gzella and Margaretha L. Folmer, 221–29. Akademie der Wissenschaften und der Literatur, Mainz; Veröffentlichungen der Orientalischen Kommission 50. Wiesbaden: Harrassowitz Verlag.
- . 2009. *Aramaic Inscriptions and Documents of the Roman Period: Textbook of Syrian Semitic Inscriptions IV*. Oxford: Oxford University Press.
- Healey, John F., and Claudia Gioia. 2023. 'A "Gift" in Syriac: A Mosaic from Osrhoene'. In *Šalmūtā Šapīrtā: Festschrift for Rifaat Y. Ebied in honour of his contributions to Semitic Studies—Presented for his 85th birthday, 29th June 2023*, edited by Erica C. D. Hunter, 29–60. Gorgias Eastern Christian Studies 65. Piscataway, NJ: Gorgias Press.

- Horrocks, Geoffrey. 2010. *Greek: A History of the Language and Its Speakers*. 2nd edition. Chichester: Wiley-Blackwell.
- Huehnergard, John. 2021. 'The Legacy of Akkadian'. In *History of the Akkadian Language*, edited by Juan-Pablo Vita, 1481–531. Handbook of Oriental Studies I/152. Leiden and Chicago: Brill.
- Khan, Geoffrey A. 1984. 'Object Markers and Agreement Pronouns in Semitic Languages'. *Bulletin of the School of Oriental and African Studies* 47: 468–500.
- Lewis, Naphtali. 1989. *The Documents from the Bar Kokhba Period in the Cave of Letters: Greek Papyri*. Judean Desert Studies. Jerusalem: Israel Exploration Society, the Hebrew University of Jerusalem, and the Shrine of the Book.
- Malbran-Labat, Florence. 2021. 'Akkadian in Elam'. In *History of the Akkadian Language*, edited by Juan-Pablo Vita, 1316–43. Handbook of Oriental Studies I/152. Leiden and Chicago: Brill.
- Matras, Yaron. 2009. *Language Contact*. Cambridge Textbooks in Linguistics. Cambridge: Cambridge University Press.
- Müller, Matthias. 2021. 'Akkadian in Egypt'. In *History of the Akkadian Language*, edited by Juan-Pablo Vita 1293–315. Handbook of Oriental Studies I/152. Leiden and Chicago: Brill.
- Noy, David, and Hanswulf Bloedhorn. 2001. *Inscriptiones Judaicae Orientis III*. Texts and Studies in Ancient Judaism 102. Tübingen: Mohr Siebeck.

- Pognon, Henri. 1907. *Inscriptions sémitiques de la Syrie, de la Mésopotamie et de la région de Mossoul*. Paris: Imprimerie Nationale.
- Rubin, Aaron D. 2005. *Studies in Semitic Grammaticalization*. Harvard Semitic Studies 57. Winona Lake, IN: Eisenbrauns.
- Segal, Judah B. (Ben). 1970. *Edessa, 'The Blessed City'*. Oxford: Clarendon.
- Thomason, Sarah G. 2001. *Language Contact: An Introduction*. Edinburgh: Edinburgh University Press.
- van Peursen, Willem Th. (Wido). 2008. 'Language Variation, Language Development, and the Textual History of the Peshitta'. In *Aramaic in Its Historical and Linguistic Setting*, edited by Holger Gzella and Margaretha L. Folmer, 231–56. Akademie der Wissenschaften und der Literatur, Mainz; Veröffentlichungen der Orientalischen Kommission 50. Wiesbaden: Harrassowitz.
- Vita, Juan-Pablo. 2020. 'Akkadian as a *Lingua Franca*'. In *A Companion to Ancient Near Eastern Languages*, edited by Rebecca Hasselbach-Andee, 357–72. Chichester: Wiley Blackwell.
- . 2021. 'Akkadian in Syria and Canaan'. In *History of the Akkadian Language*, edited by Juan-Pablo Vita, 1213–65. Handbook of Oriental Studies I/152. Leiden and Chicago: Brill.
- Wansbrough, John E. 1996. *Lingua Franca in the Mediterranean*. Richmond: Curzon Press.
- Weitzman, Michael P. 1999. *The Syriac Version of the Old Testament: An Introduction*. University of Cambridge Oriental Publication 56. Cambridge: Cambridge University Press.

Yadin, Yigael, Jonas C. Greenfield, Ada Yardeni, and Baruch A. Levine. 2002. *The Documents from the Bar Kokhba Period in the Cave of Letters: Hebrew, Aramaic and Nabataean-Aramaic Papyri*. Judean Desert Studies. Jerusalem: Israel Exploration Society, Institute of Archaeology, the Hebrew University of Jerusalem, and the Shrine of the Book, Israel Museum.

ARABIC SPELLS AGAINST MENSTRUAL BLEEDING IN MANDAIC SCRIPT

Matthew Morgenstern and Tom Alfia

In 1943, Lady Ethel Drower briefly noted the existence of Arabic magic spells in Mandaic transcription contained in two ‘recipe books’ that served amulet writers in Baghdad during the late nineteenth and early twentieth centuries (Drower 1943, 149).¹ In the course of a comprehensive survey of Mandaic manuscripts for the preparation of lexically tagged digital editions of the corpus, it became apparent that the scope of the Arabic materials demanded a separate study.

An introductory overview of the Arabic materials in these manuscripts and their linguistic and cultural background has been published elsewhere.² For reasons of space, it shall suffice

¹ The manuscripts are numbers 45 and 46 in the Drower Collection of the Bodleian Library, Oxford. For further details on these manuscripts see Morgenstern and Abudraham (f.c.).

² See Morgenstern and Alfia (2013). Since that article was completed, two additional spell handbooks containing Arabic spells in Mandaic transcription have come to our attention, both housed in the Bibliothèque Nationale de France (Codex Sabéen 24 and 27), as well as several smaller fragments held by the Berlin Staatsbibliothek. The magical

to reiterate here that the evidence indicates that these Mandaean transcriptions were prepared in the modern era from Islamic (Shiite) amulets written in Arabic script. Parallels in Arabic script indicate that the source materials were most likely composed in Standard Arabic, but have been transcribed with considerable influences of local *gilit* dialects similar, but not identical to that of Baghdad (see in brief Morgenstern and Alfia 2013, 171–72). The texts thus provide an interesting example of works composed in one idiom, yet read through the perspective of another. The corpus is also of interest for scholars of reading traditions, who must address such phenomena.

In this article, we present a preliminary edition of six amuletic formulae found in these manuscripts for treatment of excessive bleeding. The texts are *historiolae* (see, e.g., Frankfurter 1995), in which heavenly warrior “blood kings” are described as descending from heaven to cut off the flow of blood from mothers and daughters. The heavily armed kings are described in traditional fashion from head to foot, a practice already found in earlier magical and other sources.³ The Mandaic instructions indicate that the Mandaean practitioners regarded them as effective primarily against excessive menstrual bleeding.

handbooks are discussed in greater detail in Morgenstern and Abudraham (f.c.). On colloquial Arabic in Mandaic script, see now also Häberl (2021).

³ For medical and protective texts from Mesopotamia, see, e.g., Stol (1991, 49); Müller-Kessler (1991, 344); Geller (2000, 15). Compare in particular the description of Bagdānā in the Jewish Babylonian Aramaic magic bowl AMB 13, published in Naveh and Shaked (1998, 198–214).

As we noted in our previous article and discuss in some places below, the transcriptions contain many errors which stem from both a misreading of the Arabic original and inaccurate copying of the Mandaic transcription. Such errors impede the reconstruction of the Arabic *Vorlagen*. The copies of these spells in the BNF manuscripts are generally more corrupt than those in the manuscripts of the Drower Collection, but occasionally contain superior readings. Furthermore, many of the formulae follow a similar pattern and contain parallel expressions, a fact that greatly assists us in reconstructing the Arabic sources. Nonetheless, many textual problems remain, and it is likely that the interpretations presented herein may be improved upon by reference to parallels in Arabic script that are unknown to us. Our aim here is to make these texts available for further study, and to provide more substantial evidence for the phenomena that we have previously discussed. For a lack of space, our notes are kept to a minimum.

This article is happily dedicated to Prof. Geoffrey Khan, whose seminal works on Hebrew texts in Arabic transcription and on reading traditions are model for emulation.

1.0. The Texts

The amulets are presented here in a diplomatic transliteration in the Mandaic and Latin scripts, followed by the 'rubrics' found in the manuscript for the use of the amulets. The text is presented exactly according to the line divisions in the original. Variant readings are presented in Latin transliteration alone. The tran-

1.1. Text 1

[illegible]

¹ Corrected according to CS 27; DC 45: *lsam*. ² CS 27: *gam šan*; RRC: *gimišin*.
³ RRC: *ldam*. ⁴ CS 27: *fariš*; RRC: *karš*. ⁵ RRC: *ldam*. ⁶ CS 27: *uas*. ⁷ CS 27: *mn dam*. RRC: *mn ldam*. ⁸ RRC: *ldam*. ⁹ RRC: *angiṭi*^c. ¹⁰ CS 27: *ia aha*. RRC: *iaiaiaha*
¹¹ RRC: *farš*. ¹² CS 27: *flan bint falana*. RRC: [only:] *filana*. ¹³ CS 27: *haza*. ¹⁴ CS 27: *lsma*. ¹⁵ RRC: *u'um ha'an*. ¹⁶ RRC: *lbinut*. ¹⁷ CS 27: *bra hua mtak*. RRC: *bra|humtak*. ¹⁸ CS 27: *ia rahi*. RRC: *iarahim*. ¹⁹ CS 27: *lrahamin lrahim*. ²⁰ RRC: *pšqa*. ²¹ RRC: *lai*. ²² CS 27: *lhudra*. ²³ Corrected according to CS 27 and RRC; DC 45: *ḏ'uta*. ²⁴ Corrected according to CS 27; DC 45: *bnuba*; RRC: *bnura*. ²⁵ CS 27: *l šipulah*; RRC: *lšipuas*.

A king of blood descended from heaven	نزل من السماء ملك من الدم
wearing a shirt of blood,	لابسا قميصًا من الدم
upon his head a silk shawl of blood	على رأسه كريش من الدم
riding a steed of blood,	راكبا جوادا من الدم
in his hand an axe of blood.	بيده قدوم من الدم
Be cut off, O blood,	انقطع يا أيها الدم
From the loins of PN daughter of PN.	من فرج فلانة بنت فلان
By the right of these names,	بحق هذه الأسماء
from one who copulates with a daughter and her mother	من ناكح البنت وأمها
[...] away from one who copulates with a daughter [...]	عن ناكح البنت
the loins in your mercy,	الفرج برحمتك
Oh most merciful of all who show mercy!	يا أرحم الراحمين

[Mandaic rubric:]

This is (for) cutting off menstrual blood. Write on the tunic of an impure woman from her collar to her loins.

Notes

7. *uʿhmhaʿan*. The context and parallels indicate that this should be read *uʿumha ʿan* ‘and her mother from’. In this manuscript, the graphic difference between *uʿhmha* ܘܥܡܗܐ and *uʿumha* ܘܥܡܗܐ is minimal. RRC supports our suggestion, but divides the words differently: *uʿum haʿan*.

12. *mn buṣura*. The reading of CS has been preferred here. On *b(u)ṣura* ‘collar’ in Mandaic, see Morgenstern (2018, 194).

1.2. Text 2

Source: DC 46. 147:7–148:4.

1	<i>bisim alah alrahman alrahim</i>	ܒܝܨܝܡ ܐܠܗ ܐܠܪܗܡܢ ܐܠܪܗܝܡ
2	<i>nazal malk mn ldam labis gimis</i>	ܢܙܠ ܡܠܟ ܡܢ ܠܕܡ ܠܒܝܨ ܓܝܡܝܨ
3	<i>mn dam b'da gadum mn dam 'ala</i>	ܡܢ ܕܡ ܒ'ܕܐ ܓܕܘܡ ܡܢ ܕܡ ܥܠܐ
4	<i>rasah 'amamah mn dam rašib⁴</i>	ܪܫܐ ܥܡܡܐ ܡܢ ܕܡ ܪܫܝܒ
5	<i>šauadna⁵ mn dam ub'da gadum mn</i>	ܫܐܘܕܢܐ ܡܢ ܕܡ ܘܒ'ܕܐ ܓܕܘܡ ܡܢ
6	<i>ldam fada rab aldim bildam</i>	ܠܕܡ ܦܕܐ ܪܒ ܐܠܕܝܡ ܒܝܠܕܡ
	<i>angiṭi'</i>	ܐܢܓܝܬܝ
7	<i>ia aiha ldam mn fariš planita</i>	ܝܐ ܐܝܗܐ ܠܕܡ ܡܢ ܦܪܝܫ ܦܠܢܝܬܐ
8	<i>kma angiṭ'at arahma 'an nakha</i>	ܟܡܐ ܐܢܓܝܬ'ܐܬ ܐܪܚܡܐ ܥܢ ܢܚܟܐ
9	<i>al'ašuz ubint aha ua uamha ukma</i>	ܐܠ'ܐܫܘܙ ܘܒܝܢܬ ܐܗܐ ܘܐ ܘܡܗܐ ܘܟܡܐ
10	<i>angiṭ'at lrahman 'an nakha</i>	ܐܢܓܝܬ'ܐܬ ܠܪܗܡܢ ܥܢ ܢܚܟܐ
	<i>alfarah</i>	ܐܠܦܪܗ
11	<i>birahmtak ia arham alrahmin</i>	ܒܝܪܗܡܬܟ ܝܐ ܐܪܗܡ ܐܠܪܗܡܝܢ
12	<i>balf ulahul ulaqubat alah bilah</i>	ܒܠܦ ܘܠܗܘܠ ܘܠܐܩܘܒܬ ܐܠܗ ܒܝܠܗ
	<i>l'alia</i>	ܠܥܠܝܐ
13	<i>l'adim tum ukamal s—a</i>	ܠܥܠܝܡ ܬܘܡ ܘܟܡܠ ܫ—ܐ
14	<i>hazin baba psqa dhšuka kdub</i>	ܚܙܝܢ ܒܒܐ ܦܨܩܐ ܕܫܘܟܐ ܟܕܘܒ
	<i>'lai gidma dpahil</i>	ܥܠܝ ܓܝܕܡܐ ܕܦܗܝܠ
15	<i>bsikinta min giliit midad</i>	ܒܫܝܟܝܢܬܐ ܡܝܢ ܓܝܠܝܬ ܡܝܕܐܕ
	<i>ubadqath bšamšia iabuš</i>	ܘܒܕܩܬܐ ܒܫܡܫܝܐ ܝܒܘܫ

⁴ On the basis of the other spells, we take ܪܫܝܒ *rašib* to be an inner-Mandaic copying error for ܪܟܝܒ *rakib*.

⁵ Copying error, perhaps for *šauadan* or *šauadin*.

In the name of Allah, the Beneficent, the Merciful.	بسم الله الرحمن الرحيم
An angel of blood descended	نزل ملك من الدم
wearing a shirt of blood,	لابسا قميصا من دم
in his hand an axe of blood	بيده قدوم من دم
and on his head a turban of blood,	وعلى رأسه عمامة من دم
riding a steed of blood,	راكبا جوادا من دم
in his hand an axe of blood,	وبيده قدوم من الدم
and he struck the blood with blood.	فضرب الدم بالدم
Be cut off, O blood,	انقطع يا أيها الدم
from the loins of PN	من فرج ولد PN
just as mercy was cut off	كما انقطعت الرحمة
from one who copulated with an old woman	عن ناكح العجوز
and her daughter and her mother	وبنتها وأُمها
and as mercy was cut off	وكما انقطعت الرحمة
from one who copulated with the loins in your mercy.	عن ناكح الفرج ⁶ برحمتك
O Most Merciful of the Merciful, a thousand-fold!	يا أرحم الراحمين بألف
“there is no power and no strength	ولا حول ولا قوة
other than in Allah, the Exulted, the Mighty”.	إلا بالله العلي العظيم
Finished and completed.	تم وكمل

[Mandaic rubric:]

This prescription is (for) cutting off menstrual blood. Write it on a palm frond with a knife with ... ink and place it in the sun (until) it dries.

⁶ The manuscript reads *alfarah*, a misreading of the original Arabic text.

Notes

9. *ubint aha ua uamha*. On the basis of the parallels, we have taken this to be a minor graphic error for *ubintaha ua'amha*, reflecting an Arabic *Vorlage* *وبنتها وأمها*.

10. *nakha alfarah*. We have interpreted *alfarah* as a misreading of the original Arabic *الفرح* as *الفرج*. The reading *الفرح* makes no sense in this context.

15. *giliit midad*. The meaning of these words is uncertain. *midad* appears to be Arabic *مداد* 'ink'.

1.3. Text 3

DC 46. 146:8–147:6.

1	<i>bisim alah alrahman alrahim</i>	بسم الله الرحمن الرحيم
2	<i>nazal malk mn ldam ulabis gimis̄</i>	نزل ملك من لدم أولابس جيمس
3	<i>mn aldam u'ala rasah šalin mn</i>	من لدم أولاه راسه شالين من
4	<i>ldam b'dah rumhin mn dam</i> <i>umits̄anid</i>	لدم بداه رومين من دم وميثسانيد
5	<i>bisifan mn dam uarab⁷ aldam</i> <i>bildam</i>	بسيم من دم واراب ⁷ لدم بيلدم
6	<i>'ngiṭi' ia aiha ldam bhaq haua</i>	نغيتي يا ايها لدم بهاك هاوا
7	<i>uadam angiti' ia aiha ldam bihaq</i>	وادم انغيتي يا ايها لدم بيهك
8	<i>luḥ ulqalam angiti' ia aiha dam</i>	لوح القلام انغيتي يا ايها دم
9	<i>bihaq manhu bil mahad tikalam</i>	بيهك منه بيل ماهاد تيكلام
10	<i>angiti' ia aiha ldam bhaq brahim</i>	انغيتي يا ايها لدم بهاك براهيم
11	<i>'bin lduam angiti' aiha ldam mn</i>	بين لدم انغيتي ايها لدم من

⁷ Copying error of *warab* for *darab*.

12 <i>planita laḥul ulaqubat ala bilah</i> <i>l'alia</i>	ܐܠܗܐ ܕܠܗܘܠܐ ܐܠܗܐ ܕܠܗܘܠܐ ܐܠܗܐ ܕܠܗܘܠܐ ܐܠܗܐ
13 <i>l'adim tum ukamal</i>	ܐܠܗܐ ܕܐܕܡܐ ܕܐܕܡܐ ܕܐܕܡܐ
14 <i>s—a</i>	ܡܕ
15 <i>hazin baba psaqa ḏḥšuka kdub</i> <i>bkagid</i>	ܡܕܐܪܥܐ ܕܡܕܐܪܥܐ ܕܡܕܐܪܥܐ ܕܡܕܐܪܥܐ ܡܕܐܪܥܐ
16 <i>uriph l'nta lhalša mipsaq ḥšuka</i> <i>mn 'nta ugrabra</i>	ܕܡܕܐܪܥܐ ܕܡܕܐܪܥܐ ܕܡܕܐܪܥܐ ܕܡܕܐܪܥܐ ܡܕܐܪܥܐ ܕܡܕܐܪܥܐ ܕܡܕܐܪܥܐ
17 <i>bhailḥ ḏmaraian hauia aruaha</i>	ܡܕܐܪܥܐ ܕܡܕܐܪܥܐ ܕܡܕܐܪܥܐ ܕܡܕܐܪܥܐ
18 <i>s—a</i>	ܡܕ
In the name of Allah, the Beneficent, the Merciful.	ܒܝܫܡ ܐܠܗܐ ܕܪܚܡܢ ܕܪܚܝܡ
An angel of blood descended	ܢܙܠ ܡܠܟ ܡܢ ܕܡ
wearing a shirt of blood,	ܘܠܒܝܫ ܩܡܝܣܐ ܡܢ ܕܡ
and on his head, a shawl of blood.	ܘܥܠܝ ܪܥܫܐ ܫܐܠ ܡܢ ܕܡ
In his hand a lance of blood	ܒܝܕܐ ܪܡܚ ܡܢ ܕܡ
and fighting with a sword of blood,	ܘܡܬܨܢܕ ܒܫܝܦ ܡܢ ܕܡ
he struck the blood with blood.	ܘܨܪܒ ܕܡ ܒܕܡ
Be cut off, O blood,	ܐܢܩܬܥ ܝܐ ܐܝܝܗܐ ܕܡ
by the right of Eve and Adam	ܒܡܚ ܡܢ ܐܕܡ ܘܐܕܡ
Be cut off, O blood,	ܐܢܩܬܥ ܝܐ ܐܝܝܗܐ ܕܡ
by the right of the board and the pen	ܒܡܚ ܡܢ ܐܠܘܚ ܘܩܠܡ
Be cut off, O blood,	ܐܢܩܬܥ ܝܐ ܐܝܝܗܐ ܕܡ
by the right of the one who spoke in the cradle,	ܒܡܚ ܡܢ ܗܘ ܒܐܡܗܕ ܬܠܡ
Be cut off, O blood,	ܐܢܩܬܥ ܝܐ ܐܝܝܗܐ ܕܡ
by the right of Ibrahim, son of ...am,	ܒܡܚ ܡܢ ܐܒܪܗܝܡ ܒܢ ܕܠܘܡ
Be cut off, O blood,	ܐܢܩܬܥ ܐܝܝܗܐ ܕܡ
From PN	ܡܢ ܐܠܗܐ ܕܡܕܐܪܥܐ
“there is no power and no strength	ܠܐ ܠܚܘܠ ܘܠܐ ܩܘܐ

other than in Allah, the Exulted, the Mighty”.

إلا بالله العلي العظيم

Finished and completed.

تم وكمل

[Mandaic rubric:]

This prescription is (for) cutting off menstrual blood. Write on paper and tie it to a woman at her loins, and the menstrual blood will be cut off from a woman or a man by the power of our lord, there will be relief.

Notes

10–11. *brahim ‘bin lduam*. It may just be possible to read *ldham*. The name apparently also appears in Text 4, wherein DC 46 may be read *aldsam* or *albsam*, while DC 45 reads *alrham*, presumably reflecting a name based on the root *rḥm*. We have found none of these names in any Arabic source, and if this refers to the patriarch Abraham, the patronym remains opaque.

16. *‘nta ugabra*. This appears to be a mechanical copying of a formula common in these collections. The spell is of course suitable only for women.

1.4. Text 4

This spell survives in four parallel copies. All copies contain errors, and the copy in CS 27.34a ff. (here cited as CS 27 B) is particularly corrupt. The text presented here is based primarily on DC 46, with some corrections introduced from DC 45 and CS 27 as noted. There is a slight difference in the versions in the section that invokes the beneficent agents.

Source: DC 46. 26:16–27:12; DC 45.10a:10–16; CS 27.36b:10–37a:9 (below: CS 27 A); CS 27. 34a:15–34b:10 (below: CS 27 B).

- 1 *bisim alah ʿl rahman¹ lrahim* ܒܝܨܡܐܠܗ ܐܠܗܝܢ ܕܠܪܗܡܢ ܠܪܗܝܡ
- 2 *nizal malk mn aldam ulabis²* ܢܝܙܠ ܡܠܟ ܡܢ ܐܠܕܡ ܐܠܒܝܨ
- 3 *gimiṣun³* ܓܝܡܝܨܐܢ
- 4 *mn ʿl dam⁴ bʿdah⁵ <rumḥin>⁶ mn* ܡܢ ܐܠܕܡ ܒܥܕܐ ܕܪܡܚܝܢ
- 5 *dam⁷ umitšanid⁸* ܕܡܡܝܬܫܢܝܕ
- 6 *bsifin mn aldam darab ldam⁹* ܒܫܝܦܝܢ ܡܢ ܐܠܕܡ ܕܪܒ ܠܕܡ
- 7 *bldam¹⁰* ܒܠܕܡ
- 8 *ʿngiṭi¹¹ ia aiha ldam¹¹ bhaq lluh¹²* ܐܢܓܝܬܝ ܝܐ ܐܝܗܐ ܠܕܡ ܒܗܩ ܠܠܗ
- 9 *ulqalam ʿngiṭi¹¹ ia aiha ldam bhaq* ܐܠܩܠܡ ܐܢܓܝܬܝ ܝܐ ܐܝܗܐ ܠܕܡ ܒܗܩ
- 10 *brahim ʿbin aldham¹³ angīṭi¹⁴ ia* ܒܪܗܝܡ ܐܒܝܢ ܐܠܕܗܡ ܐܢܓܝܬܝ ܝܐ
- 11 *aiha¹⁵* ܐܝܗܐ
- 12 *aldam¹⁶ mn planita pt¹⁷ planita* ܐܠܕܡ ܡܢ ܦܠܢܝܬܐ ܦܬ ܦܠܢܝܬܐ
- 13 *bhaq* ܒܗܩ
- 14 *ulahul ulaqubat¹⁸ alah bilah* ܐܠܗܘܠ ܐܠܗܘܒܬ ܐܠܗ ܒܝܠܗ
- 15 *lʿalia¹⁹* ܠܐܠܝܐ
- 16 *lʿadim s—a* ܠܐܕܝܡ ܣܐ
- 17 *hazin baba psaqa²⁰ ḡhšuka kdub* ܗܙܝܢ ܒܒܐ ܦܣܩܐ ܓܝܫܘܟܐ ܕܕܒ
- 18 *bkagid* ܒܟܓܝܕ
- 19 *urupa²¹ lʿnta²² alhaṣa²³ mipsiq²⁴* ܐܪܘܦܐ ܠܐܢܬܐ ܐܠܗܫܐ ܡܝܦܨܝܩ
- 20 *hšuka mina ʿnta ugabra²⁵* ܗܫܘܟܐ ܡܝܢܐ ܐܢܬܐ ܘܓܒܪܐ
- 21 *bhailh²⁶ ḡmaraian²⁷ s—a* ܒܗܝܠܗ ܓܡܪܝܐܢ ܣܐ

¹ DC 45, CS 27 A: *lrahman*. ² CS 27 A: *ulabas*. CS 27 B: *ulasim*. ³ DC 45, CS 27 A, B: *gimiṣ*. ⁴ CS 27 B: *aldam*. ⁵ CS 27 B: *bibʿdah*. ⁶ Reconstructed on the basis of CS 27 A; DC 45: *rumḥin*; CS 27 B: *qumsin*; DC 46 omits entirely. ⁷ DC 45, CS 27 A, B: *mn ʿl dam*. ⁸ CS 27 A: *tṣat*. ⁹ CS 27 B omits the entire passage *umitšanid–ldam*. ¹⁰ DC 45: *bldam bldam* (dittography). ¹¹ DC 45: *ʿngiṭi¹¹ ia aiha ldam* is omitted here in DC 45 (haplography *ldam–ldam*). CS 27 A adds here: *ʿngiṭi¹¹ ia aiha ldam bhaq haua uadam*. ¹² Corrected according to DC 45; Sab 27 A: *lluh*; DC 46, CS 27 B:

llhus.¹³ Corrected according to CS 27 A; DC 46: *aldsam*; DC 45: *alrham*; CS 27 B: *albsanim*.¹⁴ DC 45, CS 27 A, B: *‘ngiṭi*.¹⁵ DC 45: *iaiaha*.¹⁶ CS 27 B: *ldam*.¹⁷ DC 45, CS 27 A: *pta*.¹⁸ DC 45: *ula uqubat*; CS 27 A: *ula rubat*. CS 27 B: *ula qubat*.¹⁹ CS 27 A omits.²⁰ CS 27 B omits.²¹ DC 45: *uripa*; CS 27 A: *urip*; CS 27 B: *uriupa*.²² DC 45: *al‘nta*. CS 27 A: *‘nta*.²³ CS 27 A: *‘l haṣa*. CS 27 B: *alḥa ṣa*.²⁴ DC 45: *mṗsiq*. CS 27 B: *mn p̄siq*.²⁵ CS 27 B: *gabra*; CS 27 A omits *mina* *‘nta ugabra*.²⁶ CS 27 B: *bhailia*.²⁷ CS 27 A: *bhai ḡmarai^{hun}*; CS 27 B: *ḡmaraiun*.

In the name of Allah, the Beneficent, the Merciful.

بسم الله الرحمن الرحيم

An angel of blood descended

نزل ملك من الدم

wearing a shirt of blood,

ولابس قميصاً من الدم

in his hand <a lance> of blood

بيده (رمح) من دم

and fighting with a sword of blood,

ومتجند بسيف من الدم

He struck the blood with blood.

ضرب الدم بالدم

Be cut off, O blood,

انقطع يا أيها الدم

by the right of the board and the pen

بحق اللوح والقلم

Be cut off, O blood,

انقطع يا أيها الدم

by the right of Ibrahim, son of Adham,

بحق ابراهيم بن الأدهم

Be cut off, O blood

انقطع يا أيها الدم

from PN daughter of PN,

من ولبدرءاته ولبدرءاته

by the right of “and there is no power

بحق ولا حول

and no strength other than in Allah, the Exulted, the

ولا قوة إلا بالله العلي

Mighty”.

العظيم

[Mandaic rubric:]

This prescription is (for) cutting off menstrual blood. Write on paper and tie it to a woman at her loins, and the menstrual blood will be cut off from her; (for) a woman or a man by the power of our lord.

Notes

7. *brahim* *‘bin aldsam*. In DC 46, the patronym may be read *aldsam* or *albsam*. DC 45 reads *alrham*, presumably reflecting a name

based on the root *rhm*. We have found neither name in any Arabic source.

1.5. Text 5

This text, while generally comprehensible in its structure, suffers from a number of textual corruptions that render several passages untranslatable. The parallel copies, while generally reflecting the same text, show a very large number of different corruptions and orthographic variants.

DC 46. 149:4–150:8; CS 27. 28a:3–28b:13.

1	<i>bisim alah brahman</i> <i>alrahim hibaṭ</i> ¹	ܐܠܗܐ ܒܪܗܡܢ ܐܠܗܐ ܪܗܝܡܢ ܐܠܗܐ ܪܗܝܡܢ ܐܠܗܐ ܪܗܝܡܢ
2	<i>malkin</i> ² <i>mn amalkin mn aldam</i> ³ <i>‘ala</i> <i>farašin</i> ⁴	ܡܠܟܝܢ ܡܢ ܐܡܠܟܝܢ ܡܢ ܐܠܕܡ ܐܠܗܐ ܦܪܐܫܝܢ
3	<i>mn dam</i> ⁵ <i>salṭa</i> ⁶ <i>mn dam</i> ⁵ <i>fada rab</i> ⁷ <i>ldam</i> ⁸	ܡܢ ܕܡ ܫܠܬܐ ܡܢ ܕܡ ܦܕܐ ܪܒ ܠܕܡ
4	<i>bildam</i> ⁹ <i>‘ngiṭi</i> ¹⁰ <i>ia aiha</i> ¹¹ <i>aldam</i> ¹² <i>bhaq</i> ¹³	ܒܝܠܕܡ ܢܓܝܬܝ ܝܐܝܗܐ ܐܠܕܡ ܒܗܩ
5	<i>haua uadam ubhaq</i> ¹³ <i>asm la‘ṭm</i> ¹⁴ <i>lmukaram</i> ¹⁵	ܗܘܐ ܘܕܡ ܘܒܗܩ ܐܫܡ ܠܐܬܡ ܠܡܘܟܪܡ
6	<i>‘ladia</i> ¹⁶ <i>nazal</i> ¹⁷ <i>‘ala</i> ¹⁸ <i>‘isa ‘bin ma-</i> <i>riam</i>	ܠܕܝܐ ܢܙܠ ܐܠܐ ܥܝܫܐ ܥܒܝܢ ܡܪܝܡ ܐܠܐ ܥܝܫܐ
7	<i>bhaq hada alsmat</i> ¹⁹ <i>lmu‘admat fir</i> ²⁰	ܒܗܩ ܗܕܐ ܐܠܫܡܬ ܠܡܘܥܕܡܬ ܦܝܪ
8	<i>fir fir fir fir fir fir fir fir</i>	ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ
9	<i>fir fir fir fir fir fir fir fir</i>	ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ
10	<i>fir fir fir fir fir fir fir fir</i>	ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ
11	<i>fir fir fir fir fir fir fir fir</i>	ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ ܦܝܪ
12	<i>33</i> ²¹ <i>gilia</i> ²² <i>iard abla‘ia uia sama</i> ²³	ܩܝܠܝܐ ܝܐܪܕ ܐܒܠܐܝܐ ܘܝܐ ܫܡܐ

- 13 *aglaia*²⁴ *ugaia*²⁵ *lsama*²⁶ *unil*²⁷ וּגַיָּא וְעַלְמָא דְּסַמָּא לְמַדְבָּח חֲרֵל
*unidaka*²⁸ *u'nia* חֲרֵלְכִדְרָב דְּכִרְיָא
- 14 *ma'dina mstagiria*²⁹ *fasauk*³⁰ אֲחֵד עֲלֵי אֲדָמָא דְּכִרְיָא וְדִמְדִּיר
ma'lamun אֲחֵד עֲלֵי אֲחִיר
- 15 *angiṭi*³¹ *ia*³² *aiha ldam* *'an fariš*³³ וְרַעֲלֵי עֵה וְעַסֵּה לְכִדְבָּח עֲרֵר וְדִכְמֵה
- 16 *planita kima angīta' alrahma*³⁴ *mn* וְלִדְרָאֲדָמָא דְּרַעֲלֵי עֵה וְלִכְדִּסְאֲדֵי אֲחִיר
- 17 *galb*³⁵ *aldia*³⁶ *lak l'ašuz*³⁷ *ubintaha*³⁸ עֲלֵיב וְלֵכֵה לִדְרָא לֵי עֲרֵר דְּכִרְיָאֲדָמָא
*kima*³⁹ רַעֲלֵי
- 18 *ngāṭi*⁴⁰ *lrahma*⁴¹ *mn gaum*⁴² *ldalmin* רַעֲלֵי עֵה לְכִדִּסְאֲדֵי אֲחִיר עֲמִנְכָא לְכִדִּלְכִּיר
'ala עֵה־ל
- 19 *gaum*⁴³ *lkafrin uala masaina*⁴⁴ *filail* עֲמִנְכָא לִיְדִרְוִיכִיר דְּלֵדֵה אֲדִמְדִּיר וְעֵלְדֵל
*ulnihar*⁴⁵ דִּלְרֵסֵדֵכ
- 20 *ulahul*⁴⁶ *ulaquat alah bilah l'alía*⁴⁷ דִּלְסִחַל דִּלְכִּדְבָּח וְלֵדֵה בִּלְהַב לֵי עֵה־ל
l'adim לֵי עֵה־לֵי
- 21 *hazin baba kdub uahbalah*⁴⁸ *l'nta*⁴⁹ סִדְרָאֵר בִּדְבָּחָה דְּכִדְבָּח דְּכִדִּסְאֲדֵי לְכִרְיָאֲדָמָא
*dqaima bñnupia*⁵⁰ *uraipailh*⁵¹ בִּדְבָּחָה בִּלְכִירְדִּירְוִי עֵה־לֵי דִּכְמֵה וְרַעֲלֵי
*lhalša rupa dñšuka hu*⁵² *s—a* לְסִלְסִירֵה לְכִדְבָּחָה בִּסְמִיחֵה חֲרֵל סִדְמָה

¹ Corrected according to CS 27; DC 46: *hamat*. ² CS 27: *malkan*. ³ CS 27: *ldam*.
⁴ CS 27: *farsin*. ⁵ CS 27: *ldam*. ⁶ CS 27: *salṭah*. ⁷ CS 27: *fdarub* (the *f-* is not connected the next word, and perhaps *fidarub* is to be read). ⁸ CS 27: *l dam*. ⁹ CS 27: *bldam*. ¹⁰ Corrected according to CS 27; DC 46: *agta'*. ¹¹ CS 27: *siha*. ¹² CS 27: *ldam*. ¹³ CS 27: *bhaqi*. ¹⁴ CS 27: *'sim alah l'dim*. ¹⁵ CS 27: *mukadam*. ¹⁶ CS 27: *aladia*. ¹⁷ CS 27: *nizal*. ¹⁸ CS 27 omits. ¹⁹ CS 27: *lsma*. ²⁰ CS 27: *lma'adm tñir*. ²¹ CS 27 has the magic word *fir* 39 times (including the corrupt *tñir*), followed by:
hania tša utla tin. ²² CS 27: *uqal*. ²³ CS 27: *uia sima*. ²⁴ CS 27: *aqla'ia*. ²⁵ CS 27: *ugai*. ²⁶ CS 27: *usma*. ²⁷ CS 27: *unala*. ²⁸ CS 27: *nidaka*. ²⁹ CS 27: *msta gira*. ³⁰ CS 27: *fisak*. ³¹ CS 27: *ngiṭi'*. ³² CS 27: *ii*. ³³ CS 27: *fariš*. ³⁴ CS 27: *ngit'at lrahma*.
³⁵ CS 27: *qilub qalr*. ³⁶ CS 27: *aladia*. ³⁷ CS 27: *l'auz*. ³⁸ CS 27: *ubintaha*. ³⁹ CS 27: *kim*. ⁴⁰ CS 27: *lugaṭa'*. ⁴¹ CS 27: *lra*. ⁴² CS 27: *rum*. ⁴³ CS 27 omits. ⁴⁴ CS 27: *ualama sina*. ⁴⁵ CS 27: *uln har*. ⁴⁶ CS 27: *ulahul*. ⁴⁷ CS 27 omits *bilah l'alía*. ⁴⁸ Corrected according to CS 27; DC 46 omits. ⁴⁹ Corrected according to CS 27; DC 46: *lrnta*.

⁵⁰ for *dqaima bṭnupia* CS 27 reads synonymous: *ḡhazia hšuka*. ⁵¹ CS 27: *uripa*.

⁵² For *ḡhšuka hu* CS 27 reads *mipsaq hšuka minah*.

In the name of Allah, the Beneficent, the Merciful.	بسم الله الرحمن الرحيم
An angel of blood descended ⁸	هبط ملك من ملك من الدم
on a horse of blood	على فرس من دم
... a jacket/an arrow (?) of blood	... سلطة من دم
He struck the blood with blood.	فضرب الدم بالدم
Be cut off, O blood,	انقطع يا أيها الدم
By the right of Eve and Adam	بحق حواء وآدم
By the right of the name of the Great and Honoured One.	ويحق اسم العظيم المكرم
Who sent down (his inspiration) to Jesus, son of	الذي نزل على عيسى ابن
Miriam	مريم
By the right of these great	بحق هذا (!) الأسماء
names	المعظمة
<i>fir fir fir</i> (33 [times])	فير فير فير... ٣٣
“And it was said: O earth! Swallow thy water and,	{وَقِيلَ يَا أَرْضُ ابْلَعِي مَاءَكَ وَيَا
O sky!	سَّمَاءَ
be cleared of clouds! And the water was made to	أَقْلَعِي وَغِيضَ الْمَاءِ}
subside” ⁹	
... ¹⁰ “a fixed time, and ye	... معدن {مُسْتَقَرٌّ وَسَوْفَ
will come to know.” ¹¹	تَعْلَمُونَ}
Be cut off, O blood,	انقطع يا أيها الدم
from the loins of PN	عن فرج ولد PN
just as mercy was cut off from the heart of	كما انقطع الرحمة من قلب

⁸ See notes.

⁹ Excerpt from Surat al-Hūd 44.

¹⁰ Uninterpretable text.

¹¹ Excerpt from Surat al-ʿAnʿām 63, starting mid-verse.

one who... and old woman and her daughter
and just as mercy was cut off
from the wrongdoing and heretical
folk.

الذي لك (!) العجوز وبناتها
كما انقطع الرحمة
من قوم الظالمين على قوم
الكافرين

“Unto Him belongeth whatsoever resteth
in the night and the day.”¹²

أَوَّلُهُ مَا سَكَنَ
فِي اللَّيْلِ وَالنَّهَارِ

“there is no power and no strength
other than in Allah, the Exulted, the Mighty”.

ولا حول ولا قوة
إلا بالله العلي العظيم

[Mandaic rubric:]

Write this prescription write for a woman who is in impurity and tie upon her
at her loins; it is a tie(-charm) for menstruation.

Notes

1. *hibaṭ* (var: *habaṭ*). From the context, we have interpreted this as a phonetic variant of *habaṭ*. However, it could also be an inner-Mandaic graphic error of *hamaṭ* for *hamal*.

2. *malkin mn amalkin mn aldam*. The parallels suggest that this is dittography.

3. *salṭa mn dam*. The text appears to be lacking at this point. The parallels suggest that the narrative here should contain a description of the king's clothing or weaponry, and accordingly *salṭa* may be taken to represent Arabic سَلْطَة ‘a jacket’,¹³ or سِلْطَة, which *Lisān al-‘Arab* defines as السَّهْمُ الطَّوِيلُ ‘a long arrow’.

7–12. *fir fir*... 33. Numerals are often employed in the magic recipe books when a symbol is to be repeated a specific number of

¹² Surat al-ʿAnʿām 13.

¹³ Proposed to us by Prof. R. Forster.

times in the amulet. We have interpreted *fir* here as a magic word, rather than a form of the root *frr*. If this were an imperative form, the colloquial pronunciation would be *furr*.

12. *gilia iard abla'ia*. On such corruptions in Qur'ān citations, see Morgenstern and Alfia (2013, 172–74).

16–17. *mn galb aldia lak*. The Arabic lying behind this phrase is not entirely clear. *galb* may be interpreted as قلب 'heart' or غالب 'overpower'. *aldia lak* 'who is for you/yours' makes little sense in this context. We would expect a formula that is parallel to the expression *عن ناكح العجوز وبنتها وبنتها وأمها* 'an *nakha al'ašuz ubint aha ua uamha* found above.

1.6. Text 6

This talisman survives in two parallel copies; both contain errors. The text presented here is based primarily on DC 46, with some corrections introduced from DC 45 as noted. The formula differs somewhat in its structure from the previous talismans.

Source: DC 46. 198:10–199:6; DC 45.22a:22–22b:11.

1	<i>bisim alah 'azimt¹ 'alaik² ia aih³</i>	بسم الله اعزمت عليك يا ايها
2	<i>ldam 'l šarad⁴ balah ubaladia</i>	لدام لك شراد باله اوبالاديا
3	<i>akrišak mn fariš⁵ 'l zakar askun⁶</i>	اكريشاك من فاريس لك زكار اسكون
4	<i>kima sakin 'l lail ulnahar⁷ askan</i>	كما ساكين لك ليل النهار اسكان
5	<i>bhaq⁸ rab 'l ladia⁹ 'alaqt bismah</i>	بهاق رب لك لاديا الاق بسم الله
6	<i>'l akuar 'ngiti¹⁰ aia iaha¹¹ ldam¹²</i>	لك اكوار نغيتي ايا اياها لدام
7	<i>mn fariš¹³ planita askun binur alah</i>	من فاريس پلنيتا اسكون بنور الله
8	<i>askun¹⁴ bišalal¹⁵ alah askun baqu-</i> <i>drat¹⁶</i>	اسكون بشالال الله اسكون باقو- درا
9	<i>alah askun¹⁷ bmin¹⁸ falaq¹⁹ lbahar</i>	الله اسكون بمين فالاق لبهار
10	<i>lmusa uatfa 'l nar 'an²⁰ brahim</i>	لموسا اوتفا لك نار ان براهيم

- 11 *lkalil ‘alih*²¹ *‘l salam askun mn*²² لکالیل علیہ السلام اسکن من
 12 *plana*²³ *u‘ngiṭi*²⁴ *iadam balf ulahul* وادرم دکر علیہ السلام یادلون دلسدا
 13 *ulaqubat alah bilah l’alia l’adim* دلدیقات الہ بلہ ل’الیا ل’ادیم
 14 *hazin baba kdub ‘l šidra*²⁵ *dauran* ہدایر ہدیکہ یکتیکہ کل شیدرا ددایر
 *‘l*²⁶ *ḥalša lman* کل دلسرد لکدر
 15 *amṭanpa bhšuka*²⁷ *hauia ruaha* ہاکدر ہوم بھشوکہ ہدایہ کدوس
 *uasuta lhaza hšuka*²⁸ ددوساتہ لہزا ہشوکہ
 16 *s—a* س—ا

¹ CS 27: ‘azamt. ² CS 27: ‘alaif. ³ Corrected according to DC 45, CS 27; DC 46: iaiaiah. ⁴ DC 45: šarar; CS 27: šarari. ⁵ DC 45: faraš; CS 27: faqaš. ⁶ CS 27: zaka raskun. ⁷ DC 45: ulunahar, corrected by erasure dot to ulnahar. ⁸ CS 27: bhaqa, perhaps with final -a erased. ⁹ Corrected according to CS 27; DC 46: ladai; DC 45: laria. ¹⁰ CS 27: ‘nṭiṭi. ¹¹ DC 45: aia aiha; CS 27: aia ia aha. ¹² CS 27: ‘l dam. ¹³ DC 45, CS 27: faraš. ¹⁴ CS 27: skun. ¹⁵ CS 27: baṣalah. ¹⁶ DC 45, CS 27: biqudrat. ¹⁷ CS 27: akun. ¹⁸ CS 27 omits. ¹⁹ DC 45: filaq. ²⁰ DC 45: ‘l nar‘anl; CS 27: ‘l naq‘an. ²¹ DC 45, CS 27: ‘alah. ²² CS 27: m. ²³ DC 45: pllana. ²⁴ DC 45 appears to have a false start of h- before reading u‘ngiṭi. ²⁵ CS 27: šudra. ²⁶ CS 27 omits. ²⁷ DC 45 and CS 27 omit: lman amṭanpa bhšuka. ²⁸ Corrected according to DC 45; CS 27: hšauka; DC 46 omits.

In the name of Allah

بسم الله

I have summoned against you, o expelled blood,

عزمت عليك يا أيها الدم الشريد

By Allah and by the one who removed you

بالله وبالذي اخرجك

from the male loins,

من فرج الذكر

and be still as night and day are still.

واسكن كما سكن الليل والنهار

Be still by the right of the Lord

اسكن بحق رب

in whose name the camel-saddles are tightened

الذي علققت باسمه الأكوار

Be cut off, O blood,

انقطع يا أيها الدم

From the loins of PN,

من فرج دويلدريء

Be still by the light of Allah.

اسكن بنور الله

Be still by the majesty of Allah,

اسكن بجلال الله

Be still by the might of Allah,

اسكن بقدرة الله

Be still by the one who split the sea for Moses,

اسكن بمن فلق البحر لموسى

and extinguished the fire from Abraham the beloved,

وأطفأ النار عن ابراهيم الخليل

Peace be upon him

عليه السلام

Be still from PN,

اسكن من فلانة

And be cut off, O blood, a thousand-fold.

وانقطع يا دم بألف

“And there is no power and no strength

ولا حول ولا قوة

other than in Allah, the Exulted,

إلا بالله العلي

the Mighty”.

العظيم

[Mandaic rubric:]

This prescription, write on a tunic around the loins for one who is impure by menstruation. There will be relief and healing for this menstruation.

Notes

5–6. *ladia* ‘*alaqt bismah l akuar*. The interpretation of this line is very uncertain. For *ladia*, DC 45 reads *لاديه* *laria* and DC 46 *لاديه* *ladai*. Our interpretation of this line follows a suggestion from Prof. R. Forster.

2.0. Some parallels in Arabic script

While we have not found in the Arabic magic books at our disposal texts that provide exact parallels of the Mandaean sources, several of the formulae are closely paralleled by formulae in published books or found over the years on the internet, and it is reasonable to assume that texts such as those we publish here will be identified by other scholars. The following two examples have been identified in books.

2.1. Parallel 1

ḥskh ḥskh ḥskh

Be cut off, O dark blood,
just as mercy was cut off from the elders of
the town quarters
and the heads of the villages¹⁴
(al-Māliki, *Treasure*, 62)¹⁵

حسكه حسكه حسكه
انقطع أيها الدم الدعام
كما انقطعت الرحمة عن
مشايخ الحارات
ورؤساء القرى.

2.2. Parallel 2

You should write on the front of the garment of a person whose blood or tears do not stop and the back of the garment:¹⁶

fqj mḥmt bṭd zhj w'h,

تكتب على مقدم ثوب من لا
يتوقف دمه أو دمعا ومؤخر
الثوب:
ففج مخمت بطد زهج واح

¹⁴ I.e., just as no mercy may be found with them.

¹⁵ An early twentieth-century collection.

¹⁶ The structure of these instructions is opaque, and it is not clear if the same spell is written on both the front and back of the shirt.

Be cut off, O blood from PN (M) or PN (F), just as mercy was cut off from the slaughterer of the cattle and the cutter of trees, by the right of ʾĀhya Šar ʾĀhya ʾĀdūnay ʾAšbāʾut ʾĀl Šadāy. Finished and completed, And Allah is all-knowing. (Al-Rammāl, <i>Bounty</i> , 205.)	انقطع أيتها الدم عن فلان. أو فلانة. كما انقطعت الرحمة عن ذابح البقر وقاطع الشجر بحق آهيا شراهيا أدوناي أصباؤت آل شداي. تم وكمل والله أعلم. (Al-Rammāl, <i>Bounty</i> , 205.)

During the course of our initial research, we also encountered similar texts posted to Arabic chat groups on the internet. Unfortunately, the sites are no longer active. Nonetheless, we present the texts here as they were recorded by us in 2011:

2.3. Parallel 3

In the name of Allah, the Beneficent, the Merciful To cut off blood, Allah be willing. On the authority of the king in heaven whose name is blood and who rode on a horse of blood with a sword of blood in his hand, striking blood with blood. Be cut off, O blood. Allah is the Greatest, Allah is the Greatest, Allah is the Greatest and he struck a dry path for them in the sea. Dry up, O blood,	بسم الله الرحمن الرحيم لقطع الدم باذن الله عن ملك في السماء اسمه الدم وركب على خيل من الدم وفي يده سيف من الدم ويضرب الدم بالدم انقطع ايها الدم الله اكبر الله اكبر الله اكبر وضرب لهم طريقا في البحر يبسا اييس ايها الدم

by the glory of the God of the Throne.

بعزة اله العرش

“And there is no power and no strength other than in Allah, the Exulted, the Mighty”

ولا حول ولا قوة الا بالله
العظيم

2.4. Parallel 4

In the name of Allah, the Beneficent, the Merciful

بسم الله الرحمن الرحيم

May Allah pray for our lord Muḥammad

وصلى الله على سيدنا محمد

and for his family and companions, and may he be well.

وعلى آله وصحبه وسلم

To cut off bleeding immediately

لقطع نزيف الدم في الحال

recite 7 times:

تقول 7 مرا

Send down¹⁷ a king of blood

نزل ملكاً من دم

on a horse of blood

على فرساً من دم

with a sword of blood in his hand,

بيده حربناً من دم

striking blood with blood.

يضرب الدم بالدم

Be cut off, O blood.

أنقطع أيها الدم

and dry up from PN son of PN

وايبس عن فلان بن فلانه

as the sea dried up for our lord Moses,

كما يبس البحر لسيدنا موسى

peace be upon him

عليه السلام

You should breathe into the wound after each time

تنفث في الجرح¹⁸ بعد كل مرة

that you read the incantation until it is completed

تقرأ العزيمه حتى تتم

7 times.

7 مرات.

¹⁷ The case of the following word, ملكاً, indicates that نزل in this text is construed as transitive, and we accordingly interpret it as the II-stem imperative. In the Mandaean transcriptions, the spellings *nazal* (Texts 1:1, 2:2, 2:3,) and *nizal* (Text 4:2) indicate that they read the verbs as I-stem.

¹⁸ *Sic*. We take it to be a typing error for الجرح ‘the wound’.

References

- Drower, Ethel Stefana. 1943. 'A Mandæan Book of Black Magic'. *Journal of the Royal Asiatic Society* 75/3–4: 149–81.
- Al-Maliki, *Treasure* – يونس المالكي، الكنز المدفون والفلك المشحون، البابي الحلبي، ١٩٥٦.
- Al-Rammāl, *Bounty* – عبد الله الرمال، تحفة الطلاسـم الذهبية، بيروت : ناشرون الاصدقاء ٢٠٠٩.
- Frankfurter, David. 1995. 'Narrating Power: The Theory and Practice of the Magical Historiola in Ritual Spells'. In *Ancient Magic and Ritual Power*, edited by Marvin Meyer and Paul Mirecki, 457–76. Leiden: Brill.
- Geller, Markham J. 2000. 'An Akkadian Vademecum in the Babylonian Talmud'. In *From Athens to Jerusalem: Medicine in Hellenized Jewish Lore and in Early Christian Literature*, edited by Samuel Kottek, Manfred Horstmanshoff, Gerhard Baader, and Gary Ferngren, 13–32. Rotterdam: Erasmus.
- Häberl, Charles. 2021. 'A "Mandæo-Arabic" Letter from Lady Drower's Correspondence'. In *A Handbook and Reader of Ottoman Arabic*, edited by Esther-Miriam Wagner, 431–40. Cambridge Semitic Languages and Cultures 9. Cambridge: Faculty of Asian and Middle Eastern Studies and Open Book Publishers.
- Morgenstern, Matthew. 2018. 'Neo-Mandaic in Early Mandæan Colophons. Part 1: Linguistic Features'. *Aramaic Studies* 16/2: 182–20. <https://doi.org/10.1163/17455227-01602002>

- Morgenstern, Matthew, and Ohad Abudraham. Forthcoming. *The Persistence of Magic: The Transmission of Mandaic Magic Formulae in Early and Late Witnesses*.
- Morgenstern, Matthew, and Tom Alfia. 2013. 'Arabic Magic Texts in Mandaic Script: A Forgotten Chapter in Near-Eastern Magic'. In *Durch Dein Wort ward jegliches Ding! / Through Thy Word All Things Were Made! – II. Mandäische und Samaritanistische Tagung*, edited by Rainer Voigt, 163–80. Wiesbaden: Harrassowitz.
- Müller-Kessler, Christa. 1999. 'Dämon + YTB 'L — Ein Krankheitsdämon. Eine Studie zu aramäischen Beschwörungen medizinischen Inhalts'. In *Munuscula Mesopotamica: Festschrift für Johannes Renger*, edited by Barbara Böck, Eva Cancik-Kirschbaum, and Thomas Richter, 341–54. Alter Orient und Altes Testament 267. Münster: Ugarit-Verlag.
- Naveh, Joseph, and Shaul Shaked. 1998. *Amulets and Magic Bowls*. 3rd edition with additions and corrections. Jerusalem: Magnes Press.
- Stol, Marten. 1991. 'Diagnosis and Therapy in Babylonian Medicine'. *Jaarbericht van het Vooraziatisch-egyptisch genootschap "Ex Oriente Lux"* 32: 42–65.

DOTS AND WORD STRESS IN CLASSICAL EAST SYRIAC*

Johan Lundberg

What was the dominant stress pattern in Late Classical Syriac? The treatment of word stress in grammars of Classical Syriac is often very brief and the same is true for Knudsen's (2015) recent monograph on Syriac phonology. There are some good reasons for the brevity of these treatments. For example, while the Syriac scribes devised an elaborate system of dots, they did not create signs specifically designed to mark stressed syllables—in contrast to the Greek accents or the Hebrew cantillation marks. Equally important, the Syriac grammarians, like their Arabic counterparts, did not discuss general stress patterns (Knudsen 2015, 171).

Nöldeke mentions that East Syriac stressed the penultimate syllable, and they did so distinctly. By contrast, he notes that the Maronites stressed either the ultimate or the penultimate syllable. The ultimate syllable was stressed if it was closed, while the penultimate syllable was stressed if the ultimate syllable was open (Nöldeke 2001, §56; cf. Brockelmann 1960, 48; Muraoka 1997, 16). Nöldeke (2001, §56) also mentions that Aramaic

* This article was completed as part of ongoing research, first on the DFG-AHRC-funded InterSaME project, and finished during a Leverhulme Early Career Fellowship.

stressed the final syllable at an earlier time (cf. Muraoka 1997, 16). Duval, referring to Stoddard's grammar, mentions that North-Eastern Neo-Aramaic dialects are characterised by penultimate stress. He thought that the same pattern applied to ancient Syriac, suggesting that the ultimate syllable received stress only in monosyllabic words or when this syllable was closed and had an originally long vowel (e.g., ܐܬܐ *kθav* and ܡܠܟܝܢ *malkin*). Following this line of reasoning, Duval makes a few suggestions: (1) that the prefixes of most prefix conjugation forms were stressed, e.g., ܢܩܬܐ *néqtol* and ܢܝܒܒܐ *nébboz*; (2) that the antepenultimate syllable could be stressed if an epenthetic vowel was added, thereby making the word trisyllabic (e.g., ܕܗܠܐ *déhelθā* < *déhlθā* 'fear'). Similarly, the stress remained on the ultimate syllable when an epenthetic vowel was added to suffix conjugation forms: ܐܬܝܬ *iθév* 'he sat'. Duval (1881, 135–37) also mentions that Greek words retained their accents when they were borrowed into Syriac. Knudsen's (2015, 171) discussion of word stress is centred around two types of evidence: (1) the reduction of the first vowel in originally disyllabic words such as ܕܡܐ (*dmā* < **damā*?) and ܒܪܐ (*brā* < **birā*?); and (2) the dominance of ultimate stress in other Aramaic dialects, especially Jewish dialects. Based on these observations he suggests that ultimate stress was the dominant stress pattern in Late Classical Syriac.

Knudsen mentions some exceptions to this pattern, notably imperatives with pronominal suffixes. He suggests that ܫܡܥܝܢ *šmá'ayn* 'listen to me' was stressed on the penultimate syllable /šma/. This conclusion is based on the presence of the stem

vowel, which should otherwise have been reduced. The same applies to other imperative forms, all taken from BL Add. 12138 (Knudsen 2015, 172–73):

- (1) ܗܐܒܝܢ *háven* ‘give’ (FP) (fol. 240r, ln. 16 = Matt. 25.28)
- (2) ܥܕܕܝܗ *‘véddeh* ‘make it’ (fol. 4r, lns 9, 11, 13 = Gen. 6.14–16)
- (3) ܫܡܥܝܢ *šmá‘ayn* ‘listen to us’ (fol. 10r, ln. 12 = Gen. 23.6)
- (4) ܫܝܝܥܝܗ *sayyéxeh* ‘complete it’ (fol. 4r, ln. 12 = Gen. 6.16)
- (5) ܐܡܩܝܗ *appéqeh* ‘take her away’ (fol. 9v, ln. 7 = Gen 21.10);
ܐܡܩܝܢ *appéqayn* ‘take me out’ (fol. 19r, ln. 21 = Gen. 40.14)
- (6) ܫܕܕܝܢ *šaddárayn* ‘send me’ (fol. 14r, ln. 1 = Gen. 30.25);
ܫܕܕܝܢ *‘send me’* (fol. 15v, ln. 10 = Gen. 30.25); ܫܕܕܝܢ *‘send us’* (fol. 243r, ln. 12 = Mark 5.12)

In short, the stem vowels in these forms were preserved because they occurred in stressed syllables.

Knudsen’s discussion of stress patterns ends at this point but if we take a closer look at these verbal forms in Add. 12138, we should note the large dots above the consonant that precedes the stressed vowel. These dots were made with either black or red ink. *Bābai*, who compiled Add. 12138, mentions that black dots go back to the readings of the *maqryāne*—teachers who taught students how to read the Bible—while red dots indicate an alternative reading belonging to Rabban *Rāmišo*‘ (Loopstra 2014, II:VIII–X). The Syriac grammarians called these dots *pāqodā* ‘imperative.’ This name was originally used to describe dots above imperatives and volitive prefix conjugation forms. Segal writes that this dot is placed above the first letter of the word, unless that letter is vowelless, in which case it is placed above the second letter (Segal 1953, 87).

2.0. The Position of Dots and Word Stress

Some of the early grammatical treatises contain comments about a dot called ܡܩܠܫܢܐ *mqalsānā* or ܓܐܪܪܐ *gārora*. Jacob of Edessa (Phillips 1869, 22–23) writes that this dot is called ܡܦܪܟܬܐܢܐ *paraxetānā* in Greek. The Greek word παροξύτονος is used for words with an acute accent on the penultimate syllable, the word itself being derived from the term for the ultimate syllable ὀξύτονος (Montanari et al. 2015). Two other treatises, one anonymous and one ascribed to Thomas the Deacon, mention that some grammarians thought that the term ܓܐܪܪܐ *gārora* should be reserved for the dot above the /h/ in the name ܝܗܘܕܐ *ihūdā* ‘Judas, Judah’, i.e., the dot above the consonant that precedes the nucleus of the penultimate syllable.¹ These writers connect it with the Greek term for the acute accent (ὀξύς), and suggest that *gārora* has three positions: above the ultimate, the penultimate, or the antepenultimate syllable (Phillips 1869, 83–84). It is not surprising, then, that the large dots above imperatives are placed above the consonant that precedes the nucleus of a stressed syllable.

3.0. Loanwords

In Vat sir. 273 large dots are used above some Greek loanwords and proper nouns. For example, in Matthew 22 the word ܩܝܫܐ *qésār* ‘Caesar’ is used four times and three of these have a large dot above the first letter (Matt. 22.17, 21). This dot is significant

¹ This suggests that the Syriac proper noun ܝܗܘܕܐ *ihūdā* ‘Judas, Judah’ was borrowed from Hebrew via Greek into Syriac, since it agrees with the Greek stress pattern (Ἰούδας).

because the Greek word is accented on the penultimate syllable (χαῖσαρ). Similarly, the loan words ܐܢܢܩܐ *anānqe* ‘necessity’ (Matt. 18.7) and ܠܐܦܪܬܘܪܐܢ *la-pratōren* ‘pretorium’ (Matt. 27.27) have a large dot above the same syllable as the respective Greek words ἀνάγκη and πραιτώριον. Another relevant word is ܐܫܐܢܐ *oša‘nā* ‘hosanna’ (Matt. 21.9), which has a large dot above the /n/ corresponding to the Greek accent which is placed above the last syllable (ὠσαννά). There are also several additional proper nouns that have a dot above the syllable which corresponds to the accented syllable in their Greek counterparts (see Table 1, facing page). While discussing the stress patterns of Greek loanwords in Syriac, Butts (2016, 94–95) mentions two possible traces of Greek accents: the occasional use of Syriac /y/ to represent ε, and the occasional apocopation of unaccented word-final α. Both might indicate that Greek loanwords retained the stress pattern of their Greek counterparts. The correspondence between Syriac dots and Greek accents suggests that at least some loanwords retained the Greek stress pattern. For purposes of this article, the correspondence between dots and accents adds weight to the argument that some dots were placed above the consonant which preceded the nucleus of the stressed syllable.

Table 1

Syriac	Transliteration	Greek	Proper noun	References (Matt.)
ܠܗܪܕܝܐ	<i>heródes</i>	Ἡρώδης	Herod	2.1, 2.7; 14.6 ²
ܦܝܠܝܦܡܫܐ	<i>pīlīppos</i>	Φίλιππος	Philip	10.3 ³
ܐܪܚܠܐܝܘܣ	<i>arkéle'os</i>	Ἀρχέλαος	Archelaus	2.22
ܐܢܕܪܝܐܘܣ	<i>andré'os</i>	Ἀνδρέας	Andrew	4.18; 10.2 ⁴
ܦܝܠܐܬܐܘܣ	<i>pilāṭos</i>	Πιλάτος	Pilate	27.24, 58, 58, 62

4.0. Word Stress and Word Classes

The following sections take a closer look at large dots like the ones used above imperatives. Most of the data comes from the seventh-century East Syriac manuscript Vat. sir. 273, specifically the gospel of Matthew. I have also consulted the eastern Masoretic manuscript BL Add. 12138, which Knudsen used extensively. The distribution of these dots suggest that some word classes were stressed on the first syllable while other word classes were stressed on the penultimate syllable.

² This name is the most common of those in the table. The three references in the table have a dot above the second letter, or the following vowel letter (ܐ). Some of the other attestations have a dot above the first letter (Matt. 2.3, 16, 22; 14.3; 22.12). The placement of these dots may indicate an alternative stress pattern, although there is limited space above the letter ܐ.

³ There is a dot above the first letter of this name in Add. 12138, but no dot in Vat. sir. 273. The latter has a dot above the first letter of the name in Luke 6.14.

⁴ The large dot is placed between the /d/ and the /r/ in both examples.

- The word *áyká* ‘where’ is used in two different contexts. In (16) it is used as an interrogative word, and it has a large dot above the first letter: 𐌵𐌶 𐌳𐌵𐌳𐌵. In (17) it is used as the head of a relative clause. Consequently, *ayká* is written without the large dot.

The word *aykannā* ‘how’ is used as an interrogative and—together with the clitic *d*—it is used to introduce manner or purpose clauses (*aykannā d*- ‘just as, so that’). In (21) it is used as an interrogative, and it has a large dot above the first letter of the word: ܐܝܟܢܢܐ *áykannā*. Dots are not used in non-interrogative constructions. Similarly, the shorter interrogative ܐܝܟܢ *áykan* in (22) has a large dot above the first letter.

- (21) ܐܝܟܢܢܐ ܒܥܝܢܝܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ
 ‘**How** are you who are evil able to say good things?’ (Matt. 12.34)
- (22) ܐܝܟܢ ܠܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ
 ‘**How** do you not understand that I did not speak to you about bread?’ (Matt. 16.11)

The interrogative word *kmā* ‘how much’ also has two functions. When used in variable questions, a single dot is placed above the second letter ܡܡܐ *kmā*, as in (23) (cf. Matt. 6.23; 7.11). In (24) this word is used in a polar question, but it does not have an interrogative function, and there is consequently no dot above the second letter.

- (23) ܡܡܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ
 ‘**How many** loaves do you have?’ (Matt. 15.34)
- (24) ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ ܕܝܬܝܢܐ
 ‘Can the wedding guests fast **as long as** the bridegroom is with them?’ (Matt. 9.15)

The word *emmaθ* can be used as an interrogative or as a temporal conjunction (together with *d*-). It is used as an interrogative in (25), and a large dot is placed above the first letter: ܐܡܡܐܐ *emmaθ*. In (26) this word is combined with ‘*dammā* ‘until’, and a large

dot is placed above the third letter of ‘*dammā*’: ܕܡܡܐ ܠܡܡܐθ. Duval (1881, 136) mentions ‘*dammā*’ as one of the words which retained stress on the ultimate syllable, something which is visible through the geminated /m/. In Vat sir. 273 and Add. 12138 this stressed syllable is marked with a large dot.

(25) ܕܡܡܐ ܠܡܡܐθ ܕܡܡܐ ܠܡܡܐθ ܕܡܡܐ ܠܡܡܐθ

‘And **when** did we see you a stranger and welcome you?’

(Matt. 25.38)

(26) ܕܡܡܐ ܠܡܡܐθ ܕܡܡܐ ܠܡܡܐθ ܕܡܡܐ ܠܡܡܐθ

‘**How much longer** will I be with you?’ (Matt. 17.17)

What do these patterns tell us? We can begin with the following observations: (1) large dots are placed above these words when they are used as interrogatives in variable questions; (2) these large dots are typically placed above the consonant that precedes the nucleus of the first syllable. If the interrogative word is a compound of a preposition and an interrogative word, like ‘*dammā*’, the dot is placed above the consonant that precedes the nucleus of the first syllable of the interrogative—in the case of ‘*dammā*’, the /m/ of *mā*.

If we assume that these dots indicate rising pitch, then it is also reasonable to assume that they are placed above the stressed syllable. This suggests that East Syriac interrogatives were typically stressed on the first syllable. Most of these words are disyllabic, so the dot indicates that most interrogative words were stressed on the penultimate syllable. The dot above trisyllabic interrogatives, like *áymekkā* and *áykannā*, indicates that they were stressed on the antepenultimate. These patterns also correspond to

the stress patterns of interrogative words in the Neo-Aramaic dialect of Christian Urmi (Khan 2016, I:246–47).

4.2. Demonstratives

Demonstratives, like interrogative words, often have a large dot above the first letter: ܐܠܗܐ *hăw* and ܐܠܗܐ *hăy* ‘that’, ܐܠܗܐ *hănon* and ܐܠܗܐ *hănen* ‘those’, ܐܠܗܐ *hănā* and ܐܠܗܐ *hăde* ‘this’, ܐܠܗܐ *hălen* ‘these’. The large dots are typically placed above a focused demonstrative. In (27) two dots signal that the demonstrative is a focused constituent: the dot above the first letter marks rising pitch on the stressed syllable, and the dot below the last letter marks a falling pitch contour at the end of a prosodic phrase, indicating that the demonstrative is fronted.

- (27) ܐܠܗܐ ܐܠܗܐ ܐܠܗܐ ܐܠܗܐ ܐܠܗܐ
 ‘...**this** one, will be called the greatest in the kingdom of
 heaven.’ (Matt. 5.19)

The position of the large dots above the first letter of these demonstratives indicates that they were stressed on the first syllable, like interrogative words. The same pattern applies to ܐܠܗܐ *hūyu* ‘He is, this is’ (Matt. 11.14; 12.50; 15.18; 26.48).

4.3. *Hăyden*, *hăxannā*, and *meddem*

The words ܐܠܗܐ *hăyden* ‘then’, ܐܠܗܐ *hăxannā* ‘thus’, and ܐܠܗܐ *mēddem* ‘something’ exhibit similar dotting patterns—each has a dot above the first consonant, indicating that they were stressed on the first syllable.

4.4. Adverbial particles

Large dots are placed above the adverbs ܠܠܝܠܡ *l-ʿālam* ‘forever’ (Matt. 6.13; 21.19), ܗܝܫܐ *hāšā* ‘now’ (Matt. 9.18; 26.64, 65), and ܝܘܡܢܐ *yawmānā* ‘today’ (Matt. 6.30; 16.3). Since the large dots are placed above the consonant which precedes the nucleus of the penultimate syllable, these adverbs were stressed on the penultimate syllable. This pattern corresponds to the stress pattern of adverbial particles in the Neo-Aramaic dialects of Christian Barwar and Christian Urmi, although some particles are stressed on the antepenultimate syllable in the modern dialects (Khan 2008, I:131–32; 2016, I:231).

4.5. Verbal forms

The discussion of large dots began with imperatives. Now we return to verbal forms to consider what they tell us about East Syriac stress patterns.

4.5.1. Imperatives

The Syriac grammarians called the large dots above imperatives and volitive prefix conjugation forms *pāqodā* ‘command’ or ‘imperative’. Interestingly, and perhaps somewhat surprisingly, dots are only rarely placed above imperatives. They are primarily used with weak verbs: four out of the nine attestations in the corpus have only two consonants (see Table 2, facing page).

Table 2

Verb	Reference (Matt.)	Verb	Reference (Matt.)
ܐܠܝ <i>zél</i> 'go' (PL)	28.19	ܐܬܗ <i>háv</i> 'give'	18.28; 20.8
ܐܝܠܝܢ <i>zélen</i> 'go (FP)'	28.7, 10	ܐܬܬܝܢ <i>háven</i> 'give (PL)'	25.8
ܐܡܡܐܪܝܢ <i>emmáren</i> 'say (FP)'	28.7	ܐܬܬܝܢ <i>d-θév</i> 'sit'	22.44; 26.36
ܬܐܬ <i>tá</i> 'come'	9.18	ܬܐܬ <i>tár</i> 'keep'	19.17
ܬܐܬܝܢ <i>táyen</i> 'come'	28.6	ܬܐܬܝܢ <i>addárayn</i> 'help me'	15.25
ܐܘܒܝܢܝܢ <i>wa-zbénen</i> 'give (FP)'	25.9	ܡܫܥܩܐ <i>psóqe</i> 'cut'	18.8
ܐܝܕܐܠܝܢ <i>ezdáhhar</i> 'take care'	16.6		

Moreover, the large dots which are placed above these imperatives are only sporadically used with weak verbs. For example, the 2MP form ܐܝܕܐܠܝܢ *ezdáhhar* is attested six times in the gospel of Matthew, but only one has a large dot. Similarly, the 2MS form ܬܐܬ *tá* is used seven times, but only one of these has a large dot above the first letter. For a dot which is called 'command' or 'imperative', the usage seems rather inconsistent. This inconsistency, however, is understandable if we assume that the large dot primarily indicates rising pitch, not the imperative mood of the verb. In several cases there appears to be an urgency to these commands. In Matt. 9.18 Jairus tells Jesus: 'My daughter has just died but COME (ܬܐܬ *tá*) and put your hand on her and she will live.' In Matt. 15.25 the Canaanite woman says: 'Lord, HELP ME! (ܬܐܬܝܢ *addárayn*)', because her daughter is demon possessed. Similarly, the servant in Matt. 18.28 is furiously choking the other servant when he says: 'GIVE (ܐܬܗ *háv*) me what you owe me.' Contextually, it makes sense that these verbs are read with higher pitch.

In monosyllabic imperatives the dots are placed above the consonant that precedes the nucleus of the only syllable. In disyllabic and trisyllabic forms, the dot is placed above the consonant that precedes the nucleus of the penultimate syllable. If these dots

transparent examples include: ܢܒܒܐܝܢ *nébboz* or *nebbóz* (Matt. 12.29 [2x]), ܐܬܐ *eθé* (Matt. 8.19), and ܢܬܩܠ *neštqél* (Matt. 25.29). The last two have a large dot above the ultimate syllable. This may indicate that non-volitive forms had ultimate stress.

What do these patterns tell us about Classical East Syriac words stress? At the very least, they indicate that volitive prefix conjugation forms were stressed on the initial syllable, irrespective of how many syllables the verb contained. Did the stress pattern of these volitive forms differ from that of other prefix conjugation forms? This is certainly possible, but it is difficult to prove, since so few forms have dots above a letter other than the first.

4.5.3. Suffix Conjugation Forms

The examples in this category are primarily 3FS, 2MP, and 1SG forms, verbal forms with more than one syllable. In (29) a large dot is placed above the negation *lā*, rather than one of the syllables of the verb. This combination of dots, especially the dot above the negation, is used because this is a biased polar question with reverse polarity. These questions have a very similar dotting pattern as variable questions, placing a dot above one of the first constituents in the clause—much like the dot above interrogative words.

(29) ܡܬܪܐܕܐ ܠܐ ܐܠܐ

‘Have you not read...?’ (Matt. 12.3; cf. 12.5; 19.4)

In many Neo-Aramaic dialects, the negator is part of the same stress group as the verb and the default position of the stress is on the negator (Khan 2016, I:235–36) The large dot above the

negator is probably an indication that the same was true in Classical East Syriac: *lāʿ-qrayton*. Other instances of a large dot include:

Table 3

Verb	Reference (Matt.)	Verb	Reference (Matt.)
3MS forms			
ܐܡܡܪ ܐܠܐ <i>w-émmar</i>	27.54	ܐܠܐ <i>w-ʿāl</i>	26.58
ܐܠܐ ܠܐ <i>lāʿ eθiled</i>	26.24		
3FS forms			
ܐܡܪܐ <i>émraθ</i>	15.25; 15.27	ܐܡܪܐ <i>qérbaθ</i>	10.7; 12.28; 20.20; 26.7, 29
ܐܡܪܐ <i>d-ármyaθ</i>	26.12	ܐܡܪܐ <i>ráqdaθ</i>	14.6
ܐܡܪܐ <i>hēškaθ</i>	14.23	ܐܡܪܐ <i>šélhaθ</i>	27.19
ܐܡܪܐ <i>yévnšaθ</i>	21.19	ܐܡܪܐ <i>šélyaθ</i>	14.32
ܐܡܪܐ <i>w-kéraθ</i>	14.9; 17.23; 18.31; 26.22	ܐܡܪܐ <i>šépraθ</i>	14.6
ܐܡܪܐ <i>miθáθ</i>	22.27	ܐܡܪܐ <i>téršaθ</i>	8.32
ܐܡܪܐ <i>népqaθ</i>	15.22	ܐܡܪܐ <i>eθásyaθ</i>	9.22; 15.28
ܐܡܪܐ <i>néθqaθ</i>	8.34	ܐܡܪܐ <i>etdámyaθ</i>	22.2
ܐܡܪܐ <i>séydaθ</i>	15.25; 20.20	ܐܡܪܐ <i>ettzfyáθ</i>	27.51
ܐܡܪܐ <i>sémqaθ</i>	16.2	ܐܡܪܐ <i>eštámʿaθ</i>	28.14
ܐܡܪܐ <i>qámaθ</i>	8.15		
1SG forms			
ܐܡܪܐ <i>w-ézzēθ</i>	25.25	ܐܡܪܐ <i>nétreθ</i>	19.22
ܐܡܪܐ <i>w-dēhleθ</i>	25.25	ܐܡܪܐ <i>népqeθ</i>	12.44
ܐܡܪܐ <i>hēššēθ</i>	27.19	ܐܡܪܐ <i>šévqeθ</i>	18.32
ܐܡܪܐ <i>képneθ</i>	25.35, 42		
2MP forms			
ܐܡܪܐ <i>w-eθáyton</i>	25.36	ܐܡܪܐ <i>w-yávton</i>	25.35
ܐܡܪܐ <i>baθélton</i>	15.6	ܐܡܪܐ <i>ʾestakálton</i>	16.9
ܐܡܪܐ <i>d-hayménton</i>	9.29	ܐܡܪܐ <i>da-ʿvádton</i>	25.40
ܐܡܪܐ <i>da-hzáyton</i>	24.33	ܐܡܪܐ <i>šqálton</i>	6.9

Almost all these verbal forms are either monosyllabic or stressed on the penultimate syllable. The only exceptions are ܐܡܪܐ *hēššēθ*

(Matt. 27.19) and ܡܝܬܐܐ *miθáθ* (Matt. 22.27). These patterns probably indicate that suffix conjugation forms with more than one syllable were stressed on the penultimate syllable.

4.5.4. Infinitives

There is only one infinitive with a large dot in the corpus: ܠܡܗܙܐ *l-mehzé* (Matt. 11.7). Since this dot is placed above the consonant which precedes the nucleus of the ultimate syllable, it may indicate that infinitives—like many nouns—were stressed on the ultimate syllable.

4.6. Nouns and Adjectives

Large dots are also placed above nouns. Some of these are placed above the consonant which precedes the nucleus of the first syllable. For example, there is a list of vices in Matt. 15.19: ܡܪܕܐ *gáwrá* ‘adultery’, ܩܬܠܐ *qéṭlā* ‘killing’, ܙܢܝܘܬܐ *zányuθā* ‘fornication’, ܕܢܝܒܐ *gánnāvuθā* ‘theft’, ܫܗܕܘܬ *sáhduθ šuqrā* ‘false witness’, ܕܘܕܦܐ *gúdāpā* ‘blasphemy’. There are also two instances where a large dot is placed above the first consonant of nouns with a monosyllabic stem: ܐܘܢ *áv-un* (Matt. 6.9), ܐܝܢ *áy-n-āx* (Matt. 20.15).⁸ In contrast to these nouns, there are several instances where a large dot is placed above the consonant which precedes the nucleus of the last syllable: ܒܝܡܐ *b-yammā* (Matt. 4.18), ܒܢܝܢܐ *bnaynāšā* (Matt. 21.25), ܚܒܐ *ḥarbā* (Matt. 10.34),

⁸ There are at least two cases where a pronominal suffix is stressed: ܠܒܝܬܐ *la-vnay bayt-éh* ‘sons of his house’ (Matt. 10.25), ܒܐܕܡܐ *ba-qriθ-éh* ‘in his field’ (Matt. 13.31).

ܠܟܗܢܐ *l-kāhné* (Matt. 12.4), ܒܪܗܕܢܐܐ *br-eh d-nāšā* (Matt. 16.13), ܡܠܟܐܐ *wa-xθāwā* (Matt. 22.20), ܕܗܝܝܐ *d-ḥayyē* (Matt. 22.32), ܒܠܗܐ *b-ʿelθā* (Matt. 23.13), ܡܫܝܚܐ *pešḥā* (Matt. 26.17). The placement of these large dots may indicate that there was no uniform stress pattern among nouns, but it is also possible that most nouns were stressed on the ultimate syllable in normal speech. The nouns with a dot above the first syllable are part of the same list, and they are also followed by the pausal dot *pāsoqā*, indicating that each item is followed by an intonation group boundary.

Large dots are rarely placed above adjectives. Dots are sometimes placed above ܬܘܒܐ *ṭuvā* ‘blessed’, something which was also mentioned by the early West Syriac grammarians (Phillips 1869, 81): ܬܘܒܐܝܚܐ *ṭuv-ayx* ‘you are blessed’ (Matt. 16.17), ܬܘܒܐܐܘܐ *ṭuv-aw* ‘He is blessed’ (Matt. 24.46).

5.0. Conclusion

Was ultimate or penultimate stress the dominant stress pattern in Classical East Syriac? The large dots used in manuscripts like Vat. sir. 273 and BL Add. 12138 suggest that there may have been several different stress patterns. For example, interrogative words, demonstratives, and interjections were probably stressed on the first syllable, irrespective of the number of syllables in the word—much like these word classes in many North-Eastern Neo-Aramaic dialects. Finite verbs and adverbs were probably stressed on the same syllable as these word classes in modern dialects, i.e., on the penultimate syllable. It is possible that nouns and infinitives were stressed on the ultimate syllable—like nouns

in other Aramaic dialects contemporary with Syriac—but the evidence is inconclusive. Therefore, even if we assume that nouns were stressed on the ultimate syllable, it is difficult to argue that ultimate stress was the dominant pattern in Classical East Syriac. The picture is both more varied and more complex.

References

- Brockelmann, Carl. 1960. *Syrische Grammatik*. Leipzig: Verlag Enzyklopädie.
- Butts, Aaron Michael. 2016. *Language Change in the Wake of Empire: Syriac in Its Greco-Roman Context*. Linguistic Studies in Ancient West Semitic 11. Winona Lake, IN: Eisenbrauns.
- Duval, Rubens. 1881. *Traité de Grammaire Syriaque*. Paris: F. Vieweg.
- Jacob. 1869. *A Letter by Mār Jacob, Bishop of Edessa, on Syriac Orthography: Also a Tract by the Same Author, and a Discourse by Gregory Bar Hebræus on Syriac Accents*. Edited by George Phillips. London: Williams and Norgate.
- Khan, Geoffrey. 2008. *The Neo-Aramaic Dialect of Barwar*. 3 vols. Leiden and Boston: Brill.
- . 2016. *The Neo-Aramaic Dialect of the Assyrian Christians of Urmi*. 4 vols. Leiden and Boston: Brill.
- Knudsen, Ebbe Egede. 2015. *Classical Syriac Phonology*. Perspectives on Linguistics and Ancient Languages 7. Piscataway, NJ: Gorgias Press.
- Loopstra, Jonathan, ed. 2014. *An East Syrian Manuscript of the Syriac ‘Masora’ Dated to 899 CE: Introduction List of Sample*

- Texts, and Indices to Marginal Notes in British Library, Additional MS 12138*. Vol. 2. 2 vols. Piscataway, NJ: Gorgias Press.
- Montanari, Franco, Madeleine Goh, Chad Matthew Schroeder, Gregory Nagy, Leonard Muellner, and Rachel Barritt-Costa (eds). 2015. *The Brill Dictionary of Ancient Greek*. Leiden: Brill.
- Muraoka, Takamitsu. 1997. *Classical Syriac: A Basic Grammar with a Chrestomathy*. Wiesbaden: Harrassowitz.
- Nöldeke, Theodor. 2001. *Compendious Syriac Grammar*. Translated by James A. Crichton. Winona Lake, IN: Eisenbrauns.
- Phillips, George. (ed.) 1869. *A Letter by Mār Jacob, Bishop of Edessa, on Syriac Orthography: Also a Tract by the Same Author, and a Discourse by Gregory Bar Hebræus on Syriac Accents*. London: Williams and Norgate.
- Segal, J. B. 1953. *The Diacritical Point and the Accents in Syriac*. London Oriental Series 2. London: OUP.

THE LATE WESTERN ARAMAIC SUFFIXING OF PRONOMINAL DIRECT OBJECTS VIA *-t-* < /yāt/

Ivri J. Bunis

In non-targumic Jewish Palestinian Aramaic (JPA) and in Samaritan Aramaic (SA), verbs in the *qṭal* (= suffix) and imperative conjugations and in the infinitive, whose bases end in a long vowel, attach pronominal direct objects almost exclusively by means of *-t-*.¹ This innovative element is commonly explained as reflecting the phonological reduction of the accusative preposition /yāt/. The present article aims to explain the causes for the development of the element *-t-* and its distribution within the verbal system. For this purpose, the comparative method will be employed. The historical morphosyntax of pronominal direct object expression in Jewish texts, such as the Palestinian Talmud and homiletic Midrashim, and Samaritan texts, such as *Tibat Marqe* and the Samaritan Targum, shall be elucidated within the wider framework of Western Aramaic in its Middle and Late periods, and earlier stages of Aramaic.

¹ Throughout this article, italicised representation of linguistic forms indicates orthography. The infix *-t-* thus represents the letter *tav* or its equivalents, written within an orthographic word.

The Aramaic language is commonly divided into three dialectal branches, namely, Western, Central, and Eastern Aramaic (Butts 2019, 224–25). I adopt this general division, according to which the dialects employed in Palestine by Jews, Christians, and Samaritans belong to Western Aramaic. I also adopt Fitzmyer's periodisation of Aramaic (1979, 57–84), according to which the Aramaic of the non-targumic JPA and SA belong to Late Aramaic.

1.0. Phonologically Reduced /yāt/ + Pronominal Object Suffixes in Jewish Palestinian Aramaic and Samaritan Aramaic

A typical innovation of non-targumic JPA and of SA are verbs which attach their direct object pronoun by means of *-t-*, written together as a single word (1). Nöldeke (1893, 104) suggested that such forms reflect the phonological reduction and coalescence of /yāt/ + pronominal suffix and the preceding verb form (see also Stadel 2011, 239–40), a view which has been widely accepted. Thus, the forms in (1) and (2) derive, respectively, from /*'ak'sū yātēh/ and /*nsā yātēh/.

- (1) 'k'sw-th

anger.PRF.3MPL-3MSG

'they angered him' (Samaritan Targum to Deut. 32.16)

- (2) *ns-tyh* *w-msr-yh* *l-nmrwd*
 take.PRF.3MSG-3MSG and-hand.over.PRF.3MSG-3MSG to-PN
 ‘he took him and handed him over to PN’ (Genesis Rabbah, 363)²

I stress the orthography of these forms, rather than their morphological status, because it is uncertain whether such single orthographic words reflect fully fledged verbal inflection or orthographic representation of a cliticised, phonologically reduced, yet syntactically independent /yāt/ + pronominal suffix. An exact morphosyntactic interpretation is unnecessary, however, for my present argument. Schulthess (1924, 78–80), followed by Müller-Kessler (1991, 261–62), report the same phenomenon in Christian Palestinian Aramaic (CPA), a Late Western Aramaic (LWA) used by the Christian community. In the published renditions of the manuscripts, however, the examples provided by Schulthess are written as two separate orthographic words, namely, the verb followed by /yāt/ + pronominal suffix.

1.1. Pronominal Direct Object Expression in Non-Targumic Jewish Palestinian Aramaic and Samaritan Aramaic in Wider Perspective

Non-targumic JPA and SA generally prefer to express pronominal direct objects with forms which at the orthographic level occur

² Throughout the present article, the text of Genesis Rabbah is cited according to the *Ma’agarim* database of the Academy of the Hebrew Language, <http://maagarim.hebrew-academy.org.il/>. Pagination is according to Albeck and Theodor (1912–1929).

as single words, rather than periphrastically, by means of a separately written word consisting of the accusative preposition /yāt/ + pronominal suffix. Among such single orthographic words, while the forms with ‘bridging -t-’ may not necessarily reflect fully fledged inflection, other orthographic forms do. In non-targumic JPA, such forms occur in various conjugations, such as *qṭal* (3) and the *yiqṭol* (prefix) conjugation (4).

- (3) *w-ḥṭpwn-yh* *mn* *yd-yy*
 and-snatch.PRF.3MPL-3MSG from hands-1SG
 ‘and they snatched him from my hands’ (y. Berakot 2.3 [5a],
 Cairo Genizah fragment T-S F 17.6)
- (4) *d-yḥzwr* *w-ysbyn-h*
 COMP-return.SUBJV.3MSG and-take.SUBJV.3MSG-3MSG
 ‘[...] that he would return and take it’ (y. Bava Batra 10.7
 [17d])³

Verbal inflection in non-targumic SA is also quite frequent (Macuch 1982, 224–36), although perhaps less so than in non-targumic JPA. A quick examination of Tibat Marqe is sufficient to observe that verbal inflection (5) is no less common than the periphrastic construction (6) for the expression of pronominal direct objects.

³ Throughout this article, unless stated otherwise, citations from the Palestinian Talmud are taken from Codex Leiden as found on the *Ma’agarim* database of the Academy of the Hebrew language, <http://maagarim.hebrew-academy.org.il/>.

- (5) *ʿlyn mly-h d-qrt-yn qdmy-k*
these word.FPL-DEF REL-read.PRF.1SG-3FPL before-2MSG
‘these words which I have read before you’ (Tibat Marque, Book One, Tal 2019, 54)
- (6) *kmh d-ʿbdt yt-wn qdmy-k*
as comp-do.PRF.1SG do-3MPL before-2MSG
‘as I have done them before you’ (Tibat Marque Book One, Tal 2019, 60)

1.2. The Distribution of *-t-* + Pronominal Suffix *vis-à-vis* Other Pronominal Object Attachment Patterns

Bridging *-t-* has a specific distribution in non-targumic JPA and in non-targumic as well as targumic SA, namely, it is almost entirely restricted to the *qṭal*, imperative, and infinitive—specifically, to forms whose bases end in a historical long vowel (Florentin 1991), as examples (1) and (2) illustrate. *Qṭal* verb forms with historically long-vowel-final bases can suffix pronominal direct objects by means other than bridging *-t-*, as seen in *ḥṭpwn-yh* in (3). Yet such forms are less common, especially in SA. Conversely, bridging *-t-* is absent from *qṭal* forms with synchronically consonant-final bases (historically ending with short vowels), such as *msr-yh* in (2), which likely reflects /masrē(h)/. This distribution is paralleled by CPA, where vowel-final *qṭal* forms express pronominal direct objects periphrastically only with /yāt/ + pronominal suffix and not by means of verbal inflection (vowel-final imperative forms with a pronominal direct object are fortuitously unattested in CPA), whereas consonant-final *qṭal* and imperative forms *can* take pronominal object suffixes (Müller-Kessler 1991, 259–62).

The parallelism between the CPA periphrastic construction with /yāt/ and JPA and SA single orthographic words with pronominal object suffixes attached via *-t-* confirms Nöldeke's suggestion that *-t-* developed from /yāt/ through phonological reduction. The phonological reduction of /yāt/ reflected in the orthography *-t-* must have been a development in spoken LWA or its precursors and not in the literary language. Speakers of the precursors to LWA appear to have frequently employed the periphrastic construction with /yāt/ with vowel-final *qṭal*, imperative, and infinitive forms. With such verb forms, the habitual use in speech of the periphrastic construction with /yāt-/ eventually resulted in its phonological reduction and realisation together with the preceding verb form, likely as a single prosodic word.

In contrast with the *qṭal* conjugation, *yiqṭol* forms completely lack object suffixes attached by means of *-t-*. Rather, throughout the *yiqṭol* conjugation in non-targumic JPA (4) and SA (7), as well as in CPA (Müller-Kessler 1991, 260–62), one finds that pronominal suffixes are attached by means of so-called energetic *nun*. In JPA and SA, pronominal object suffixes via *-n-* have even been analogically expanded to the infinitive of the *pə'al* stem (8). The comparative examination below shows the attachment of direct object pronominal suffixes to *yiqṭol* with *-n-* and to consonant-final *qṭal* directly to be a retention of earlier Aramaic morphology, unlike the innovative bridging with *-t-*.

(7) *w-ypsl-nk*

and-disqualify.SUBJV.3MSG-2MSG

‘and disqualify you’ (JPA) (y. Yevamot 4.13 [6c])

(8) *b-y mpth-nwn*

in-1SG open.INF-3MPL

‘I am able to open them’ (SA) (Tibat Marque, Book One, Tal 2019, 45)

2.0. Pronominal Direct Object Expression in Earlier Western Aramaic

The morphosyntax of pronominal direct object expression in non-targumic JPA and in SA is elucidated by a comparison with earlier Aramaic dialects, especially from the Western Aramaic region. First, in Western Aramaic dialects that predate non-targumic JPA and SA, a general preference for expressing pronominal direct objects periphrastically by means of /yāt/ is attested. This overlaps with the use of /yāt/, or its reduced form *-t-* with vowel-final *q̄tal*, imperative, and infinitive forms, in SA, non-targumic JPA, and CPA. In the Aramaic of the Targum fragments from the Cairo Geniza, an apparently earlier LWA dialect, pronominal direct objects are in fact never expressed as verbal suffixes, but only periphrastically via /yāt/ (9). The use of periphrasis in example (9) contrasts with the construction in the BH *Vorlage* וַיִּשְׁלַח, where the pronominal direct object is inflectional (Fassberg 1990, 252).

(9) *v-yiṣʿol* *yat-ak*

and-ask.PRF.3MSG DO-2MSG

‘and [he] asks you’ (Targum fragment C, to Gen. 32.18; see Fassberg 1990, 15)

Second, unlike the Targum fragments from the Cairo Geniza, in other dialects from the region, the preference for periphrasis is not absolute. Crucially, the uncommon verb forms that do exhibit pronominal object inflection in those dialects are also found in later non-targumic JPA, SA, and CPA.

Three relevant textual sources of Western Aramaic are documented from the earlier Middle Aramaic period, which predates the Aramaic of the Targum fragments.⁴ Of these, Qumran Aramaic (QA) shows no apparent constraint on pronominal object inflection (Muraoka 2011, 44–45), but the Aramaic of the Nabataean documents and of the Bar-Kosiba letters shows the above-mentioned preference for /yāt/ + pronominal suffix, inasmuch as such limited corpora are instructive. In Nabataean Aramaic (10), ten or so occurrences of /yāt/ + pronominal suffix complement a *yiqʿol* conjugation (8x) or infinitive (2x). Two or three occurrences of a *qʿal* form with pronominal object suffix are found in the Nabataean Aramaic texts within a single document, all within the same phrase (11). The form *ktb-yh* in (11), just like non-targumic JPA *msr-yh* (2), attaches the pronominal suffix directly, to a base without a final long vowel.

⁴ On the relative chronologies of Middle and Late Western Aramaic dialects see Fassberg (2010).

- (10) *w-l' ynpq yth 'nwš*
 and-not take.out.JUSS DO person
 'and let no one take him out' (H9.7, Healey 1993, 123)
- (11) PN *l n[pš-h] ktb-yh*
 PN.MSG on self-3MSG write.PRF.3MSG-3MSG
 'PN has written it for himself' (P. Yadin 1.60) (Yadin et al. 2002, 182)

In the Aramaic of the Bar-Kosiba letters we find five occurrences of the periphrastic construction (12) and two with a pronominal object suffix (13), both attached to *yiqtol* forms by means of so-called energetic *nun*.

- (12) *w-tqn yt-hn*
 and-tithe.IMPV.2MSG DO-3FPL
 'and tithe them' (P. Yadin 57.4) (Yadin et al. 2002, 326)
- (13) *w-mn dy yšhbn-kn*
 and-who REL disturb.IMPERF.3MSG-2MPL
 'and whoever disturbs you' (P. Yadin 50.7-8) (Yadin et al. 2002, 290)

Despite their limited size, the ratio of /yāt/ + pronominal suffix to verbal inflection in those texts is apparently not incidental. A similar ratio is found in texts in later Western Aramaic, specifically the much larger Samaritan Targum and Targum Neophyti of the Pentateuch. Both Targums, but especially the latter, were composed in dialects very close to the Aramaic of the Targum fragments from the Cairo Geniza, and likewise reflect an early phase of LWA. The Samaritan Targum and Targum Neophyti both show a marked preference for the periphrastic construction, while still documenting verbal inflection in a limited capacity.

Lund (1981, 76, 78), in his syntax of the non-translated passages of Targum Neophyti, which are expansions of the Hebrew Masoretic Text and thus not morphosyntactically dependent on it, reports 74 occurrences of /yāt/ + pronominal suffix (14), and seven of verbal inflection with *q̄tal*, showing direct attachment to bases not ending in a long vowel (15) and with *yiq̄tol*, showing attachment with *-n-* (16).

- (14) *w-šwy* *yt-hwn*
 and-put.PRF.3MSG DO-3MPL
 ‘and he put them’ (Gen. 28.10)

- (15) *d-brk-yh*
 that-bless.prf.3MSG-3MSG
 ‘That [he] blessed him’ (Gen. 33.14)

- (16) *l’* *’tyb-n’* [read: *’tyb-nh*]
 not return.IMPERF.1SG-3MSG
 ‘I shall not return it’ (Gen. 44.18)

As noted above, the situation is very similar in CPA (Müller-Kessler 1991, 259), where the periphrastic construction with /yāt-/ (17) dominates, but verbal inflection is still found with *q̄tal* attached directly to bases without a final long vowel (18), and with *yiq̄tol* attached by means of *-n-* (19).

- (17) *w-rwmy-y* *’wblw* *yt-h*
 and-roman.PL-DEF lead.PRF.3MPL DO-3MSG
 ‘and the Roman soldiers led him’ (Mark 15.16, according to Müller-Kessler and Sokoloff 1998, 75)

- (18) *w-msr-y* *mr-³*
 and-hand.over.PRF.3MSG-1SG lord-DEF
 ‘and the Lord handed me over’ (Lam. 1.14, according to Müller-Kessler and Sokoloff 1997, 183)
- (19) *yškḥ-nh*
 find.IMPERF.3MSG-3MSG
 ‘[he] find him’ (Matthew 24.46, according to Müller-Kessler and Sokoloff 1998, 64)

In the categories of *qṭal* with synchronically consonant-final bases and of *yiqṭol*, while the earlier dialects and CPA prefer expressing pronominal direct objects using the periphrastic construction, later non-targumic JPA and SA prefer verbal inflection. Nonetheless, the specific verb forms in both categories, which do show pronominal direct object inflection in the earlier dialects are by and large identical to inflected verb forms found in later non-targumic JPA and SA. All attested *qṭal* forms with pronominal direct object inflection have bases without a final long vowel and all attested *yiqṭol* forms attach pronominal object suffixes by means of energetic *nun*. The attachment of pronominal direct objects to *qṭal* forms directly and to *yiqṭol* forms by means of *-n-* is already found in Official Egyptian Aramaic (OEA),⁵ Biblical Aramaic (BA), e.g., /satr-ēh/, /yšēzb-innāk/ (Rosenthal 1961, 71), and, more closely in time and place, in QA (Muraoka 2011, 141–43). Therefore, throughout Western Aramaic these two inflectional categories are simply a retention.

⁵ See many examples in Official Egyptian Aramaic in Muraoka and Porten (1998, 144–46).

Thus, for the most part, the difference between non-targumic JPA and SA and other typologically earlier Western Aramaic dialects is not in their specific verbal morphology or verbal morphosyntactic constructions, but in the frequency of those forms and constructions, and in the morphophonemic shape of the periphrastic construction with /yāt/. The Aramaic of the Targum fragments from the Cairo Geniza alone stands out in not showing any verbal inflection for pronominal direct objects.

Below, the comparative approach is expanded to further examine features which have been retained from earlier Aramaic in non-targumic JPA and SA, and, no less importantly, features which have been lost altogether.

3.0. Possible Explanations

The overview above shows the morphosyntactic expression of pronominal direct objects in both Middle- and Late Western Aramaic to have been different from that of the earliest stages of Aramaic, where verbal inflection was widely used. Before offering an explanation of my own for the general change and for the specific situation in non-targumic JPA and SA, I would like to review the main possibilities already suggested.

Within Western Aramaic, differences between non-targumic JPA and SA and the rest of the dialects can be interpreted in at least three ways: as differences between (1) separate dialects or dialect branches, (2) separate chronological stages in a single dialect or dialect branch, and (3) the spoken and literary registers of a single dialect or dialect branch. The three possibilities are not mutually exclusive.

Tal (1985, especially 20–21) expresses the clear opinion that the divergent morphosyntaxes of pronominal direct object expression among the Middle and Late Western Aramaic dialects reflect differences between the spoken registers of *separate dialects*. In Tal's view, non-targumic JPA, from the Galilee, and SA from Samaria, were distinct from the Judaeen Aramaic dialect in the Cairo Geniza Targum fragments. The latter indeed completely lost verbal inflection for pronominal direct objects, whereas the former dialects preserved it. Verbal inflection later reappeared in literary texts, such as the Palestinian Talmud and Tibat Marqe, when those non-Judaeen dialects attained literary status. Tal notes that in non-targumic JPA and SA, some pronominal suffix forms changed from earlier Aramaic, but he does not connect this to other developments in the morphosyntax of Western Aramaic pronominal direct object expression, such as the lack of pronominal object inflection in targumic JPA. Stadel (2011, 240) suggests for SA that stylistics may have played a part in the propagation of the periphrastic construction.

In what follows, I argue for a different explanation from Tal's and Stadel's. Namely, all Western Aramaic dialects at the Late Aramaic stage or perhaps earlier had lost some of their verbal inflection for pronominal direct objects in the spoken language. This occurred specifically in the *q̄tal* and imperative conjugations, which had long-vowel-final bases. A single underlying cause—morphophonological, not stylistic—was common to all Western Aramaic dialects of the region. As an initial result, pronominal direct object expression entered a state of flux, by which some older inflectional forms in the spoken language were lost

and replaced by novel morphosyntax, while other inflectional forms were retained. This state of asymmetry, whereby certain verb forms could express pronominal direct objects inflectionally, while others could do so only periphrastically via /yāt/, likely prompted authors of literary texts to widely avoid verbal inflection and employ periphrasis with all verb forms. Later, the state of flux was resolved when novel verbal inflection for pronominal direct object expression, which had originated in the spoken language, acquired literary status. This is directly related to the changes noted by Tal in the forms of pronominal suffixes in LWA, in comparison to earlier Aramaic. To elucidate these developments, special attention will be devoted to verbal inflectional suffixes which were lost in LWA.

4.0. Historical Development of the Late Western Aramaic 3MSG Pronominal Direct Object

4.1. Loss of the 3MSG Biform /*-hī/ in the Verbal System

Perhaps the most notable morphological change in the pronominal object inflection of verbs in LWA, one which has not been identified by scholars, is the complete loss of the 3MSG pronominal suffix biform /*-hī/, so common outside of LWA. Tal (1985, 19–21), as mentioned above, recognises the replacement of specific verbal suffix forms with others in LWA, without diagnosing the loss of /*-hī/ as a general phenomenon. This sweeping change likewise goes unmentioned in Stadel's (2011) analysis of the historical development of SA pronominal object suffixes.

Originally, /*-hī/ occurred with Aramaic verbs, nouns, and prepositions, apparently only after long vowels or diphthongs, in complementary distribution with /*-ēh/, which occurred after consonants (Muraoka and Porten 1998, 148–51). Throughout the pronominal object inflection of LWA verbs, however, only reflexes of /*-ēh/ survived. The biform /*-hī/ only survived in LWA with nouns (20)–(21) and prepositions (22), where, in combination with the preceding stressed vowel, it was reduced to /-y/ or /-yi/, through elision of the /h/, a typical sound-shift in LWA.

(20) ʾbwy [ʾəʿbū-y(i)] ‘his father’ < /*ʾəʿbū-hī/

(21) bnwy [bnō-y(i)] ‘his sons’ < /*ʿbnō-hī/

(22) ʿlwy [ʿəʿlō-y(i)] ‘upon him’ < /*ʿlō-hī/

Tracking this loss of /*-hī/ in the verbal system and its outcomes in LWA contributes to the clarification of the question of pronominal direct object expression in LWA in general. In *qṭal*, forms with /*-hī/ would have been comparable with long-vowel-final verbal bases in earlier Aramaic, such as BA /ʿbnā^o-hī/ (23), and QA /naʿḥmū-hī(?)/ (24). From such forms, the /h/ of the suffix would have been elided in inter-vocalic position, as reflected in (20)–(22). Instead of the novel LWA forms of the type ʾkʿsw-th /ʾakʿsū-tēh/ (1), ns-tyh /nsā-tēh/ (2), and ḥṭpwn-yh (3), the historically expected forms, comparable with the BA (23) and QA (24) forms, should have been /*ʾakʿsū-y/, /*nsā-y(i)/, and /*ḥaṭpū-y(i)/ from earlier /*ʾakʿsū-hī/, /*ʿnsā-hī/, and /*ḥaṭpū-hī/, respectively. Such historically expected forms, however, are completely absent in LWA.

(23) /^obnā-hī/

build.PRF.3MSG-3MSG

‘he built it’ (Ezra 5.11)

(24) *nḥmw-hy* /na^hḥmū-hī(?)/

console.PRF.3MPL-3MSG

‘they consoled him’ (6Q8 2.1) (Muraoka 2011, 40)

We can already observe from (1)–(3) that where the earlier verbal inflection involving the pronominal biform /*-hī/ would have occurred in the LWA *qṭal* conjugation, it was mainly replaced by periphrasis by means of /yāt-ēh/—which in non-targumic JPA and in SA coalesced with the preceding verb. Other novel inflectional forms with *-n-* mediating the attachment of the 3MSG object suffix, such as *ḥṭpwn-yh* /ḥaṭpūnēh(?)/ (3), competed with forms such as /ʔak^ʕsū-tēh/ (1). Likewise, among III-weak 3MSG verbs, a form such as *ḥmn-yh* (25) from III-weak /ḥmā/ ‘he saw’, competed with the type /nsā-tēh/ (2). A third type of *qṭal* inflection in LWA attaches the 3MSG object suffix to 3MSG third-weak verbs as though they were strong verbs, such as with /qrā/ ‘he read’ (26). This might be an innovation, or conversely, a reflex of the earlier inflection of III-glottal roots, such as **qrʔ*, as strong verbs.

(25) *ḥmn-yh*

see.PRF.3MSG-3MSG

‘he saw him’ (Genesis Rabbah, 302)

(26) *w-qry-h* perhaps < /*w-qar^ʔ-ēh/

and-read.PRF.3MSG-3MSG

‘and he read it’ (Genesis Rabbah, 883)

On comparative considerations, the biform /*-hī/ likely occurred in the precursors to LWA in the imperative conjugation as well.

BA from the last centuries BCE shows the use of /-hī/ with the 2MPL imperative form ending in /-ū/ (27), and in QA from the directly preceding Middle Aramaic period, /-hī/ is found attached to a 2MSG imperative form of a III-weak verb in the *pə'al* stem (28).

(27) /ḥab'blū-hī/

destroy.IMPV.2MPL-3MSG

‘destroy it’ (Dan. 4.20)

(28) *pṣ-hy* /'pṣā-hī(?)/

rescue.IMPV.2MSG-3MSG

‘rescue him’ (Muraoka 2011, 40)

Nonetheless, only reflexes of /*-ēh/, not /*-hī/, are attested with LWA imperative forms for expressing 3MSG direct objects. As in the *qṭal* conjugation, forms ending in a long vowel, which historically take /*-hī/, attach /*-ēh/ by means of either *-t-*, deriving from periphrastic /*yāt-ēh/, or *-n-*. Attachment via *-t-* can be seen in *bzy* in the *pa'al* stem (29), a III-weak 3MSG verb (for further examples from SA, see Macuch 1982, 234). Comparable with BA /ḥab'blū-hī/ (27) is the 2MPL imperative form *ʾrpw* (30), ending in /-ū/, which attaches the 3MSG pronominal object suffix /*-ēh/ via *-n-* mediation.

(29) *w-bzy-tyh* /v-bazzī-tēh(?)/

and-humiliate.IMPV.2MSG-3MSG

‘and humiliate him’ (y. Pe'ah. 1.1 [15d])

(30) *ʾrpwn-h* /ʾarpūn-ēh(?)/

let.go.IMPV.2MPL-3MSG

‘let go of him’ (y. Ber. 7.3 [11c], Cairo Geniza fragment T-S F 17.52)

4.2. The ‘Missing Link’ between Early Aramaic /*-hī/ and Late Western Aramaic /-y(i)/

It can be assumed that at an earlier, undocumented stage, *qṭal* forms of the type /*nsā-y(i)/, /*ḥmā-y(i)/, /*ʾakʿsū-y(i)/, and /*ḥaṭpū-y(i)/ had indeed developed in the speech of Western Aramaic speakers from /*nsā-hī/, /*ḥmā-hī/, /*ʾakʿsū-hī/, and /*ḥaṭpū-hī/, respectively, through the typical elision of intervocalic /h/. Comparable imperative forms, such as /*ʾarʿpū-y(i)/ from /*ʾarʿpū-hī/ had likely also developed during that earlier period. The very phonological process is observed, as noted above, with the same historical suffix, when attached to nouns and prepositions (20)–(22).

In the verbal system, this missing link, so to speak, i.e., verb forms containing the inherited pronominal suffix /*-hī/, with intervocalic elision of the /h/, possibly occurs in a document from Wadi Sdeir in the form *ḥtmwy* /ḥatmū-y(i)(?)/ < /*ḥatmū-hī/ ‘they signed it’ (Muraoka 2011, 142). Outside LWA and the Western Aramaic region, such forms are documented in contemporaneous Syriac in *qṭal* (31) (Denz 1962, 50–54; see also Nöldeke 1904, 144–45), and in the imperative (32) (Nöldeke 1904, 140–43, 146).

- (31) /glā-y/ < /*^lglā-hī/

reveal.PRF.3MSG-3MSG

‘He revealed him’

- (32) /ʾapʿqū-y/ < /*ʾapʿpqū-hī/

cast.out.IMPV.2MPL-3MSG

‘cast him out’

4.3. Expression of 3MSG Pronominal Direct Objects in the *yiqtol* Conjugation

Reflexes of the biform /*-hī/ are also absent in the *yiqtol* conjugation of LWA dialects, but in contrast to *qṭal* and the imperative, this situation appears to have been inherited from earlier Aramaic and does not necessarily indicate a loss of /*-hī/ in *yiqtol*. We have already seen that LWA attaches pronominal suffixes to the *yiqtol* conjugation with energetic *nun*. The form of the 3MSG object suffix attached in that manner is indeed a reflex of /*-ēh/, spelled *-h* (16), (19), and (33), or *-yh* (34), not /*-hī/. Unlike the attachment of the pronominal suffix by means of *-t-* in *qṭal*, the imperative, and the infinitive, which is conditioned on base forms ending in a long vowel, in the case of *yiqtol*, the pronominal suffix attaches by means of *-n-* whether the base form is consonant- (33) or vowel-final (34).

- (33) *yškḥ-nh* *d-ʿbd-ø* *k-dn*
 find.SUBJV.3MSG-3MSG COMP-do.PART-MSG like-this.MSG
 ‘[...] would find him doing so’ (CPA) (Matt. 24.46, according to Müller-Kessler and Sokoloff 1998, 48)

- (34) *kd* *ṭḥmy-nyh*
 when see.SUBJV.2MSG-3MSG
 ‘when you see him’ (JPA) (y. Berakot 2.1 [4a])

As pointed out above, LWA *yiqtol* inflection by means of energetic *nun* is generally an inherited Aramaic feature. Specifically, the attachment of the biform /*-ēh/ to energetic *yiqtol* is found already in BA (35) and QA (36).

(35) /ʰōdʰ-innēh/

inform.IMPERF.1SG-3MSG

‘I shall inform him’ (Dan. 5.17; see Rosenthal 1961, 71)

(36) *yhd-nh*

take.IMPERF.3MSG-3MSG

‘he will take it’ (4Q556 1.5; Muraoka 2011, 142)

Unlike the *qṭal* and imperative conjugations, where it is rather certain that the biform /-hī/ had been used in Western Aramaic, but lost in that branch by the LWA stage, a comparative analysis of non-LWA sources does not reveal unequivocally what changes had affected the biform /*-hī/ in the prefix conjugation of pre-LWA. OEA, from nearly a millennium before the Late Aramaic period, apparently documents both the biform /*-ēh/ (37) and /*-hī/ (38) attached to energetic *yiqṭol*. Orthographically, these are expressed respectively as *-n-h* (37) and *-n-hy* (38).

(37) *ʾntnn-h*

give.IMPERF.1SG-3MSG

‘I shall give it’ (B4.6:5; Muraoka and Porten 1998, 145–46)

(38) *ykbšn-hy*

press.IMPERF.3MSG-3MSG

‘he will press him’ (B3.9:5; Muraoka and Porten 1998, 145)

By contrast, BA, from the latest phase of Official Aramaic, and QA, from the Middle Aramaic periods, document only the biform /*-ēh/ attached to energetic *yiqṭol* (35)–(36).

Syriac, from the Late Aramaic period itself, appears to document both the pronominal suffix /*-ēh/ (39) and /-y/ < /*-hī/

(40), attached by means of -n- to the prefix conjugation (Nöldeke 1904, 137, 139–40).

(39) /neštōn-ē/ < /*neštōn-ēh/

drink.IMPERF.3MPL-3MSG

‘they drink it’

(40) /nsīmū¹nā-y/ < /*nsīmū¹nā-hī/

place.IMPERF.3MPL-3MSG

‘they place him’

Syriac *yīqtol*, however, differs in several details from LWA *yīqtol* in its pronominal direct object suffix inflection. Most importantly, unlike in LWA, it does not consistently attach pronominal suffixes, including the 3MSG biforms /*-ēh/ and /*-hī/, by means of energetic *nun* (Nöldeke 1904, 137, 144–45). Thus, in the morphosyntax of their *yīqtol* conjugation, LWA and earlier phases of Western Aramaic correspond most closely to the energetic *yīqtol* conjugation in BA and QA, where only the 3MSG pronominal object biform /*-ēh/ is found. It is therefore likely that already in the precursor of the LWA *yīqtol* conjugation, the 3MSG biform /*-hī/ was not part of the inflection, and was not lost as LWA developed.

4.4. Summary of the Historical Development of the 3MSG Pronominal Direct Object

The 3MSG pronominal suffix biform /*-hī/, which is still found in LWA with nouns and prepositions in the reduced form -y, had been lost as an object suffix with verbs. Specifically, wherever /*-hī/ occurred in earlier Aramaic, it was replaced, either by the

periphrastic construction via /yāt/ or by novel non-inherited verbal inflection. In non-targumic JPA and in SA, the periphrastic construction was later phonologically reduced. Wherever verbal inflection using the biform 3MSG /*-ēh/ had already occurred before the loss of /*-hī/, it continued being used in LWA. Since prior to LWA, complementary distribution in the form of the 3MSG direct object between /*-C-ēh/ and /*-V̄-hī/ had existed in *q̄tal* and the imperative (Nöldeke 1904, 134–39; Rosenthal 1961, 71; Muraoka and Porten 1998, 144–45), this resulted in complementary distribution in LWA between the forms /-C-ē/ < /*-C-ēh/ and /-V̄-tē/ (/ -V̄ yātē/ in CPA), in place of /*-V̄-hī/. By contrast, with *yiq̄tol*, the verbal morphology found in LWA, whereby the biform /*-ēh/ is suffixed to the verb by means of energetic *nun*, had already existed in earlier Aramaic either as the sole means, or possibly in free interchange with the biform /*-hī/. For this reason, in the case of *yiq̄tol*, LWA does not employ novel verbal morphology for expressing the 3MSG pronominal direct object. The result in all cases is that a reflex of the biform /*-ēh/ is the only form of the 3MSG direct object suffix in LWA. This analysis establishes a clear correspondence, presented in Table 1, between non-targumic JPA, SA, and CPA and earlier Aramaic in the morphosyntactic expression of 3MSG pronominal direct objects.

Table 1: Expression of 3MSG pronominal direct objects in OEA, BA, QA and LWA

OEA, BA, QA	LWA
<i>yiq̄tol-n</i> + /*-ēh/	<i>yiq̄tol-n</i> + /*-ēh/
<i>q̄tal</i> /imperative + /*-ēh/	<i>q̄tal</i> /imperative + /*-ēh/
<i>q̄tal</i> /imperative + /*-hī/	<i>q̄tal</i> /imperative + /yāt-ēh/ or novel verbal morphology

5.0. Causes for the Loss of the 3MSG Pronominal Object Biform /*-hī/

After establishing that the 3MSG form /*-hī/ was eliminated from verbal inflection in pre-LWA and replaced by periphrasis or novel inflectional morphology, I now turn to offering an explanation for the elimination of /*-hī/. In so doing, I suggest that the complete absence of pronominal object suffixes with verbs in targumic JPA from the Cairo Geniza and the paucity of such object suffixes in other targumic texts reflect a transitional period, perhaps before /*-hī/ was completely eliminated, in which a state of flux in the spoken language caused the avoidance of pronominal object suffixes in the literary language.

5.1. Clash between 3MSG /*-y(i)/ < /*-hī/ and 1SG /-ī/ Verbal Suffixes in pre-Late Western Aramaic

As noted in §§4.1–2, a common sound shift in LWA and elsewhere was the intervocalic elision of /h/, which caused the 3MSG pronominal suffix /*-hī/ to shift to /-y(i)/, as can be seen in LWA with nouns and prepositions (20)–(22) and in Syriac with verbs (31)–(32). In §4.2, I proposed that at an earlier undocumented stage, the form /*-y(i)/ had indeed developed as the 3MSG pronominal direct object suffix, comparable with that documented in Syriac, in the speech of Western Aramaic speakers. I shall now argue that the elision of /h/ made the 3MSG pronominal suffix form /*-y(i)/ similar in sound to the 1SG pronominal suffix /-ī/. In combination with additional developments in LWA verbs, this brought about morphological ambiguity and confusion between the 1SG and 3MSG pronominal object suffixes. Resolution of that

ambiguity was the root cause of the loss of the biform */*-y(i)/* < */*-hī/* as the 3MSG pronominal direct object suffix in the LWA verbal system.

A starting point in my proposal is that ambiguity between LWA 3MSG */-y(i)/* < */*-hī/* and 1SG */-ī/* has already been shown by Fassberg (1987, 199–206; 1990, 118–19; 2001, 104–12) to have developed when those suffixes were attached to nouns and prepositions. Fassberg points out that in these non-verbal categories, JPA and CPA texts employ on occasion *-wy* */-ōy(i)/* < */*-ō-hī/*, not for 3MSG as in (21)–(22), but for 1SG (20), convincingly arguing that such occurrences are the result of reanalysis of 3MSG */-y(i)/* after MPL nouns and MPL-like prepositions as indicating 1SG (Fassberg 2001, 105).

(41) *ʾd-w-y* < */ydōy(i)(?)/* < */*yʾdō-hī/* ‘his hands’

hand-PL-1SG

‘my hands’

Similar fluctuation is noted in Fassberg’s (1987, 204) analysis of singular nouns, such */ʾab/* ‘father’, */ʾaḥ/* ‘brother’, */ḥam/* ‘father-in-law’, whose bases end in */ū/* when taking pronominal suffixes. In earlier Aramaic, such nouns took the 3MSG suffixal form */*-hī/*, reduced to */-y(i)/* in LWA. The orthographic form *-y*, which reflects */-y(i)/* < */*-hī/*, is still the most prevalent form in LWA texts for expressing the 3MSG pronominal suffix with such nouns, as in (20), reproduced in (42). Fassberg notes, however, that JPA, CPA, and SA all document less common forms of these nouns, whereby the 3MSG pronoun has the orthographic form *-h* (43). Fassberg suggests that the same development, namely, the reanalysis of */-y(i)/* < */*-hī/* in forms such as */ʾəbūy(i)/* <

/ʔabūhī/ as expressing 1SG brought about the development of forms such as (43), in which 3MSG is expressed by a suffix other than /-y(i)/ < /*-hī/.

(42) ʔbw-y < /*ʔaʿbū-hī/

father-3MSG

‘his father’

(43) ʔbw-h

father-3MSG

‘his father’

The fluctuations analysed by Fassberg disclose how, in the speech of LWA users, the phonologically reduced form of the 3MSG pronominal suffix /*-hī/ > /-y(i)/ and the 1SG form /-ī/ were confused, due to their similar phonetic realisation. With nouns and prepositions, this confusion did not cause the abolition of the 3MSG pronominal suffix /*-hī/ > /-y(i)/, but rather its incipient reanalysis as representing 1SG. I argue that the same clash between the phonetic realisation of the 3MSG pronominal suffix /*-hī/ > /-y(i)/ and the 1SG /-ī/ had developed in the pre-LWA verbal system, where, by contrast, the very 3MSG pronominal suffix form /*-hī/ > /-y(i)/ was eliminated. The development in the pre-LWA verbal system has not been recognised thus far, because the 3MSG pronominal suffix /*-hī/ > /-y(i)/ had completely disappeared before the creation of the extant texts, leaving no discernible traces.

5.2. Reanalysis of 1SG /-nī/ as /-n-ī/

In conjunction with the loss of 3MSG /*-hī/ > /-y(i)/ as a direct object suffix, LWA evinces another important development in the

morphology of pronominal direct object suffixes which bears upon the suffix for both 1SG and 3MSG. Historically, the 1SG pronominal object suffix form /-ī/ could attach to verbs only by means of *-n-*, as seen, for instance, in earlier dialects, such as OEA (44) (and see Muraoka and Porten 1998, 143–48 for additional examples) and in contemporaneous Syriac (Nöldeke 1904, 144–45). In LWA, however, the *q̄tal* and imperative conjugations document the attachment of /-ī/ directly, without /-n-/ (45) (Macuch 1982, 225–26; Müller-Kessler 1991, 259–60; Stadel 2011, 242). This novel inflection, however, did not displace, but coexisted with, the older combination /-nī/, seen in the *q̄tal* form in (46) (Macuch 1982, 225–27; Heijmans 2005, 112).

(44) *hn̄sl-ny*

reclaim.from.PRF.3MSG-1SG

‘he reclaimed from me’ (B8.6:5) (Muraoka and Porten 1998, 144).

(45) *w-ʔl-y*

and-bring.in.PRF.3MSG-1SG

‘and he brought me in’ (JPA) (Genesis Rabbah, 762)

(46) *šlh-ny*

send.PRF.3MSG-1MSG

‘he sent me’ (SA Targum) (Macuch 1982, 226)

This development is no doubt linked to two further developments in LWA. The first is that verb forms without direct object suffixes that had historically ended in a long open syllable came to terminate in /-n/ (47)–(48) (see Tal 1979; Fassberg 1990, 165). Here, too, however, novel verb forms with /-n/ appear to have

coexisted with earlier vowel-final verb forms (49) (see Macuch 1982, 146).

(47) *w-ʾmrwn* < /*wV-ʾmarū/

and-say.PRF.3MPL

‘and they said’ (SA Targum to Gen. 19.2, Macuch 1982, 146)

(48) *šwmʿwn* < /*šumʿū/

hear.IMPV.2MPL

‘listen!’ (CPA) (Sokoloff 2014, 102)

(49) *w-ʿbdw*

and-do.PRF-3MPL

‘and they did’ (SA) (Tibat Marqe, Book One, Tal 2019, 34)

The second additional development in LWA was that formerly vowel-final *qṭal* and imperative verb forms, such as 3MPL *qṭal* /*ʾrīmū/ ‘they raised’ (50), had come to attach pronominal suffixes by means of final -n, thus taking suffixal biforms that attach to a final consonant.

(50) *w-rymwn-h* /v-ārīmūn-ā(?)/ in place of earlier Aramaic /*ʾrīmū-hā/

and-raise.PRF.3MPL-3FSG

‘and they raised it’ (JPA) (y. Beša 1.5 [60c], Cairo Geniza fragment T-S 17 34.2)

It is beyond the scope of the current article to determine the relative chronologies of the LWA verbal forms in (47)–(49), whose bases came to end in /-n/, and the form in (50), which came to attach pronominal suffixes using -n-. What is clear is that the increase in both types of verb forms facilitated the reanalysis of the older 1SG pronominal object suffix form /-nī/ (51), as consisting

of /-n/ belonging to the verbal base, together with the suffix /-ī/, which could then be attached directly to other verbal bases, as in *w-ʔl-y* in (45).

- (51) *ʔlbšwn-y* /ʔalbšūn-ī/ < /*ʔalbšū-nī/
 dress.IMPV.2MPL-1SG
 ‘dress me’ (JPA) (y. Kil. 9.4 [32b])

5.3. Effects of Reanalysis of 1SG /-nī/ as /-n-ī/ on the 3MSG Form /*-hī/

As the reanalysis of the direct object suffix /-nī/ as consisting of /-n-ī/ became established and the use of the direct object suffix /-ī/ for 1SG in place of /-nī/ expanded with *qṭal* and imperative verb forms in the precursors to LWA, the possibility that other occurrences of word-final /-ī/ could be interpreted as expressing the 1SG direct object pronoun would have increased. Especially the inherited 3MSG object suffix /*-hī/, from which intervocalic /h/ was elided, would have become ambiguous. With verb forms in Western Aramaic corresponding to Syriac /glā-y/ < /*glā-hī/ (31) and /apqū-y/ < /*appqū-hī/ (32), the 3MSG object suffix /*-y(i)/ could now be understood to signify both 3MSG and 1SG. This linguistic situation, to which I referred earlier as a state of flux, was likely not tolerated by speakers of Western Aramaic. Wherever the 3MSG object suffix /*-y/ < /*-hī/ occurred in the verbal system, it was eliminated, replaced in speech by other inflectional possibilities where available, or by periphrasis with /yāt + ēh/, where alternative verbal inflection was unavailable. This explains why no verb form with the inherited 3MSG direct object suffix /*-y(i)/ < /*-hī/ survived in any LWA dialect.

6.0. Relative Chronology

First, the historical morphophonology of pronominal direct object periphrasis via /yāt/ in *q̄tal* and the imperative reveals something about its relative chronology. The reduced form of /yāt/, *-t-*, consistently follows verbal bases ending in /-V̄/, not /-V̄n/. This is indicated both orthographically and by the phonetic realisation of combinations with *-t-* in the Samaritan oral tradition. With respect to orthography, phonologically reduced *-t-* is never preceded by *-n*, i.e., SA *ʔkʿsw-th* (1). According to the Samaritan oral tradition, the *-t-* is preceded by a long vowel, i.e., *šbqw-th* /šābāqū-te/ (Florentin 1991, 74), ruling out an underlying /-n-/, which assimilated to the following /-t-/.

It thus appears that periphrasis was already an established morphosyntactic alternative for expressing pronominal direct objects before verbal bases in *q̄tal* and the imperative with final /-V̄/ began to shift to final /-V̄n/ and, therefore, before the 1SG pronominal object suffix began to fluctuate between /-nī/ and /-ī/. Moreover, the prepositional phrase /yāt + pronominal suffix/ must have already become tightly associated with the verbal base preceding it, preventing the older verbal bases with final /-V̄/ from shifting to final /-V̄n/.

Second, a comparison between the LWA verbal system, on the one hand, and its nominal and prepositional systems, on the other, regarding the fate of 3MSG /*-hī/, indicates that, upon elision of the /h/ from /*-hī/ > /*y(i)/, its reanalysis as signifying 1SG had taken place earlier in the verbal system. By the LWA stage, it had been completely abolished with verbs, but only began being reanalysed with nouns and prepositions. The historical

depth of the ambiguity of /*y(i)/ < /*-hī/ as marking either 3MSG or 1SG in the verbal systems of the precursors to LWA is further indicated by the existence of established innovative morphological and morphosyntactic means for expressing the 3MSG object suffix in place of /*y(i)/ < /*-hī/, i.e., bridging -t-, and other novel morphology, especially -n-.

7.0. The Transitional Character of Palestinian Targumic Aramaic Pronominal Object Inflection

Integrating all the data presented above, I suggest, as opposed to Tal (§4.0), that the complete lack of pronominal direct object inflection in targumic JPA from the Cairo Geniza does not reflect a situation that actually obtained in any spoken LWA dialect. Rather, it reflects a state of flux in the morphology of pronominal direct object inflection that had developed in the spoken language of the author(s) of the Targum as in other LWA dialects. A complete loss of pronominal direct object inflection in the spoken language underlying targumic JPA from the Cairo Geniza, as Tal suggests, cannot be attributed to phenomena particular to that dialect, nor to general LWA developments. By contrast, the loss of the 3MSG direct object suffix /*-hī/ > /*y(i)/ and its replacement with periphrastic /yāt-ēh/ specifically with *q̄tal* and imperative forms, together with the retention of other older Aramaic inflectional morphology, can be explained by the general LWA phenomena outlined in the present article.

I thus suggest that the intervocalic elision of the /h/ in the 3MSG suffix /*-hī/ > /*y(i)/, the increase in verb forms whose

bases end in /- $\bar{V}n$ /, and resulting reanalysis of /-n/ in the 1SG pronominal object suffix /-nī/ as belonging to the verbal base /- $\bar{V}n$ -ī/ should be seen as indicative of transition, not unlike the fluctuation that LWA itself documents with regard to the 3MSG suffix /*-hī/ with nouns and prepositions.

During this transition period, in which pronominal object inflection was in a state of flux, especially regarding 1SG and 3MSG pronominal direct objects, and the morphosyntax of pronominal object expression was being reestablished in the spoken language, the author(s) of the Palestinian Targum from the Cairo Geniza refrained completely from employing pronominal object inflection, even those forms, which, historically, were inherited from earlier Aramaic, such as *yiqtol* forms with energetic *nun*, and consonant-final *qṭal* forms, attaching the 3MSG direct object suffix /*-ēh/. Instead, the author(s) of the Targum employed periphrasis via /yāt/, an alternative which had been established in LWA or its precursors.

Later, in talmudic JPA and elsewhere in LWA, the novel morphosyntax of the transition period, namely, the attachment of pronominal suffixes by means of phonologically reduced /yāt/ or -n-, which had been considered colloquial and unfit for literary use, became acceptable. The earlier abstinence from any verbal inflection for pronominal direct objects was abandoned, and the newly established system, containing both inherited and novel inflection was used in literary creation as well.

References

- Albeck, Chanoch, and Juda Theodor. 1912–1929. *Bereschit Rabba*. Berlin: Akademie Verlag.
- Arnold, Werner. 1990. *Das Neuwestamäische*. V. *Grammatik*. Semitica Viva 4. Wiesbaden: Harrassowitz.
- Butts, Aaron M. 2019. ‘The Classical Syriac Language’. In *The Syriac World*, edited by Daniel King, 222–42. New York: Routledge.
- Denz, Adolf. 1962. ‘Strukturanalyse der pronominalen Objektsuffixe im Altsyrischen und klassischen Arabisch’. PhD dissertation, Ludwig Maximilians Universität.
- Fassberg, Steven E. 1987. ‘Miscellanea in Western Aramaic’. *Language Studies* 2–3: 199–206. [Hebrew]
- . 1990. *A Grammar of the Palestinian Targum Fragments from the Cairo Genizah*. Harvard Semitic Studies 38. Atlanta, GA: Scholars Press.
- . 2001. ‘The 1st Sg. Suffix -ay in Western Neo-Aramaic: A Historical Perspective’. *Orientalia* 70/1: 104–12.
- . 2010. ‘Salient Features of the Verbal System in the Aramaic Dead Sea Scrolls’. In *Aramaica Qumranica: Proceedings of the Conference on the Aramaic Texts from Qumran in Aix-en-Provence, 30 June–2 July 2008*, edited by Katell Berthelot and Daniel Stökl Ben Ezra, 65–81. *Studies on the Texts of the Desert of Judah* 94. Leiden: Brill.
- Fitzmyer, Joseph A. 1979. ‘The Phases of the Aramaic Language’. In *A Wandering Aramean: Collected Aramaic Essays*, edited by Joseph A. Fitzmyer, 57–84. Society for Biblical Literature Monograph Series 25. Chico, CA: Scholars Press.

- Florentin, Moshe. 1991. 'The Object Suffixes in Samaritan Aramaic and the Modes of their Attachment to the Verb'. *Abr-Nahrain* 29: 67–82.
- Healey, John F. 1993. *The Nabatean Tomb Inscriptions of Mada'in Salih*. Journal of Semitic Studies Supplement 1. Oxford: Oxford University Press.
- Heijmans, Shai. 2005. 'Morphology of the Aramaic Dialect in the Palestinian Talmud according to Geniza Manuscripts'. MA thesis, Tel-Aviv University.
- Lund, Jerome. 1981. 'A Descriptive Syntax of the Non-Translational Passages According to Codex Neophyti 1'. MA thesis, The Hebrew University of Jerusalem. [Hebrew]
- Macuch, Rudolf. 1982. *Grammatik des samaritanischen Aramäisch*. Berlin: De Gruyter.
- Müller-Kessler, Christa. 1991. *Grammatik des christlich-palästinisch-Aramäischen: Teil 1, Schriftlehre, Lautlehre, Formenlehre*. Texte und Studien zur Orientalistik 6. Hildesheim: Olms.
- Müller-Kessler, Christa, and Michael Sokoloff. 1997. *A Corpus of Christian Palestinian Aramaic, Vol. I: The Christian Palestinian Aramaic Old Testament and Apocrypha Version from the Early Period*. Groningen: STYX.
- . 1998. *A Corpus of Christian Palestinian Aramaic, Vol. IIA: The Christian Palestinian New Testament Version from the Early Period—Gospels*. Groningen: STYX.
- Muraoka, Takamitsu. 2011. *A Grammar of Qumran Aramaic*. Ancient Near Eastern Studies Supplement 38. Leuven: Peeters.

- Muraoka, Takamitsu, and Bezalel Porten. 1998. *A Grammar of Egyptian Aramaic*. Handbook of Oriental Studies 32. Leiden: Brill.
- Nöldeke, Theodor. 1893. 'Bemerkungen zu den Aramäischen Inschriften von Sendschirli'. *Zeitschrift der Deutschen Morgenländischen Gesellschaft* 47: 96–105.
- . 1904. *Compendious Syriac Grammar*. London: Williams & Norgate.
- Rosenthal, Franz. 1961. *A Grammar of Biblical Aramaic*. Porta Linguarum Orientalum Neue Serie 5. Wiesbaden: Harrassowitz.
- Schulthess, Friedrich. 1924. *Grammatik des christlich-palästischen Aramäisch*. Tübingen: Mohr-Siebeck.
- Sokoloff, Michael. 2014. *Texts of Various Contents in Christian Palestinian Aramaic*. Orientalia Lovaniensia Analecta 235. Leuven: Peeters.
- Stadel, Christian. 2011. 'Object Suffixes in Samaritan Aramaic from the First Two Books of Tîbât Mârqe and Some Considerations as to Their Development'. *Ancient Near Eastern Studies* 48: 232–47.
- Tal, Abraham. 1979. 'Stratification in Jewish Palestinian Aramaic: The Added Nun as a Yardstick'. *Leshonenu* 43: 165–84. [Hebrew]
- . 1985. 'The Aramaic Dialects of Palestine and the "Yerushalmi" Targum to the Pentateuch'. In *Proceedings of the World Congress of Jewish Studies*, 13–21. Jerusalem: World Union of Jewish Studies.

———. 2019. *Tibât Mårqe*. Studia Judaica 92; Studia Samaritana 9. Berlin: De Gruyter.

Yadin, Yigael, Jonas C. Greenfield, Ada Yardeni, and Baruch A. Levine. 2002. *The Documents from the Bar Kochba Period in the Cave of Letters: Hebrew, Aramaic and Nabatean-Aramaic Papyri*. Jerusalem: Israel Exploration Society.

THE SIGNIFICANCE OF THE NEWLY FOUND AMORITE–AKKADIAN BILINGUALS FOR HEBREW LEXICOGRAPHY

Viktor Golinets

The question of the antiquity of a language can be of linguistic, historical, political, and ideological interest and importance—to name only a few realms of scholarly activity and human interaction. In the case of Ancient Hebrew, the question of its antiquity strikes all the aspects mentioned above as well as some others. A linguist writing the grammar of an ancient tongue may feel himself obliged to mention the most ancient attestation of the object described. A historian or theologian arguing about whether a specific piece of the Hebrew Bible could or could not have been written during a given period may find himself in need of (dis)proving the plausibility of the existence of the language or script in that specific period. The Gezer Calendar has been regarded as the oldest Hebrew text (Donner and Röllig 1962, 34; 1964, 181; Gibson 1971, 1; Naveh 1982 [1987], 65), although its script is Phoenician (Renz 1995, I:32; II:155; Rollston 2010, 30; cf. also the literature in Koller 2013, 190, fn. 78) and its morphology and

lexis exhibit no feature that can definitely be determined as Hebrew. Indeed, some scholars have argued that the language of the inscription is Canaanite, while others have found reasons to view the language as Phoenician (Pardee 2013).¹ The discovery of the Khirbet Qeiyafa inscription has sparked controversy about not only the language of the artefact, but also the historical repercussions of the find of what is presumably the oldest Hebrew text.² These two examples illustrate the quest for oldest attestations of Hebrew.

The 'Hebrew Language' entry in the *Encyclopaedia Judaica* starts with a section on the "pre-biblical" period (Brovender 1972 = 2007), where another path is taken in search of the oldest evidence of Hebrew. There, non-Akkadian phonological and morphological forms, as well as lexemes and personal and geographical names attested in cuneiform texts from Tell el-Amarna, are referred to as "(pre-biblical) Hebrew" (*passim*). In so doing, the *Encyclopaedia's* entry places this language in "the period from the mid-20th to the 13th centuries B.C.E." and even supposes that "the written evidence... reflects the Hebrew spoken in Palestine during the pre-biblical period" (Brovender 1972, 1560 = 2007,

¹ Cf. there also the references to older literature in fn. 5, where Pardee lists references for the identification of the language as Canaanite.

² Cf. Misgav, Garfinkel, and Ganor (2009a, 254): "we can refer to this inscription as the most ancient Hebrew inscription known to us" (the Hebrew version of the article has a less resolute formulation [2009b, 121]: גם פועל זה, אפוא, מצביע על שפתה העברית של הכתובת); "this inscription is the earliest known text written in Hebrew" (255; the Hebrew version here, too, has a less emphatic formulation: זהו הטקסט הראשון מתחילת תקופת הברזל II הכתוב עברית [122]). Cf. the criticism of such assertions in Millard (2011, 12); Rollston (2011).

620). Both formulations are misrepresentations due to linguistic and historical anachronisms they contain. The non-Akkadian evidence from the Amarna texts is best designated as Canaanite, as it had been termed before and continues to be defined after Brovender’s entry. Consulting the entry, one is amazed to read about “the earliest stage of Hebrew” written “in non-Hebrew syllabaries” (Brovender 1972, 1561 = 2007, 621). More confusing is the fact that the appellation “Canaanite” is also used there side by side with the designation “pre-biblical Hebrew.” This rather adventurous equation of the language of the Amarna texts with Hebrew might have found support in the existence of the verbal form *hi-ih-bi-e* ‘he has hidden’ attested in the letter of Mut-Ba’lu of Pella (no. 256:7), a form that was equated with the Hebrew form *הִתְחַבֵּי* at least as early as 1909 (Böhl 1909, 84; Albright 1943, 11, fn. 19; Cochavi-Rainey 2013, 97), and which Brovender (1972, 1566 = 2007, 624) described as “clearly a Hebrew form which is impossible in Akkadian.”

Today, however, no serious study would equate any kind of West Semitic linguistic record from the second millennium BCE with Hebrew, unless there are distinctive Hebrew lexical features or morphological innovations in the evidence at hand.³ Therefore, Cochavi-Rainey (2013), while giving a short comparison be-

³ However, in a newspaper article on the Amorite language the latter is described as “a kind of Hebrew” (cf. *Haaretz* from 20 January 2023 at <https://www.haaretz.com/archaeology/2023-01-20/ty-article/two-3-800-year-old-cuneiform-tablets-found-in-iraq-give-first-glimpse-of-hebrew-precursor/00000185-ca23-d3a8-a3cf-cf3326430000>).

tween Amarna Canaanite and Hebrew, describes the Ancient Canaanite forms as “cognate with Hebrew” (96), “related to... Hebrew,” “West Semitic in origin” (97), and “paralleled in Biblical Hebrew” (98).

It should also be mentioned that the term ‘pre-biblical Hebrew’ is imprecise in the present context, since it contrasts putative Hebrew data with the Hebrew language of the Bible, the (oldest) texts of which cannot be precisely dated, thus removing any basis for temporal comparison. The term might at the most assert that the data in dispute differs from the language of the Bible, but the scarcity of pre-biblical Hebrew linguistic data does not allow for detailed statements about the character of the pre-biblical idiom.

1.0. Newly Discovered Amorite–Akkadian Bilingual Texts

While there is no evidence of ‘pre-biblical’ Hebrew documenting the existence of Hebrew in the second millennium BCE, there are new pieces of evidence for West Semitic from the beginning of the millennium. This evidence is of great interest not only for Amorite and general Semitic studies, but also for *Hebraistik*, as will be demonstrated below. Generally, examples of West Semitic attested in the Akkadian texts are designated as ‘Amorite’, and the usage of this designation is justified as long as we can find no linguistic features within the evidence at hand that should be assigned to another language or dialect (see Golinets 2018, §3.1, 9–11; §6.1.1.2.3, 32–34, §6.1.2, 41; §6.3.3.4, 54; §6.3.5, 56–57; §6.3.9, 59).

Until recently, our knowledge of Amorite was limited to Amorite loanwords in Akkadian (Streck 2000, 82–130) and to Amorite personal and geographical names attested in cuneiform texts (Gelb 1980; Streck 2000; Golinets 2018). At the end of 2022, in an article entitled ‘Two Remarkable Vocabularies: Amorite–Akkadian Bilinguals!’ (henceforward TRV), Andrew George and Manfred Krebernik published two Amorite–Akkadian bilingual texts that contain names of West Semitic deities as well as Amorite words and phrases. The discovery of the bilinguals is both unsurprising and sensational. It is unsurprising, because many bilingual texts of ancient Near Eastern cultures are known to us. Given the attention of the speakers of Sumerian, Akkadian, Hittite, Hebrew, and other ancient oriental languages to the reality of multilingualism,⁴ it stands to reason that ancient scribes might have recorded some examples of (spoken) Amorite. The find is sensational, because after the discovery of Amorite personal names in 1884 (Delitzsch 1884, 70–73), it took almost 140 years to find (short) Amorite texts, and because the latter offer scholars the oldest known examples of West Semitic phrases. Since the texts are written in cuneiform, the vocalism of the language is recorded—an advantage of which scholars of unvocalised ancient West Semitic languages, such as Ugaritic, Phoenician, ancient Hebrew, ancient Aramaic, etc., can only dream. So

⁴ On multilingualism in the Ancient Near East, cf. Tavernier (2018); Hasselbach-Andee (2020); Jonker, Berlejung, and Cornelius (2021); George and Krebernik (2022, 148, fns 47 and 48, where further literature on the subject is cited). See Streck (2000, 76–80) for primary sources about the knowledge of Amorite.

spectacular was the discovery that the publication title ends with an exclamation mark—a feature rarely found in the titles of scholarly publications and rather rarely used at the end of a declarative clause.

The Akkadian of the bilinguals belongs to the Old Babylonian dialect, which, together with the layout and the script of the tablets, points to the Old Babylonian period (ca. 2000–1600 BCE) as the time of the text production, and they may even be the work of the same scribe (TRV 113–114). The first tablet, which belongs to the Jonathan and Jeanette Rosen Cuneiform Collection (Number CUNES 50-11-020; here no. 1), contains names of deities (lns 1–10), names of stars or constellations (lns 11–13), names of foodstuffs (lns 14–18), names of clothes (lns 19–21), and phrases (lns 22–31). The second tablet, from a private collection in London (here no. 2), features 25 lines, which contain “phrases drawn from social intercourse” (TRV 114). The words and phrases written in the right-hand column explain in Akkadian words and phrases written in the left-hand column. There is no Akkadian counterpart to lns 22b–26 in the first text. Some signs on both tablets are broken, rendering the text incomplete.

Since the Akkadian part of the texts translates the Amorite phrases very closely, and the word order of the translation corresponds to the word order of the source text (TRV 140–141, 147), it is not difficult to understand the Amorite text. Many phonological, morphological, syntactic, and lexical features in the source text are of interest for Hebrew and Semitic grammar and lexicography. In what follows, some of the lexical items are discussed.

2.0. Lexical Analysis

2.1. *bikrāt* and בִּכּוּרִים

In 2:22, the Amorite phrase *bi-ik-ra-ti-ia za-ba-a-ḥa ana DIĜIR-ia la-am-ṯi-l-in* is translated into Akkadian as *nīqam*(SÍSKUR) *a-na ili*(DIĜIR)-*ia lu-ud-di-in* ‘I will make a sacrifice to my god’. Two terms for sacrifice feature in the Amorite phrase. While the noun **dabāḥ*⁵ ‘slaughter offering’, derived from the verb *DBḤ*, which is attested in all branches of the Semitic language family, is not especially noteworthy,⁶ the term *bikrāti-ya* ‘my offerings’ is worthy of comment. The noun is plural, which is obvious due to the form *-ya* of the 1SG suffix pronoun. This allomorph of the suffix pronoun *-ī* is also attested in the form *ra-ḥa-a-a /raṣay-ya/* ‘my friends’ (2:16; cf. TRV 127). Thus, the Amorite plural noun *bikrāt-*, derived from the Semitic noun **bVkr*, reflexes of which are attested in all branches of Semitic,⁷ and which the editors (TRV 128) compare with the Hebrew noun בִּכּוּרִים ‘early fruits, first fruits’, features the same morphological form as the Hebrew

⁵ The form *za-ba-a-ḥa* is accusative with adverbial function; cf. “I will give *bikrāti-ya* as a sacrificial offering” (TRV 128).

⁶ From a morphological perspective, it is worth observing that the *plene* orthography *za-ba-a-ḥa* suggests the morpheme *qatāl*, which is used *inter alia* as a derivational pattern for infinitives in Semitic languages (cf. Fox 2003, 179–86).

⁷ Cf., e.g., Leslau (1987, 94). The Arabic noun has the vowel /i/, while Akkadian, Jewish Palestinian Aramaic, and Jewish Babylonian Aramaic (Sokoloff 1992, 87; 2002, 190) feature the vowel /u/, which may have resulted from vowel assimilation to the labial /b/.

noun, although in another gender. Besides the morphological similarity, there is also semantic proximity between the two terms, since the Hebrew expression מִנְחַת בְּכוֹרִים ‘first-fruit offering’ (Lev. 2.14 [2x]) also puts the term ‘first fruits’ in the context of ‘offerings’.

2.2. *kēmat* and כִּמָּה

In 1:11, the Amorite constellation name *ke-e-ma-at* /*kēmat*/ is translated by Akkadian *ḏa-ap-pu* ‘mane’ in the sense of ‘Pleiades’ (TRV 115). The Amorite term corresponds to the Biblical Hebrew (= BH) and Syriac *kīmā* (TRV 119). The etymologically related Akkadian noun *kīmtu* ‘family’⁸ does not have the meaning that is attested in the West Semitic languages. The Eblaitic noun *kā-ma-tū* /*kaymatu*/ (TRV 119) has the same meaning as its Amorite, Hebrew, and Syriac cognates. This lexeme is not frequently used in the ‘classical periods’ of later attested languages,⁹ so it is interesting to find its attestation in a West Semitic language¹⁰ ca a

⁸ Civil et al. (1971, 376), with a short /i/. The vowel /i/ is assessed by George and Krebernik (2022, 119) as long probably due to the long vowel of the Amorite, Hebrew, and Syriac cognate.

⁹ Cf. Amos 5.8; Job 9.9; 38.31; and Sokoloff (2009, 619) for Syriac. In Hebrew, the word is also attested in rabbinic period: cf. Midrash *Seder Olam Rabba*, ch. 4 (manuscripts Parma, Bibliotheca Palatina 2298; Oxford, Bodleian Library 692); b. Brachot, *mishna* 2 (manuscript Oxford, Bodleian Library 366); p. Taanit, *mishna* 3 (manuscript Leiden, Bibliothek der Rijksuniversiteit, Scaliger 3), and other attestations (to be found on the internet site of *The Historical Dictionary of the Hebrew Language* at <https://maagarim.hebrew-academy.org.il>).

¹⁰ If one does not count Eblaitic as West Semitic.

millennium earlier than its first Hebrew attestation. The Amorite form with its Akkadian translation supports the meaning of the Hebrew word.

2.3. *sābu* and סָבָא

In 1:17, the Amorite name of a beverage *sà-a-bu* is explained ideographically as *karānum*(ĜEŠTIN) ‘wine’ (TRV 116, 120). The Amorite noun *sābu* corresponds to the Hebrew noun **sub*’ (Tiberian **/sōḇe/*) attested in the construct forms סָבָאָה (Isa. 1.22), סָבָאָם (Hos. 4.18), and וַיִּסְבְּעָם (Nah. 1.10), from which the verb סָבַע* ‘quaff’ is derived (Stamm 1995, 697; so, tentatively, Donner 2007, 868). The /a/ vowel of the Amorite noun makes clear that the word is not a borrowing from Akkadian, since in the latter the etymologically corresponding noun is *sību* ‘beer’ (Brinkman et al. 1971, 231; von Soden 1972, 1000). The existence of the Amorite lexeme suggests that the explanation of the Hebrew term in *KAHAL* (370; 374 in second edition) as an Akkadian loan is incorrect and that the word is genuine Hebrew. Von Soden (1972, 1000) compared the Akkadian verb *sābum* ‘draw beer’ to the verb Š’B ‘draw or carry water (from a spring or a well)’ attested in Ugaritic, Hebrew, Sabaean, Arabic (‘drink enough’), and Ethiopian (‘drag, pull, follow’). In the light of Amorite and Hebrew attestations of the verb SB’, it can be suggested that the basic form of the Akkadian verb was *sabû*. Attestations of forms with the auslaut /a/ support this assumption (von Soden 1972, 1000).

If the assumption is correct, then Akkadian *sibu* should be transcribed as *sibu*.¹¹

2.4. **šahr* and שָׁהַר

In 2:21, the Amorite phrase *šar-ra-me-ḥa-da lu-uš-ba-am-ma* is translated into Akkadian as *warḥam*(ITI.DA) *ištēn*(DIŠ) *i-na āli*(URU)-*ia lu-uš-ba-[am]* ‘I will stay one month here in my town!’ (TRV 117). The form *šar-ra-me-ḥa-da* /*šāram* = (ʔ)*eḥada*/ or /*šar-ram* = (ʔ)*eḥada*/ is a sandhi spelling for **šahram* ‘month’ and **yaḥada* ‘one’ (both in accusative) with the loss or assimilation of /h/ in the first word and with possible reduction *yi-* > *ye-* > (ʔ)*e-* in the second word (TRV 128–29; cf. Streck 2002, 187–91 on this sound change). The noun **šahr* has equivalents in Syriac *sahrā* and Arabic *šahr* ‘month’ (Sokoloff 2009, 974; Lane 112), as noticed by the editors (TRV 128). The original meaning of the Semitic noun **šahr* is ‘moon’, as it is attested in the ancient Aramaic deity name *Šhr* (Donner and Röllig 1962; 1964, nos 225:2; 226:1, 9). The meaning ‘moon’ and not ‘month’ is proven, first, by the fact that the noun designates a deity and, second, by the existence of the collocation *šhr wšmš* ‘the Moon and the Sun’ (Donner and Röllig 1962; 1964, nos 225:9; 258:5; 259:4) as well as *wšmš wšhr* ‘and the Sun, and the Moon’ (Donner and Röllig 1962; 1964, no. 202B 24). In Ethiopian, *šāhr* means ‘moon, first day of the month’ (Leslau 1987, 528), and similarly in Sabaeen *s²hr* designates ‘beginning of month’ (Beeston et al. 1982, 132), i.e., a new moon.

¹¹ A singular instance of the *plene* orthography *si-i-bu* (Brinkman et al. 1971, 231; von Soden 1972, 1000) thus requires an explanation.

While the etymological explanation of the BH plural noun שְׁהַרְגִּים (Judg. 8.21, 26; Isa. 3.18) ‘(half)moon-shaped embellishments, *lunula*’, was ‘uncertain’ to Stamm (1995, 1222), the attestation of the Amorite noun proves that the Hebrew *qaṭlōn* form derives from the ancient West Semitic lexeme with the meaning ‘moon’. This meaning lived on in medieval Hebrew in the noun סְהַר (Even-Shoshan 2003, 1267),¹² which underwent orthographic adaptation (ש > ס) following the phonetic change from /ś/ to /s/.

2.5. *ṣinīpt* and צִנִּיף

In 1:19, the Amorite garment name *ṣi-¹ni-ip-tum*¹ is equated with ^{túg}*paršigum*(BAR.SI) ‘headscarf’ (TRV 115, 120). The word in the left column corresponds to the Hebrew noun צִנִּיף (< **ṣanīp*) with the same meaning. While etymologically related lexemes are attested in other Semitic languages,¹³ their meaning differs from the meaning of the Amorite and the Hebrew words. The antiquity

¹² The form *saharon* is also attested in medieval Hebrew and in Modern Hebrew in the same meaning as in BH (Even-Shoshan 2003, 1267). For medieval attestations, see also the internet site of *The Historical Dictionary of the Hebrew Language* at <https://maagarim.hebrew-academy.org.il>. The forms סְהַרְוֹן and שְׁהַרְוֹן are also attested in Modern Hebrew with the meaning ‘croissant’ (Even-Shoshan 2003, 1267, 1849).

¹³ Jewish Palestinian and Babylonian Aramaic *ṣānpā* ‘corner, fringe’ (Sokoloff 1990, 468; 2002, 969); Christian Palestinian Aramaic *ṣnp*’ (Sokoloff 2014, 357); Arabic *ṣinfat* ‘fringe, border’ (Lane 1735); Ge‘ez *ṣə/anf* ‘rim, border, edge, fringe, margin, hem, end, side, extremity, outskirts, confines’ (Leslau 1987, 559); cf. BH מְצַנְפָּת ‘headband like a turban’ (Stamm 1995, 590).

of the nominal lexeme supports the view that the Hebrew verbal root קָנַח ‘to wrap around, wrap together’ is derived from the corresponding substantive (*KAHAL* 481 = 485 in the second edition) and not vice versa (cf. Stamm 1995, 973; Donner 2009, 1126).

2.6. *yayn* and יַיִן

In 2:6, the Amorite phrase *ia-a-a-nam si-qí-ni-a-ti* is translated *karānam*(ĠEŠTIN) *ši-ṛqí-ni-a-ti*¹ ‘Pour us wine!’ (TRV 116). The attestation of the noun **yayn* is of great importance, since it sheds new light on an old *crux interpretum*, namely the question of whether the West Semitic word for ‘wine’ is of Indo-European or Semitic origin. Stamm (1995, 391), following Koehler and Baumgartner (1953, 379) and Rabin (1963, 138), explained the Hebrew word יַיִן and its underlying Semitic lexeme as a loan from Hittite. Donner (1995, 462) assessed the Hebrew word as an “indogerman.” loan.

The present writer, while working on the etymological entries for *KAHAL*, followed the aforementioned and other scholars (e.g., Gamkrelidze and Ivanov 1984, 650) in the etymological explanation of Hebrew יַיִן as a loanword from “Indo-European” (*KAHAL* 214). Some time after the dictionary went into print, the author became aware of the article by Illich-Svitych (1964), where 24 Indo-European lexical items with presumed phonetic and semantic cognates in Semitic languages are discussed. Illich-Svitych finds that none of the twenty-four words, including what

he reconstructs as **u(o)ino-* ‘wine’ (5), “could not be etymologised by proper Indo-European means” (8).¹⁴ Further, he finds that the root structure of a number of words does not conform to Indo-European types. This includes **u(o)ino-*, since it features two “sonants” in contact position. Illich-Svitych concludes that the words he lists are best explained as Semitic loans into Indo-European languages (8–9). To amplify the notion of absence of an Indo-European etymology for **w/yayn*, the fact should be emphasised that the oldest Indo-European cognates for ‘wine’ are confined to the Anatolian languages Hittite, cuneiform and hieroglyphic Luwian, as well as to Greek, Latin (see Beekes 1987, 22, for attestations from Italic languages), Armenian, and Albanian (Kloekhorst 2008, 1012). All these languages are attested in geographically close areas (Latin might have borrowed the word from Greek or another neighbour language), which makes the attestation of this lexeme a local isogloss within the Indo-European family.¹⁵

Alongside the grounds for rejecting the theory that **w/yayn* is an Indo-European loanword in Semitic, there are arguments in favour of seeing it as a genuine Semitic lexeme. Without delving into the history of etymological interpretation of **w/yayn* and into a review of scholarly literature, the following reasons may be mentioned:

¹⁴ In the original: “не этимологизируется собственно индоевропейскими средствами.”

¹⁵ Cf. Gamkrelidze and Ivanov (1984, 653–54) on the absence of Indo-Iranian cognates for Indo-European **u(e/o)ino-* (in the reconstruction of these scholars; cf. 648).

1. The lexeme is broadly attested in Central and South Semitic languages: in Amorite, Canaanite (*ye-nu*); Ugaritic, Phoenician, and Ammonite (*yn*); Hebrew; Sabaeen and Qatabanian (*wyn*); Arabic and Ge'ez (*wayn*) (see Kogan 2015, 313–14 for attestations).
2. Phonologically, the form **wayn* perfectly fits Semitic sound rules. The Sabaeen, Qatabanian, Arabic, and Ge'ez form *(*)wayn* represents the oldest form of the lexeme. The North-West Semitic sound change of word-initial /w/ to /y/ occurred in Amorite, Ugaritic, and the Canaanite languages. The Amorite evidence¹⁶ suggests that this sound change was already—or at the earliest—operative in the first half of the second millennium BCE.
3. The meaning of the Sabaeen and Qatabanian ('vineyard'), Arabic ('black grapes'), and Ge'ez ('vine, wine, grapes') cognates suggests that the original meaning of the Semitic lexeme was 'vine' and that it later evolved to 'vineyard' and to 'wine', following the semantic development from a floral term, through the name of place where it was grown (by metonymy), to the name of product (by further metonymy).¹⁷

Due to the considerations described above, the present writer dismissed in the second edition of *KAHAL* (216) the Indo-European etymology of קַח and explained it as "zentralsem. **wayn*." The

¹⁶ Cf. TRV 129 (also in the cardinal number **yaḥad*; cf. section **šahr* and שָׁהַר* above).

¹⁷ Illich-Svitych (1964, 9) already mentions the latter semantic change.

newly found Amorite evidence makes the attestation of the Semitic lexeme at least as old as the Hittite records (Kloekhorst 2008, 1012), undermining any chronological argument on the loan direction. However, the Hieroglyphic Luwian forms starting with *wi-* (Kloekhorst 2008, 1012) may indicate that the Semitic word was borrowed into this language before the West Semitic sound change /w/ > /y/ occurred.

Other lexemes attested in the Amorite portions of the bilinguals, although having cognates in Hebrew and other languages, offer nothing new for Hebrew lexicography. However, their attestations expand our knowledge of the basic Amorite lexicon. To this category belong such lexemes as the nouns **laḥm-* (*la-aḥ-ma-am*) ‘bread’ (2:4, cf. 1:16), **malik-* (*ma-li-kum*; *mal-li-ki*) ‘king’ (2:18, 25; 2:20), **mal’ak-* (*ma-al-ḥa-kum*) ‘messenger’ (2:19), **na’l-* (*na-ḥa-lu*) ‘shoe’ (1:21), **pa‘m-* (*pa-aḥ-ma{x}-a*) ‘foot’ (2:25), **ṭulḥān-* (*ṣu-ul-ḥa-nam*) ‘table’ (2:5, 7). There are also a number of Amorite verbs attested in the text, but these lie beyond the scope of the present brief study. It should only be mentioned that George and Krebernik’s analysis of the form *Ku-ú* (translated into Akkadian as *i-zi-iz* ‘Stand ready!’, 2:2) as an imperative of the verb QWM (or KWN) gains support from the observation that the sign *Ú* at the end of lexemes in Amorite personal names expresses the sound /uw/ or the nasalised sound /ũ/ that developed from syllable-final /um/ (Golinets 2010). The form *Ku-ú* can, then, be normalised as *qūm*.

References

- Albright, William Foxwell. 1943. 'Two Little Understood Amarna Letters from the Middle Jordan Valley'. *Bulletin of the American Schools of Oriental Research* 89: 7–17.
- Beekes, R. S. P. 1987. 'On Indo-European "wine"'. *Münchener Studien zur Sprachwissenschaft* 48: 21–26.
- Beeston, A. F. L., M. A. Ghul, W. W. Müller, and J. Ryckmans. 1982. *Sabaic Dictionary (English-French-Arabic)*. Louvain-la-Neuve: Peeters and Beirut: Librairie du Liban.
- Böhl, Franz M. Th. 1909 [1968]. *Die Sprache der Amarnabriefe mit besonderer Berücksichtigung der Kanaanismen*. Leipziger semitische Studien 5/2. Leipzig: J. C. Hinrichs (reprinted Leipzig: Zentralantiquariat der DDR).
- Brinkman, John A., Miguel Civil, Ignace J. Gelb, A. Leo Oppenheimer, and Erica Reiner (eds). 1984. *The Assyrian Dictionary of the University of Chicago. Volume 15*. S. Chicago, IL: Oriental Institute and Glückstadt: J. J. Augustin.
- Brovender, Chaim. 1972 [2007]. 'Hebrew Language, Pre-Biblical'. In *Encyclopaedia Judaica. Volume 16. Ur-Z. Supplementary Entries*, 1560–1568. Jerusalem: Encyclopaedia Judaica (reprinted in *Encyclopaedia Judaica*, 2nd edition, edited by Michael Berenbaum and Fred Skolnik, 8:620–25. Detroit: Macmillan Reference USA).
- Civil, Miguel, Ignace J. Gelb, A. Leo Oppenheimer, and Erica Reiner (eds). 1971. *The Assyrian Dictionary of the University of Chicago. Volume 8. K*. Chicago, IL: Oriental Institute and Glückstadt: J. J. Augustin.

- Cochavi-Rainey, Zipora. 2013. 'Amarna Canaanite and Hebrew'. In *Encyclopedia of Hebrew Language and Linguistics*, edited by Geoffrey Khan et al., 1:96–98. Leiden: Brill.
- Delitzsch, Friedrich. 1884. *Die Sprache der Kossäer: Linguistisch-historische Funde und Fragen*. Leipzig: J. C. Hinrichs.
- Donner, Herbert (ed.). 1995. *Wilhelm Gesenius hebräisches und aramäisches Handwörterbuch über das Alte Testament*. 18. Auflage. 2. Lieferung ט–י. Berlin: Springer.
- . 2007. *Wilhelm Gesenius hebräisches und aramäisches Handwörterbuch über das Alte Testament*. 18. Auflage. 4. Lieferung י–כ. Berlin: Springer.
- . 2009. *Wilhelm Gesenius hebräisches und aramäisches Handwörterbuch über das Alte Testament*. 18. Auflage. 5. Lieferung כ–ש. Berlin: Springer.
- Donner, Herbert, and Wolfgang Röllig. 1962 [2002]. *Kanaanäische und aramäische Inschriften. Band I. Texte*. Wiesbaden: Harrassowitz (2nd, revised and expanded edition, 1966; 5th expanded and corrected edition).
- . 1964 [1968]. *Kanaanäische und aramäische Inschriften. Band II. Kommentar*. Wiesbaden: Harrassowitz (2nd, revised and expanded edition).
- Even-Shoshan, Avraham. 2003. *Milon 'Even-Shoshan*. Jerusalem: Ha-Milon He-Ḥadash.
- Fox, Joshua. 2003. *Semitic Noun Patterns*. Harvard Semitic Studies 52. Winona Lake, IN: Eisenbrauns.
- Gamkrelidze, T. V., and V. V. Ivanov. 1984. *Indo-European and the Indo-Europeans: A Reconstruction and Historical Typological Analysis of a Protolanguage and a Proto-Culture, Part*

- Two). Tbilisi: Publishing House of the Tbilisi State University. [Russian]
- Gelb, Ignace J. 1980. *Computer-Aided Analysis of Amorite*. With the assistance of Joyce Bartels, Stuart-Morgan Vance, Robert M. Whiting. Assyriological Studies 21. Chicago: The Oriental Institute of the University of Chicago.
- Gibson, John C. L. 1971. *Textbook of Syrian Semitic Inscriptions: Vol I. Hebrew and Moabite Inscriptions*. Oxford: Clarendon.
- Golinets, Viktor. 2010. 'Amorite Names Written with the Sign Ú and the Issue of the Suffixed Third Person Masculine Singular Pronoun in Amorite'. In *Proceedings of the 53e Rencontre Assyriologique Internationale. Vol. I. Part 2: Language in the Ancient Near East—Papers outside the Main Subjects*, edited by L. Kogan, N. Koslova, S. Loesov, and S. Tishchenko, 593–616. Babel und Bibel 4. Orientalia et Classica 30. Winona Lake, IN: Eisenbrauns.
- . 2018. *Verbalmorphologie des Amurritischen und Glossar der Verbalwurzeln: Das amurritische Onomastikon der altbabylonischen Zeit, Vol. 2. Alter Orient und Altes Testament 271/2*. Münster: Ugarit Verlag.
- Hasselbach-Andee, Rebecca. 2020. 'Multilingualism and Diglossia in the Ancient Near East'. In *A Companion to Ancient Near Eastern Languages*, edited by Rebecca Hasselbach-Andee, 457–70. Hoboken, NJ: Wiley and Blackwell.
- Illich-Svitych, V. M. 1964. 'The Earliest Indo-European–Semitic Language Contacts'. In *Problems of Indo-European Linguistics. Studies in Comparative Grammar of the Indo-European*

- Languages*, edited by V. N. Toropov, 3–12. Moscow: Nauka. [Russian]
- Jonker, Louis C., Angelika Berlejung, and Izak Cornelius (eds). 2021. *Multilingualism in Ancient Contexts: Perspectives from Ancient Near Eastern and Early Christian Contexts*. Stellenbosch: SUN PreSS.
- KAHAL = Dietrich, Walter, and Samuel Arnet (eds). 2019 [2013]. *Konzise und aktualisierte Ausgabe des Hebräischen und Aramäischen Lexikons zum Alten Testament*. Leiden: Brill (2nd revised edition).
- Kloekhorst, Alwin. 2008. *Etymological Dictionary of the Hittite Inherited Lexicon*. Leiden: Brill.
- Koehler, Ludwig, and Walter Baumgartner. 1953 [1998]. *Lexicon in Veteris Testamenti libros: A Dictionary of the Hebrew Old Testament in English and German*. Leiden: Brill (Editio photomechanice iterata cui adjectum est supplementum, 1958; reprinted 1985; reprinted as *A Bilingual Dictionary of the Hebrew and Aramaic Old Testament*).
- Kogan, Leonid. 2015. *Genealogical Classification of Semitic: The Lexical Isoglosses*. Berlin: De Gruyter.
- Koller, Aaron. 2013. ‘Ancient Hebrew מַעְצָר and עֶצֶר in the Gezer Calendar’. *Journal of Near Eastern Studies* 72: 179–93.
- Lane = Lane, E. W. 1863–1893 [1955–1956]. *Arabic–English Lexicon*. London: Williams and Norgate (Reprint New York: Frederick Ungar).
- Leslau, Wolf. 1987. *Comparative Dictionary of Ge‘ez (Classical Ethiopic)*. Wiesbaden: Harrasowitz.

- Millard, Allan. 2011. 'The Ostrakon from the Days of David Found at Khirbet Qeiyafa'. *Tyndale Bulletin* 62: 1–13.
- Misgav, Haggai, Yosef Garfinkel, and Saar Ganor. 2009a. 'The Ostrakon'. In *Khirbet Qeiyafa Vol. 1: Excavation Report 2007–2008*, edited by Y. Garfinkel and S. Ganor, 243–57. Jerusalem: Israel Exploration Society.
- . 2009b. 'The Khirbet Qeiyafa Ostrakon'. In *New Studies in the Archaeology of Jerusalem and Its Region: Collected Papers* 3, edited by D. Amit, G. D. Stiebel, and O. Peleg-Barkat, 111–23. Jerusalem: Israel Antiquities Authority and the Institute of Archaeology, The Hebrew University of Jerusalem. [Hebrew]
- Naveh, Joseph. 1982 [1987]. *Early History of the Alphabet: An Introduction to West Semitic Epigraphy and Paleography*. Jerusalem: Magnes (2nd revised edition).
- Pardee, Dennis. 2013. 'A Brief Case for Phoenician as the Language of the "Gezer Calendar"'. In *Linguistic Studies in Phoenician Grammar: In Memory of J. Brian Peckham*, edited by Robert Holmstedt and Aaron Schade, 226–46. Winona Lake, IN: Eisenbrauns.
- Rabin, Chaim. 1963. 'Hittite Words in Hebrew'. *Orientalia* 32: 113–39 (Hebrew version published as 'Milim Ḥitiot be-'Ivrit' in *Studies in the Bible Presented to Professor M. H. Segal by his Colleagues and Students*, edited by J. M. Grintz and J. Liver, 151–79. Publications of the Israel Society for Biblical Research 17. Jerusalem: Kiryat Sefer).

- Renz, Johannes. 1995. *Die althebräischen Inschriften, Teil 1: Text und Kommentar*. Handbuch der althebräischen Epigraphik 1. Darmstadt: Wissenschaftliche Buchgesellschaft.
- . 1995. *Die althebräischen Inschriften, Teil 2: Zusammenfassende Erörterungen, Paläographie und Glossar*. Handbuch der althebräischen Epigraphik 2/1. Darmstadt: Wissenschaftliche Buchgesellschaft.
- Rollston, Christopher. 2010. *Writing and Literacy in the World of Ancient Israel: Epigraphic Evidence from the Iron Age*. Archaeology and Biblical Studies 11. Atlanta: Society of Biblical Literature.
- . 2011. ‘The Khirbet Qeiyafa Ostrakon: Methodological Musings and Caveats’. *Tell Aviv* 38: 67–82.
- von Soden, Wolfram. 1972. *Akkadisches Handwörterbuch. Band II. M–S*. Wiesbaden: Harrassowitz.
- Sokoloff, Michael. 1990 [2002]. *A Dictionary of Jewish Palestinian Aramaic of the Byzantine Period*. Dictionaries of Talmud, Midrash and Targum 2. Ramat-Gan: Bar Ilan University Press and Baltimore: The Johns Hopkins University Press (2nd edition).
- . 2002b. *A Dictionary of Jewish Babylonian Aramaic of the Talmudic and Gaonic Periods*. Dictionaries of Talmud, Midrash and Targum 3. Ramat-Gan: Bar Ilan University Press and Baltimore: The Johns Hopkins University Press.
- . 2009. *A Syriac Lexicon: A Translation from the Latin, Correction, Expansion, and Update of C. Brockelmann’s Lexicon Syriacum*. Winona Lake, IN: Eisenbrauns and Piscataway, NJ: Gorgias.

- . 2014. *A Dictionary of Christian Palestinian Aramaic*. Orientalia Lovaniensia Analecta 234. Leuven: Peeters.
- Stamm, Johann Jakob (ed.). 1995. *Hebräisches und aramäisches Lexikon zum Alten Testament von Ludwig Koehler und Walter Baumgartner*, 3rd edition. Leiden: Brill.
- Streck, Michael P. 2000. *Die Amurriter: Die onomastische Forschung. Orthographie und Phonologie—Nominalmorphologie*. Das amurritische Onomastikon der altbabylonischen Zeit 1. Alter Orient und Altes Testament 271/1. Münster: Ugarit-Verlag.
- Tavernier, Jan. 2018. 'Multilingualism in the Elamite Kingdoms and the Achaemenid Empire'. *Multilingualism, Lingua Franca and Lingua Sacra*, edited by Jens Braarvig and Markham J. Geller, 307–20. Max Planck Research Library for the History and Development of Knowledge, Studies 10. Berlin: Max Planck Institute for the History of Science.
- TRV = George, Andrew, and Manfred Krebern timer. 2022. 'Two Remarkable Vocabularies: Amorite–Akkadian Bilinguals!' *Revue d'Assyriologie* 116: 113–66.

INDEX

- ‘Abdul-Mun‘im, Sāmi, 684
 abecedaries, 493, 500
 ablative, 695, 698, 700 n. 7,
 703, 709 n. 33, 724–25,
 730, 741
 abstract, 172–75, 177–80, 306,
 311, 315, 318, 319 n. 37,
 322, 496, 705
 Abulafia, R. Meir ben Todros
 Ha-Levi, 430
 Academy of the Hebrew Lan-
 guage, 233, 363, 475, 645 n.
 27, 846 n. 3
 accents, 119–20, **189–221**, 456,
 470–71, 586 n. 19, 590,
 821–22, 825–26, 828
 conjunctive accents, 120 n.
 7, 197–98, 201–3, 207–14,
 415
 disjunctive accents, 120,
 197–98, 202–3, 205, 210,
 212, 214
 accusative, 538, 556, 617–18,
 754 n. 10, 787, 843, 846
 Achaemenids, 753, 773, 777–
 78, 782, 788–89
 acrostic, 493, 496–97, 504, 511
 adjunct, 88 n. 50, 720, 743
 Aeneid, *see* Virgil
 Africa, 259, 262, 491, 529
 agentive, 529, 532–33, 535,
 537, 539, 545, 698 n. 4
 Aḡmātī, R. Zecharia ben Ye-
 huda, 430–31
 Agobard of Lyon, 502
 Akkadian, 104, 111, 139 n. 5,
 150, 368 n. 10, 397, 533–
 34, 535 n. 9, 538 n. 15, 557,
 614–15, 621, 633, 634 n. 5,
 636–37, 641–42, 644–47,
 649 n. 39, 650–51, 652 n.
 42, 777–78, 788–89, **879–**
 93
 Assyrian, 649
 Babylonian, 543, 649, 778
 Neo-Assyrian (NA), 150, 644
 Neo-Babylonian, 150
 Old Akkadian (Oakk), 368
 n. 10, 631, 637, 649
 Old Assyrian (OA), 534,
 631, 637
 Old Babylonian (OB), 542,
 631, 638 n. 11, 736
 Akko, 249–50
 al-Bandanijī, 506
 al-Farahidi, al-Khalīl ibn Aḥmad,
 505
 al-Fāsī, David, 507, 509–10
 al-Karkhī, ‘Abbūd, 681–84
 al-Zamakhsharī, 506
 Alexander, 671, 776

- Alexandria, 498–99
 Algeria, 241–42, 507, 588
 allative, 413–14
 alliteration, 209
 allomorph, 619, 621, 748 n. 2
 alphabet, 243, 362, **491–527**
 Amarna, 8–9, 22–24, 26, 29, 55–56, 788. *See also* Canaanite
 American, 437, 492 n. 2, 683, 687, 690 n. 541, 691
 Amharic, 557–58. *See also* Ethiopic
 amoraim, 249
 Amorite, 533–35, **879–93**
 amulet, 578, 797–99, 813
 analogy, 57, 173, 175, 343, 619, 625, 636, 764, 778, 848
 anaphor, 15, 131, 139, 149, 152, 309–10
 Ancient Near East, 539, 783
 angel, 197, 370, 393, 541, 543, 707–8, 803, 805, 808, 811
 Anglicism, 245, 555
 Aphrahat, 504–5, 780
 apocalyptic, 544 n. 21
 apocopation, 826
 apodosis, 8–10, 12–13, 16–18, 21–27, 29–30, **69–97**
 approximant, 459, 468, 470
 Aquila, 373–74
 Arab, 437, 445, 643–46, 648–51, 662, 681
 Arabia, Arabian, 493, 678, 763–64, 789
 Arabic, 44, 104, 106, 144, 261–63, 385, 386 n. 3, 397, 399, 439–40, 442, 446–47, 461, 503, 505–6, 513, 534, 556–57, 566, 584, 588–90, 592–93, 596 nn. 37–38, 598, 600, 611, 612 n. 2, 613, 615–17, 619–22, 624–25, 631, 638, 641–46, 648–51, 652 n. 42, 662–64, 670, 681, 682 n. 512, 683, 685, 700, 708 n. 30, 720, **747–70**, 772–74, 789, **797–820**
 Classical Arabic, 137, 139, 144 n. 8, 147–48, 439, 446, 557, 588, 613–18, 620–21, 623–24, 643, 763, 778–80, 789
 Dhofari Arabic, 633 n. 3, 646 n. 30
 Iraqi Arabic, **681–94**
 Judaeo-Arabic, 460–61, 468, 510, 583, 588
 Modern Standard Arabic (MSA), 631, 643, 681, 684
 Moroccan Arabic, 558
 Old Arabic, 747, 764
 Palestinian Arabic, **421–53**, 591 n. 29
 Quranic Arabic, 104
 San‘ani Arabic, 669
 Standard Arabic, 798

- Yemeni Arabic, 675
- Arabism, 701 n. 8, 721 nn. 53–54, 759–60, 762
- Aramaeans, 778
- Aramaic, 50, 118, 141, 144, 150, 225 n. 5, 235, 368 n. 10, 385, 387, 397–99, 403, 408, 410–14, 416, 418–19, 442, 445–47, 467–68, 504, 505 n. 16, 578, 583, 592, 595, 611, 613, 616, 618, 619 n. 6, 621–23, 636, 641–47, 647 n. 36, 648–49, 651, 652 n. 42, **747–70**, **771–95**, 821–22, 841, **843–77**. *See also* Mandaic; Syriac
- Babylonian Aramaic, 418
- Biblical Aramaic (BA), 398, 580, 613, 616, 624, 853, 857, 859, 861–64
- Christian Aramaic, 444, 747, 781
- Christian Palestinian Aramaic (CPA), **747–70**, 845, 847–50, 852–53, 861, 864, 866, 869
- Early Aramaic, 411, 860
- Eastern Aramaic, 752 n. 7, 844
- Galilean Aramaic, 444
- Imperial Aramaic, 411, 777–78, 782
- Jewish Aramaic, 365, 418, 440 n. 12, 543, 634 n. 5, 773, 778–80, 782–84
- Jewish Babylonian Aramaic (JBA), 137 n. 3, 144, 631, 645, 648–49, 779, 798 n. 3
- Jewish Palestinian Aramaic (JPA), 747, 764, 779, **843–77**
- Late Aramaic, 444, 844, 855, 862
- Late Western Aramaic (LWA), 444, **843–77**
- Middle Aramaic, 783, 789–90, 850, 859, 862
- Nabataean Aramaic, 759, 762, 778, 784–85, 850
- Neo-Aramaic (NA), 7–8, 582, 584, 586 n. 19, 590–91, 595, 751, 772, 833–34, 837
- Barwar, 7–8, 834
- North-Eastern Neo-Aramaic (NENA), 6, 8–9, 16, 25 n. 24, 590 n. 27, 593 n. 34, 642 n. 22, 643 n. 23, 645, 648 n. 38, 782, 822, 836
- Ṭuroyo, 590 n. 27, 592 n. 33
- Urmi, 590–91, 598–99, 642 n. 22, 643 n. 23, 751 n. 4, 833–34
- Western Neo-Aramaic (WNA), 590, 748, 762
- Official Aramaic, 862

- Official Egyptian Aramaic (OEA), 853, 862, 864, 868
 Palestinian Aramaic, 144, 748, 750, 752, 872
 Proto-Aramaic, 619 n. 6
 Qumran Aramaic (QA), 850, 853, 857, 859, 861–64
 Samaritan Aramaic (SA), 44, 144, 444, 747, 764, **843–77**
 Western Aramaic, 747–48, 752 n. 7, 762, 786–87, 843–44, 849–51, 853–55, 860, 862–63, 865, 870
 Aramaism, 419, 442
 archaeology, 250, 433–34, 438, 485
 archaic, 20, 21 n. 18, 22 n. 20, 23, 26, 42–43, 56 n. 15, 118, 395, 535 n. 3, 595, 615–16, 619, 622
 archaism, 363, 594–95, 598–99, 611, 617, 772, 787–88
 archive, 417 n. 6, 497–98, 672–73, 784–85
 Aristotle, 492 n. 1, 756
 articulation, 225, 229–30, 232–33, 235, 247–48, 462, 506, 587–88, 675
 Ashkenazi, 232, 239, 429, 474, 595
 Assyrians, 777
 Assyrian Akkadian, *see under* Akkadian
 Assyrian Christians, 593, 598–99
 asyndesis, 22, 26, 29–30
 'atbaš cipher, 493
 auxiliary, 11, 111, 114, 279 n. 11, 404
 Avdima of Haifa, R., 225, 228, 250
 Babylonia, Babylonian, 191 n. 148, 373, 494, 540, 752, 777, 779, 782
 Babylonian Akkadian, *see under* Akkadian
 Babylonian reading tradition, *see under* Hebrew reading traditions
 background, 16–17, 19, 134, 137–39, 169, 171, 250, 294, 332, 373, 436, 458, 467 n. 9, 544 n. 21, 591, 753, 758, 797
 Baghdad, 469, 502, 507, 581, 587–88, 600, 682, 688 n. 530, 797–98
 Baltic, 558, 567–68
 bar Sisi, R. Levi, 225, 229, 233–35, 249–50
 Bavarian, 559
 Bedouin, 591, 684–91
 ben Abraham of Sens, R. Samson (ha-Rash), 427
 ben Asher, R. Jacob, 237
 ben Labrāṭ, Dunash, 509
 ben Saruq, Menaḥem, 507–9

- Ben Sira, 50 n. 12, 53, 412
 ben Yehi'el, Nathan, 429, 432
 benefactive, 335, 344–45, 530
 n. 2
 Berber, 789
 Bereshit Rabbah, *see* Genesis
 Rabbah
 Bible, 58, 104, 106, 158–60,
 162–63, 179, 181–82, 209,
 233, 365, 404, 405 n. 1,
 479–88, 511, 560, 755,
 780–81, 787, 790, 823. *See*
 also Hebrew Bible; New Tes-
 tament
 biblicism, 487
 biform, 137, 367–68, 856–58,
 861–66, 869
 bilingual, 533, 698 n. 4, 750,
 755–56, 785, **879–93**
 bishop, 162, 750, 780–81
 borrowing, 243, 411, 418, 474,
 493, 503, 595, 615, 649 n.
 39, 686 n. 523, 748, 754–
 56, 760, 822, 825
 British, 664, 666 n. 3, 674,
 681–82, 684
 British Academy, 661, 664,
 669–70,
 Bronze Age, 26
 Byblos, 245–46
 byform, 159–61, 173
 Byzantine, 40, 195, 436, 438,
 504, 508, 747, 750–52, 765,
 781
 bāt-qatāl, 6–9, 16, 25
 Cairo, 665
 Cairo Geniza, 226–29, 508 n.
 18, 510, 577, 583, 849–51,
 854–55, 859, 865, 869,
 872–73
 calque, 414–15, 555–56
 Canaan, 352, 389, 788
 Canaanite, 8–9, 22–24, 26, 29,
 55–56, 250, 485, 500, 544
 n. 21, 611, 642 n. 21, 652 n.
 42, 835. *See also* Amarna
 Canaanite shift, 391
 canon, 69, 190, 191 n. 147,
 632, 709–10, 735
 cantillation, 821
 Catholic, 403, 664, 772
 causal, 27, 196, 405, 417, 635,
 653
 Celtic, 492 n. 1, 567
 chanting, 191, 193–95, 197–98,
 207, 214–15
 chiasitic concord, 613, 620
 China, Chinese, 495 n. 6, 781
 Christian, 194, 378, 386, 492 n.
 1, 493 n. 3, 495, 502, 504,
 513, 579, 591, 593, 595,
 598–99, 749, 751–52, 754,
 756–59, 763–65, 771–74,
 780, 783, 786, 789, 833–34,
 844–45
 chunking, 10–11, 22–23, 26
 church, 502–3, 597, 753, 772,
 781, 783

- circumcision, 364, 392, 703
 circumlocution, 577, 580
 clause-type, 5, 6 n. 2, 8, 12, 19,
 23, 25–26, 29–30
 codex, 190, 195 n. 152, 364,
 365 n. 6, 760, 797 n. 2, 846
 n. 3
 Aleppo Codex, 189, 370 n.
 16, 372 n. 18, 376 n. 21
 Codex Climaci Rescriptus,
 761, 763
 Codex Sinaiticus, 189
 Codex Vaticanus, 189
 Leningrad Codex, 108 n. 3,
 118 n. 5, 160, 214
 cognate, 47, 50, 53–54, 235,
 368 n. 10, 447, 535, 556–
 57, 561, 634, 762–63
 collective, 136, **259–90, 291–**
 329, 634 n. 7
 colloquial, 442, 447, 560, 579,
 681, 685, 798 n. 2, 813, 873
 commentary, 79–80 n. 24, 161–
 67, 177, 181, 229 n. 9, 230
 n. 10, 238, 240, 244, 367 n.
 8, 375, 376 n. 22, 429–30,
 440, 508 n. 18, 681, 682 n.
 512, 691
 concrete, 172, 174–75, 177–80,
 319 n. 37, 335–36, 352
 conditional, 9, 11 n. 5, 12–16,
 21, 24 n. 22, 25, 30, **69–97**,
 306, 349
 conjugation, 26, 537, 749, 843,
 846, 848, 850, 855, 858–59,
 861–63, 868
 prefix conjugation, 46, 536,
 822–23, 834, 836–37, 862–
 63
 suffix conjugation, 535 n.
 10, 636, 822, 837
 conjunction *waw*, 11, 22, 39–40
 consecutive, 5, 6 n. 2, 14
 conservative, 580, 593, 772,
 787–88
 Constantine, Algeria, 588
 construct, 189, 233, 259, 264,
 304 n. 16, 309, 364, 368,
 408, 410, 464, 469–71, 473,
 538 n. 14, 557, 570, 618,
 788
 construction theory, 6, 9–10, 19
 Coptic, 111, 504, 543, 558, 789
 creole, 775, 778
 cuneiform, 493 n. 3, 494, 535
 n. 9, 777, 788
dagesh, 39, **157–88**, 441, 589,
 595
 dagesh mavhin, **157–88**
 strong *dagesh*, 5 n. 2, 158,
 171
 weak *dagesh*, 171
 database, 46 n. 9, 103 n. 1, 243,
 458, 845 n. 2, 846 n. 3
 Dead Sea Scrolls (DSS), 47, 50–
 52, 169 n. 11, 182, **359–83**,

- 385, 496, 579, 594. *See also*
Qumran
- defective, 363–64, 365 n. 6,
370, 372, 374 n. 20, 376 n.
21, 623
- definiteness, 264, 286, 294,
299–302, 304, 308–9, 313–
14, 324
- deity, 334–36, 343, 497 n. 8,
533, 540, 541 n. 18, 544,
577–78, 580–81, 584–85,
592, 594–95
- demon, 542–44, 750, 829, 835
- demonstrative, 247 n. 42, 272,
309, 362, 623–25, 654, 786,
833, 840
- Demotic, 499
- denominative, 145 n. 8, 530–31
- dependency treebank, **99–130**
- determiner, 259–61, 263, 286,
291–92, 304–5, 308 n. 20,
324
- devoicing, 236–38, 247
- Dhofar, 661–62, 671, 676, 678
- diachronic, 12, 27, 39–40, 49,
53, 56, 96, 262–64, 283,
345, 403, 441, 765
- dialect, 6–8, 25 n. 24, 225 n. 5,
250, 262, 403, 408, 411–12,
418, 439, 444, 557–58, 565,
567–68, 590–91, 595, 596
n. 37, 598, 600, 624, 634 n.
5, 638, 641 nn. 18–19, 646
n. 30, 652 n. 42, 662–64,
697, 743, 748, 752–53, 755,
762, 764, 773–74, 776–77,
779–84, 787, 789, 798, 822,
833–34, 836–37, 840–41,
844, 849–51, 853–55, 861,
868, 870, 872
dialect continuum, 411, 783
- digital, 230 n. 10, 236 n. 23,
360, 661, 669–71, 674–75,
797
- diphthong, 372 n. 19, **455–78**,
595 n. 36, 616, 619, 857
- diplomacy, 482, 497, 773, 777–
78, 782, 789, 799
- directionality, 332, 333 n. 3,
334–37, 344 n. 15, 345–46,
350–52
- discourse active, 73, 76, 79–80,
82, 85, 86, 92
- discourse dependency, 6, 9 n. 3,
13, 42–44
- distributive, **259–90**, **291–329**,
538
- dittography, 807, 812
- dots, 584, 623, **821–42**
- Ebla, 534, 540, 788
- ecclesiastical, 747, 750, 752–
54, 756, 765, 783
- Edessa, 752 n. 7, 754, 778, 780,
785–87, 825
- Egeria, 750–51
- Egypt, Egyptian, 13, 80, 138–
39, 245–46, 320, 332, 343,
352, 410, 493 n. 3, 497–

- 500, 542–43, 681, 779, 788–89
- ending, 51, 422, 424–25, 468, 583, 612, 616–20, 622–23, 626, 637, 664, 748, 763, 847, 852, 859, 861, 871
- energetic, 848, 851, 853, 861–64, 873
- English, 10, 79 n. 24, 106, 131 n. 1, 162–63, 165, 199, 259 n. 1, 260–61, 265, 269, 277, 279 n. 11, 292, 294, 296, 298, 305, 312 n. 25, 337 n. 8, 369 n. 12, 385 n. 1, 387 n. 4, 398, 417, 466, 492 n. 1, 510, 560, 562, 584, 682 n. 512, 685, 694, 757, 772–73, 789, 800
- Old English, 567
- epenthesis, 614, 618–19, 621, 822
- Ephrem, 780
- epigraphy, 105, 119, 121–22, 747 n. 1, 753, 756, 786–87
- Epiphanius of Salamis, 749
- epithet, 370, 377, 391, 577, 580
- Eretz Israel, 385, 437–38, 456, 482, 484, 487
- Ethiopia, Ethiopian, 446, 493 n. 3, 556, 578
- Ethiopic, 533, 636, 645. *See also* Amharic; Ge'ez
- Etruscan, 243
- etymology, 40, 139, 398, 408, 423, 433, 441, 445–47, 457, 462, 464–65, 472, 500, 599, 640, 642 n. 20, 648, 649 n. 39, 755 n. 11, 759–61
- euphemism, 166, 577, 741 n. 84
- euphony, 332–33, 344, 346, 352
- European languages, 121 n. 8, 417, 560, 569
- exegesis, 180–81, 197–98, 200, 202–4, 207, 209, 211, 213–15, 361, 366, 371, 378, 394, 398, 406, 429, 753
- factitive, 143, 760
- Farsi, 774, 781
- Fayyum, 499
- Feierberg, Mordechai Zeev, 482
- feminine, 159, 238 n. 25, 267, 272 n. 5, 362, 367, 392, 537, 540, **611–29, 631–60**, 726 n. 63, 748
- fieldwork, **661–80**
- figura etymologica*, **555–75**
- figurative, 209, 376, 711
- Flaccus, Verius, 501
- focus, 18, 19 n. 15, 25, 29–30, 69–71, 87, 89–92, 94 n. 63, 95–96, 139, 152, 198, 342, 569, 833
- formalism, 100–101, 105, 107, 111, 115–16, 121–22
- French, 417, 562, 775, 789

- fricative, 595, 750
- fronting, **69–97**, 199, 202, 833
- future, **5–36**, 30, 45, 55, 749
- Galilee, 249–50, 435, 437, 753, 855
- Gaza, 246 n. 41
- Ge'ez, 556, 613 n. 2, 614 n. 4, 617, 621, 622 n. 9. *See also* Ethiopic
- gematria*, 494–95
- gemination, 37–42, 46, 158–59, 162 n. 5, 171, 173–74, 177–79, 234, 364, 368, 390–92, 446, 469, 589, 832
- gender, 404, 458, 460, 465, 612, 613 n. 3, 619–20, 623, **631–60**
- Genesis Rabbah, 249, 496 n. 7, 845, 858, 868
- genitive, 695, 698 n. 4, 785
- geography, 249–50, 484, 487, 663, 669, 752, 754 n. 8, 771, 783
- German, 555, 558, 562–64, 566–68, 570, 615, 632 n. 2, 698, 729 n. 68, 750
- Old High German, 567
- Germanic, 492 n. 1, 566–67, 569
- glottal, 390, 442, 444, 447, 858
- Gnostic, 578
- gospels, 190, 191 n. 147, 749, 760, 827, 835–36
- Gothic, 556
- grammar, 11, 37 n. 1, 103 n. 1, 104, 173, 246, 248, 260–61, 331, 352, 388, 697, 821–22
- construction grammar, 42
- dependency grammar, 103, 105–7, 111–12, 114, 121–22
- generative grammar, 663
- phrase structure grammar, 103–5, 121
- grammarians, 175, 179–80, 192, 237, 821, 823–25, 834, 840
- grammaticalisation, 11, 260, 263, **403–20**, 625
- Greek, 37, 39, 41, 44, 47, 101, 104, 116–19, 121, 189–90, 195 n. 152, 261, 365, 372–74, 376–78, 379 n. 26, 407, 493–96, 503–4, 508, 510, 560, 567, 578, 580, 593–94, **747–70**, 772, 776, 778–81, 784–85, 821–22, 825–27
- koinē* Greek, 776, 780–81
- Gregorian chant, 194–95, 214
- guttural, 209, 444, 468, 475, 750
- habitual, 5–8, 10–11, 16–20, 24–25, 306–7, 393, 848
- Haifa, 225, 228, 249–50, 463, 467–68, 529
- halakha*, 228, 239, 405, 455–56 n. 2, 577, 582
- hapax legomenon*, 508–9
- haplography, 807
- haplology, 618
- Hashemite, 684, 688 n. 530

Haskala, 479–80, 482–83

hatef qameṣ, 363

Hebrew, 23–24, 27, 39, 46 n. 9,
47 n. 10, 101, 104, 108 n. 3,
111, 118, 120, 131, 145,
160 n. 2, 165, 168, 179–80,
182, 189, 209, 223, 232–33,
235–36, 239, 246, 250, 259–
63, 265, 292 n. 1, 300 n. 9,
302 n. 13, 312 n. 25, 332,
363, 365–66, 368 n. 10, 376
n. 22, 377, 379 n. 26, 385,
387, 391, 403, 407–8, 411–
12, 414, 416, 418–19, 432,
440 n. 12, 442, 445–46,
455, 457–59, 461, 465–66,
468, 470, 472–75, **479–88**,
495, 503, 505 n. 16, 507,
509–13, 534, 556, 560,
564–65, 568, 570, 578, 579,
583, 585–88, 590–91, 593,
595, 600, 614–16, 621–23,
632 nn. 1–2, 633, 634 n. 5,
637–8, 641–51, 772, 778–
79, 786, 799, 821, 825, 845
n. 2, 846 n. 3, 852

Amoraic Hebrew, 233

ancient Hebrew, 42 n. 6, 53,
104–5, 234, 342–43, 364–
65, 578

Archaic Hebrew, 11, 20

Biblical Hebrew (BH), **5–36**,
37–68, **69–97**, **99–130**,
131–56, **157–88**, **189–221**,

223–58, **259–90**, **291–329**,
331–57, **359–83**, 399, 404,
406, 408–9, 411, 414, 418,
443, 445, 479–80, 538 n.
15, 556–57, 561, 570, 580,
589, 592–94, 600, 611,
613–14, 616–17, 619, 621,
623, 641–44, 646–51, 849

Classical Biblical Hebrew
(CBH), 12, 16, 21–25, 27–
29, 53–54, 57, 58 n. 16, 294,
306, 312 n. 24, 315, 317,
321–25, 418

Classical Hebrew, 12, 20,
407 n. 2, 465

contemporary Hebrew, **455–
78**

General Israeli Hebrew
(GIH), **455–78**

Israeli Hebrew, 363–64, 557

Late Biblical Hebrew (LBH),
49, 54, 82–83, 306, 345 n.
16, 414

medieval Hebrew, 175, 179–
80, 586 n. 18

Mishnaic/Middle Hebrew
(MH), 250, 398, **403–20**

Modern Hebrew, 165, 259–
60, 262–64, 269, 277, 293–
94, 298, 301, 304 n. 16, 310,
312, 314–17, 319 n. 36, 322,
325, 362–64, 458, **479–88**,
570, 633 n. 3, 639, 641,
645, 647 n. 33, 650 n. 41

- Old Hebrew, 403, 412–14, 418
 palaeo-Hebrew, 47, 579, 594
 post-biblical Hebrew, 173, 180, 570, 580, 589, 644
 post-Tannaitic Hebrew, 416–17
 pre-exilic Hebrew, 12 n. 7, 27, 29
 pre-modern Hebrew, 259, 264
 pre-rabbinic Hebrew, 53
 Qumran Hebrew (QH), 304 n. 15, **359–83**, 403, 641, 648
 Rabbinic Hebrew (RH), 53, 58, 160, 165, 168, 170, 172–75, 178–79, 181, 232, 234–35, 263, 293 n. 2, **421–53**, 631, 644, 648–51
 Samaritan Hebrew (SH), 51–52, **385–401**, 444, 581
 spoken hebrew, 456, 459 n. 4, 465, 475, 479
 Tannaitic Hebrew, 414–17
 Hebrew Bible, 72, 85, 119, 158–59, 182 n. 15, 191, 203 n. 155, 281, 291, 340, 343, 353, 364, 367 n. 9, 412–13, 479–80, 488, 541, 560, 579, 585, 594, 780. *See also* Tanakh
 Hebrew reading traditions, 5 n. 2, 37, 38 n. 3, 39–41, 44, 52 n. 13, 161, 166, 170–71, 174, 178, 182, 192, 195–96, 212, 223, 225 n. 4, 387, 398, 455, 461, 469, 475, 587, 593, 798–99
 Ashkenazic, 455–57, 459 n. 4, 467 n. 9, 469
 Babylonian, 39, 41, 160 nn. 2 and 4, 171 n. 12, 172, 178–79, 192, 213 n. 161, 235 n. 22, 442, 444–45, 447, 586, 589, 623 n. 11
 Cochin, Kerala, 593
 Mizrahi, **455–78**
 Palestinian, 41
 Samaritan, 39–41, 44, 52, 172, 178, 586, 871
 Sephardic, 455–56, 459 n. 4
 Tiberian, 38 n. 2, 39–41, 43–44, 46–47, 53–54, 57, 161, 165, 170–71, 180–82, 190–92, 213 n. 161, 223, 225 n. 4, 390–92, 455–56, 600, 619, 623. *See also* Masoretic
 Yemenite, 173, 462, 595 n. 36
 Hekhalot, 504
 hierarchy, 120, 201, 205–9, 214, 343
 hieratic/hieroglyphic, 245
 Hindu, 193, 195
 H̱isda, R., 225–26, 233
 historical linguistics, 264, 332, 343 n. 13

- historiologiae, 798
 Hittite, 8
 homily, 194, 843
 homonym, 378 n. 25, 498 n. 8
 homophone, 38–39, 161, 171, 174
 honorific, 334, 337 n. 9, 342, 556
 Hungarian, 422 n. 2, 558
 Hurrian, 615–16
 hymn, 194, 542
 ibn al-Muzaffar, al-Layth, 505
 ibn Balaam, Judah, 177, 180
 Ibn Ezra, 507 n. 18, 585 n. 17
 Ibn Gabirol, 586 n. 18
 ibn Janāḥ, Jonah, 176, 180, 507–8 n. 18
 ibn Ḳuraysh, Judah, 507
 idiom, 407, 595, 683, 748, 750, 756, 764, 774, 776, 798
 Iliad, 117
 imperative, 27–28, 148, **331–57**, 404, 479, 590, 676, 749, 813, 818 n. 17, 822–25, 827, 834–36, 843, 847–49, 855, 858–62, 864, 868–72
 imperfect, 272, 389, 397, 409, 580, 611 n. 1, 764, 782
 imperfective, 5, 16, 20, 24–25, 27
 incantation, 543, 818
 Indo-European, 102, 104–5, 107, 116, 558, 567
 Proto-Indo-European, 567
 infinitive, 73, 78–80, 84, 148 n. 11, 233, 367 n. 7, 404, 409, 535 n. 10, 556–57, 560–62, 565, 569–70, 632 n. 2, 748, 764, 840, 843, 847–50, 861
 inflection, 146, 148 n. 10, 194, 267, 296 n. 4, 305, 310, 314–15, 318, 335, 405, 612, 622 n. 9, 637, 654, **843–77**
 innovation, 5 n. 2, 12, 23, 38, 39, 55, 178–79, 261, 388–89, 390 n. 5, 397, 511, 535 n. 3, 612, 615, 617, 622 n. 9, 626, 748, 843–44, 848, 858, 872
 inscriptions, 12 n. 7, 27, 29, 101, 241 n. 31, 243–45, 613 n. 2, 747, 753, 755–59, 763–64, 771, 784–87
 interchange, 234, 236–37, 374, 440 n. 12, 614, 864
 interdental, 588, 599–600
 interjection, 179, 397–98, 824, 840
 interrogative, 279 n. 11, 306, 397, 625, 828–33, 837, 840
 intonation, 201, 207, 209, 214, 840
 Iran, Iranian, 777–78, 781, 789
 Iraq, Iraqi, 468, **681–94**, 781
 Irenaeus of Lyon, 503
 Iron Age, 27, 37, 40, 43, 50, 54, 434–35, 493
 irrealis, 42–43

- Ishmael, R., 494
- Islamic, Muslim, 193, 457, 461, 475, 491, 505, 513, 578, 584, 588, 590–91, 600, 663, 747, 756–58, 761, 763–65, 772, 774, 789, 798
- isogloss, 611 n. 1, 748
- Israel, 75, 80, 86, 94, 137–38, 147, 165–67, 181, 224 n. 1, 239, 274–75, 282, 305, 307, 311, 316, 320–21, 323, 333, 359–60, 386, 389, 460, 465–66, 475, 479, 485, 487–88, 493, 495, 500, 587, 589, 739. *See also* Eretz Israel
- Israeli, 363, 457–58, 459 n. 4, 466, 468, 470, 474, 487
- Israelite, 86, 90–91 n. 57, 138, 272, 274, 282, 301, 373
- Italian, 105, 500, 559, 579, 774
- Jerome, 376 n. 22, 749–51
- Jewish, 41, 170, 178, 181, 191, 224 n. 1, 231 n. 12, 236, 249–50, 363, 378, 389, 411, 418, 455, 458, 475, 479–80, 482–85, 495, 502–4, 507, 510–11, 513, 543, 544 n. 21, 560, 564–65, 569, 577–82, 584, 587, 590–91, 593, 595, 598, 600, 751, 752 n. 7, 756–57, 765, 773–74, 779–80, 782–87, 789, 822, 843–44
- Jijān, ‘Abbās, 681–83
- Jonah, R., 225, 233 n. 16
- Jordan, 465, 752, 756, 758, 765
- Josephus, 752 n. 7
- Joshua of Sikhnin, R., 249
- Judaeans, 47, 367, 371, 377, 484, 784, 855
- Judah, Judahite, 80, 273, 311, 374, 479, 481, 507, 825
- Judah ha-Nasi, 249
- Judezmo, 564, 581
- jussive, 5 n. 1, 27, 40, 44, 55–57
- Karaite, 192, 224, 584–85
- ketiv*, 46 n. 9, 47, 344, 395. *See also qere*
- Kimḥi, *see* Qimḥi, David
- kinship, 696 n. 1, 699, 742–43
- koine, 771–95. *See also koinē Greek under Greek*
- Land of Israel, *see* Eretz Israel
- Late Antiquity, 167, 170, 543, 747, 773, 779
- Latin, 37, 39, 41, 44, 101, 104, 116–19, 121, 194, 243, 365, 374, 376 n. 22, 503, 511, 513, 560, 567, 593–94, 749–50, 752, 754, 772–74, 778–80, 799
- Lebanon, 241–43, 408
- legal, 21 n. 18, 30, 86, 87 n. 48, 338, 497, 559, 778, 781, 783–85, 790
- Levant, 411, 434, 500
- Levi, R., 225, 228–29, 233–35, 249–50

lexicography, 144 n. 8, 361,
407, 505–7, 750, 763, **879–
93**
Libya, 241, 666
ligature, 583–84
lingua franca, **771–95**
linking, 9 n. 3, 13–16, 20–21,
24 n. 22, 25, 55
Lithuanian, 558
liturgy, 194, 214–15, 224, 504,
750, 753, 756, 772, 789
loanwords, 412, 466, 555, 560,
644, 700, 722, 754 nn. 9–
10, 755 n. 11, 758–59, 761–
62, 825–26
locative, 622
Luther, 560–62
Lycian, 778
magic, 193, 543, 577–78, 797,
798, 810, 812–13, 816
Maimonides, 227–28, 232, 236,
238, 240, 430–31, 577 n. 1
Malayalam, 261, 774, 781
Maltese, 557–58
Mandaean, 504, 798, 816, 818
n. 17
Mandaic, 586 n. 19, 649, **797–
820**
Manoah of Narbonne, R., 238–
39, 250 n. 47
manuscript, 52–53, 169, 191,
194, 211–12, 214, 226–31,
239, 249 n. 46, 359, 365 n.
6, 370 n. 16, 376 n. 21, 386–

87, 394, 397–98, 422, 469,
508 n. 19, 511–13, 583, 749
n. 3, 753, 757–58, 760–63,
787, 797, 798–99, 801, 803
n. 6, 827, 840–41, 845
Mapu, Abraham, 480, 483
Maronites, 821
Masada, 189, 500
masculine, 267, 272, 367–68,
537, **611–29**, **631–60**
maskilim, 479, 482–83
Masorah, 225 n. 4
Masoretes, 165
Masoretic, 37–38, 40–41, 45,
47–51, 54, 56–58, 119, 122,
171 n. 12, 190–92, 197, 365
n. 6, 370, 374, 376 n. 21,
507–8, 780, 827. *See also* Ti-
berian *under* Hebrew read-
ing traditions
Masoretic Text (MT), 45–49,
52, 54, 158, 163, 167–71,
192, 203, 211, 214, 235,
359, 362, 365 n. 6, 369,
371–77, **385–401**, 759, 852
matres lectionis, 372 n. 19, 388,
457
medieval, 144, 168, 175, 179–
80, 211, 212 nn. 160–61,
237, 364, 365 n. 6, 375,
502, 507, 511, 765, 774,
779. *See also* Middle Ages
medicine, 507 n. 18, 510, 641,
645 n. 27, 798 n. 3

- medio-passive, 135, 143, 534
 Mediterranean, 246, 491, 508,
 772, 775, 778, 782, 788
 melody, 194–95
 menstruation, **797–820**
 Mesopotamia, 497, 498 n. 8,
 542, 752, 758, 771–72, 777,
 779, 782–83, 788, 798 n. 3
 Messiah, 169–70, 361, 371,
 596–98, 830 n. 7
 metalinguistic, 492, 494, 502,
 504
 metaphor, 279 n. 10, 336, 352,
 483
 metre, 194, 208, 436, 683 n.
 513, 686 n. 524
 Middle Ages, 170, 492 n. 1,
 502, 504, 513, 773. *See also*
 medieval
 Middle East, 191 n. 148, 502,
 773, 777–80, 788
 midrash, 406, 504 n. 14, 843
 mimation, 616, 619
 Mishna, 160, 250, 403, 405,
 421, 424–25, 427–28, 430,
 432–33, 438, 440–42, 444–
 45, 447, 456 n. 2, 469, 501
 Mishneh Torah, 236, 238, 240,
 430–31
 Moabite, 50
 modal, 22–24, 26–29, 42, 46,
 48, 55–56, 88, 114, 260,
 293, 302 n. 13, 306, 339,
 559, 759
 monks, monasteries, 502, 747,
 752–53, 781
 monophthong, **455–78**
 monster, 533, 542, 545
 Morocco, 468
 morphology, 38–40, 44, 46–58,
 100, 102, 114, 131, 133,
 135, 142, 150, 159, 173,
 182, 232–33, 261, 310–11,
 390, 392–93, 396–97, 399,
 442–43, 445, 459, 469, 533,
 592 n. 32, 593–94, 622,
 632–33, 635, 637, 639, 645,
 654–55, 663–64, 845, 848,
 854, 856, 864–65, 868, 872
 morphophonemic, 854
 morphophonology, 171, 855,
 871
 morphosemantics, 53
 morphosyntax, 264, 286, 294,
 308–9, 313, 317 n. 32, 318,
 321, 324, 631, 843, 845,
 849, 852, 854–56, 863–64,
 871–73
 Mossinsohn, Ben-Tzion, 484
 Mosul, 595
 mountains, 7, 393, 484, 563,
 663–67, 669, 676, 679
 Mount Carmel, 437, 483
 Mount Ebal, 389
 Mount Ephraim, 484
 Mount Gerizim, 389, 396
 Mount Sinai, 284–85, 308
 Muḥammad, 193, 584, 600, 818

- musical, 194, 198
- Muslim, *see* Islamic
- Nabataeans, 784–85
- names
 - personal names, 243, 462, 467–68, 535 n. 9, 763, 785
 - place names, 246 n. 41, 368, 468
 - sacred names, **577–610**
- narrative, 6–7, 25 n. 24, 41, 44, 95 n. 66, 340, 483, 533, 536, 812
- neologism, 233, 235, 388
- New Hebrews, 484
- New Testament, 118, 162 n. 5, 361, 495, 543
- nominative, 538 n. 14, 594, 617, 622 n. 9, 637, 763
- Norwegian, 133
- numeral, 310–11, 462, 467, 470, 495 n. 6, 498 n. 8, 582, **611–29**, 646 n. 29, 812
- nunation, 616
- Obama, Barack, 682
- oblique, 134, 137–38, 146 n. 9, 150, 619, 620 n. 7, 637
- Occitan, 250 n. 47
- Old Church Slavonic, 749
- Old Frisian, 567
- Old Irish, 567
- Old Norse, 566–67
- olives, 429–32, 434, 472
 - olive oil, 434, 436, 597 n. 39
 - olive press, **421–53**
- Oman, Omani, 613, 675
- onomastics, 534, 535 n. 3, 750, 763
- onomatopoetic, 234–35
- oral, 159 n. 1, 166, 170, 182, 223, 225 n. 4, 387, 579, 600, 871
- orthoepy, 38, 362 n. 3
- orthography, 41, 169 n. 11, **359–83**, 459, 473, 577, 581, 584, 594, 843 n. 1, 845, 848, 862, 871
- ostraca, 493, 500, 781
- Ottomans, 230, 682
- pagan, 172, 174, 584, 593, 751, 753 n. 8, 783, 787
- palaeography, 228, 244, 359, 577, 762 n. 15
- palatal, 459, 468, 470, 474
- Palestine, Palestinian, 41, 191, 368 n. 9, 434, 444–45, 436, 482–83, **747–70**, 779, 782, 784, 788–89, 844
- Palestinian reading tradition, *see under* Hebrew reading traditions
- papyri, 498, 578, 753, 759, 778, 781
- parabiblical tradition, 169–70, 181
- paragogic *heh*, 334
- parchments, 778
- parliament, **681–94**
- paronomasia, 556

- participle, 6–7, 15, 17–18, 149, 159, 173, 179, 272, 274, 405, 462, 472, 748–49
- particle, 56 n. 15, 82, 108, 110, 339, 344, 347 n. 19, 397–98, 404, 406–7, 412–15, 538 n. 14, 755, 786–87, 830, 834
- partitive, 308 n. 19, 317 n. 31, 703
- passive, 135, 159, 392, 532 nn. 3–4, 556, 735 n. 75, 748 n. 2
- passivisation, 566
- Passover, 140, 409, 593, 830
- pataḥ*, 38 n. 2, 456, 585–86, 592, 595
furtive *pataḥ*, 465, 468
- patronym, 246 n. 41, 249, 806, 808
- pausal forms, 28, 189, 585–87, 592, 594 n. 35, 623–24, 840
- Pentateuch, 21 n. 18, 45, 47–48, 50–51, 53–54, 57, 195 n. 152, 385, 390, 399, 851. *See also* Torah
- Samaritan Pentateuch (SP), 44, 50–51, 144 n. 7, 159 n. 1, 318 n. 34, **385–401**
- perfective, 5, 23, 41, 43, 45, 55
- periphrastic, 749, 846–56, 858–59, 864–65, 870–73
- Persian, 510, 686 n. 523, 773, 777, 783
- Peshitta, 149 n. 12, 369, 376, 407 n. 3, 780–81, 783, 786
- Petachia of Ratisbon, R., 191 n. 148
- pharyngeal, 595, 598 n. 44, 616
- pharyngealisation, 193
- Philo, 170
- philology, 157–58, 160, 163, 173, 180, 228, 338, 421, 600, 765, 771
- philosophy, 196, 483 n. 1, 498, 692, 753, 756
- Phoenician, **223–58**, 534 n. 6
- phonetics, 11–12, 20, 39, 193, 195, 364, 390–93, 459, 492 n. 2, 505, 581, 589–90, 595, 622, 665, 674, 695, 753, 758, 812, 867, 871
- phonology, 44–45, 55, 100, 119, 122, 159, 161, 237, 246–47, 261, 390, 415, 455, 457–59, 462, 465–66, 468–69, 473–75, 587–89, 592–94, 596, 598–99, 632, 662–64, 674, 760, 763, 821, 843–45, 848, 860, 864, 867, 871, 873
- pidgin, 774–75, 778
- Plautus, 243
- plene*, 363–64, 370, 372, 374, 376, 378 n. 25, 462, 468, 473, 585, 786
- plosive, 171, 391 n. 6, 587
- Plutarch, 499–500

- poetry, 12, 20, 26 n. 24, 49–50, 56, 77, 80, 95 n. 66, 189–92, 194, 197–98, 200–1, 203–4, 207, 209, 213–15, 299, 306, 312 n. 24, 340, 352, 486–87, 495–96, 498, 504–5, 507 n. 17, 531–32, 536, 538 n. 14, 540, 544–45, 563, 566, 586 n. 18, **681–94**
 twentieth-century Arabic poets, 681–82
 Umayyad poets, 681
- polarity, 293, 299, 301, 306, 410, 824, 831, 837
- politeness, **331–57**
- polyfunctionality, 139 n. 5
- polysemy, 40, 173
- possessive, **695–745**, 786
- pragmatic, 11, 24, 42–43, 102, 105, 107, 283, 297, 332–33, 340, 342, 506, 545, 758
- prayer, 194, 224, 333, 345, 350 n. 24, 413, 463, 504, 568, 579, 772, 818
- predicate, 20 n. 17, 21–22, 26, 29–30, 69–70, 76 n. 14, 87, 92, 95 n. 64, 112, 133, 269, 273–76, 280, 294–98, 304–5, 310 n. 22, 312–13, 320, 654
- prefix, 55, 173, 537, 580, 585, 748, 822–23, 829–30, 846.
See also prefix conjugation
under conjugation
- presentative, 397
- preterite, 26 n. 24, **37–68**
- priest, 27, 87, 90, 172, 280, 285, 317, 334, 363, 411, 578
- prominence, 112, 134, 152, 198–202, 207, 209, 211, 214–15, 594, 754, 758
- pronunciation, 5 n. 2, 38 n. 3, 39–40, 54, 161, 169 n. 11, 171, 195, **223–58**, 364, 376 n. 22, 387, 390–91, 393–94, 397, 399, 445, **455–78**, **577–610**, 618, 623, 625, 750, 758, 783, 813
- prophecy, 18, 191 n. 147, 482, 485, 758
- prophet, 193, 285, 334, 370, 375, 377, 480, 482, 591, 600
- Prophets, 48–51, 190 n. 146, 191, 378–79
- prose, 49, 190–92, 197, 201, 294, 306, 308 n. 20, 324–25, 505, 531–32, 545, 613 n. 3
- prosody, 119–21, 198, 203, 207, 211–13, 833, 848
- protasis, 9, 13, 16, 20–21, **69–97**
- Provençal, 250 n. 47
- proverb, 141, 497, 505 n. 15, 683 n. 513, 684–85, 688 n. 530, 692, 694
- Ptolemaic, 498–99
- punctuation, 114–15, 119, 121–22, 194, 585

- Punic, 101, 240, 242–43, 247 n. 42
- Purim, 456 n. 2
- qameš*, 363, 583–87, 592–93, 594 n. 35, 599
- Qaro, R. Joseph, 239–40
- qatal*, 5, 9, 11, 19, 22–23, 26, 29, 43, 46, 72, 77 n. 17, 80, 84–85, 96. *See also* suffix conjugation *under* conjugation
- qatil*, 135, 393, 639 n. 14
- qere*, 46 n. 9, 47, 579, 600. *See also* *ketiv*
- Qimḥi, David, 237, 585, 586 n. 17
- qotel*, 393
- qtal*, 843–77. *See also* suffix conjugation *under* conjugation
- quantification, 259–90, 291–329, 409, 469, 471
- quatrain, 685, 691
- Qumran, 248 n. 44, 304 n. 15, 359, 361–62, 365, 370 n. 15, 412, 493 n. 4, 579, 850. *See also* Dead Sea Scrolls
- Quran, 104, 193, 195, 488, 563, 589, 772, 800, 813
- rabbinic, 39, 223–58, 406–7, 411, 423, 444, 496 n. 7, 503, 581, 586, 588 n. 23, 595 n. 36, 780
- Rabbūlā of Edessa, Bishop, 780
- rafe*, 586 n. 20, 589
- Ramadan, 667
- realis, 41–43
- reciprocal, 131–56, 530–31, 534
- recitation, 38, 191 n. 148, 193, 195, 224–25, 237–38, 455 n. 2, 587, 685 n. 516, 772, 818
- reduplication, 305
- reflexive, 529–31, 761
- religion, 192, 245 n. 39, 334, 344, 389, 411, 458, 460, 465, 480, 487, 569, 584, 588, 595–98, 691, 754, 756, 772–74, 776, 778–82, 789
- resumptive, 284, 308
- rhetoric, 194, 281, 351, 498, 693
- rhyme, 506, 507 n. 17, 683 n. 513, 685
- ritual, 343, 367 n. 9, 578–79, 594
- linguistic ritual, 343, 350
- Roman, 495, 501, 752, 754, 776, 781, 783–84, 852
- Rome, 226, 429
- rubric, 513 n. 24, 799, 801, 803, 806, 808, 812, 815
- rural, 457, 662–63, 665, 754, 756
- Russian, 239, 558, 595, 695, 697–98
- Saʿadya Gaon, 507, 509 n. 20

- Sabaic, 148, 534 n. 6, 611–16, 619, 644 n. 24
- Sabbath, 91, 224 n. 2, 456 n. 2, 828
- sacred text, 191–93, 195, 215
- Saddam, 682
- Samaria, Samaritan, 170, **385–401**, 437, 503, 579, 756–57, 765, 843–44, 855,
- Samaritan reading tradition, *see under* Hebrew reading traditions
- Samson of Chinon, R., 427
- sanhedrin, 232
- Sargon, 494–95 n. 6
- satire, 457, **681–94**
- Saxonian, 560
- schematisation, 10, 13, 15–17, 17 n. 13, 18, 20, 25, 30, 38, 42, 54
- science, 359, 422 n. 2, 485, 498, 695, 756
- scribes, 169 n. 11, 189–90, 246, 359–61, 365–67, 370–71, 378, 421, 440–41, 499, 511, 513 n. 24, 754, 784, 788, 821
- script, 245 n. 38, 499, 503, 510, 511 n. 22, 579, 594, 674, 752, 757, 764, 784–85, 788, 797–99, 801, 803, 805, 807, 809, 811, 813, 815–17
- scripture, 192–94, 378, 406, 580, 772
- scrolls, 47, 189–90, 195 n. 152, 359, 361, 365, 496, 580 n. 7, 593
- seafaring, 755
- seal, 244, 496 n. 7
- Second Temple, 5 n. 2, 39–40, 42, 51, 53, 55, 170, 173, 178, 182, 195 n. 152, 361, 370–71, 378, 387, 395, 411, 414
- sedarim, 511
- Sefer Yeşirah*, 504, 641
- segol*, 455–57, 623 n. 11
- segolate, 208 n. 157, 363, 455
- Seleucid, 776
- semantic, 6, 9 n. 3, 13–14, 16–17, 24, 27, 29, 37–45, 51, 53–57, 79 n. 23, 85, 102, 107–14, 116, 122, 132–36, 137 n. 3, 152, 159, 161, 173–76, 233–34, 259 n. 1, 261, 269, 283–84, 292–94, 297, 299, 300 n. 9, 304, 308–10, 314–15, 322–25, 332–33, 346 n. 19, 368 n. 10, 373, 392–94, 404, 407–8, 410, 433, 441, 445–46, 529, 530 n. 1, 532 n. 3, 569, 589, 599, 611, 631–36, 639, 653, 654 n. 46, 655, 696, 699, 702, 713, 719 n. 48, 721, 760

- Semitic, 5, 26 n. 24, 29, 101,
104, 235, 368 n. 10, 385,
446–47, 503–4, 512, 533,
535 n. 3, **555–75**, 585, 592,
600, 611–12, 615, 623,
631–60, 758, 771, 774, 789
Central Semitic, **611–29**
Northwest Semitic, 8–9, 13,
22, 26, 119, 173, 179, 248–
49, 368 n. 10, 611, 612 n. 2,
620–21, 624–26, 642 n. 21
Proto-Semitic, 5 n. 1, 26 n.
24, 42, 46, 57, 612, 614,
622 n. 9, 625–26, 636, 639–
40, 642 n. 20, 652, 655
West Semitic, 26, 150, 540,
614, 617, 625, 644, 649 n. 39
Septuagint, 145, 149 n. 12,
161, 182, 249 n. 46, 322 n.
43, 346 n. 17, 369, 370 n.
15, 371–77, 406–7, 560,
562, 580, 755
šere, **455–78**, 595, 623 n. 11
Shakespeare, 488
Shalev, Meir, 487
Shema, 224, 236–38, 240, 587
shewa, 5 n. 2, 38 n. 2, 390–91,
579
Shiite, 691, 798
Shmuel ha-Nagid, 507–8 n. 18
shureq, 160 n. 2
sibilant, 209, 235–37, 247, 649
n. 39
Sicily, 101
simile, 543
Singapore, 581
Slavic, 492 n. 1, 558, 564, 567–
68
sociolect, 474
sociolinguistic, 363, 365, 457–
58, 473, 475
software, 99, 103 n. 1, 459
sonorant, 470, 675
Soqotra, 695
South Arabian, 613
Ancient South Arabian, 611–
12 n. 1
Hadramitic, 611 n. 1
Minaic, 611 n. 1, 614
Qatabanic, 611 n. 1,
614–15
Modern South Arabian
(MSAL/MSA), 613 n. 2, 641
n. 16, 645 n. 26, 646 n. 28,
647 n. 32, 650 n. 40, 672,
695, 696 n. 2, 697
Bathari, 672–73
Harsusi, 672–73
Hobyot, 641 n. 16, 646
n. 28, 650 n. 40, 653 n.
43, 672–73
Jibbali, 632 n. 2, 698 n.
4
Mehri, 613, 670–76, 678
Shehret, 672–74
Soqotri, 641, 641 n. 16,
645, 646 n. 28, **695–
745**

- Spain, 430, 491, 666, 750
- Spanish, 144 n. 8
- stanza, 486–87, 498 n. 8, 691
- statistics, 21, 24 n. 22, 52, 84, 425, 455, 460–61, 465, 563, 655, 734
- stative, 29, 148 n. 10, 617–18, 636
- stem
- C-stem, *hiʿil*, 54, 56–57, 143, 144 n. 8, 232–34, 404, 432
 - D-stem, 149, 536
 - paʿel*, 225 n. 5, 859
 - piʿel*, 392–94
 - Dt-stem, *hitpaʿel*, 152
 - G-stem, 132, 135, 137, 139, 141, 143–44, 147–48, 150–52
 - pəʿal*, 848, 859
 - qal*, 56 n. 15, 159, 166, 232, 392–94
 - Gt-stem, **529–53**
 - itpeʿel*, 168 n. 9
 - N-stem, *nifʿal*, 15, **131–56**, 232, 392, 534 n. 7, 536
 - Št-stem, 761
- stichometry, 189
- stress, 46, 203, 364, 390, 462, 465, 590, 595, 616, 618, 621–23, **821–42**
- subjunctive, 6, 8–9
- subordination, 7, 9 n. 3, 13–14, 27–28, 111, 206, 337, 343, 348, 406, 416–18, 830
- substrate, 403, 411–12, 440–41, 447, 747, 758
- Sudan, 664
- suffix, 15, 142, 145, 146 n. 9, 148 n. 11, 264, 267, 276, 283–84, 308, 318, 335–36, 344, 348 n. 22, 397, 409, 424–25, 431, 585, 613–15, 618–25, 632, 635–37, 695–96, 698 n. 3, 716 n. 43, 742–43, 822, 839, **843–77**. *See also* suffix conjugation *under* conjugation
- Sumerian, 497, 540
- Swahili, 782
- syllable, 38 n. 3, 46, 192, 195, 205, 208, 223, 376 n. 22, 390, 462–65, 467–69, 471–75, 585, 592, 618, 621, 623 n. 11, 749 n. 3, 821–28, 832–41, 868
 - closed syllable, 464–65, 468, 473
 - open syllable, 462–64, 467, 469, 471–75, 868
- symbolism, 539, 543 n. 20, 599
- Symmachus, 372
- synagogue, 52 n. 13, 191 n. 148, 456 n. 2, 568
- synchronic, 174, 564, 618, 725, 847, 853
- syndeton, 22, 404
- synharmonism, 593

- syntax, 9 n. 3, 19 n. 15, 22 n. 20, 42, 72, **99–130**, 133–34, 136, 195, 203–4, 259 n. 1, 261–63, 266, 283, 293–94, 299, 301, 304 n. 16, 314–15, 324–25, 367 n. 7, 409, 441, 445, 459, 469, 530 n. 2, 536, 556, 561, 625, 640, 664, 669, 671, 724, 734, 743, 748, 763, 765, 845, 852
- Syria, Syrian, 416, 497, 588, 598, 752, 755, 757–58, 762, 772, 777, 781, 783, 788
- Syriac, 137, 194–95, 365, 410–12, 496, 503–5, 510, 557, 580, 586 n. 18, 589, 592, 618, 619 n. 6, 620–21, 623–25, 645, 747, 750–54, 756–57, 772–74, 780–81, 783, 785–87, 789, 821–23, 825–27, 834, 839, 841, 860, 862–63, 865, 868, 870
- Classical Syriac, 591, 595, 772, 780–82, 787, 821–22
- Classical East Syriac, **821–42**
- Late Classical Syriac, 821–22
- East Syriac, 586 n. 18, 821, 823, 827–28, 832, 834
- Jewish Syriac, 786–87
- West Syriac, 586 n. 18, 618, 752, 824, 840
- Syriac Christianity, 194, 503, 783
- tablets, 497, 533
- taboo, 577, 580–82
- talisman, 813
- Talmud, 227–30, 248, 345 n. 17, 424, 433, 873
- Babylonian Talmud, 426, 428–29, 443, 445, 447
- Palestinian Talmud, 227–30, 426, 843, 846 n. 3, 855
- Tanakh, 69–70. *See also* Hebrew Bible
- Tannaitic, 232, 405–6, 412 n. 5, 413, 433
- Targum, 149, 164, 166–70, 181, 235, 318, 346 n. 17, 369, 372, 376, 386, 406–7, 416, 418, 641, 780, 786, 849–51, 854–55, 868–69, 872–73
- Palestinian Targum, 418, 584, 873
- Samaritan Targum (ST), 386 n. 3, 394, 397, 399, 843–44, 851
- Targum Neofiti, 397, 851–52
- Targum Onqelos, 235, 416, 585 n. 17, 595 n. 36
- tautological infinitive, 535 n. 10, 556, 560–62, 565, 569–70
- taxonomy, 332, 335, 339, 341, 345, 348, 351

- teacher, 250, 467 n. 9, 484–85, 665, 679, 684, 751 n. 4, 823
- tefillin, 405
- Temple, 169–70, 494, 578
- tense, 5–6, 12, 14, 19, 41, 307, 404–5, 749
- terminative, 622–23
- Tetragrammaton, 578–85, 587, 594, 598
- theology, 371, 377–78, 496, 753, 780, 789
- thetic, 19 n. 15, 69, 71, 95–96, 619 n. 6
- Tibat Marqe, 843, 846–47, 849, 855, 869
- Tiberian reading tradition, *see under* Hebrew reading traditions
- Timothy I (Eastern-Syriac Patriarch), 756
- topic, 14–15, 18, 42, 69, 140, 198–200, 202, 211, 537, 569
alternative topics, **69–97**
- Torah, 47, 49–50, 54, 56, 58 n. 16, 190, 192, 387–88, 395, 399–400, 405, 417 n. 6, 418, 591. *See also* Pentateuch
- Tosefta, 426–28
- transitive, 117, 135, 145–46, 529, 532 n. 4, 537, 724, 818
- Transjordan, 275, 436, 748, 764, 784
- Tunisia, 582, 588
- Turkish, 558, 665
- Ugarit, 493, 540, 788
- Ugaritic, 8, 22, 26, 104, 119, 368 n. 10, **529–53**, 545, 611, 613 n. 3, 614–16, 620, 622–24, 641, 642 n. 21, 643–51, 652 n. 42
- urban, 457, 676, 749, 756
- Urdu, 772
- Vedas, 193, 195, 197
- Vedic, 567
- velar, 236–37
- velarisation, 588, 590–91, 593–94, 599–600
- vernacular, 408, 414, 418, 479, 485, 595–98, 748, 751, 752 n. 7, 756, 761–64, 772, 777, 788–89
- Virgil, 243, 500
- vocalisation, 39–41, 158, 160–61, 161 n. 5, 163, 165–71, 180–82, 235 n. 22, 372 n. 19, 387, 421–22, 425–26, 441, 445, 447, 456 n. 2, 459, 469, 535 n. 10, 537, 538 n. 14, 579, 585–87, 589, 615, 623, 800
- vocative, 586, 589, 590, 592–94
- Vorlage*, 366, 374, 376 n. 22, 377–78, 698 n. 4, 762 n. 15, 799, 800, 804, 849
- Vulgate, 369, 374, 376, 406–7

- wayyiqtol*, 5 n. 2, 6, 19, 25 n.
24, **37–68**, 141, 173
- weqaṭal*, **5–36**, 339 n. 10
- word lists, 497, 507, 674–75
- Writings, 49–50, 191
- Yemen, Yemeni, 581, 662–64,
666, 668–70, 674–76, 678–
79, 695, 697–98
- Yiddish, 479, **555–75**, 584
- yiqtol*, 5, 14, 16–22, 24–25, 26
n. 24, 27, 29–30, 39–40, 42,
46, 54–55, 56 n. 15, 57–58,
72–73, 75, 77 n. 17, 80, 82,
84–85, 96, 173, 846, 848,
850–53, 861–4, 873. *See also*
prefix conjugation *under*
conjugation
- Yishuv*, 482–84
- Zach, Natan, 486–87
- Zionism, 479–80, 482–84, 488

About the Team

Aaron Hornkohl and Alessandra Tosi were the managing editors for this book.

Aaron Hornkohl performed the copyediting of the book in Word. Anne Burberry indexed this volume.

The fonts used in this volume are Cambria Math, Charis SIL, David, Estrangelo Edessa, Kahle, Mandaic Hebrew, Narkisim, Paleo Hebrew, SBL Greek, SBL Hebrew, Scheherazade New, Segoe UI Historic, Times New Roman.

Cameron Craig created the paperback, hardback, and PDF editions. Conversion was performed with open source software freely available on our GitHub page at <https://github.com/OpenBookPublishers>.

Jeevanjot Kaur Nagpal designed the cover of this book. The cover was produced in InDesign using Fontin and Calibri fonts.

Interconnected Traditions

Semitic Languages, Literatures, and Cultures

A Festschrift for Geoffrey Khan

Volume 1: Hebrew and the Wider Semitic World

Edited by Aaron D. Hornkohl, Nadia Vidro, Janet C. E. Watson,
Eleanor Coghill, Magdalen M. Connolly, and Benjamin M. Outhwaite

Geoffrey Khan's pioneering scholarship has transformed the study of Semitic languages, literatures, and cultures, leaving an indelible mark on fields ranging from Biblical Hebrew and Aramaic dialectology to medieval manuscript traditions and linguistic typology. This *Festschrift*, celebrating a distinguished career that culminated in his tenure (2012–2025) as Regius Professor of Hebrew in the Faculty of Asian and Middle Eastern Studies at the University of Cambridge, brings together contributions from a vast and representative array of scholars—retired, established, and up and coming—whose work has been influenced by his vast intellectual legacy.

Reflecting the interconnected traditions that Khan has illuminated throughout his career, this two-volume *Festschrift* presents cutting-edge research on Hebrew and Aramaic linguistics, historical syntax, manuscript studies, and the transmission of textual traditions across centuries and cultures. Contributors engage with topics central to Khan's scholarship, including the evolution of the Biblical Hebrew verbal system, the intricacies of Masoretic notation, Geniza discoveries, Samaritan and medieval Judaeo-Arabic texts, and computational approaches to linguistic analysis.

As Khan retires from his role as Regius Professor, this collection stands as both a tribute and a continuation of his work, honouring his lifelong dedication to understanding and preserving the linguistic and literary heritage of the Semitic world.

This is the author-approved edition of this Open Access title. As with all Open Book publications, this entire book is available to download for free on the publisher's website. Printed and digital editions, together with supplementary digital material, can also be found at <http://www.openbookpublishers.com>.

Cover image: Cambridge University Library T-S NS 264.63, assorted writing exercises in Hebrew, Judaeo-Arabic, and Arabic, part of a letter, and some legal text (courtesy of the Syndics of Cambridge University Library).

Cover design: Jeevanjot Kaur Nagpal



UNIVERSITY OF
CAMBRIDGE

Faculty of Asian and Middle
Eastern Studies

e book

ebook and OA editions
also available

OpenBook
Publishers 

